

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Summerlin
Pump to
INITIAL SYSTEM: APPROVED 25% REDUCTION

LOT 57
Pump to
REPAIR APPROVED 25% Reduction

DISTRIBUTION: D-Box

DISTRIBUTION D-Box

BENCHMARK: 100.0

LOCATION Top of stake FC 57/58

NO. BEDROCKS: 4

LIAR 0.8 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
I { 1	B	91.00	75
2	Y	89.83	75
			<u>150</u>
R { 3	B	88.83	75
4	Y	88.25	75
			<u>150</u>

BY B.C. Raynor

DATE 07/16/2018

TYPICAL PROFILE

0 - 36 LS vfri gran
36 - 40 SCL firm SBK
CF 2 > 36"

THERE SHALL BE NO GRADING,
CUTTING, LOGGING OR OTHER SOIL
DISTURBANCE IN SEPTIC AREA

Add French Drain on repair

