

APPROVED
 02/02/2021


FO5 313

SPACE DATA



FIRST FLOOR, HEATED:	830 SF
SECOND FLOOR, HEATED:	1704 SF
FRONT PORCH:	104 SF
GARAGE:	465 SF

ATTIC VENT CALCS.

ATTIC AREA, JOIST SF:	N/A
GABLE VENTS:	90 L.F. / 115 SF. (718)
RIDGE VENTS:	87 L.F. / 155 SF. (238)
SOFFIT VENT:	16 = 113
RATIO:	175 = 113



2 RIGHT ELEVATION
 1/4" = 1'-0"
XND 1x4 ON Middle Windows



- 1a FRONT ELEVATION**
 1/8" = 1'-0" OPTION
- 9' CEILINGS
 - ON 9' CEILINGS UPGRADE ALL FIRST FLOOR WINDOWS SHOWN AS 210x62 TO 210x60 WINDOWS (2 SINGLES / 3 TRIPLES)
 - 8' CEILINGS

T:\CavLand\CL 3034 GR 2-6-20.dwg, 2/6/2020 7:38:54 AM



TODD TUCKER 34-156

© 2019 CavLand
1041-B Robeson St
Fayetteville, NC 28305
Office: 910-339-6330
Fax: 910-339-6333

CL 3034

ELEVATIONS

SCALE:
AS NOTED


DATE:
MAY 2019

PLAN:
CL 3034 B

LOT NO:

SHEET NO:


2



2 LEFT ELEVATION
1/4" = 1'-0"




1 REAR ELEVATION
1/4" = 1'-0"




3 TYPICAL WALL SECTION
1/2" = 1'-0"

● plumbing drops



CHECK BOX FOR:
 SCREEN PORCH



GENERAL NOTE:
 ALL 2x4 WALLS DRAWN AS 3 1/2"
 ALL 2x6 WALLS DRAWN AS 5 1/2"
 ALL EXTERIOR DIMENSIONS INCLUDE WALL SHEATHING
 ALL WALLS ARE 2x4 WALLS UNLESS OTHERWISE NOTED
 IN LOAD-BEARING WALLS:
 ALL OPENINGS, WINDOW & DOOR HEADERS TO BE (2) 2x10 SYP #2 & (2) STUDS ON EACH SIDE UNLESS NOTED OTHERWISE
 ◊ SYMBOL FOR REQUIRED STUDS FOR BEAM ABOVE
 ARROW INDICATES SPAN DIRECTION FOR TRUSSES TRUSS MFR TO CALCULATE ALL UPLIFT LOADS AND SPECIFY ADEQUATE HANGERS & TIE DOWNING



© 2019 CavLand
 1041-B Robeson St
 Fayetteville, NC 28305
 Office: 910-339-6330
 Fax: 910-339-6333

CL 3034
 FIRST FLOOR PLAN

SCALE:
 AS NOTED




DATE:
 MAY 2019

PLAN:
 CL 3034 B

LOT NO:

SHEET NO:
 4

T:\CavLand\CL 3034 GR 2-6-20.dwg, 2/6/2020 7:38:56 AM



1 SECOND FLOOR PLAN
1/4" = 1'-0"



© 2019 CavLand
1041-B Robeson St
Fayetteville, NC 28305
Office: 910-339-6330
Fax: 910-339-6333

CL 3034

SECOND FLOOR PLAN

SCALE:
AS NOTED

DATE:
MAY 2019




PLAN:
CL 3034 B

LOT NO.:

SHEET NO.:

5

T:\CavLand\CL 3034 GR 2-6-20.dwg, 2/6/2020 7:38:54 AM



© 2019 CavLand
 1041-B Robeson St
 Fayetteville, NC 28305
 Office: 910-339-6330
 Fax: 910-339-6333

CL 3034
 SLAB PLAN



SCALE:
 AS NOTED

DATE:
 MAY 2019

PLAN:
 CL 3034

LOT NO:

SHEET NO:
 3



TO USE:

- Select the required table, and design.
- Determine the support condition for the nearest bearing or support or interior support (including cantilever end supports).
- Select the row corresponding to the required Clear Span. For spans between those listed, use the next largest value.
- Select the column corresponding to the required hole diameter. For diameters between those listed, use the next largest value.
- The intersection of the Clear Span row and Hole Diameter column gives the maximum distance from the inside face of bearing to the center of a circular hole.
- Double check the table to the other support using the appropriate support condition.


Depth	Clear Span (ft)	Distance from End Support					Distance from Interior or Cantilever-End Support					
		Hole Diameter	Hole Diameter	Hole Diameter	Hole Diameter	Hole Diameter	Hole Diameter	Hole Diameter	Hole Diameter	Hole Diameter		
14"	14'	1'-0"	1'-0"	1'-0"	1'-0"	2'-2"	-	1'-0"	1'-0"	1'-5"	2'-2"	3'-9"
	18'	1'-0"	1'-0"	1'-5"	3'-1"	4'-6"	-	1'-8"	2'-10"	3'-11"	5'-1"	6'-3"
	22'	1'-5"	2'-9"	4'-1"	5'-6"	7'-0"	-	4'-2"	5'-4"	6'-5"	7'-7"	8'-9"
	26'	3'-8"	5'-0"	6'-5"	8'-0"	9'-8"	-	6'-8"	7'-10"	8'-11"	10'-1"	11'-4"
16"	18'	1'-0"	1'-0"	1'-4"	2'-5"	3'-7"	-	1'-6"	2'-8"	3'-6"	4'-6"	5'-6"
	22'	1'-4"	2'-5"	3'-6"	4'-8"	6'-0"	-	4'-0"	5'-2"	6'-0"	7'-0"	8'-0"
	26'	3'-6"	4'-8"	5'-11"	7'-2"	8'-7"	-	6'-6"	7'-5"	8'-6"	9'-4"	10'-6"
	30'	5'-9"	7'-0"	8'-4"	9'-9"	11'-3"	-	9'-0"	10'-0"	11'-0"	12'-0"	13'-2"

DESIGN ASSUMPTIONS:

- The hole locations listed above are valid for floor joists supporting only uniform loads. The total uniform load shall not exceed 130 plf (e.g. 40 psf Live Load and 25 psf Dead Load spaced 24" oc).
- Hole location is measured from the stable face of bearing to the center of a circular hole, from the closest support.
- Clear Span has not been verified for these joists and is shown for informational purposes only. Verify that the joist selected will work for the span and loading conditions needed before checking hole location.
- The maximum hole depth for circular holes is the joist depth less 4", except the maximum hole depth is 5" for 3-1/2" (R) joists, and 8" for 10-7/8" (R) joists.
- Holes cannot be located in the span where designated "X" without further analysis by a design professional.

NOTES:

- Holes may be placed anywhere within the depth of the joist. A maximum 1/4" clear distance is required between the hole and the flanges.
- Round holes up to 1 1/2" diameter may be placed anywhere in the web.
- Perforated "steels" may be neglected when making web holes.
- Holes larger than 1 1/2" are not permitted in capstems without special engineering.
- Multiple holes shall have a clear separation along the length of the joist of at least twice the length of the larger adjacent hole, or a minimum of 12" center-to-center, whichever is greater.
- Notched joists may be spaced closer together if they fall within the boundary of an acceptable target hole. Example: two 2" round holes aligned parallel to the joist length may be spaced 2" apart (center distance) provided that a 3" high by 8" long rectangle or an 8" diameter round hole are acceptable for the joist depth at that location and completely encloses the holes.
- For conditions not covered on this table, use LPS's design software or contact your local LPS Sales/Engineered Wood Products Distributor for more information.



NOTES:

- These guidelines apply to uniformly loaded beams supported from the Girders Reference Tables in the Uniform Load Tables or designed with LPS design optimization software only. For all other applications, such as beams with concentrated loads, please contact your LPS Sales/Engineered Wood Products distributor for assistance.
- Round holes can be drilled anywhere in "Area A" provided that no more than four holes are cut with the minimum spacing described in the diagram. The maximum hole size is 1 1/2" for depths up to 3' 11", and 2" for depths greater than 3' 11".
- Rectangular holes are NOT allowed.
- NO NOTCHES are allowed without prior approval from the project designer.
- Other hole sizes and configurations MAY be possible with further engineering analysis. For more information, contact your LPS Sales/Engineered Wood Products distributor.
- Up to three 3/4" holes may be drilled in "Area B" to accommodate wiring and/or rebar. These holes shall be at least 12" apart. The holes shall be located in the middle third of the depth, or a minimum of 27" from the bottom and top of the beam. For beams shallower than 9'-1 1/2" include holes at mid-depth.
- Prevent splintering holes from occurring.

Important Notes:

WARNING: Failure to follow engineer provisions for handling, storage and installation may result in unacceptable performance, unsafe conditions and possible injury.

These instructions are reference to a given good practice in the handling, storage and installation of this product. LPS, its distributors, LPS, its distributors, LPS, its designers, its users, however, accept general responsibilities and, in some instances, other additional provisions may be applicable. In all cases, the provisions used must be specified by the architect/engineer responsible for the entire building.

This is not intended as a manual for selecting products, and assumes that components and details have been specified correctly.


For contact your LPS Sales/Engineered Wood Products distributor for assistance.

All on-site blocking, connections and temporary bracing must be installed before construction begins.

No loads other than the weight of the structure are to be imposed on the structure unless a contractor is qualified.

After finishing, do not overload joists with construction materials exceeding design loads.

LPS Sales/Engineered Wood Products, LPS, its distributors, LPS, its designers, its users, however, accept general responsibilities and, in some instances, other additional provisions may be applicable. In all cases, the provisions used must be specified by the architect/engineer responsible for the entire building.



2ND FLOOR FRAMING
SCALE: 1/4" = 1'

2160 Satellite Blvd., Suite 450
Duluth, GA 30097
888-613-5078

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
H10	LP APA 200Plus	2.5	14			7	23'-0"
J5	LP 200Plus	2.5	14			10	25'-0"
J6	LP 200Plus	2.5	14			2	30'-0"
H11	LP 200Plus	2.5	14			8	30'-0"
H15	LP 200Plus	2.5	14			4	18'-0"
J1	LP 200Plus	2.5	14			15	18'-0"
J6	LP 200Plus	2.5	14			1	8'-0"
J2	LP 200Plus	2.5	14			8	4'-0"
H34	LP 200Plus	2.5	14			1	8'-0"

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
H18-A	LP 1.5L 1.55I	3.5	14			1	11'-0"
H18-B	LP 1.5L 1.55I	3.5	14			1	8'-0"
H18-C	LP 1.5L 1.55I	3.5	14			4	25'-0"

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
H18-A	LP 1.5L 1.55I	3.5	9.25			1	8'-0"
H18-B	LP 1.5L 1.55I	3.5	11.875			1	22'-0"
H18-C	LP 1.5L 1.55I	3.5	11.875			1	18'-0"
H18-D	LP 1.5L 1.55I	3.5	11.875			1	10'-0"

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
R1	LP APA Rated GFR 1.125 X 14	1.125	14			17	12'-0"

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
H11	HUS2.5614 (Min)	12.100					
H12	HUS2.5614 (Max)	14.100					

Label	Description	Skew	Slope	Fasteners	Supported Member
H1					
H2					

Dealer
84 Lumber-Fayetteville #2307
620 Bell Road
Fayetteville, NC 28301
(910) 867-9185

Project
CL3048 GR CP CT

Created
March 30, 2015

Layout Name
CL3048 GR CP CT

Description
Cypress Land
CL3048 GR CP CT

Designer
Kyle Miltzer

Revised
March 26, 2020

2nd Floor
Design Method
Building Code
ASD (USA)
IRC 2012

Floor
Loads
Live
Dead
Deflection Joist
LL Span L
TL Span L
LL Cant 2L
TL Cant 2L
LL Span L
TL Span L
LL Cant 2L
TL Cant 2L
Decking
Decking
23/32 APA Rated Stud-
1-Floor
Nailed & Glued

Legend


- Load from Above
- 3.5" Non-Eng Wall
- Wall
- Partition Wall (Non-Load-Bearing)
- LP APA Rated OSB 1.125 X 14
- LP 200Plus 14
- LP 1.5L 1.55E 3.5 X 9.25 (Dropped)
- LP 1.5L 1.55E 3.5 X 11.875 (Dropped)
- LP 1.5L 1.55E 3.5 X 14
- LP 1.5L 1.55E 3.5 X 14
- 1.5 X 9.25 (Dropped)

GENERAL NOTES:

DO NOT CUT OR MODIFY TRUSSES.
 TRUSSES ARE SPACED 24" ON CENTER UNLESS NOTED OTHERWISE.
 REFER TO THE INDIVIDUAL TRUSS DESIGN DRAWINGS FOR THE LOCATION OF LATERAL BRACING AND MULTI-PLY CONNECTION REQUIREMENTS.
 PER ANSI TP1 1-2002 THE TRUSS ENGINEER IS RESPONSIBLE FOR TRUSS TO TRUSS CONNECTIONS AND TRUSS PLY TO PLY CONNECTIONS. THIS TRUSS PLACEMENT PLAN RECOMMENDS TRUSS TO BEARING CONNECTIONS AND TRUSS TO BEAM CONNECTIONS WHICH SHALL BE REVIEWED BY THE BUILDING DESIGNER. IT IS THE RESPONSIBILITY OF THE BUILDING DESIGNER TO RESOLVE ALL ROOF FORCES ADEQUATELY TO THE FOUNDATION.

THIS LAYOUT IS INTENDED FOR THE PURPOSE OF TRUSS LOCATION AND PLACEMENT ONLY. REFER TO THE BUILDING PLANS FOR ACTUAL BUILDING CONSTRUCTION.

ORDER: **Order #**



Hardware List:		
A	9	HUS26
B	-	-
C	-	-
D	-	-
-	-	-
-	-	-
-	-	-

ROOF LOADING:
TOP LIVE: 20 PSF
TOP DEAD: 10 PSF
BOTTOM DEAD: 10 PSF
WIND SPEED: 115 MPH



DEDICATED TO QUALITY AND EXCELLENCE
 200 EMMETT ROAD
 DUNN, NORTH CAROLINA 28334
 PHONE: 910-892-8400

PROJECT:	CL-3034 CP		
CUSTOMER:	Caviness Land		
MODEL:	CL 3034 W/CP GOR		
SCALE:	NOT TO SCALE	P.O. NUMBER:	PO #
DRAWN BY:	User designed roof truss	REV:	SHIP DATE:
			Order # Schd Delivery