
## Harnett County Department of Public Health

## Improvement Permit

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: 376 Mill Bend Dr. (Rawls Ch. Rd. - SR 141 ISSUED TO: Dan Ryan Builders subdivision Olde Mill Village REPAIR 🔲 EXPANSION 🔲 NEW 🔯 Site Improvements required prior to Construction Authorization Issuance: Type of Structure: 50x56 (4bed/2.5ba) Proposed Wastewater System Type: 25% Reduction Sys. Projected Daily Flow: 480 Number of Occupants: 8 \_ max Number of bedrooms: 4\_\_\_\_ Basement Yes ☐ No May be required based on final location and elevations of facilities Pump Required: Yes Type of Water Supply: Community Public Well Distance from well NA feet **⊠** Five years. Permit valid for: ■ No expiration Permit conditions: \_ 62/10/2021 Date: Authorized State Agent:: \_\_ The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their tequirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules . 1950, . 1952, . 1954, . 1955, . 1955, . 1955, . 1958, and . 1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. ISSUED TO: Dan Ryan Builders PROPERTY LOCATION: 376 Mill Bend Dr. (Rawls Ch. Rd. - SR 1 SUBDIVISION Olde Mill Village LOT # 43 Facility Type: 50x56 (4bed/2.5ba) Expansion Basement Fixtures? Yes Basement? Tyes × No 25% MEDICAN STS. (Initial) Wastewater Flow: Type of Wastewater System\*\* GPD (See note below, if applicable ) 25% NEONETON STS -Number of trenches \_\_\_\_3 Installation Requirements/Conditions\_ Trench Spacing: \_\_\_\_\_\_ Exact length of each trench 135 Septic Tank Size 1000 gallons Trenches shall be installed on contour at a Soil Cover: \_\_\_ Pump Tank Size \_\_\_\_\_gallons Maximum Trench Depth of: \_\_\_\_\_ 24\_\_\_ (Maximum soil cover shall not exceed (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: \_\_\_\_\_\_ft. TDH vs. \_\_\_ \_\_\_ \_ inches below pipe inches above pipe Aggregate Depth: \_\_\_\_\_\_ inches total WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. \*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This SEE ATTACHED SITE SKETCH Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. Authorized State Agent: Construction Authorization Expiration Date: \_\_\_\_


## Harnett County Department of Public Health Site Sketch

Property Location: 376 Mill Bend Dr. (Rawl	s Ch. Rd SR 1415)	
Issued To: Dan Ryan Builders	Subdivision Olde Mill Village	Lot # 43
Authorized State Agent:	The same of the sa	Date:
ومريط	onew como	·



This drawing is for illustrative purposes only. System installation must meet all pertinent laws, rules, and regulations.


## Olde Mill Village 4-Bedroom Septic Proposal Lot #43



\*Preliminary Design Not a Permit

System: Gravity to D-Box Lines: 1-3 (405') 0.3 LTAR 24" Trench Bottom Accepted Status System Repair: Gravity to D-Box Lines: 4-6(405') 0.3 LTAR 24" Trench Bottom Accepted Status System

If plumbing is not sufficient a pump and tank may be required to septic drain field.



Adams Soil Consulting 919—414—6761 Job #699