

Estimate

Carter Components - Sanford

298 Harvey Faulk Road

Sanford NC 27332

Phone: FAX:



Quote In:	3/9/2021	Job Number:	21020141
Quote Sent:		Customer Acct #:	TT04189
Order Date:		Job Category:	Roof
Estimator:	PG - Au Do	Sales Rep:	Steve Kuehner
Truss Rep:	Kelly Hudson	Sch. Delivery	
Customer P.O. #			

SOLD TO	J&R Group	Job Name:	2854 Norrington Roof-Marinette	Lot:	2854	Subdiv:	
		Model:	40132WM	Delivery Area:	Richmond		
SHIPP TO	40132WM	Job Notes: 2/24: cancelled per KH. Customer went another direction-JF 3/9: job is reinstated with a different plan name per KH-JF					

Rectangular EWP

Roof Trusses

2.0 RigidLam DF LVL 1-3/4 x 11-7/8

LABEL	SIZE	QTY	LENGTH	NOTE
FB6-2	2.0 RigidLam DF LVL 1-3/4 x 11-7/8	2	4-00-00	
Total: 2.0 RigidLam DF LVL 1-3/4 x 11-7/8			(2)	8-00-00 - L/F
Total: Roof Trusses			(2)	8-00-00 - L/F

Hangers

QTY	TYPE	SIZE	LENGTH	NOTE
12	Hanger	JUS26		
Total:				

Roof Trusses

QTY	TYPE	SIZE	LENGTH	NOTE
2	Hanger	MSH29		
260	Hanger	One RT7A		
2	Hanger	One RT8A		
12	Hanger	One RT16A		
6	Hanger	THD26		
Total: Roof Trusses				

Roof Trusses

DIAGRAM	QTY		LABEL	Shipping		Base Span		OVERHANG		CANTILEVER		STUB	
	PLY	PITCH		(Alternate)	SPAN	LUMBER	LEFT	RIGHT	LEFT	RIGHT	LEFT	RIGHT	
	1	12 /12 12 /12	A01	12-00-00 (11-08-13)	32-00-00	2 x 4	1-00-00	-	-	-	-	-	-
	4	12 /12 12 /12	A02	12-00-00 (11-08-13)	32-00-00	2 x 4	1-00-00	-	-	-	-	-	-
	4	12 /12 12 /12	A03	11-03-01	32-00-00	2 x 4		-	-	-	-	-	-
	1	12 /12 12 /12	B01	10-10-14	26-10-00	2 x 4		-	-	-	-	-	-

Roof Trusses

DIAGRAM	QTY PLY	PITCH	LABEL	Height		LUMBER	OVERHANG		CANTILEVER		STUB	
				Shipping (Alternate)	Base Span SPAN		LEFT	RIGHT	LEFT	RIGHT	LEFT	RIGHT
	1	12 /12 12 /12	B02	10-10-14	26-10-00	2 x 4			-	-	-	-
	2	12 /12 12 /12	B03	10-10-14	26-10-00	2 x 4			-	-	-	-
	3	12 /12	B05	7-10-14	22-02-00	2 x 4			-	-	-	-
	1	12 /12	B06	7-10-14	22-02-00 21-10-08	2 x 4			-	-	3-08	-
	2	12 /12	B07	7-10-14	22-02-00 21-10-08	2 x 4			-	-	3-08	-
	1	12 /12	B08	7-10-14	22-02-00	2 x 4			-	-	-	-
	1	12 /12	B09	7-10-14	22-03-08	2 x 4			-	-	-	-
	1	12 /12	B10	7-10-14	22-03-08	2 x 4			-	-	-	-
	1	12 /12	C01	11-00-00 (10-02-13)	21-00-00	2 x 6 2 x 4	1-00-00	1-00-00	-	-	-	-
	2	12 /12	C02	11-00-00 (10-02-13)	21-00-00	2 x 6 2 x 4	1-00-00	1-00-00	-	-	-	-
	3	12 /12	C03	11-00-00	21-00-00	2 x 6 2 x 4	1-00-00		-	-	-	-
	1	12 /12	C04	11-00-00 (10-03-10)	21-00-00	2 x 6 2 x 4			-	-	-	-
	2	12 /12	C05	11-00-00 (10-03-10)	21-00-00	2 x 6 2 x 4			-	-	-	-
	1	12 /12	C06	11-00-00 (10-03-10)	21-00-00 20-08-00	2 x 6 2 x 4			-	-	-	4-00
	1	12 /12	D01	11-03-01	19-00-00	2 x 4	1-00-00		-	-	-	-
	4	12 /12	D02	11-03-01	19-00-00	2 x 4	1-00-00		-	-	-	-
	1 2-ply	12 /12	D03	11-03-01	19-00-00	2 x 4 2 x 6	1-00-00		-	-	-	-
	1	12 /12	E01	7-10-07	12-04-00	2 x 4	1-00-00	1-00-00	-	-	-	-
	2	12 /12	E02	7-10-07	12-04-00	2 x 4	1-00-00	1-00-00	-	-	-	-
	1	12 /12	E03	7-10-07	12-04-00	2 x 4			-	-	-	-
	1 2-ply	12 /12	E04	7-10-07	12-04-00	2 x 4 2 x 6			-	-	-	-
	3	4 /12	EJ1	1-03-11 (1-01-05)	2-00-00	2 x 4	1-00-00		-	-	-	-
	1	12 /12	F01	11-06-05	17-00-00	2 x 4	1-00-00	1-00-00	-	-	-	-
	1	12 /12	F02	11-06-05	17-00-00	2 x 4	1-00-00	1-00-00	-	-	-	-
	1	12 /12	F03	11-06-05	17-00-00	2 x 4			-	-	-	-
	1	12 /12	G01	7-10-14	11-02-00 11-02-00	2 x 4			-	-	0-00	-

Roof Trusses

DIAGRAM	QTY	PLY	PITCH	LABEL	Height		OVERHANG		CANTILEVER		STUB	
					Shipping (Alternate)	Base Span SPAN	LUMBER	LEFT	RIGHT	LEFT	RIGHT	LEFT
	4		12 /12	G02	7-10-14	11-02-00 11-02-00	2 x 4				0-00	
	1		12 /12	G03	7-10-14	11-02-00	2 x 4					
	2		12 /12	H01	10-10-13 (7-08-08)	7-10-08	2 x 4	1-00-00				
	7		12 /12	H03	11-00-05 (7-09-09)	8-00-00	2 x 4	1-00-00				
	1		12 /12	H04	8-08-05 (7-09-09)	8-00-00	2 x 4	1-00-00				
	2		12 /12	H05	8-08-05 (7-09-09)	8-00-00	2 x 4	1-00-00				
	1		12 /12	H06	8-08-05 (7-09-09)	8-00-00	2 x 4	1-00-00				
	1		2.83 /12	HJ1	1-03-04 (1-01-05)	2-08-07	2 x 4	1-05-00				
	6		4 /12	I01	2-11-11 (2-08-05)	7-00-00	2 x 4	1-00-00				
	1		4 /12	I02	1-11-11 (1-10-11)	7-00-00	2 x 4	1-00-00				
	1		4 /12	I03	2-07-11 (2-06-04)	7-00-00	2 x 4	1-00-00				
	1		4 /12	I04	1-03-11 (1-03-01)	7-00-00	2 x 4	1-00-00				
	2		4 /12	J01	2-11-11 (2-08-05)	7-00-00	2 x 4	1-00-00				
	1		4 /12	J03	2-11-11 (2-08-05)	7-00-00	2 x 4 2 x 6	1-00-00				
	1		0 /12	K01	9-03-14 (5-09-00)	5-09-00	2 x 6					
	1		12 /12	PB01	6-07-02	13-02-03	2 x 4					
	8		12 /12	PB02	6-07-02	13-02-03	2 x 4					
	5		12 /12	PB03	10-09-04 (7-06-04)	10-09-04	2 x 4					
	1		12 /12	PB04	4-10-09	9-09-02	2 x 4					
	12		12 /12	PB05	4-10-09	9-09-02	2 x 4					
	5		12 /12	PB06	4-10-09 (3-04-15)	4-11-09	2 x 4					
	1		12 /12	PB07	4-10-09 (3-04-15)	4-11-09	2 x 4					
	1		12 /12	PB08	2-06-05	5-00-10	2 x 4					
	9		12 /12	PB09	2-06-05	5-00-10	2 x 4					
	1		12 /12	PB10	10-09-04 (7-06-04)	10-09-04	2 x 4					
	1		12 /12	VL01	8-00-00	16-00-00	2 x 4					

Roof Trusses

DIAGRAM	QTY PLY	PITCH	LABEL	Height		LUMBER	OVERHANG		CANTILEVER		STUB	
				Shipping (Alternate)	Base Span SPAN		LEFT	RIGHT	LEFT	RIGHT	LEFT	RIGHT
	2	12 /12	VL02	6-00-00	12-00-00	2 x 4			-	-	-	-
	1	12 /12	VL03	4-00-00	8-00-00	2 x 4			-	-	-	-
	2	12 /12	VL04	2-00-00	4-00-00	2 x 4			-	-	-	-
	1	12 /12	VL05	4-00-00	8-00-00	2 x 4			-	-	-	-
	1	12 /12	VL06	2-00-00	4-00-00	2 x 4			-	-	-	-
	1	12 /12	VL07	5-11-04 (4-02-06)	5-11-04	2 x 4			-	-	-	-
	1	12 /12	VL08	3-11-04 (2-09-07)	3-11-04	2 x 4			-	-	-	-
	1	12 /12	VL09	5-06-08 (3-11-00)	5-06-08	2 x 4			-	-	-	-
	1	12 /12	VL10	3-07-04 (2-06-09)	3-07-04	2 x 4			-	-	-	-
	1	12 /12	VL11	1-07-04 (1-01-10)	1-07-04	2 x 4			-	-	-	-
141					1778.85							

- Price good for 30 days.
- Temporary and permanent bracing by others.

NOTES: 2/24: cancelled per KH. Customer went another direction-JF
 3/9: job is reinstated with a different plan name per KH-JF

	Tax	Not Included
Grand Total		\$15,732.11

Accepted by Seller

BY: _____
 TITLE: _____
 DATE OF ACCEPTANCE: _____

Accepted by Buyer

PURCHASER: _____
 BY: _____ TITLE: _____
 ADDRESS: _____
 PHONE: _____ DATE: _____