

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: MasterFT1
McKee - Nelson II

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Builders FirstSource-Apex,NC.

Pages or sheets covered by this seal: I43307033 thru I43307044

My license renewal date for the state of North Carolina is December 31, 2020.

North Carolina COA: C-0844



October 22,2020

Sevier, Scott

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job	Truss	Truss Type	Qty	Ply	McKee - Nelson II	143307033
MASTERFT1	F01G	ROOF TRUSS	1	1		
Builders FirstSource (Apex, NC), Apex, NC - 27523,						Job Reference (optional)

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Oct 21 14:01:00 2020 Page 1
 ID:vWaSDMfftCgqouPoGL_JAoy3UfR-iEaa1mVl0b2znsfPly_k?xE6BSfsCzeCFauP3lyRAEH

0-1-8

0-1-8

Scale = 1:27.5




Plate Offsets (X,Y)--	[4:0-1-8,Edge], [25:0-1-8,Edge]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.09	Vert(LL) n/a - n/a 999	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.01	Vert(CT) n/a - n/a 999		
BCLL 0.0	Rep Stress Incr NO	WB 0.03	Horz(CT) 0.00 25 n/a n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S		Weight: 73 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 16-7-8.
 (lb) - Max Uplift All uplift 100 lb or less at joint(s) 16
 Max Grav All reactions 250 lb or less at joint(s) 30, 29, 28, 26, 25, 24, 23, 22, 21, 20, 19, 18, 17

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.



- NOTES-**
- All plates are 1.5x3 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 16.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



October 22, 2020

Job	Truss	Truss Type	Qty	Ply	McKee - Nelson II	143307035
MASTERFT1	F03	ROOF TRUSS	6	1		

Builders FirstSource (Apex, NC), Apex, NC - 27523, 8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Oct 21 14:01:02 2020 Page 1
 ID:vWaSDMfftCgqouPoGL_JAoy3UfR-edikSSWZYClg0AposM1C4MKF_F8dgkxViuNW8dyRAEF



LOADING (psf)	SPACING-	CSL	DEFL.	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.91	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.89	Vert(LL) -0.37 16 >594 480	MT20HS	187/143
BCLL 0.0	Rep Stress Incr YES	WB 0.56	Vert(CT) -0.51 15-16 >433 360		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S	Horz(CT) 0.08 12 n/a n/a		
				Weight: 93 lb	FT = 20%F, 11%E


LUMBER-
 TOP CHORD 2x4 SP No.2(flat)
 BOT CHORD 2x4 SP No.2(flat) *Except*
 12-19: 2x4 SP SS(flat)
 WEBS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 21=0-3-8, 12=0-3-8
 Max Grav 21=1009(LC 1), 12=1009(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-2164/0, 3-4=-3554/0, 4-5=-4439/0, 5-6=-4439/0, 6-7=-4311/0, 7-9=-3572/0, 9-10=-2159/0
 BOT CHORD 20-21=0/1266, 18-20=0/3021, 17-18=0/4087, 16-17=0/4439, 15-16=0/4439, 14-15=0/4106, 13-14=0/3015, 12-13=0/1268
 WEBS 10-12=-1588/0, 2-21=-1586/0, 10-13=0/1160, 2-20=0/1169, 9-13=-1115/0, 3-20=-1115/0, 9-14=0/725, 3-18=0/694, 7-14=-696/0, 4-18=-694/0, 7-15=0/425, 4-17=-7737, 6-15=-501/183, 5-17=-267/0

NOTES-
 1) Unbalanced floor live loads have been considered for this design.
 2) All plates are MT20 plates unless otherwise indicated.
 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



October 22, 2020

Job	Truss	Truss Type	Qty	Ply	McKee - Nelson II	143307036
MASTERFT1	F03G	ROOF TRUSS	1	1	Job Reference (optional)	

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Oct 21 14:01:04 2020 Page 1
ID:vWaSDMfftCgqouPoGL_JAoy3UfR-a0p5t8Yp4pYOGUyB_n3g9nPnA30o8mdoACsdCWyRAED

0-1/8

0-1/8

Scale: 3/8"=1'




Plate Offsets (X,Y)-- [4:0-1-8,Edge], [29:0-1-8,Edge]		19-4-8 19-4-8					
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d
TCLL 40.0	Plate Grip DOL	1.00	TC 0.09	Vert(LL)	n/a	-	n/a 999
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a 999
BCLL 0.0	Rep Stress Incr	NO	WB 0.03	Horz(CT)	0.00	18	n/a n/a
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S				
				PLATES	GRIP		
				MT20	244/190		
				Weight: 84 lb	FT = 20%F, 11%E		


LUMBER-
TOP CHORD 2x4 SP No.2(flat)
BOT CHORD 2x4 SP No.2(flat)
WEBS 2x4 SP No.3(flat)
OTHERS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 19-4-8.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 34, 18, 33, 32, 30, 29, 28, 27, 26, 25, 24, 23, 22, 21, 20, 19

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) All plates are 1.5x3 MT20 unless otherwise indicated.
2) Gable requires continuous bottom chord bearing.
3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
4) Gable studs spaced at 1-4-0 oc.
5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails.
Strongbacks to be attached to walls at their outer ends or restrained by other means.



October 22, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	McKee - Nelson II	143307037
MASTERFT1	F03GR	ROOF TRUSS	3	1	Job Reference (optional)	

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Oct 21 14:01:05 2020 Page 1
 ID:vWaSDMfftCgqouPoGL_JAoy3UfR-2CNT4UZr7gFdXNXVavi_ytKTcet_CxOsbAkyyRAEC





Plate Offsets (X,Y)--	[7:0-3-0,Edge], [18:0-3-0,0-0-0], [19:0-3-0,Edge], [24:0-1-8,0-0-8], [25:0-1-8,0-0-8]
-----------------------	---

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.39	Vert(LL)	-0.37	18	>600	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.68	Vert(CT)	-0.50	18	>437	360	MT20HS	187/143
BCLL 0.0	Rep Stress Incr	NO	WB 0.97	Horz(CT)	0.05	13	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S							
									Weight: 144 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP SS(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP SS(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 23=0-3-8, 13=0-3-8
 Max Grav 23=1833(LC 1), 13=1833(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-4278/0, 3-5=-7132/0, 5-6=-8946/0, 6-7=-8946/0, 7-8=-8674/0, 8-10=-7167/0, 10-11=-4270/0
 BOT CHORD 22-23=0/2640, 20-22=0/6056, 19-20=0/8231, 18-19=0/8946, 17-18=0/8946, 16-17=0/8275, 14-16=0/6043, 13-14=0/2644
 WEBS 2-23=-3078/0, 2-22=0/2037, 3-22=-2204/0, 3-20=0/1335, 5-20=-1362/0, 5-19=0/1176, 6-19=-453/0, 11-13=-3083/0, 11-14=0/2022, 10-14=-2199/0, 10-16=0/1393, 8-16=-1375/0, 8-17=0/673, 7-17=-672/25, 7-18=-266/30

- NOTES-**
- Unbalanced floor live loads have been considered for this design.
 - All plates are MT20 plates unless otherwise indicated.
 - All plates are 6x8 MT20 unless otherwise indicated.
 - Magnitude of user added load(s) on this truss have been applied uniformly across all gravity load cases with no adjustments.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 13-23=-10, 1-12=-190(F=90)



October 22, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ENGINEERING BY
TRENCO
 A MiTek Affiliate
 818 Soundside Road
 Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	McKee - Nelson II	I43307038
MASTERFT1	F04G	ROOF TRUSS	1	1	Job Reference (optional)	


Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Oct 21 14:01:06 2020 Page 1
ID: vWaSDMfftCgqouPoGL_JAoy3UfR-WOxrlpZ3cRo6Vn6Z5C58ECU7cti9cg55dWLkHOyRAEB

0-1-β

0-1-β

Scale = 1:17.7




LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.10	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.02	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	NO	WB 0.03	Horz(CT)	0.00	10	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S						
								Weight: 45 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 9-8-0.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 17, 10, 16, 15, 14, 13, 12, 11

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- All plates are 1.5x3 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



October 22, 2020

Job MASTERFT1	Truss F05	Truss Type ROOF TRUSS	Qty 2	Ply 1	McKee - Nelson II Job Reference (optional)	143307039
------------------	--------------	--------------------------	----------	----------	---	-----------

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Oct 21 14:01:08 2020 Page 1
ID:vWaSDMfftCgqouPoGL_JAoy3UfR-Tn3cjVbK722qk5GyDd7cKdaO4gF14XON5qqqLHyRAE9

0-1-8



0-1-8
Scale: 3/4"=1'




Plate Offsets (X,Y)--	[4:0-1-8,Edge], [10:0-1-8,Edge]									
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.42	Vert(LL)	-0.06	8-9	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.59	Vert(CT)	-0.07	8-9	>999	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.24	Horz(CT)	0.01	7	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S						Weight: 45 lb	FT = 20%F, 11%E

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		

REACTIONS. (size) 11=0-3-8, 7=0-3-8
Max Grav 11=457(LC 1), 7=457(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-899/0, 3-4=-899/0, 4-5=-766/0
BOT CHORD 10-11=0/524, 9-10=0/899, 8-9=0/899, 7-8=0/560
WEBS 5-7=-701/0, 2-11=-653/0, 5-8=0/267, 2-10=0/500

NOTES-
1) Unbalanced floor live loads have been considered for this design.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



October 22, 2020

Job MASTERFT1	Truss F05G	Truss Type ROOF TRUSS	Qty 1	Ply 1	McKee - Nelson II Job Reference (optional)	I43307040
------------------	---------------	--------------------------	----------	----------	---	-----------

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Oct 21 14:01:08 2020 Page 1
ID:vWaSDMfftCgqouPoGL_JAoy3UfR-Tn3cjVbK722qk5GyDd7cKdaTAgOk4adN5qqqLHyRAE9

0'-1-8"

0'-1-8"

Scale: 3/4"=1'




Plate Offsets (X,Y)--	[2:0-1-8,Edge], [14:0-1-8,Edge]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.09	Vert(LL) n/a - n/a 999	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.01	Vert(CT) n/a - n/a 999		
BCLL 0.0	Rep Stress Incr NO	WB 0.03	Horz(CT) 0.00 9 n/a n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S		Weight: 41 lb	FT = 20%F, 11%E

LUMBER-

TOP CHORD 2x4 SP No.2(flat)
 BOT CHORD 2x4 SP No.2(flat)
 WEBS 2x4 SP No.3(flat)
 OTHERS 2x4 SP No.3(flat)

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 8-8-0.

(lb) - Max Grav All reactions 250 lb or less at joint(s) 16, 9, 15, 14, 13, 12, 11, 10

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- All plates are 1.5x3 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 1-4-0 oc.
- Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



October 22, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601





818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	McKee - Nelson II	143307041
MASTERFT1	F06	ROOF TRUSS	7	1		

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Oct 21 14:01:09 2020 Page 1
ID: vWaSDMfftCgqouPoGL_JAoy3UfR-xzd_wrcyuMAhMFr8mLfrsq6WQ4YUpwPXJUZOtjyRAE8



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.64	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.81	Vert(LL) -0.28 15-16 >731 480	MT20HS	187/143
BCLL 0.0	Lumber DOL 1.00	WB 0.51	Vert(CT) -0.39 15-16 >532 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.07 12 n/a n/a		
	Code IRC2015/TPI2014			Weight: 87 lb	FT = 20%F, 11%E


LUMBER-
TOP CHORD 2x4 SP No.2(flat)
BOT CHORD 2x4 SP No.2(flat) *Except*
12-18: 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-7-14 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 20=0-3-8, 12=0-3-8
Max Grav 20=947(LC 1), 12=947(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2006/0, 3-4=-3262/0, 4-5=-3921/0, 5-6=-3921/0, 6-7=-3921/0, 7-9=-3262/0, 9-10=-2006/0
BOT CHORD 19-20=0/1184, 17-19=0/2794, 16-17=0/3701, 15-16=0/3921, 14-15=0/3701, 13-14=0/2794, 12-13=0/1184
WEBS 10-12=-1483/0, 2-20=-1482/0, 10-13=0/1070, 2-19=0/1070, 9-13=-1027/0, 3-19=-1026/0, 9-14=0/609, 3-17=0/609, 7-14=-571/0, 4-17=-571/0, 7-15=-91/608, 4-16=-91/607, 5-16=-267/0, 6-15=-267/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) All plates are 3x4 MT20 unless otherwise indicated.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



October 22, 2020

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p>	<p>818 Soundside Road Edenton, NC 27932</p>
---	---

Job	Truss	Truss Type	Qty	Ply	McKee - Nelson II	143307042
MASTERFT1	F06G	ROOF TRUSS	1	1	Job Reference (optional)	

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Oct 21 14:01:10 2020 Page 1
 ID:vWaSDMfftCgqouPoGL_JAoy3UfR-P9BM7BcaffiY_PQKK2A4P2fpIU39YU2gY8JxQAYRAE7

0-1/8

0-1/8

Scale = 1:29.2




Plate Offsets (X,Y)-- [4:0-1-8,Edge], [25:0-1-8,Edge]		17-7-0 17-7-0					
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d
TCLL 40.0	Plate Grip DOL	1.00	TC 0.12	Vert(LL)	n/a	-	n/a 999
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a 999
BCLL 0.0	Rep Stress Incr	NO	WB 0.04	Horz(CT)	0.00	16	n/a n/a
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S				
				PLATES			GRIP
				MT20			244/190
				Weight: 75 lb			FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.2(flat)
 BOT CHORD 2x4 SP No.2(flat)
 WEBS 2x4 SP No.3(flat)
 OTHERS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 17-7-0.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 30, 16, 29, 28, 26, 25, 24, 23, 22, 21, 20, 19, 18, 17

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 2) Gable requires continuous bottom chord bearing.
 - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 4) Gable studs spaced at 1-4-0 oc.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



October 22, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ENGINEERING BY
TRENCO
 A MiTek Affiliate
 818 Soundside Road
 Edenton, NC 27932

Job MASTERFT1	Truss F07GR	Truss Type ROOF TRUSS	Qty 1	Ply 1	McKee - Nelson II Job Reference (optional)	143307043
------------------	----------------	--------------------------	----------	----------	---	-----------

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Oct 21 14:01:11 2020 Page 1
ID:vWaSDMfftCgqouPoGL_JAoy3UfR-tMikLXdCQzQPbY?XulhJxFCn9uHRHkgqno2UycyRAE6





Plate Offsets (X, Y)--	[2:0-3-8,Edge], [10:0-3-8,Edge], [16:0-3-0,Edge], [17:0-3-0,Edge]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.94	Vert(LL) -0.35 16-17 >586 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.52	Vert(CT) -0.48 16-17 >426 360	MT20HS	187/143
BCLL 0.0	Rep Stress Incr NO	WB 0.84	Horz(CT) 0.03 12 n/a n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S		Weight: 110 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP SS(flat)	TOP CHORD Structural wood sheathing directly applied or 3-10-5 oc purlins, except end verticals.
BOT CHORD 2x4 SP SS(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 12=0-1-12, 21=0-3-8
Max Grav 12=1706(LC 1), 21=1706(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-3691/0, 3-4=-6073/0, 4-5=-7292/0, 5-6=-7292/0, 6-7=-7292/0, 7-9=-6073/0, 9-10=-3691/0
BOT CHORD 20-21=0/2300, 18-20=0/5205, 17-18=0/6912, 16-17=0/7292, 15-16=0/6912, 13-15=0/5205, 12-13=0/2300
WEBS 10-12=-2739/0, 2-21=-2739/0, 10-13=0/1772, 2-20=0/1772, 9-13=-1923/0, 3-20=-1923/0, 9-15=0/1103, 3-18=0/1103, 7-15=-1066/0, 4-18=-1066/0, 7-16=0/771, 4-17=0/771, 5-17=-296/0, 6-16=-296/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 12.
 - 4) Magnitude of user added load(s) on this truss have been applied uniformly across all gravity load cases with no adjustments.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 12-21=-10, 1-11=-190(F=90)





October 22, 2020

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p>	<p>ENGINEERING BY TRENCO A MiTek Affiliate</p> <p>818 Soundside Road Edenton, NC 27932</p>
---	---

Job	Truss	Truss Type	Qty	Ply	McKee - Nelson II	143307044
MASTERFT1	F08	ROOF TRUSS	4	1		
						Job Reference (optional)

Builders FirstSource (Apex, NC), Apex, NC - 27523,

8.240 s Mar 9 2020 MiTek Industries, Inc. Wed Oct 21 14:01:12 2020 Page 1
ID:vWaSDMfftCgqouPoGL_JAoy3UfR-LYI6YteqBHYGDiajSTCYUTkx?HXt0GMz?So2U2yRAE5



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 1.00	Vert(LL)	-0.26	16	>796	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.96	Vert(CT)	-0.36	15-16	>580		
BCLL 0.0	Rep Stress Incr	NO	WB 0.56	Horz(CT)	0.05	13	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S						
								Weight: 101 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 4-9-13 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat) *Except* 13-19: 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 20-21,18-20.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 21=0-3-8, 13=0-3-8
Max Grav 21=1736(LC 1), 13=886(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=0/1097, 2-3=0/1097, 3-4=-1162/414, 4-5=-2552/0, 5-6=-3417/0, 6-7=-3417/0,
 7-8=-3417/0, 8-10=-2972/0, 10-11=-1851/0
 BOT CHORD 20-21=-733/272, 18-20=-127/2020, 17-18=0/3071, 16-17=0/3417, 15-16=0/3326,
 14-15=0/2569, 13-14=0/1104
 WEBS 1-21=-1242/0, 3-21=-1554/0, 3-20=0/1175, 4-20=-1134/0, 4-18=0/703, 5-18=-691/0,
 5-17=0/791, 6-17=-338/0, 11-13=-1382/0, 11-14=0/972, 10-14=-936/0, 10-15=0/524,
 8-15=-461/0, 8-16=-280/441

- NOTES-**
- Unbalanced floor live loads have been considered for this design.
 - All plates are 3x4 MT20 unless otherwise indicated.
 - Magnitude of user added load(s) on this truss have been applied uniformly across all gravity load cases with no adjustments.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 500 lb down at 0-2-4 on top chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 13-22=-10, 1-12=-100
 Concentrated Loads (lb)
 Vert: 1=-500(F)




October 22, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601


ENGINEERING BY
TRENCO
 A MiTek Affiliate
 818 Soundside Road
 Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

* Plate location details available in **MITek 20/20 software or upon request.**

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing, Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8
dimensions shown in ft-in-sixteenths
(Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITteK® All Rights Reserved



MITek Engineering Reference Sheet: Mill-7473 rev. 5/19/2020



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T or I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.