Client: Watermark Homes


Project: Address: Date: 11/13/2020


Input by: Anthony Williams Job Name: River Oak - RG25-A07

Project #: J1120-5330

1.750" X 11.875" 2-Ply - PASSED **Kerto-S LVL** GDH-9

\_evel: Level





Page 1 of 6

### Member Information

Type: Plies: 2 Moisture Condition: Dry Deflection LL: 360 Deflection TL: 240 Importance: Normal Temperature: Temp <= 100°F

Application: Floor Design Method: ASD **Building Code: IBC/IRC 2015** Load Sharing: No

Deck: Not Checked

## Reactions UNPATTERNED Ib (Uplift)

Brg	Live	Dead	Snow	Wind	Const
1	0	1696	1400	0	0
2	0	1696	1400	0	0

# **Bearings**

Bearing Length Can React D/L lb Total Ld Case Ld Comb

# **Analysis Results**

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	6803 ft-lb	5'	22897 ft-lb	0.297 (30%)	D+S	L
Unbraced	6803 ft-lb	5'	9857 ft-lb	0.690 (69%)	D+S	L
Shear	2290 lb	1'3 5/8"	10197 lb	0.225 (22%)	D+S	L
LL Defl inch	0.058 (L/1928)	5'	0.312 (L/360)	0.190 (19%)	S	L
TL Defl inch	0.129 (L/872)	5'	0.469 (L/240)	0.280 (28%)	D+S	L

## **Design Notes**

- 1 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 2 Refer to last page of calculations for fasteners required for specified loads.
- 3 Girders are designed to be supported on the bottom edge only.
- 4 Top loads must be supported equally by all plies.
- 5 Top braced at bearings.
- 6 Bottom braced at bearings.
- 7 Lateral slenderness ratio based on single ply width.

Self Weight

Doaring	Longui	oup. I	todot B/L ib	Total	Lu. Ouco	Ed. Comb.
1 - SPF End Grain	4.500"	23%	1696 / 1400	3096	L	D+S
2 - SPF End Grain	4.500"	23%	1696 / 1400	3096	L	D+S

### Load Type ID Trib Width Side Dead 0.9 Wind 1.6 Const. 1.25 Comments Location Live 1 Snow 1.15 1 Uniform Top 50 PLF 0 PLF 0 PLF 0 PLF 0 PLF Uniform 280 PLF 0 PLF 280 PLF 0 PLF 0 PLF ROOF 2 Тор

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive
- Handling & Installation

- LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code
- approvals

  Damaged Beams must not be used Design assumes top edge is laterally restrained
  Provide lateral support at bearing points to avoid
  lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

9 PLF

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

**Manufacturer Info** 

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS



Client: Watermark Homes

Project: Address:

11/13/2020


Input by: Anthony Williams Job Name: River Oak - RG25-A07 Page 2 of 6

Project #: J1120-5330

Date:

1.750" X 11.875" **Kerto-S LVL** 2-Ply - PASSED GDH-9

Level: Level



## Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6"

Capacity	0.0 %
Load	0.0 PLF
Yield Limit per Foot	163.7 PLF
Yield Limit per Fastener	81.9 lb.
Yield Mode	IV
Edge Distance	1 1/2"
Min. End Distance	3"
Load Combination	
Duration Factor	1.00

### Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

# Handling & Installation

- Handling & Installation

  1. UVI beams must not be cut or drilled

  2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

  3. Damaged Beams must not be used

  4. Design assumes top edge is laterally restrained


  5. Provide lateral support at bearing points to avoid lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Manufacturer Info

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS







Client: Watermark Homes


Project: Address: Date: 11/13/2020

Input by: Anthony Williams Job Name: River Oak - RG25-A07

Project #: J1120-5330

**Kerto-S LVL** 1.750" X 9.250" 2-Ply - PASSED HDR1

Level: Level



Application:

Design Method:

**Building Code:** 

Load Sharing:

Deck:


Floor

ASD

No

**IBC/IRC 2015** 

Not Checked



Page 3 of 6

### Member Information

Type: Plies: 2 Moisture Condition: Dry Deflection LL: 360 Deflection TL: 240 Importance: Normal Temperature:

Temp <= 100°F

## Reactions UNPATTERNED Ib (Uplift)

Brg	Live	Dead	Snow	Wind	Const
1	0	1294	1272	0	0
2	0	1294	1272	0	0

# **Bearings**

Bearing Length Cap. React D/L lb Total Ld. Case Ld. Comb. 1-SPF 3.000" 1294 / 1272 2566 L D+S End Grain 2 - SPF 3.000" 1294 / 1272 2566 L D+S End Grain

### **Analysis Results**

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	3382 ft-lb	3'	14423 ft-lb	0.235 (23%)	D+S	L
Unbraced	3382 ft-lb	3'	10944 ft-lb	0.309 (31%)	D+S	L
Shear	1746 lb	11 1/2"	7943 lb	0.220 (22%)	D+S	L
LL Defl inch	0.027 (L/2532)	3'	0.188 (L/360)	0.140 (14%)	S	L
TL Defl inch	0.054 (L/1256)	3'	0.281 (L/240)	0.190 (19%)	D+S	L

## **Design Notes**

- 1 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 2 Refer to last page of calculations for fasteners required for specified loads.
- 3 Girders are designed to be supported on the bottom edge only.
- 4 Top loads must be supported equally by all plies.
- 5 Top braced at bearings.
- 6 Bottom braced at bearings.
- 7 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Top	424 PLF	0 PLF	424 PLF	0 PLF	0 PLF	A01

Self Weight 7 PLF

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

### Handling & Installation

LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals Damaged Beams must not be used

Design assumes top edge is laterally restrained
Provide lateral support at bearing points to avoid
lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Manufacturer Info

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS



Client: Watermark Homes


Project: Address: Date: 11/13/2020


Input by: Anthony Williams Job Name: River Oak - RG25-A07

Project #: J1120-5330

1.750" X 9.250" 2-Ply - PASSED **Kerto-S LVL** HDR1

Level: Level





Page 4 of 6

# Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6"

Capacity	0.0 %
Load	0.0 PLF
Yield Limit per Foot	163.7 PLF
Yield Limit per Fastener	81.9 lb.
Yield Mode	IV
Edge Distance	1 1/2"
Min. End Distance	3"
Load Combination	
Duration Factor	1.00

### Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

# Handling & Installation

- Handling & Installation

  1. UVI beams must not be cut or drilled

  2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

  3. Damaged Beams must not be used

  4. Design assumes top edge is laterally restrained

  5. Provide lateral support at bearing points to avoid lateral displacement and rotation

For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/26/2023

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Manufacturer Info

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS





Client: Watermark Homes


Project: Address: Date: 11/13/2020

Input by: Anthony Williams Job Name: River Oak - RG25-A07 Page 5 of 6

Project #: J1120-5330

**Kerto-S LVL** 1.750" X 11.875" 2-Ply - PASSED **GDH-16** 

Level: Level



### Member Information Reactions UNPATTERNED Ib (Uplift) Application: Brg Wind Type: Floor Live Dead Snow Const Plies: 2 Design Method: ASD 345 1675 0 173 0 1 Moisture Condition: Dry **Building Code: IBC/IRC 2015** 2 345 1675 173 0 0 Deflection LL: 480 Load Sharing: No Deflection TL: 360 Deck: Not Checked Importance: Normal Temperature: Temp <= 100°F **Bearings** Bearing Length Cap. React D/L lb Total Ld. Case Ld. Comb. 1-SPF 6.000" 1675 / 388 D+0.75(L+S) 2063 L End Grain Analysis Results 2-SPF 6.000" 1675 / 388 D+0.75(L+S) 2063 L

End Grain

•						
Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	7851 ft-lb	8'7 1/2"	19911 ft-lb	0.394 (39%)	D+L	L
Unbraced	8019 ft-lb	8'7 1/2"	8032 ft-lb	0.998 (100%)	D+0.75(L+S)	L
Shear	1686 lb	15'9 7/8"	8867 lb	0.190 (19%)	D+L	L
LL Defl inch	0.079 (L/2497)	8'7 9/16"	0.409 (L/480)	0.190 (19%)	0.75(L+S)	L
TL Defl inch	0.418 (L/470)	8'7 9/16"	0.546 (L/360)	0.770 (77%)	D+0.75(L+S)	L

## **Design Notes**

- 1 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 2 Refer to last page of calculations for fasteners required for specified loads.
- 3 Girders are designed to be supported on the bottom edge only.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at a maximum of 12' 3/4" o.c.
- 6 Bottom braced at bearings.
- 7 Lateral slenderness ratio based on single ply width.

	orriodo ramo bacca em emigro	p.,									
ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments	
1	Uniform			Тор	150 PLF	0 PLF	0 PLF	0 PLF	0 PLF	Wall	
2	Uniform			Тор	35 PLF	40 PLF	20 PLF	0 PLF	0 PLF	F+R	
	Self Weight				9 PLF						

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

- Handling & Installation
- LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

  Damaged Beams must not be used
- Design assumes top edge is laterally restrained
  Provide lateral support at bearing points to avoid
  lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

**Manufacturer Info** 

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS



Client: Watermark Homes


Project: Address: 11/13/2020

Input by: Anthony Williams Job Name: River Oak - RG25-A07 Page 6 of 6

Project #: J1120-5330

1.750" X 11.875" 2-Ply - PASSED **Kerto-S LVL GDH-16** 

Level: Level



## Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6"

1 3		`	,
Capacity	0.0 %		
Load	0.0 PLF		
Yield Limit per Foot	163.7 PLF		
Yield Limit per Fastener	81.9 lb.		
Yield Mode	IV		
Edge Distance	1 1/2"		
Min. End Distance	3"		
Load Combination			
Duration Factor	1.00		

### Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

# Handling & Installation

- Handling & Installation

  1. UVI beams must not be cut or drilled

  2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

  3. Damaged Beams must not be used

  4. Design assumes top edge is laterally restrained

  5. Provide lateral support at bearing points to avoid lateral displacement and rotation

For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS



This design is valid until 2/26/2023

Manufacturer Info