

# Job Estimate



**ROOF & FLOOR TRUSSES & BEAMS**

Reilly Road Industrial Park P.O. Box 40408  
Fayetteville, N.C. 28309 (910) 864-TRUS

REQ. QUOTE DATE	/ /	ORDER #	J0221-1067
ORDER DATE	02/18/21	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT #	000127
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	NONE	INVOICE #	
SUPERINTENDANT	NONE	SALES REP	Bob Lewis
JOBSITE PHONE #	( ) -		
DESIGNER	BL	TRACKING	Bob Lewis

<b>SHIPTO</b>	<b>Cash</b> <b>CASH OR CHECKS ONLY</b> <b>NO CREDIT CARDS,</b> <b>( ) -</b>	<b>JOB NAME:</b> RAY & CHRISTINE HYMBAUGH	<b>LOT #</b> 25351	<b>SUBDIV:</b> NC HWY 24/27
	<b>CASH: DONALD MOORE</b> <b>25351 NC HWY 24/27</b> <b>CAMERON, NC</b>	<b>MODEL:</b> ROOF	<b>TAG:</b> HYMBAUGH RESIDENCE	<b>JOB CATEGORY:</b> Residential - Roof
		<b>DELIVERY INSTRUCTIONS:</b>		
		<b>SPECIAL INSTRUCTIONS:</b>		
				<b>PLAN SEAL DATE:</b> NONE

## ROOF TRUSSES

PROFILE	QTY PLY	PITCH		ID	SPAN FT-IN-16	LUMBER		OVERHANG		CANTILEVER		NOTES
		TOP	BOT			TOP	BOT	LEFT	RIGHT	LEFT	RIGHT	
	4	8.00	0.00	A1	35-10-00	2 X 6	2 X 6	01-03-08	01-03-08	00-00-08	00-00-08	
	1	8.00	0.00	A1A	35-10-00	2 X 6	2 X 6	01-03-08	01-03-08	00-00-08	00-00-08	
	1	8.00	5.50	A1B	35-10-00	2 X 6	2 X 6	01-03-08		00-00-08	00-00-08	
	7	8.00	5.50	A1C	35-10-00	2 X 6	2 X 6			00-00-08	00-00-08	
	1	8.00	0.00	A2	35-10-00	2 X 6	2 X 6	01-03-08	01-03-08	00-00-08	00-00-08	
	1	8.00	0.00	A2A	35-10-00	2 X 6	2 X 6	01-03-08	01-03-08	00-00-08	00-00-08	
	1	8.00	0.00	A2B	35-10-00	2 X 6	2 X 6	01-03-08	01-03-08	00-00-08	00-00-08	
	1	8.00	0.00	A3	35-10-00	2 X 6	2 X 6	01-03-08		00-00-08	00-00-08	
	1	8.00	0.00	A3A	35-10-00	2 X 6	2 X 6	01-03-08		00-00-08	00-00-08	
	1 2 Ply	8.00	0.00	A3GR	35-10-00	2 X 6	2 X 6	01-03-08		00-00-08	00-00-08	
	1	8.00	5.50	A4	35-10-00	2 X 6	2 X 6			00-00-08	00-00-08	
	1	8.00	5.50	A4A	35-10-00	2 X 6	2 X 6			00-00-08	00-00-08	
	1	8.00	0.00	A4B	35-10-00	2 X 6	2 X 6			00-00-08	00-00-08	
	1	8.00	0.00	A4C	35-10-00	2 X 6	2 X 6			00-00-08	00-00-08	
	1	8.00	0.00	A4D	35-10-00	2 X 6	2 X 6			00-00-08	00-00-08	
	1	8.00	0.00	A4E	35-10-00	2 X 6	2 X 6	01-03-08		00-00-08	00-00-08	
	1 2 Ply	8.00	0.00	A4GR	35-10-00	2 X 6	2 X 6	01-03-08		00-00-08	00-00-08	
	3	8.00	0.00	B1	23-10-00	2 X 6	2 X 6	01-03-08		00-00-08	00-01-08	
	2	8.00	0.00	B2	23-10-00	2 X 6	2 X 6	01-03-08		00-00-08	00-01-08	
	2	8.00	0.00	B3	23-10-00	2 X 6	2 X 6	01-03-08		00-00-08	00-01-08	
	2	8.00	0.00	B4	23-10-00	2 X 6	2 X 6	01-03-08		00-00-08		
	1 2 Ply	8.00	0.00	B5GR	23-10-00	2 X 6	2 X 6	01-03-08	01-03-08	00-00-08	00-00-08	
	1 2 Ply	8.00	0.00	B6GR	23-10-00	2 X 6	2 X 6	01-03-08		00-00-08	00-01-08	
	3	8.00	0.00	C1	21-00-00	2 X 6	2 X 6	00-10-08	00-10-08	00-05-00	00-05-00	

# Job Estimate



**ROOF & FLOOR  
TRUSSES & BEAMS**

Reilly Road Industrial Park P.O. Box 40408  
Fayetteville, N.C. 28309 (910) 864-TRUS

REQ. QUOTE DATE	/ /	ORDER #	J0221-1067
ORDER DATE	02/18/21	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT #	000127
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	NONE	INVOICE #	
SUPERINTENDANT	NONE	SALES REP	Bob Lewis
JOBSITE PHONE #	( ) -		
DESIGNER	BL	TRACKING	Bob Lewis

<b>SUBTOTAL</b>	<b>Cash</b> <b>CASH OR CHECKS ONLY</b> <b>NO CREDIT CARDS,</b> <b>( ) -</b>	<b>JOB NAME:</b> RAY & CHRISTINE HYMBAUGH <b>LOT #</b> 25351 <b>SUBDIV:</b> NC HWY 24/27 <b>MODEL:</b> ROOF <b>TAG:</b> HYMBAUGH RESIDENCE <b>JOB CATEGORY:</b> Residential - Roof
	<b>CASH: DONALD MOORE</b> <b>25351 NC HWY 24/27</b> <b>CAMERON, NC</b>	<b>DELIVERY INSTRUCTIONS:</b>  <b>SPECIAL INSTRUCTIONS:</b>
		<b>PLAN SEAL DATE: NONE</b>

## ROOF TRUSSES

PROFILE	QTY PLY	PITCH		ID	SPAN FT-IN-16	LUMBER		OVERHANG		CANTILEVER		NOTES
		TOP	BOT			TOP	BOT	LEFT	RIGHT	LEFT	RIGHT	
	1	8.00	0.00	C1GE	21-00-00	2 X 6	2 X 6	00-10-08	00-10-08	00-05-00	00-05-00	
	1	8.00	0.00	C2GE	11-08-00	2 X 6	2 X 6	00-10-08	00-10-08	00-05-00	00-05-00	
	2	8.00	0.00	D1	21-09-08	2 X 6	2 X 6	01-03-08		00-00-08		
	5	8.00	0.00	E1	20-00-00	2 X 6	2 X 6	00-10-08	00-10-08			
	1	8.00	0.00	E1GE	20-00-00	2 X 6	2 X 6	00-10-08	00-10-08			
	1	8.00	0.00	E2	20-00-00	2 X 6	2 X 6					
	1	8.00	0.00	F1	11-09-00	2 X 6	2 X 6	01-03-08		00-00-08		
	1	8.00	0.00	F1GE	11-09-00	2 X 6	2 X 6	01-03-08				
	1	14.42	0.00	QA1	24-00-11	2 X 4	2 X 4					
	1	14.42	14.42	QA2	18-11-08	2 X 4	2 X 4					
	1	14.42	0.00	QA3	09-07-03	2 X 4	2 X 4					
	1	14.42	0.00	QB1	16-00-11	2 X 4	2 X 4					
	1	14.42	14.42	QB2	13-11-08	2 X 4	2 X 4					
	1	8.00	0.00	V1	27-03-10	2 X 4	2 X 4					
	1	8.00	0.00	V2	25-03-10	2 X 4	2 X 4					
	1	8.00	0.00	V3	23-03-10	2 X 4	2 X 4					
	1	8.00	0.00	V4	21-02-05	2 X 4	2 X 4					
	1	8.00	0.00	V5	17-02-05	2 X 4	2 X 4					
	1	8.00	0.00	V6	13-02-05	2 X 4	2 X 4					
	1	8.00	0.00	V7	09-02-05	2 X 4	2 X 4					
	1	8.00	0.00	V8	05-02-05	2 X 4	2 X 4					
	1	8.00	0.00	VA1	15-08-05	2 X 4	2 X 4					
	1	8.00	0.00	VA2	11-08-05	2 X 4	2 X 4					
	1	8.00	0.00	VA3	07-08-05	2 X 4	2 X 4					

## Job Estimate

ROOF & FLOOR  
TRUSSES & BEAMSReilly Road Industrial Park P.O. Box 40408  
Fayetteville, N.C. 28309 (910) 864-TRUS

REQ. QUOTE DATE	/ /	ORDER #	J0221-1067
ORDER DATE	02/18/21	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT #	000127
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	NONE	INVOICE #	
SUPERINTENDANT	NONE	SALES REP	Bob Lewis
JOB SITE PHONE #	( ) -		
DESIGNER	BL	TRACKING	Bob Lewis

SOLD TO	Cash CASH OR CHECKS ONLY NO CREDIT CARDS, ( ) -	JOB NAME: RAY & CHRISTINE HYMBAUGH	LOT # 25351	SUBDIV: NC HWY 24/27
	SHIP TO	CASH: DONALD MOORE 25351 NC HWY 24/27 CAMERON, NC	MODEL: ROOF	TAG: HYMBAUGH RESIDENCE
DELIVERY INSTRUCTIONS:				
SPECIAL INSTRUCTIONS:				
PLAN SEAL DATE: NONE				

## ROOF TRUSSES

PROFILE	QTY PLY	PITCH		ID	SPAN FT-IN-16	LUMBER		OVERHANG		CANTILEVER		NOTES
		TOP	BOT			TOP	BOT	LEFT	RIGHT	LEFT	RIGHT	
	1	8.00	0.00	VA4	03-08-05	2 X 4	2 X 4					
	1	8.00	0.00	VB1	17-03-02	2 X 4	2 X 4					
	1	8.00	0.00	VB2	15-03-02	2 X 4	2 X 4					
	1	8.00	0.00	VB3	12-09-05	2 X 4	2 X 4					
	1	8.00	0.00	VB4	08-09-05	2 X 4	2 X 4					
	1	8.00	0.00	VB5	04-09-05	2 X 4	2 X 4					
	1	8.00	0.00	VC1	05-06-10	2 X 4	2 X 4					
	1	8.00	0.00	VC2	03-06-10	2 X 4	2 X 4					
	1	8.00	0.00	VC3	01-06-10	2 X 4	2 X 4					
	21	8.00	0.00	X1	05-09-08	2 X 6	2 X 6	01-03-08		00-00-08		
	2	8.00	0.00	X1GE	05-09-08	2 X 6	2 X 6	01-03-08				
	1 2 Ply	8.00	0.00	X1GR	05-09-08	2 X 6	2 X 6			00-00-08		
	14	8.00	0.00	X2	03-09-08	2 X 6	2 X 6	01-03-08		00-00-08		
	1 2 Ply	8.00	0.00	X2GR	03-09-08	2 X 6	2 X 6	01-03-08		00-00-08		
	2	8.00	0.00	Y1	03-08-07	2 X 6	2 X 6	01-03-08		00-00-08		
	2	8.00	0.00	Y1A	01-08-07	2 X 6	2 X 6	01-03-08		00-00-08		
	4	8.00	0.00	Y2	01-08-07	2 X 6	2 X 6	01-03-08		00-00-08		
	1	5.66	0.00	Z1	08-00-13	2 X 6	2 X 6	01-09-15				
	2	5.66	0.00	Z2	05-02-14	2 X 6	2 X 6	01-09-15				
	1	Truss Drawings With B-1 and B-3 Bracing And Handling Instructions (Included in truss price)										

ROOF SUB-TOTAL: \$ 18,389.74

## ITEMS

QTY	ITEM TYPE	SIZE	LENGTH FT-IN-16	PART NUMBER	NOTES
3	Hangers, USP	JUS26			SIMPSON (LUS26)

## Job Estimate

ROOF & FLOOR  
TRUSSES & BEAMSReilly Road Industrial Park P.O. Box 40408  
Fayetteville, N.C. 28309 (910) 864-TRUS

REQ. QUOTE DATE	/ /	ORDER #	J0221-1067
ORDER DATE	02/18/21	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT #	000127
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	NONE	INVOICE #	
SUPERINTENDANT	NONE	SALES REP	Bob Lewis
JOBSITE PHONE #	( ) -		
DESIGNER	BL	TRACKING	Bob Lewis

SOLD TO	Cash CASH OR CHECKS ONLY NO CREDIT CARDS, ( ) -	JOB NAME: RAY & CHRISTINE HYMBAUGH MODEL: ROOF TAG: HYMBAUGH RESIDENCE DELIVERY INSTRUCTIONS:	LOT # 25351 SUBDIV: NC HWY 24/27 JOB CATEGORY: Residential - Roof
	SHIP TO	CASH: DONALD MOORE 25351 NC HWY 24/27 CAMERON, NC	SPECIAL INSTRUCTIONS:
PLAN SEAL DATE: NONE			

## ITEMS

QTY	ITEM TYPE	SIZE	LENGTH FT-IN-16	PART NUMBER	NOTES
2	Hangers, USP	JUS26-2			SIMPSON (LUS26-2)
2	LVL Beams (Sized)	LVL, 1-3/4" x 9-1/4" (S)	10-00-00		DB1
2	LVL Beams (Sized)	LVL, 1-3/4" x 9-1/4" (S)	08-00-00		DB2
2	LVL Beams (Sized)	LVL, 1-3/4" x 14" (S)	28-00-00		GDH

ITEMS SUB-TOTAL: \$ 510.26

Please examine this quote, as we agree to furnish at the price herein specified only the articles named and described herein. Prices quoted are valid for jobs released for production within thirty days of date of estimate unless otherwise specified. Additional design time made necessary by incorrect foundation installation or plan changes may require additional charges. This estimate includes sealed engineering of individual truss drawings only. Any requirement for additional engineering services will be billed in quarter hour increments as costs are incurred.	<b>SUB-TOTAL</b>	\$18,900.00
	<b>DELIVERY</b>	\$300.00
	<b>SUB-TOTAL</b>	\$19,200.00
<b>ACCEPTED BY SELLER</b>  BY: _____ TITLE: _____ DATE OF ACCEPTANCE: _____	<b>SALES TAX 7.00%</b>	\$1,323.00
	<b>GRAND TOTAL</b>	<b>\$20523.00</b>
<b>ACCEPTED BY BUYER</b>  PURCHASER: _____ BY: _____ TITLE: _____ ADDRESS: _____ PHONE: _____ DATE: _____		

**WARNING:** As part of this proposal, we warn that trusses can be dangerous and cause property damage or personal injury if improperly installed and / or braced. Customer acceptance hereof shall constitute his affirmative representation to us that he is trained in the proper and safe methods of truss installation and bracing, and will use such methods. Customer acknowledges receipt of instructional pamphlet entitled: 'Bracing Wood Trusses: Commentary and recommendations', HIB-91, as published by the Truss Plate Institute, Inc., and also the engineering drawings showing the required lateral bracing. By his acceptance, Customer agrees, for himself, his agents and employees, to hold Comtech Inc. harmless from any and all actions for property damage, personal injury, or wrongful death resulting from improper installation and / or bracing during erection of the trusses comprehended hereby.