

Harnett County Department of Public Health Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: 530 Pope Lake Road (SR 1566)
 SUBDIVISION _____ LOT # 1
 ISSUED TO: Barefoot Building Company, LLC
 NEW REPAIR EXPANSION
 Type of Structure: 66x54(3bed/3.5ba)
 Proposed Wastewater System Type: 25% Reduction Sys.
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well NA feet
 Permit valid for: Five years No expiration
 Permit conditions: BASED ON 18-5-432182

Authorized State Agent: [Signature] Date: 08/26/2021 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Barefoot Building Company, LLC PROPERTY LOCATION: 530 Pope Lake Road (SR 1566)
 SUBDIVISION _____ LOT # 1
 Facility Type: 66x54(3bed/3.5ba) New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** 25% Reduction System (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable 50% Reduction System (Repair)
 Installation Requirements/Conditions:
 Septic Tank Size 1000 gallons Number of trenches 4
 Exact length of each trench 60 feet
 Pump Tank Size _____ gallons Trenches shall be installed on contour at a
 Maximum Trench Depth of: 18-20 inches
 (Trench bottoms shall be level to +/-1/4" in all directions)
 Trench Spacing: 9 Feet on Center
 Soil Cover: 6-8 inches
 (Maximum soil cover shall not exceed 36" above the trench bottom)
 Pump Requirements: _____ ft. TDH vs. _____ GPM
 Aggregate Depth: NA inches below pipe
NA inches above pipe
NA inches total
 Conditions: Gravity to D-Box Equal Distribution; Sys. flagged onsite

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
 NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.
 Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 08/26/2021
ANDREW CURRIE Construction Authorization Expiration Date: 08/26/2026

Application # SFD2102-0119

Harnett County Department of Public Health Site Sketch

Property Location: 530 Pope Lake Road (SR 1566)

Issued To: Barefoot Building Company, LLC

Subdivision _____

Lot # 1

Authorized State Agent: _____


[Signature]

Date: _____

08/24/2021
~~08/16/2021~~

ANDREW CORNIO
244'

* BASED ON 2018 PERMIT
18-S-432182



[Signature]

NOTE:

- (1) FOLLOW CONSULTANT FLAGS
- (2) CUT SWELL ABOVE SIS AS SHOWN AND ON LEFT/UPPER SIDE

* GRAVITY TO D-BOX
EQUAL DISTRIBUTION

* SIS. FLAGGED ON SITE

* EXT SWELL ALONG LEFT P.L. AND LOW AREA B/H DET. GARAGE. SWELL SHALL CONNECT TO WET AREA BY CUTTING ACROSS REAR AND NOT DRAIN TOWARD SEPTIC AREA

This drawing is for illustrative purposes only. System installation must meet all pertinent laws, rules, and regulations.

EXT RSMT TO POPE LAKE RD (SR 1566)