



Products				
PlotID	Length	Product	Plies	Net Qty
J-35	35' 4"	14" BCI@ 4500s-1.8	1	7
J-35-2	35' 4"	14" BCI@ 4500s-1.8	2	2
J-34	34' 4"	14" BCI@ 4500s-1.8	1	5
J-34-2	34' 4"	14" BCI@ 4500s-1.8	2	2
J-21	21' 6 1/2"	14" BCI@ 4500s-1.8	1	1
J-20	20' 6 1/2"	14" BCI@ 4500s-1.8	1	1
J-17	17' 7"	14" BCI@ 4500s-1.8	1	12
J-17-2	17' 7"	14" BCI@ 4500s-1.8	2	2
J-17A	17' 3 1/2"	14" BCI@ 4500s-1.8	1	7
J-17-2A	17' 3 1/2"	14" BCI@ 4500s-1.8	2	2
J-11	11' 0 1/4"	14" BCI@ 4500s-1.8	1	1
J-10	10' 11 1/4"	14" BCI@ 4500s-1.8	1	1
J-7	7' 4"	14" BCI@ 4500s-1.8	1	1
J-4	4' 1 1/4"	14" BCI@ 4500s-1.8	1	1
J-3	3' 4 1/2"	14" BCI@ 4500s-1.8	1	1
DB1-2	8' 0"	1-3/4" x 9-1/4" VERSA-LAM@ 2.0 3100 SP	2	2
FB1-2	16' 0"	1-3/4" x 14" VERSA-LAM@ 2.0 3100 SP	2	2
GDH	22' 0"	1-3/4" x 18" VERSA-LAM@ 2.0 3100 SP	3	3
RIM1	12' 0"	1" x 14" BC RIM BOARD OSB	1	13
BK1	2' 0"	14" BCI@ 4500s-1.8	1	23

Hangers			
PlotID	Qty	Manuf	Product
H1	11	Simpson	IUS 1.81/14
H2	1	Simpson	IUS 3.56/14

This layout and associated materials list has been prepared based on project plans and/or information provided to Builders FirstSource (BFS). It remains the responsibility of the builder, architect, designer, or other responsible persons to review this information to assure that it is appropriate, accurate, complete and complies with applicable building codes.

- GENERAL NOTES**
- 1.) READ THE INSTALLATION GUIDE BEFORE FRAMING.
  - 2.) ALL WALL SHOWN ARE LOAD BEARING UNLESS NOTES OTHERWISE. WALLS NOT SHOWN HAVE BEEN CONSIDERED NON-LOAD BEARING.
  - 3.) UNLESS STATED OTHERWISE ALL CEILING & BEARING WALLS SUPPORTED BY FOUNDATION FIRST SOURCE LOCATION BEFORE MAKING ANY ALTERATION & ADJUSTMENTS. FAILURE MAY RESULT IN COSTLY REPAIRS.
  - 4.) CONTACT YOUR LOCAL BUILDERS FIRST SOURCE LOCATION BEFORE MAKING ANY ALTERATION & ADJUSTMENTS. FAILURE MAY RESULT IN COSTLY REPAIRS.

<b>H &amp; H HOMES</b>	<b>WAYFARE - GL</b>	2nd FLOOR EWP PLACEMENT PLAN	Builders FirstSource, Central Carolina Markets	DATE: 3-26-18	JOB #
	DRAWN BY: LEE ATKINS				
	SCALE: NTS				

<b>MINIMUM DESIGN DATA</b>
LIVE LOAD 40 PSF
DEAD LOAD 10 PSF
<b>TOTAL LOAD 50 PSF</b>
STRESS DURATION = 100%
DEFLECTION CRITERIA L/480 (MINIMUM)

<b>ARCHITECTURAL PLAN DATE</b> 11-16-17
<b>REVISED ARCH. PLAN DATE</b> XX-XX-XX
<b>SEALED PLAN DATE</b> 12-27-17