Harnett County Department of Public Health

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: 172 Planters Lane (Red Hill Church Rd \$ ISSUED TO: Vicki Wicker / Smith Douglas Homes SUBDIVISION Cane Mill Ests Lot # 18
NEW REPAIR EXPANSION Site Improvements required prior to Construction Authorization Issuance:
Type of Structure: 60x48(3be/3.5ba)w/deck
Proposed Wastewater System Type: 25% Reduction Sys.
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6max
Basement Yes No ———————————————————————————————————
Pump Required: ⊠Yes
" " " T " T " T " T " T " T T T T T T T
Permit conditions: No expiration
Authorized State Agent:: Date: 03/19/2021 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.
Construction Authorization
(Required for Building Permit)
The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance
with the attached system layout.
ISSUED TO: Vicki Wicker / Smith Douglas Home PROPERTY LOCATION: 172 Planters Lane (Red Hill Church Rd. SUBDIVISION Cane Mill Ests LOT # 18
Facility Type: 60x48(3be/3.5ba)w/deck New Expansion Repair
Basement? Yes No Basement Fixtures? Yes No
Type of Wastewater System** 25% NEOUCTION STOTEM (Initial) Wastewater Flow: 366 GPD
(See note below, if applicable)
50% 1202000 PCD15 S75. (Repair)
Installation Requirements/Conditions Number of trenches 4
Septic Tank Size 1000 gallons Exact length of each trench 70 feet Trench Spacing: 9 Feet on Center
Pump Tank Size 1000 gallons Trenches shall be installed on contour at a Soil Cover: E inches
Maximum Trench Depth of:inches (Maximum soil cover shall not exceed
(Trench bottoms shall be level to $\pm 1/4$ " 36" above the trench bottom)
in all directions)
Pump Requirements:ft. TDH vsGPMinches below pipe
Aggregate Depth: inches above pipe
Conditions: PUMP MEDIUM D-BOX ECUAL DISTRIBUTION MA inches total
WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.
**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.
Owner/Legal Representative Signature: Date:
This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This
Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment_and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH
Authorized State Agent: Date: 03/19/2021
Construction Authorization Expiration Date: 03/19/2026

Harnett County Department of Public Health Site Sketch

