

AF 2 - 3CC

Rear covered
Porch

**PLANS DESIGNED TO THE
2018 NORTH CAROLINA STATE
RESIDENTIAL BUILDING CODE**



MEAN ROOF HEIGHT: 19'-9" HEIGHT TO RIDGE: 27'-5"

| CLIMATE ZONE | ZONE 3A | ZONE 4A | ZONE 5A |
|--------------------------|------------|------------|------------|
| FENESTRATION U-FACTOR | 0.35 | 0.35 | 0.35 |
| SKYLIGHT U-FACTOR | 0.55 | 0.55 | 0.55 |
| GLAZED FENESTRATION SHGC | 0.30 | 0.30 | 0.30 |
| CEILING R-VALUE | 38 or 30ci | 38 or 30ci | 38 or 30ci |
| WALL R-VALUE | 15 | 15 | 19 |
| FLOOR R-VALUE | 19 | 19 | 30 |
| BASMENT WALL R-VALUE | 5/13 | 10/13 | 10/13 |
| SLAB R-VALUE | 9 | 10 | 10 |
| CRAWL SPACE WALL R-VALUE | 5/13 | 10/15 | 10/19 |

DESIGNED FOR WIND SPEED OF 130 MPH, 3 SECOND GUST (10) FASTEST MILE EXPOSURE "B"

COMPONENT & CLADDING DESIGNED FOR THE FOLLOWING LOADS


| MEAN ROOF | UP TO 30' | 30'-1" TO 35' | 35'-1" TO 40' | 40'-1" TO 45' |
|-----------|-----------|---------------|---------------|---------------|
| ZONE 1 | 14.2 | -15.0 | 14.9 | -15.8 |
| ZONE 2 | 14.2 | -18.0 | 14.9 | -18.9 |
| ZONE 3 | 14.2 | -18.0 | 14.9 | -18.9 |
| ZONE 4 | 15.5 | -16.0 | 16.3 | -16.8 |
| ZONE 5 | 15.5 | -20.0 | 16.3 | -21.0 |

GUARD RAIL NOTES

SECTION R312
R312.1 Where required. Guards shall be located along open-sided walking surfaces, including stairs, ramps and landings, that are located more than 30 inches (762 mm) measured vertically to the floor or grade below at any point within 36 inches (914 mm) horizontally to the edge of the open side. Insect screening shall not be considered as a guard.
R312.2 Height. Required guards at open-sided walking surfaces, including stairs, porches, balconies or landings, shall be not less than 36 inches (914 mm) high measured vertically above the adjacent walking surface, adjacent fixed seating or the line connecting the leading edges of the treads.
Exceptions:
1. Guards on the open sides of stairs shall have a height not less than 34 inches (864 mm) measured vertically from a line connecting the leading edges of the treads.
2. Where the top of the guard also serves as a handrail on the open sides of stairs, the top of the guard shall not be not less than 34 inches (864 mm) and not more than 38 inches (965 mm) measured vertically from a line connecting the leading edges of the treads.
R312.3 Opening limitations. Required guards shall not have openings from the walking surface to the required guard height which allow passage of a sphere 4 inches (102 mm) in diameter.
Exceptions:
1. The triangular openings at the open side of a stair, formed by the riser, tread and bottom rail of a guard, shall not allow passage of a sphere 6 inches (153 mm) in diameter.
2. Guards on the open sides of stairs shall not have openings which allow passage of a sphere 4 3/8 inches (111 mm) in diameter.

ROOF VENTILATION

SECTION R806
SQUARE FOOTAGE OF ROOF TO BE VENTED = 2,477 SQ.FT.
NET FREE CROSS VENTILATION NEEDED:
WITHOUT 50% TO 80% OF VENTING 3'-0" ABOVE EAVE = 16.51 SQ.FT.
WITH 50% TO 80% OF VENTING 3'-0" ABOVE EAVE, OR WITH CLASS I OR II VAPOR RETARDER ON WARM-IN-WINTER SIDE OF CEILING = 8.26 SQ.FT.



FRONT ELEVATION - A

SCALE 1/4" = 1'-0"

SQUARE FOOTAGE

| HEATED | |
|-------------------|-------------|
| FIRST FLOOR | 1791 SQ.FT. |
| TOTAL | 1791 SQ.FT. |
| HEATED OPTIONAL | |
| CAROLINA ROOM | 148 SQ.FT. |
| TOTAL | 148 SQ.FT. |
| UNHEATED | |
| FRONT PORCH | 188 SQ.FT. |
| GARAGE | 469 SQ.FT. |
| TOTAL | 657 SQ.FT. |
| UNHEATED OPTIONAL | |
| SCREENED PORCH | 160 SQ.FT. |
| DECK OR PATIO | 108 SQ.FT. |
| THIRD GARAGE | 292 SQ.FT. |
| TOTAL | 560 SQ.FT. |


AIR LEAKAGE

Section N1102.4
N1102.4.1 Building thermal envelope. The building thermal envelope shall be durably sealed with an air barrier system to limit infiltration. The sealing methods between dissimilar materials shall allow for differential expansion and contraction. For all homes, where present, the following shall be caulked, gasketed, weather stripped or otherwise sealed with an air barrier material or solid material consistent with Appendix E-2.4 of this code:
1. Blocking and sealing floor/ceiling systems and under knee walls open to unconditioned or exterior space.
2. Capping and sealing shafts or chases, including flue shafts.
3. Capping and sealing soffit or dropped ceiling areas.




WINDOWS WITH SIDE LOAD

SCALE 1/8" = 1'-0"



REAR ELEVATION

SCALE 1/8" = 1'-0"




LEFT SIDE ELEVATION

SCALE 1/8" = 1'-0"



RIGHT SIDE ELEVATION

SCALE 1/8" = 1'-0"



PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS. HAYNES HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTOR PRACTICES AND PROCEDURES. CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION. THESE DRAWINGS ARE INSTRUMENTS OF SERVICE AND AS SUCH SHALL REMAIN PROPERTY OF THE DESIGNER.

ELEVATION - A
The Lauren III

HAYNES WEAVER HOMES

HOME PLANS, INC.
200 BAY 102, WAKE FOREST, NC 27688 919-654-0180 FAX 919-656-4814

| SQUARE FOOTAGE | |
|--------------------------|--------------|
| HEATED | |
| FIRST FLOOR | 1791 SQ. FT. |
| TOTAL | 1791 SQ. FT. |
| HEATED OPTIONAL | |
| CAROLINA ROOM | 148 SQ. FT. |
| TOTAL | 148 SQ. FT. |
| UNHEATED | |
| FRONT PORCH | 188 SQ. FT. |
| GARAGE | 469 SQ. FT. |
| TOTAL | 657 SQ. FT. |
| UNHEATED OPTIONAL | |
| SCREENED PORCH | 160 SQ. FT. |
| DECK OR PATIO | 108 SQ. FT. |
| THIRD GARAGE | 292 SQ. FT. |
| TOTAL | 560 SQ. FT. |

Z:\Builder\Weaver Development Company, Inc.\200220B Lauren III\200220B Lauren III-Left.aec

PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS.
 HAYNES HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTOR'S PRACTICES AND PROCEDURES.
 CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION.
 THESE DRAWINGS ARE INSTRUMENTS OF SERVICE AND AS SUCH SHALL REMAIN PROPERTY OF THE DESIGNER.


FIRST FLOOR PLAN
The Lauren III

HAYNES WEAVER
HOME PLANS, INC.
 910.630.2100 • 910.606.4996

HAYNES WEAVER
HOME PLANS, INC.
 P.O. BOX 702, LIME ROCK, NC 27588 919.454.6180 FAX 1.866.49.4366

| SQUARE FOOTAGE | |
|--------------------------|-------------|
| HEATED | |
| FIRST FLOOR | 1791 SQ.FT. |
| TOTAL | 1791 SQ.FT. |
| HEATED OPTIONAL | |
| CAROLINA ROOM | 148 SQ.FT. |
| TOTAL | 148 SQ.FT. |
| UNHEATED | |
| FRONT PORCH | 188 SQ.FT. |
| GARAGE | 469 SQ.FT. |
| TOTAL | 657 SQ.FT. |
| UNHEATED OPTIONAL | |
| SCREENED PORCH | 160 SQ.FT. |
| DECK OR PATIO | 108 SQ.FT. |
| THIRD GARAGE | 292 SQ.FT. |
| TOTAL | 560 SQ.FT. |

© Copyright 2020
 Haynes Home Plans, Inc.
4/29/2020
2002208
PAGE 3 OF 6



DWELLING / GARAGE SEPARATION

REFER TO SECTIONS R302.5, R302.6, AND R302.7
WALLS. A minimum 1/2" gypsum board must be installed on all walls supporting floor/ceiling assemblies used for separation required by this section.
STAIRS. A minimum of 1/2" gypsum board must be installed on the underside and exposed sides of all stairways.
CEILING. A minimum of 1/2" gypsum must be installed on the garage ceiling if there are no habitable room above the garage. If there are habitable room above the garage a minimum of 5/8" type X gypsum board must be installed on the garage ceiling.
OPENING PENETRATIONS. Openings between the garage and residence shall be equipped with solid wood doors not less than 1 3/8 inches (35 mm) in thickness, solid or honeycomb core steel doors not less than 1 3/8 inches (35 mm) thick, or 20-minute fire-rated doors.
DUCT PENETRATIONS. Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum No. 26 gage (0.48 mm) sheet steel or other approved material and shall have no openings into the garage.
OTHER PENETRATIONS. Penetrations through the separation required in Section R302.6 shall be protected as required by Section R302.11, Item 4.

| SQUARE FOOTAGE | |
|--------------------------|-------------|
| HEATED | |
| FIRST FLOOR | 1791 SQ.FT. |
| TOTAL | 1791 SQ.FT. |
| HEATED OPTIONAL | |
| CAROLINA ROOM | 148 SQ.FT. |
| TOTAL | 148 SQ.FT. |
| UNHEATED | |
| FRONT PORCH | 188 SQ.FT. |
| GARAGE | 469 SQ.FT. |
| TOTAL | 657 SQ.FT. |
| UNHEATED OPTIONAL | |
| SCREENED PORCH | 160 SQ.FT. |
| DECK OR PATIO | 108 SQ.FT. |
| THIRD GARAGE | 292 SQ.FT. |
| TOTAL | 560 SQ.FT. |

FIRST FLOOR PLAN
 SCALE 1/4" = 1'-0"

STRUCTURAL NOTES

All construction shall conform to the latest requirements of the 2018 North Carolina Residential Building Code, plus all local codes and regulations. This document in no way shall be construed to supersede the code.

JOB SITE PRACTICES AND SAFETY: Haynes Home Plans, Inc. assumes no liability for contractor practices and procedures or safety program. Haynes Home Plans, Inc. takes no responsibility for the contractor's failure to carry out the construction work in accordance with the contract documents. All members shall be framed, anchored, and braced in accordance with good construction practice and the building code.

| DESIGN LOADS | LIVE LOAD (PSF) | DEAD LOAD (PSF) | DEFLECTION (L) |
|------------------------------|-----------------|-----------------|----------------|
| Attics without storage | 10 | 10 | L/240 |
| Attics with limited storage | 20 | 10 | L/360 |
| Balconies and decks | 40 | 10 | L/360 |
| Fire escapes | 40 | 10 | L/360 |
| Guardrails and handrails | 200 | -- | -- |
| Guardrail in-fill components | 50 | -- | -- |
| Passenger vehicle garages | 50 | 10 | L/360 |
| Rooms other than sleeping | 40 | 10 | L/360 |
| Sleeping rooms | 30 | 10 | L/360 |
| Snow | 40 | -- | L/360 |
| Snow | 20 | -- | -- |

FRAMING LUMBER: All non treated framing lumber shall be SPF #2 (Fb = 875 PSI) or SYP #2 (Fb = 750 PSI) and all treated lumber shall be SYP #2 (Fb = 750 PSI) unless noted otherwise.

ENGINEERED WOOD BEAMS:
 Laminated veneer lumber (LVL) = Fb=2600 PSI, Fv=285 PSI, E=1,9x10⁶ PSI
 Parallel strand lumber (PSL) = Fb=2900 PSI, Fv=290 PSI, E=2.0x10⁶ PSI
 Laminated strand lumber (LSL) = Fb=2250 PSI, Fv=400 PSI, E=1.5x10⁶ PSI
 Install all connections per manufacturer's instructions.

TRUSSES AND I-JOIST MEMBERS: All roof truss and I-joist layouts shall be prepared in accordance with this document. Trusses and I-joists shall be installed according to the manufacturer's specifications. Any change in truss or I-joist layout shall be coordinated with Haynes Home Plans, Inc.

LINTELS: Brick lintels shall be 3 1/2" x 3 1/2" x 1/4" steel angle for up to 6'-0" span, 6" x 4" x 1/16" steel angle with 6" leg vertical for spans up to 9'-0" unless noted otherwise. 3 1/2" x 3 1/2" x 1/4" steel angle with 1/2" bolts at 2'-0" on center for spans up to 18'-0" unless noted otherwise.

FLOOR SHEATHING: OSB or CDX floor sheathing minimum 1/2" thick for 16" on center joist spacing, minimum 5/8" thick for 19.2" on center joist spacing, and minimum 3/4" thick for 24" on center joist spacing.

ROOF SHEATHING: OSB or CDX roof sheathing minimum 3/8" thick.

CONCRETE AND SOILS: See foundation notes.

ROOF TRUSS REQUIREMENTS

TRUSS DESIGN: Trusses to be designed and engineered in accordance with these drawings. Any variation with these drawings must be brought to Haynes Home Plans, Inc. attention before construction begins.

KNEE WALL AND CEILING HEIGHTS: All finished knee wall heights and ceiling heights are shown furled down 10" from roof decking for insulation. If for any reason the truss manufacturer fails to meet or exceed designated heel heights, finished knee wall heights, or finished ceiling heights shown on these drawings the finished square footage may vary. Any discrepancy must be brought to Haynes Home Plans, Inc. attention, so a suitable solution can be reached before construction begins. Any variation due to these conditions not being met is the responsibility of the truss manufacturer.

ANCHORAGE: All required anchors for trusses due to uplift or bearing shall meet the requirements as specified on the truss schematics.

BEARING: All trusses shall be designed for bearing on SPF #2 plates or ledgers unless noted otherwise.

Plate Heights & Floor Systems: See elevation page(s) for plate heights and floor system thicknesses.

BRACE WALL PANEL NOTES

EXTERIOR WALLS: All exterior walls to be sheathed with CS-WSP or CS-SFB in accordance with section R602.10.3 unless noted otherwise.

GYPSUM: All interior sides of exterior walls and both sides interior walls to have 1/2" gypsum installed. When not using method GB gypsum to be fastened per table R702.3.5. Method GB to be fastened per table R602.10.1.

REQUIRED LENGTH OF BRACING: Required brace wall length for each side of the circumscribed rectangle are interpolated per table R602.10.3. Methods CS-WSP and CS-SFB contribute their actual length. Method GB contributes 0.5 it's actual length. Method PF contributes 1.5 times its actual length.

H01: 800 lbs hold down hold down device fastened to the edge of the brace wall panel closets to the corner.


Methods: Per Table R602.10.1

CS-WSP: Shall be minimum 3/8" OSB or CDX nailed at 6" on center at edges and 12" on center at intermediate supports with 6d common nails or 8d(2 1/2" long x 0.113" diameter).

CS-SFB: Shall be minimum 1/2" structural fiber board nailed at 3" on center at edges and 3" on center at intermediate supports with 1 1/2" long x 0.12" diameter galvanized roofing nails.

GB: Interior walls show as GB are to have minimum 1/2" gypsum board on both sides of the wall fastened at 7" on center at edges and 7" on center at intermediate supports with minimum 5d cooler nails or #6 screws.

PF: Portal frame per figure R602.10.1



PF PORTAL FRAME AT OPENING
 (METHOD PF PER FIGURE AND SECTION R602.10.1)
 SCALE 1/4" = 1'-0"

EXTERIOR HEADERS

(2) 2 X 6 WITH 1 JACK STUD EACH END UNLESS NOTED OTHERWISE

KING STUDS EACH END PER TABLE BELOW

| HEADER SPAN | < 3' | 3'-4' | 4'-8' | 8'-12' | 12'-16' |
|--------------|------|-------|-------|--------|---------|
| KING STUD(S) | 1 | 2 | 3 | 5 | 6 |


INTERIOR HEADERS

LOAD BEARING HEADERS (2) 2 X 6 WITH 1 JACK STUD AND 1 KING STUD EACH END UNLESS NOTED OTHERWISE

NON LOAD BEARING HEADERS TO BE LADDER FRAMED

FIRST FLOOR STRUCTURAL

SCALE 1/4" = 1'-0"



Z:\Builder\Weaver Development Company, Inc\2002208 Lauren III\2002208 Lauren III-Left.aec

PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS. HAYNES HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTOR PRACTICES AND PROCEDURES. CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION. THESE DRAWINGS ARE INSTRUMENT SERVICES AND AS SUCH SHALL REMAIN PROPERTY OF THE DESIGNER.

FIRST FLOOR STRUCTURAL
The Lauren III

HAYNES WEAVER HOMES

HAYNES HOME PLANS, INC.
 910.630.2100 • 919.606.4506
 20,802 02, TAKE FOREVER 919.456.6180 FAX 919.456.4916

| SQUARE FOOTAGE | |
|----------------------------------|--------------|
| HEATED FLOOR | 1791 SQ. FT. |
| TOTAL | 1791 SQ. FT. |
| HEATED OPTIONAL CAROLINA ROOM | 148 SQ. FT. |
| TOTAL | 148 SQ. FT. |
| UNHEATED FRONT PORCH | 188 SQ. FT. |
| SCREENED PORCH | 468 SQ. FT. |
| TOTAL | 656 SQ. FT. |
| UNHEATED OPTIONAL SCREENED PORCH | 60 SQ. FT. |
| DECK OR PATIO | 128 SQ. FT. |
| TOTAL | 128 SQ. FT. |


© Copyright 2020 Haynes Home Plans, Inc.
4/29/2020
2002208
PAGE 4 OF 6

4 X 4 TREATED POST OR EQUIVALENT TYPICAL. ATTACH RAFTERS TO HEADER WITH HURRICANE CONNECTORS (SIMPSON H2.5 OR EQUIVALENT). ATTACH HEADER TO POST AND POST TO BASE WITH POST CAP, METAL STRAPS, AND/OR POST BASE.


ROOF TRUSS REQUIREMENTS

TRUSS DESIGN. Trusses to be designed and engineered in accordance with these drawings. Any variation with these drawings must be brought to Haynes Home Plans, Inc. attention before construction begins.
KNEE WALL AND CEILING HEIGHTS. All finished knee wall heights and ceiling heights are shown turned down 10" from roof decking for insulation. If for any reason the truss manufacturer fails to meet or exceed designated heel heights, finished knee wall heights, or finished ceiling heights shown on these drawings the finished square footage may vary. Any discrepancy must be brought to Haynes Home Plans, Inc. attention, so a suitable solution can be reached before construction begins. Any variation due to these conditions not being met is the responsibility of the truss manufacturer.
ANCHORAGE. All required anchors for trusses due to uplift or bearing shall meet the requirements as specified on the truss schematics.
BEARING. All trusses shall be designed for bearing on SPF #2 plates or lodgers unless noted otherwise.
 Plate Heights & Floor Systems. See elevation page(s) for plate heights and floor system thicknesses.

● HEEL HEIGHT ABOVE FIRST FLOOR PLATE ● HEEL HEIGHT ABOVE SECOND FLOOR PLATE



DORMER WITH ELEVATION - B



ROOF PLAN WITH ELEVATIONS - A & B

SCALE 1/4" = 1'-0"

DORMER WITH ELEVATION - A


PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS. HAYNES HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTOR PRACTICES AND PROCEDURES. CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION. THESE DRAWINGS ARE INSTRUMENTS OF SERVICE AND AS SUCH SHALL REMAIN PROPERTY OF THE PROVIDER.

ROOF PLAN WITH ELEVATIONS - A & B
The Lauren III


HAYNES WEAVER HOMES
 910-630-2100 • 919-606-4606

HAYNES HOME PLANS, INC.
 820 SOUTH WIDE FOREST, WYOMING, NE 68068 • 313-536-0187 FAX: 313-536-8100


| SQUARE FOOTAGE | |
|------------------------------|--------------|
| HEATED FIRST FLOOR | 1791 SQ. FT. |
| HEATED OPTIMAL CAROLINA ROOM | 1791 SQ. FT. |
| UNHEATED FRONT PORCH | 148 SQ. FT. |
| UNHEATED OPTIMAL PORCH | 148 SQ. FT. |
| UNHEATED OPTIMAL RICKS PATIO | 148 SQ. FT. |
| UNHEATED OPTIMAL TOOL SHED | 148 SQ. FT. |
| TOTAL | 3664 SQ. FT. |




A CRAWL SPACE WALL
SCALE 3/4" = 1'-0"




B DROPPED/ FLUSH PIER
SCALE 3/4" = 1'-0"



C CRAWL SPACE AT GARGE
SCALE 3/4" = 1'-0"



D GARAGE STEM WALL
SCALE 3/4" = 1'-0"



E <48" GARAGE WING WALL
SCALE 3/4" = 1'-0"

DECK STAIR NOTES
SECTION AM110
AM110.1 Stairs shall be constructed per Figure AM110. Stringer spans shall be no greater than 7 foot span between supports. Spacing between stringers shall be based upon decking material used per AM107.1. Each Stringer shall have minimum 3 1/2 inches between step out and back of stringer. If used, suspended headers shall be attached with 3/8 inch galvanized bolts with nuts and washers to securely support stringers at the top.





FIGURE AM110
TYPICAL DECK STAIR DETAIL
SCALE 3/4" = 1'-0"

DECK BRACING
SECTION AM109
AM109.1 Deck bracing. Decks shall be braced to provide lateral stability. The following are acceptable means to provide lateral stability.
AM109.1.1 When the deck floor height is less than 4'-0" above finished grade per Figure AM109 and the deck is attached to the structure in accordance with Section AM104, lateral bracing is not required.
AM109.1.2 4 x 4 wood knee braces may be provided on each column in both directions. The knee braces shall attach to each post as a point not less than 1/3 of the post length from the top of the post, and the braces shall be angled between 45 degrees and 60 degrees from the horizontal. Knee braces shall be bolted to the post and the girders/sole band with one 5/8 inch hot dip galvanized bolt with nut and washer at both ends of the brace per Figure AM109.1
AM109.1.3 For freestanding decks without knee braces or diagonal bracing, lateral stability may be provided by embedding the post in accordance with Figure AM109.2 and the following:
TABLE 1: POST SIZE, TRUSS/WALL HEIGHT, MAX. POST HEIGHT, EMBEDMENT DEPTH, CONCRETE DIAMETER

| POST SIZE | TRUSS/WALL HEIGHT | MAX. POST HEIGHT | EMBEDMENT DEPTH | CONCRETE DIAMETER |
|-----------|-------------------|------------------|-----------------|-------------------|
| 4 X 4 | 48 SF | 4'-0" | 2'-6" | 1'-0" |
| 6 X 6 | 120 SF | 6'-0" | 3'-6" | 1'-8" |

AM109.1.4 2 x 6 diagonal vertical cross bracing may be provided in two perpendicular directions for freestanding decks or parallel to the structure at the exterior column line for attached decks. The 2 x 6's shall be attached to the posts with one 5/8 inch hot dip galvanized bolt with nut and washer at each end of each bracing member per Figure AM109.2.
AM109.1.5 For embedment of posts in Coastal Regions, see Chapter 45.




WEEP Screenshot
SCALE 3/4" = 1'-0"




DECK ATTACHMENT DETAIL TO FRAMED WALL
SCALE 3/4" TO 1'-0"

SMOKE ALARMS
SECTION R314
R314.1 Smoke detection and notification. All smoke alarms shall be listed in accordance with UL 217 and installed in accordance with the provisions of this code and the household fire warning equipment provisions of NFPA 72.
R314.2 Smoke detection systems. Household fire alarm systems installed in accordance with NFPA 72 that include smoke alarms, or a combination of smoke detector and audible notification device. Installed as required by this section for smoke alarms, shall be permitted. The household fire alarm system shall provide the same level of smoke detection and alarm as required by this section for smoke alarms. Where a household fire warning system is installed using a combination of smoke detector and audible notification device(s), it shall become a permanent fixture of the occupancy and owned by the homeowner. The system shall be monitored by an approved supervising station and be maintained in accordance with NFPA 72.
Exceptions:
1. In each sleeping room.
2. Outside each separate sleeping area in the immediate vicinity of the bedrooms.
3. On each additional story of the dwelling including basements and habitable attics (finished) but not including garages, unfinished (unfinished) attics and uninhabitable (unfinished) attic stories. In dwellings or dwelling units with split levels and with an interior level fire warning system, a smoke alarm installed on the upper level shall suffice for the adjacent lower level provided that the lower level is less than one full story below the upper level.
Where more than one smoke alarm is required to be installed within an individual dwelling unit, the alarm devices shall be interconnected in such a manner that the actuation of one alarm shall activate all of the alarms in the individual unit.
Where a household fire warning system is installed in accordance with a commercial source, and when primary power is interrupted, shall receive power from a battery. Wiring shall be permanent and without a disconnecting switch other than those required for overcurrent protection. Smoke alarms shall be interconnected.




PORCH HEADER WITH TAPERED COLUMN
SCALE 3/4" = 1'-0"

STAIRWAY NOTES
R311.7
R311.7.1 Headroom. The minimum headroom in all parts of the stairway shall not be less than 6 foot 8 inches (2032 mm) measured vertically from the sloped line adjoining the tread nosing or from the floor surface of the landing or platform on that portion of the stairway.
R311.7.2 Riser height. The maximum riser height shall be 8 1/4 inches (210 mm). The riser shall be measured vertically between leading edges of the adjacent treads.
R311.7.3 Tread depth. The minimum tread depth shall be 9 inches (229 mm). The tread depth shall be measured horizontally between the vertical planes of the foremost projection of adjacent treads and at a right angle to the tread's leading edge. Winder treads shall have a minimum tread depth of 9 inches (229 mm) measured as above at a point 12 inches (305 mm) from the side where the treads are narrower. Winder treads shall have a minimum tread depth of 4 inches (102 mm) at any point.
R311.7.4 Profile. The radius of curvature at the nosing shall be no greater than 9/16 inch (14 mm), a nosing not less than 3/4 inch (19 mm) but not more than 1 1/4 inches (32 mm) shall be provided on stairways with solid risers.
R311.7.5 Handrails. Handrails shall be provided on at least one side of each continuous run of treads or flight with four or more risers.
R311.7.6 Height. Handrail height, measured vertically from the sloped plane adjoining the tread nosing, or finish surface of ramp slope, shall be not less than 34 inches (864 mm) and not more than 38 inches (965 mm).
Exceptions:
1. The use of a volute, turnout or starting casing shall be allowed over the lowest tread.
2. When handrail fittings or bendings are used to provide continuous transition between flights, the transition from handrail to guardrail, or used at the start of a flight, the handrail height at the fittings or bendings shall be permitted to exceed the maximum height.
R311.7.7 Continuity. Handrails for stairways shall be continuous for the full length of the flight, from a point directly above the top riser of the flight to a point directly above the lowest riser of the flight. Handrail ends shall be returned or shall terminate in newel posts or safety terminals. Handrails adjacent to a wall shall have a space of not less than 1 1/2 inch (38 mm) between the wall and the handrails.
Exceptions:
1. Handrails shall be permitted to be interrupted by a newel post.
2. The use of a volute, turnout, starting casing or starting newel shall be allowed over the lowest tread.
3. Two or more separate rails shall be considered continuous if the combination of the two rails over 6 inches (152 mm) of each other, if transitioning between a wall-mounted handrail and a guardrail/handrail, the wall-mounted rail must return into the wall.



TYPICAL WALL DETAIL
SCALE 3/4" = 1'-0"



TYPICAL STAIR DETAIL
SCALE 1/4" = 1'-0"

OWNER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS. HAYNES WEAVER HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTOR PRACTICES AND PROCEDURES. CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGN AUTHORITY'S REVIEW SHOULD BE CONSULTED BEFORE CONSTRUCTION. THESE DRAWINGS ARE PROVIDED FOR GENERAL INFORMATION AND AS SUCH SHALL BE THE PROPERTY OF THE DESIGNER.

TYPICAL DETAILS
The Lauren III

HAYNES WEAVER HOME PLANS, INC.
910-630-2100 • 910-606-4696

SQUARE FOOTAGE
HEATED FLOOR AREA: 1875 SQ. FT.
UNHEATED FLOOR AREA: 1875 SQ. FT.
TOTAL SQUARE FOOTAGE: 3750 SQ. FT.
UNHEATED ATTIC AREA: 148 SQ. FT.
UNHEATED GARAGE AREA: 200 SQ. FT.
TOTAL UNHEATED AREA: 348 SQ. FT.
TOTAL SQUARE FOOTAGE: 4098 SQ. FT.

© Copyright 2020
Haynes Weaver Home Plans, Inc.
4/29/2020
2002208
PAGE 6 OF 6

PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS. HAYNES HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTOR PRACTICES AND PROCEDURES. CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION. THESE DRAWINGS ARE INSTRUMENTS OF SERVICE AND AS SUCH SHALL REMAIN PROPERTY OF THE DESIGNER.

SCREENED PORCH ADDENDUM
The Lauren III

HAYNES WEAVER HOMES
910-630-2100 • 910-606-4636

HAYNES HOME PLANS, INC.
P.O. BOX 102, WISE FOREST, NC 27888 919-659-1180 FAX 988-91-0099

SQUARE FOOTAGE

| | |
|----------------------------------|--------------|
| HEATED FIRST FLOOR | 1791 SQ. FT. |
| HEATED OPTIONAL CAROLINA ROOM | 771 SQ. FT. |
| TOTAL | 2562 SQ. FT. |
| UNHEATED FRONT PORCH | 186 SQ. FT. |
| UNHEATED OPTIONAL SCREENED PORCH | 186 SQ. FT. |
| DECK OR PATIO | 138 SQ. FT. |
| THIRD GARAGE | 202 SQ. FT. |
| TOTAL | 2662 SQ. FT. |


© Copyright 2020 Haynes Home Plans, Inc.
4/29/2020
200220B
ADDENDUM




RIGHT SIDE ELEVATION
SCALE 1/4" = 1'-0"




REAR ELEVATION
SCALE 1/4" = 1'-0"




LEFT SIDE ELEVATION
SCALE 1/4" = 1'-0"




MONOLITHIC SLAB PLAN
SCALE 1/4" = 1'-0"




CRAWL SPACE PLAN
SCALE 1/4" = 1'-0"



STEM WALL SLAB
SCALE 1/4" = 1'-0"




FIRST FLOOR PLAN
SCALE 1/4" = 1'-0"




ROOF PLAN
SCALE 1/4" = 1'-0"

Z:\Builder\Weaver Development Company, Inc\200220B Lauren III\200220B Lauren III-Left.aec




REAR ELEVATION

SCALE 1/8" = 1'-0"



SIDE ELEVATION


SCALE 1/4" = 1'-0"



FRONT ELEVATION


SCALE 1/4" = 1'-0"

SEE BASE PLAN FOR NOTES AND DETAILS




MONOLITHIC SLAB PLAN

SCALE 1/4" = 1'-0"




CRAWL SPACE / STEM WALL

SCALE 1/4" = 1'-0"



ROOF PLAN

SCALE 1/4" = 1'-0"



FIRST FLOOR PLAN

SCALE 1/4" = 1'-0"

PURCHASER MUST VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION BEGINS. HAYNES HOME PLANS, INC. ASSUMES NO LIABILITY FOR CONTRACTORS PRACTICES AND PROCEDURES. CODES AND CONDITIONS MAY VARY WITH LOCATION. A LOCAL DESIGNER, ARCHITECT OR ENGINEER SHOULD BE CONSULTED BEFORE CONSTRUCTION. THESE DRAWINGS ARE INSTRUMENTS OF SERVICE, AND AS SUCH SHALL REMAIN PROPERTY OF THE DESIGNER.

FRONT LOAD THIRD CAR


The Lauren III

HAYNES WEAVER HOME PLANS, INC.
910-630-2100 • 910-606-1616
www.haynesweaver.com

HAYNES WEAVER HOME PLANS, INC.
P.O. BOX 102, LAKE FOREST, NC 27588 • 919-455-1181 FAX 919-455-1435

| SQUARE FOOTAGE | |
|-------------------|--------------|
| HEATED | |
| FIRST FLOOR | 1791 SQ. FT. |
| TOTAL | 1791 SQ. FT. |
| HEATED OPTIONAL | |
| CAROLINA ROOM | 148 SQ. FT. |
| TOTAL | 148 SQ. FT. |
| UNHEATED | |
| FRONT PORCH | 188 SQ. FT. |
| GARAGE | 460 SQ. FT. |
| TOTAL | 648 SQ. FT. |
| UNHEATED OPTIONAL | |
| SCREENED PORCH | 188 SQ. FT. |
| DECK OR PATIO | 228 SQ. FT. |
| THIRD GARAGE | 292 SQ. FT. |
| TOTAL | 688 SQ. FT. |

© Copyright 2020
Haynes Home Plans, Inc.
4/29/2020
2002208
ADDENDUM



▲ = Denotes Left End of Truss
(Reference Engineered Truss Drawing)
Do Not Erect Trusses Backwards

All Truss Reactions are Less than 3,000 lbs. Unless Noted Otherwise.

○ -- Denotes Reaction Greater than 3,000 lbs.

Truss Placement Plan
SCALE: 3/16" = 1'

HANGER LEGEND

| | |
|---|----------------------------------|
| ■ | = USP THD28-2 / Double 2x Hanger |
| ● | = USP HUS26 / Single 2x Hanger |

Beam Legend

| PlotID | Length | Product | Plies | Net Qty |
|--------|--------|-----------------------------|-------|---------|
| BM1 | 8' 0" | 1-3/4"x 9-1/4" LVL Kerto-S | 2 | 2 |
| BM2 | 6' 0" | 1-3/4"x 9-1/4" LVL Kerto-S | 2 | 2 |
| BM4 | 6' 0" | 1-3/4"x 9-1/4" LVL Kerto-S | 2 | 2 |
| GDH-1 | 14' 0" | 1-3/4"x 11-7/8" LVL Kerto-S | 2 | 2 |
| GDH | 23' 0" | 1-3/4"x 14" LVL Kerto-S | 2 | 2 |
| BM3 | 6' 0" | 2x10 SPF No.2 | 2 | 2 |

LOAD CHART FOR JACK STUDS

(BASED ON TABLES R502.5(1) & (2))
NUMBER OF JACK STUDS REQUIRED @ EA END OF HEADS/SPOUSE

| END REACTION (UP TO) (DOWN TO) (TOTAL) HANGER | END REACTION (UP TO) (DOWN TO) (TOTAL) HANGER | END REACTION (UP TO) (DOWN TO) (TOTAL) HANGER |
|---|---|---|
| 1700 | 2550 | 3400 |
| 3400 | 5100 | 6800 |
| 5100 | 7650 | 10200 |
| 6800 | 10200 | 13600 |
| 8500 | 12750 | 17000 |
| 10200 | 15300 | |
| 11900 | | |
| 13600 | | |
| 15300 | | |

| | | | |
|------------------|-----------------------------|-------------------|----------------------------|
| BUILDER | Weaver Development Co. Inc. | CITY / CO. | Johnston County / Johnston |
| JOB NAME | | ADDRESS | |
| PLAN | The Lauren H | MODEL | Roof |
| SEAL DATE | 2/24/20 | DATE REV. | 11/25/20 |
| QUOTE # | Quote # | DRAWN BY | Curtis Quick |
| JOB # | J1020-5083 | SALES REP. | Lenny Norris |

THIS IS A TRUSS PLACEMENT DIAGRAM ONLY.
These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing. The building designer is responsible for temporary and permanent bracing of the roof and floor system and for the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer. For general guidance regarding bracing, consult BCSI-B1 and BCSI-B3 provided with the truss delivery package or online @ sbcindustry.com

Bearing reactions less than or equal to 3000# are deemed to comply with the prescriptive Code requirements. The contractor shall refer to the attached Tables (derived from the prescriptive Code requirements) to determine the minimum foundation size and number of wood studs required to support reactions greater than 3000# but not greater than 15000#. A registered design professional shall be retained to design the support system for any reaction that exceeds those specified in the attached Tables. A registered design professional shall be retained to design the support system for all reactions that exceed 15000#.

Signature: Curtis Quick
Curtis Quick



ROOF & FLOOR TRUSSES & BEAMS

Reilly Road Industrial Park
Fayetteville, N.C. 28309
Phone: (910) 864-8787
Fax: (910) 864-4444




Client: Weaver Development
 Project:
 Address:

Date: 2/8/2021
 Input by: Curtis Quick
 Job Name: The Lauren III Beams
 Project #:

GDH Kerto-S LVL 1.750" X 16.000" 2-Ply - PASSED

Level: Level



Member Information

| | |
|---------------------|---------------|
| Type: | Girder |
| Plies: | 2 |
| Moisture Condition: | Dry |
| Deflection LL: | 480 |
| Deflection TL: | 360 |
| Importance: | Normal |
| Temperature: | Temp <= 100°F |

| | |
|----------------|-------------|
| Application: | Floor |
| Design Method: | ASD |
| Building Code: | IBC 2012 |
| Load Sharing: | No |
| Deck: | Not Checked |

Reactions UNPATTERNED Ib (Uplift)

| Brg | Live | Dead | Snow | Wind | Const |
|-----|------|------|------|------|-------|
| 1 | 0 | 1840 | 1723 | 0 | 0 |
| 2 | 0 | 1840 | 1723 | 0 | 0 |

Bearings

| Bearing | Length | Cap. React | D/L Ib | Total | Ld. Case | Ld. Comb. |
|---------|--------|------------|-------------|-------|----------|-----------|
| 1 - SPF | 3.500" | 68% | 1840 / 1723 | 3564 | L | D+S |
| 2 - SPF | 3.500" | 68% | 1840 / 1723 | 3564 | L | D+S |

Analysis Results

| Analysis | Actual | Location | Allowed | Capacity | Comb. | Case |
|--------------|----------------|-----------|---------------|--------------|-------|------|
| Moment | 16009 ft-lb | 9'5" | 39750 ft-lb | 0.403 (40%) | D+S | L |
| Unbraced | 16009 ft-lb | 9'5" | 16016 ft-lb | 1.000 (100%) | D+S | L |
| Shear | 2976 lb | 17'3 3/8" | 13739 lb | 0.217 (22%) | D+S | L |
| LL Defl inch | 0.213 (L/1035) | 9'5 1/16" | 0.460 (L/480) | 0.460 (46%) | S | L |
| TL Defl inch | 0.441 (L/501) | 9'5 1/16" | 0.613 (L/360) | 0.720 (72%) | D+S | L |

Design Notes

- 1 Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 2 Refer to last page of calculations for fasteners required for specified loads.
- 3 Girders are designed to be supported on the bottom edge only.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at a maximum of 7'4 1/2" o.c.
- 6 Bottom braced at bearings.
- 7 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|-------------|----------|------------|------|----------|--------|-----------|----------|-------------|----------|
| 1 | Uniform | | | Top | 183 PLF | 0 PLF | 183 PLF | 0 PLF | 0 PLF | A4A |
| | Self Weight | | | | 12 PLF | | | | | |

Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive

chemicals

Handling & Installation

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/26/2023

Manufacturer Info

Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
www.metsawood.com/us
 ICC-ES: ESR-3633

Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS







Client: Weaver Development
 Project:
 Address:

Date: 2/8/2021
 Input by: Curtis Quick
 Job Name: The Lauren III Beams
 Project #:

GDH-1 Kerto-S LVL 1.750" X 11.875" 2-Ply - PASSED

Level: Level



Member Information

| | |
|---------------------|---------------|
| Type: | Girder |
| Plies: | 2 |
| Moisture Condition: | Dry |
| Deflection LL: | 480 |
| Deflection TL: | 360 |
| Importance: | Normal |
| Temperature: | Temp <= 100°F |

| | |
|----------------|-------------|
| Application: | Floor |
| Design Method: | ASD |
| Building Code: | IBC 2012 |
| Load Sharing: | No |
| Deck: | Not Checked |

Reactions UNPATTERNED Ib (Uplift)

| Brg | Live | Dead | Snow | Wind | Const |
|-----|------|------|------|------|-------|
| 1 | 0 | 1696 | 1631 | 0 | 0 |
| 2 | 0 | 1696 | 1631 | 0 | 0 |

Bearings

| Bearing | Length | Cap. React | D/L Ib | Total | Ld. Case | Ld. Comb. |
|---------|--------|------------|-------------|-------|----------|-----------|
| 1 - SPF | 3.500" | 64% | 1696 / 1631 | 3327 | L | D+S |
| 2 - SPF | 3.500" | 64% | 1696 / 1631 | 3327 | L | D+S |

Analysis Results

| Analysis | Actual | Location | Allowed | Capacity | Comb. | Case |
|--------------|---------------|----------|---------------|--------------|-------|------|
| Moment | 10893 ft-lb | 7' | 22897 ft-lb | 0.476 (48%) | D+S | L |
| Unbraced | 10893 ft-lb | 7' | 10911 ft-lb | 0.998 (100%) | D+S | L |
| Shear | 2747 lb | 1'2 5/8" | 10197 lb | 0.269 (27%) | D+S | L |
| LL Defl inch | 0.195 (L/832) | 7' 1/16" | 0.339 (L/480) | 0.580 (58%) | S | L |
| TL Defl inch | 0.398 (L/408) | 7' 1/16" | 0.451 (L/360) | 0.880 (88%) | D+S | L |

Design Notes

- 1 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 2 Refer to last page of calculations for fasteners required for specified loads.
- 3 Girders are designed to be supported on the bottom edge only.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at a maximum of 8'2 5/8" o.c.
- 6 Bottom braced at bearings.
- 7 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead | 0.9 | Live | 1 | Snow | 1.15 | Wind | 1.6 | Const. | 1.25 | Comments |
|----|-------------|----------|------------|------|------|-----|------|-----|------|------|------|-----|--------|------|----------|
| 1 | Uniform | | | Top | 233 | PLF | 0 | PLF | 233 | PLF | 0 | PLF | 0 | PLF | G1 |
| | Self Weight | | | | 9 | PLF | | | | | | | | | |

Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive

chemicals

Handling & Installation

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/26/2023

Manufacturer Info

Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
www.metsawood.com/us
 ICC-ES: ESR-3633

Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS







Client: Weaver Development
 Project:
 Address:

Date: 2/8/2021
 Input by: Curtis Quick
 Job Name: The Lauren III Beams
 Project #:

BM1 Kerto-S LVL 1.750" X 9.250" 2-Ply - PASSED

Level: Level



Member Information

| | |
|---------------------|---------------|
| Type: | Girder |
| Plies: | 2 |
| Moisture Condition: | Dry |
| Deflection LL: | 480 |
| Deflection TL: | 360 |
| Importance: | Normal |
| Temperature: | Temp <= 100°F |

| | |
|----------------|-------------|
| Application: | Floor |
| Design Method: | ASD |
| Building Code: | IBC 2012 |
| Load Sharing: | No |
| Deck: | Not Checked |

Reactions UNPATTERNED Ib (Uplift)

| Brg | Live | Dead | Snow | Wind | Const |
|-----|------|------|------|------|-------|
| 1 | 0 | 1987 | 1965 | 0 | 0 |
| 2 | 0 | 1987 | 1965 | 0 | 0 |

Bearings

| Bearing | Length | Cap. React | D/L Ib | Total | Ld. Case | Ld. Comb. |
|---------|--------|------------|-------------|-------|----------|-----------|
| 1 - SPF | 3.500" | 76% | 1987 / 1965 | 3952 | L | D+S |
| 2 - SPF | 3.500" | 76% | 1987 / 1965 | 3952 | L | D+S |

Analysis Results

| Analysis | Actual | Location | Allowed | Capacity | Comb. | Case |
|--------------|----------------|----------|---------------|-------------|-------|------|
| Moment | 5056 ft-lb | 3' | 14423 ft-lb | 0.351 (35%) | D+S | L |
| Unbraced | 5056 ft-lb | 3' | 11027 ft-lb | 0.459 (46%) | D+S | L |
| Shear | 2634 lb | 1' | 7943 lb | 0.332 (33%) | D+S | L |
| LL Defl inch | 0.039 (L/1703) | 3' | 0.139 (L/480) | 0.280 (28%) | S | L |
| TL Defl inch | 0.079 (L/847) | 3' | 0.185 (L/360) | 0.430 (43%) | D+S | L |

Design Notes

- 1 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 2 Refer to last page of calculations for fasteners required for specified loads.
- 3 Girders are designed to be supported on the bottom edge only.
- 4 Top loads must be supported equally by all plies.
- 5 Top braced at bearings.
- 6 Bottom braced at bearings.
- 7 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|-------------|----------|------------|------|----------|--------|-----------|----------|-------------|----------|
| 1 | Uniform | | | Top | 655 PLF | 0 PLF | 655 PLF | 0 PLF | 0 PLF | A2 |
| | Self Weight | | | | 7 PLF | | | | | |

Notes
 Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber
 1. Dry service conditions, unless noted otherwise
 2. LVL not to be treated with fire retardant or corrosive chemicals

Handling & Installation
 1. LVL beams must not be cut or drilled
 2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
 3. Damaged Beams must not be used
 4. Design assumes top edge is laterally restrained
 5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/26/2023

Manufacturer Info
 Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
www.metsawood.com/us
 ICC-ES: ESR-3633

Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS





Client: Weaver Development
 Project:
 Address:

Date: 2/8/2021
 Input by: Curtis Quick
 Job Name: The Lauren III Beams
 Project #:

BM2 Kerto-S LVL 1.750" X 9.250" 2-Ply - PASSED

Level: Level



Member Information

| | |
|---------------------|---------------|
| Type: | Girder |
| Plies: | 2 |
| Moisture Condition: | Dry |
| Deflection LL: | 360 |
| Deflection TL: | 240 |
| Importance: | Normal |
| Temperature: | Temp <= 100°F |

| | |
|----------------|-------------|
| Application: | Floor |
| Design Method: | ASD |
| Building Code: | IBC 2012 |
| Load Sharing: | No |
| Deck: | Not Checked |

Reactions UNPATTERNED Ib (Uplift)

| Brg | Live | Dead | Snow | Wind | Const |
|-----|------|------|------|------|-------|
| 1 | 0 | 1447 | 1425 | 0 | 0 |
| 2 | 0 | 1447 | 1425 | 0 | 0 |

Bearings

| Bearing | Length | Cap. | React D/L Ib | Total | Ld. Case | Ld. Comb. |
|---------|--------|------|--------------|-------|----------|-----------|
| 1 - SPF | 3.500" | 55% | 1447 / 1425 | 2872 | L | D+S |
| 2 - SPF | 3.500" | 55% | 1447 / 1425 | 2872 | L | D+S |

Analysis Results

| Analysis | Actual | Location | Allowed | Capacity | Comb. | Case |
|--------------|----------------|----------|---------------|-------------|-------|------|
| Moment | 3674 ft-lb | 3' | 14423 ft-lb | 0.255 (25%) | D+S | L |
| Unbraced | 3674 ft-lb | 3' | 11027 ft-lb | 0.333 (33%) | D+S | L |
| Shear | 1914 lb | 1' | 7943 lb | 0.241 (24%) | D+S | L |
| LL Defl inch | 0.028 (L/2348) | 3' | 0.185 (L/360) | 0.150 (15%) | S | L |
| TL Defl inch | 0.057 (L/1165) | 3' | 0.277 (L/240) | 0.210 (21%) | D+S | L |

Design Notes

- 1 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 2 Refer to last page of calculations for fasteners required for specified loads.
- 3 Girders are designed to be supported on the bottom edge only.
- 4 Top loads must be supported equally by all plies.
- 5 Top braced at bearings.
- 6 Bottom braced at bearings.
- 7 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|-------------|----------|------------|------|----------|--------|-----------|----------|-------------|----------|
| 1 | Uniform | | | Top | 475 PLF | 0 PLF | 475 PLF | 0 PLF | 0 PLF | a1 |
| | Self Weight | | | | 7 PLF | | | | | |

Notes
 Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber
 1. Dry service conditions, unless noted otherwise
 2. LVL not to be treated with fire retardant or corrosive chemicals

Handling & Installation
 1. LVL beams must not be cut or drilled
 2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
 3. Damaged Beams must not be used
 4. Design assumes top edge is laterally restrained
 5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/26/2023

Manufacturer Info
 Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
www.metsawood.com/us
 ICC-ES: ESR-3633

Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS





Client: Weaver Development
 Project:
 Address:

Date: 2/8/2021
 Input by: Curtis Quick
 Job Name: The Lauren III Beams
 Project #:

BM3 Kerto-S LVL 1.750" X 9.250" 2-Ply - PASSED

Level: Level



Member Information

| | |
|---------------------|---------------|
| Type: | Girder |
| Plies: | 2 |
| Moisture Condition: | Dry |
| Deflection LL: | 480 |
| Deflection TL: | 240 |
| Importance: | Normal |
| Temperature: | Temp <= 100°F |

| | |
|----------------|-------------|
| Application: | Floor |
| Design Method: | ASD |
| Building Code: | IBC 2012 |
| Load Sharing: | No |
| Deck: | Not Checked |

Reactions UNPATTERNED lb (Uplift)

| Brg | Live | Dead | Snow | Wind | Const |
|-----|------|------|------|------|-------|
| 1 | 0 | 883 | 861 | 0 | 0 |
| 2 | 0 | 883 | 861 | 0 | 0 |

Bearings

| Bearing | Length | Cap. React | D/L lb | Total | Ld. Case | Ld. Comb. |
|---------|--------|------------|-----------|-------|----------|-----------|
| 1 - SPF | 3.500" | 33% | 883 / 861 | 1744 | L | D+S |
| 2 - SPF | 3.500" | 33% | 883 / 861 | 1744 | L | D+S |

Analysis Results

| Analysis | Actual | Location | Allowed | Capacity | Comb. | Case |
|--------------|----------------|----------|---------------|-------------|-------|------|
| Moment | 2249 ft-lb | 3' 1/4" | 14423 ft-lb | 0.156 (16%) | D+S | L |
| Unbraced | 2249 ft-lb | 3' 1/4" | 10986 ft-lb | 0.205 (20%) | D+S | L |
| Shear | 1166 lb | 5' 1/2" | 7943 lb | 0.147 (15%) | D+S | L |
| LL Defl inch | 0.017 (L/3840) | 3' 1/4" | 0.140 (L/480) | 0.130 (13%) | S | L |
| TL Defl inch | 0.035 (L/1896) | 3' 1/4" | 0.279 (L/240) | 0.130 (13%) | D+S | L |

Design Notes

- Girders are designed to be supported on the bottom edge only.
- Multiple plies must be fastened together as per manufacturer's details.
- Top loads must be supported equally by all plies.
- Top braced at bearings.
- Bottom braced at bearings.
- Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|-------------|----------|------------|------|----------|--------|-----------|----------|-------------|----------|
| 1 | Uniform | | | Top | 285 PLF | 0 PLF | 285 PLF | 0 PLF | 0 PLF | A4A |
| | Self Weight | | | | 7 PLF | | | | | |

Notes
 Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber
 1. Dry service conditions, unless noted otherwise
 2. LVL not to be treated with fire retardant or corrosive chemicals

Handling & Installation
 1. LVL beams must not be cut or drilled
 2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
 3. Damaged Beams must not be used
 4. Design assumes top edge is laterally restrained
 5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/26/2023

Manufacturer Info
 Metsä Wood
 301 Merritt 7 Building, 2nd Floor
 Norwalk, CT 06851
 (800) 622-5850
www.metsawood.com/us
 ICC-ES: ESR-3633

Comtech, Inc.
 1001 S. Reilly Road, Suite #639
 Fayetteville, NC
 USA
 28314
 910-864-TRUS