



April 21, 2021

C & C Services  
Chad Tyndall  
3782 Tyndall Bridge Road  
Salemberg, NC 28385

Reference: Engineering Services  
Lot 16, Forest Ridge  
173 Tanna Place  
Harnett County, NC  
Project No.: 2101-020310

To Whom It May Concern:

As requested by the client, a representative of Tyndall Engineering & Design, PA (TE&D) has reviewed and analyzed the following project items:

- 1) Recommend a repair for the proposed footing to accommodate the “undercut area” that was encountered within the existing rear wall footing excavation.

The following conclusions and recommendations were noted:

- 1) Based on our conversations with the contractor and supplemental analyses, it was recommended that the section of footing containing the “undercut area” be reinforced with (2) #4 rebars. The reader is referred to the photographs below. The existing “undercut area” excavation may be backfilled with additional concrete. These recommended repairs/enhancements will be structurally adequate to support the anticipated loading conditions.

We appreciate being able to assist you during this phase of the project. If you need further assistance or require additional information, please do not hesitate to contact us.

Sincerely,  
Tyndall Engineering & Design

Prentice A. Tyndall Jr., PE  
PTII| 2001-20310









