

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: J0521-3405
Lot 3 Cypress Rd

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Comtech, Inc - Fayetteville.

Pages or sheets covered by this seal: E15828489 thru E15828502

My license renewal date for the state of North Carolina is December 31, 2021.

North Carolina COA: C-0844



June 11, 2021

Gilbert, Eric

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job	Truss	Truss Type	Qty	Ply	Lot 3 Cypress Rd	E15828489
J0521-3405	ET-1	Floor Supported Gable	1	1	Job Reference (optional)	


Comtech, Inc., Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Fri Jun 11 07:16:42 2021 Page 1
ID:Cx08YMfSk??cVMzGzaSRDzyTIJ-cbWoNbCywt7ARWJkgjE2itO43?Aall1D5PX6X1z7QjJ

0-1-8

0-1-8

Scale = 1:58.4




LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES		GRIP	
TCLL	40.0	Plate Grip DOL	2-0-0	TC	0.08	in	(loc)	l/defl	L/d	MT20	244/190		
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(LL)	n/a	-	n/a	Weight: 142 lb FT = 20%F, 11%E			
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Vert(CT)	n/a	-	n/a				
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-R		Horz(CT)	0.00	30	n/a				

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1 (flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1 (flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3 (flat)		
OTHERS	2x4 SP No.3 (flat)		

REACTIONS. All bearings 34-11-0.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 58, 30, 57, 56, 55, 54, 53, 52, 51, 50, 49, 48, 47, 45, 44, 43, 41, 40, 39, 38, 37, 36, 35, 34, 33, 32, 31

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- All plates are 1.5x3 MT20 unless otherwise indicated.
 - Plates checked for a plus or minus 1 degree rotation about its center.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.





June 11, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 3 Cypress Rd	E15828492
J0521-3405	F02	Floor	3	1	Job Reference (optional)	

Comtech, Inc, Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Fri Jun 11 07:16:48 2021 Page 1
ID:Cx08YMfsk???cVMzGzaSRDzyTJ-Rlt3deHjWjuJ9Rmu0_LsX8e_eQ1piL66UK_QlhZ7QjD



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.53	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.79	Vert(LL) -0.15 20-21 >999 480		
BCLL 0.0	Rep Stress Incr YES	WB 0.57	Vert(CT) -0.20 20-21 >833 360		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S	Horz(CT) 0.04 19 n/a n/a		
				Weight: 168 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. All bearings 0-5-0 except (jt=length) 27=0-3-8, 24=0-5-8, 19=Mechanical.
(lb) - Max Grav All reactions 250 lb or less at joint(s) except 32=662(LC 3), 27=1235(LC 3), 24=1253(LC 4), 19=677(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1961/0, 3-4=-1961/0, 4-5=-1839/0, 5-7=-1839/0, 7-8=0/1061, 8-9=0/1061, 9-10=-269/762, 10-12=0/1098, 12-13=0/1098, 13-14=-1870/0, 14-15=-1870/0, 15-16=-2011/0, 16-17=-2011/0
BOT CHORD 31-32=0/1362, 30-31=0/1839, 29-30=0/1839, 27-29=-122/833, 26-27=-762/269, 25-26=-762/269, 24-25=-762/269, 22-24=-123/832, 21-22=0/1870, 20-21=0/1870, 19-20=0/1386
WEBS 8-27=-299/0, 12-24=-297/0, 9-27=-777/0, 10-24=-800/0, 13-24=-1813/0, 13-22=0/1200, 14-22=-338/0, 17-19=-1491/0, 17-20=0/674, 16-20=-294/0, 15-20=-115/408, 7-27=-1777/0, 7-29=0/1168, 5-29=-338/0, 2-32=-1459/0, 2-31=0/646, 3-31=-318/0, 4-31=-114/444


- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x6 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.



Job	Truss	Truss Type	Qty	Ply	Lot 3 Cypress Rd	E15828493
J0521-3405	F03	Floor	3	1	Job Reference (optional)	

Comtech, Inc, Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Fri Jun 11 07:16:49 2021 Page 1
ID:Cx08YMfSk??cVMzGzaSRDzyTJJ-vxRRr_HLH10AnbL4ahshULB96qNuRpHFj_jzH8z7QjC



5-4-8	6-9-12	7-6-0	8-3-0	13-7-8
5-4-8	1-5-4	0-8-4	0-9-0	5-4-8

Plate Offsets (X,Y)-- [4:0-1-8,Edge], [9:0-1-8,Edge]


LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.54	Vert(LL) -0.18	10-11	>904	480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.80	Vert(CT) -0.23	10-11	>700	360		
BCLL 0.0	Rep Stress Incr YES	WB 0.45	Horz(CT) 0.03	8	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S						
							Weight: 67 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 12=0-5-0, 8=0-3-8
Max Grav 12=729(LC 1), 8=729(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2298/0, 3-4=-2298/0, 4-5=-2264/0, 5-6=-2264/0
BOT CHORD 11-12=0/1531, 10-11=0/2264, 9-10=0/2264, 8-9=0/1528
WEBS 2-12=-1641/0, 2-11=0/828, 3-11=-278/10, 6-8=-1636/0, 6-9=0/898, 5-9=-279/0, 4-11=-327/266

- NOTES-**
- Unbalanced floor live loads have been considered for this design.
 - Plates checked for a plus or minus 1 degree rotation about its center.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



June 11, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 3 Cypress Rd	E15828494
J0521-3405	F04	Floor	4	1	Job Reference (optional)	

Comtech, Inc, Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Fri Jun 11 07:16:50 2021 Page 1
ID:Cx08YMfSk???cVMzGzaSRDzyTIJ-N7?p2K1z1K81OlwH8PNw0ZkkNEj6AHgOxeTXpaz7QjB





Plate Offsets (X,Y)--	[4:0-1-8,Edge], [9:0-1-8,Edge]
-----------------------	--------------------------------

LOADING (psf)	SPACING-	CSL.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.57	Vert(LL) -0.17	10-11	>901	480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.80	Vert(CT) -0.23	10-11	>693	360		
BCLL 0.0	Rep Stress Incr YES	WB 0.44	Horz(CT) 0.03	8	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S					Weight: 66 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 12=0-5-0, 8=Mechanical
Max Grav 12=713(LC 1), 8=719(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2221/0, 3-4=-2221/0, 4-5=-2144/0, 5-6=-2144/0
BOT CHORD 11-12=0/1491, 10-11=0/2144, 9-10=0/2144, 8-9=0/1493
WEBS 2-12=-1598/0, 2-11=0/788, 3-11=-284/0, 6-8=-1607/0, 6-9=0/843, 5-9=-298/0, 4-11=-277/293



- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Plates checked for a plus or minus 1 degree rotation about its center.
 - 3) Refer to girder(s) for truss to truss connections.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) CAUTION, Do not erect truss backwards.



Job	Truss	Truss Type	Qty	Ply	Lot 3 Cypress Rd	E15828495
J0521-3405	F05	FLOOR	1	1	Job Reference (optional)	

Comtech, Inc., Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Fri Jun 11 07:16:51 2021 Page 1
ID:Cx08YMfsk???cVMzGzaSRDzyTJ-rKZBGgJboeGu0vVTI6u9ZmGRbd1ZvgMYAIC4L0z7QjA



Scale = 1:28.5




Plate Offsets (X,Y)--	[8:0-1-8,Edge], [14:Edge,0-1-8], [18:0-1-8,Edge]	9-1-12 9-1-12	10-3-8 1-1-12	16-11-12 6-8-4
-----------------------	--	------------------	------------------	-------------------

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.80	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.85	Vert(LL) -0.24 18-20 >820 480	M18SHS	244/190
BCLL 0.0	Rep Stress Incr NO	WB 0.67	Vert(CT) -0.34 18-20 >597 360		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S	Horz(CT) 0.06 14 n/a n/a		
				Weight: 90 lb	FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP 2400F 2.0E(flat) *Except* 19-22: 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 22=0-5-0, 14=Mechanical
Max Grav 22=977(LC 1), 14=1169(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2075/0, 3-4=-3469/0, 4-5=-3469/0, 5-7=-4163/0, 7-8=-4163/0, 8-9=-3840/0,
9-10=-3850/0, 10-12=-2564/0
BOT CHORD 21-22=0/1228, 20-21=0/2888, 18-20=0/3891, 17-18=0/4163, 16-17=0/4163, 15-16=0/3654,
14-15=0/1468
WEBS 2-22=-1538/0, 2-21=0/1102, 3-21=-1059/0, 3-20=0/741, 5-20=-538/0, 5-18=0/704,
12-14=-1842/0, 12-15=0/1402, 10-15=-1410/0, 9-16=-15/268, 8-16=-637/113,
7-18=-306/0

- NOTES-**
- Unbalanced floor live loads have been considered for this design.
 - All plates are MT20 plates unless otherwise indicated.
 - Plates checked for a plus or minus 1 degree rotation about its center.
 - Refer to girder(s) for truss to truss connections.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 391 lb down at 13-5-12 on top chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 14-22=-10, 1-13=-100
Concentrated Loads (lb)
Vert: 24=-311(B)



Job	Truss	Truss Type	Qty	Ply	Lot 3 Cypress Rd	E15828496
J0521-3405	F06	FLOOR	3	1	Job Reference (optional)	

Comtech, Inc., Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Fri Jun 11 07:16:52 2021 Page 1
ID:Cx08YMfsk???cVMzGzaSRDzyTIJ-JW7aT0KDZyOle24FqPO6_pdj1MGeAXhPyduSz7Qj9





Plate Offsets (X,Y)--	[8:0-1-8,Edge], [17:0-1-8,Edge]	9-1-12 9-1-12	10-3-8 1-1-12	16-11-12 6-8-4
-----------------------	---------------------------------	------------------	------------------	-------------------

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.71	Vert(LL) -0.27	17-19	>749	480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.95	Vert(CT) -0.37	17-19	>545	360	M18SHS	244/190
BCLL 0.0	Rep Stress Incr YES	WB 0.48	Horz(CT) 0.06	13	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S						
							Weight: 86 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 2-2-0 oc bracing: 17-19,16-17.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 21=0-5-0, 13=Mechanical
Max Grav 21=914(LC 1), 13=920(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1916/0, 3-4=-3163/0, 4-5=-3163/0, 5-7=-3626/0, 7-8=-3626/0, 8-9=-3133/0, 9-10=-3133/0, 10-11=-1921/0
 BOT CHORD 20-21=0/1144, 19-20=0/2659, 17-19=0/3500, 16-17=0/3626, 15-16=0/3626, 14-15=0/2655, 13-14=0/1146
 WEBS 2-21=-1433/0, 2-20=0/1004, 3-20=-968/0, 3-19=0/643, 5-19=-430/0, 5-17=-147/527, 11-13=-1438/0, 11-14=0/1008, 10-14=-956/0, 10-15=0/610, 8-15=-888/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) All plates are 3x6 MT20 unless otherwise indicated.
 - 4) Plates checked for a plus or minus 1 degree rotation about its center.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 7) CAUTION, Do not erect truss backwards.




June 11, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 3 Cypress Rd	E15828497
J0521-3405	F07	Floor	3	1	Job Reference (optional)	

Comtech, Inc., Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Fri Jun 11 07:16:53 2021 Page 1
ID:Cx08YMfsk???cVMzGzaSRDzyTIJ-nihyhLKrkFWcFCfspXxdeBL4RIONc7rdchBQvz7Qj8



Scale = 1:34.9




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [2:0-1-8,Edge], [3:0-1-8,Edge], [8:0-1-8,Edge], [15:0-1-8,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.42	Vert(LL)	-0.16 13-14	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.76	Vert(CT)	-0.20 13-14	>798	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.52	Horz(CT)	0.03 12	n/a	n/a		
BCDL 5.0	Code	IRC2015/TPI2014	Matrix-S					Weight: 103 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 20=Mechanical, 17=0-5-8, 12=Mechanical
Max Grav 20=359(LC 3), 17=1266(LC 1), 12=716(LC 7)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-565/84, 3-4=0/678, 4-5=0/678, 5-7=-2157/0, 7-8=-2157/0, 8-9=-2193/0, 9-10=-2193/0
BOT CHORD 19-20=-84/565, 18-19=-84/565, 17-18=-84/565, 15-17=0/1245, 14-15=0/2157, 13-14=0/2157, 12-13=0/1485
WEBS 4-17=-279/0, 2-20=-606/90, 3-17=-967/0, 10-12=-1597/0, 10-13=0/765, 9-13=-277/16, 5-17=-1734/0, 5-15=0/1096, 7-15=-319/0, 8-13=-247/301

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x6 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.



June 11, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Lot 3 Cypress Rd	E15828498
J0521-3405	F08	Floor	3	1	Job Reference (optional)	

Comtech, Inc, Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Fri Jun 11 07:16:54 2021 Page 1
 ID:Cx08YMfsk???cVMzGzaSRDzyTIJ-FvFKuhLU5ZeTtME2NFsBPu?mr2t62?_sGRkylz7Qj7



Scale = 1:29.0




Plate Offsets (X,Y)--	[1:Edge,0-1-8], [4:0-1-8,Edge], [9:0-1-8,Edge], [10:0-1-8,Edge], [17:0-1-8,Edge]
	14-5-8 14-5-8
	17-4-12 2-11-4

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 40.0	Plate Grip DOL	1.00	TC 0.61	Vert(LL)	-0.23	18-19	>733	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.94	Vert(CT)	-0.31	18-19	>558	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.61	Horz(CT)	0.03	15	n/a	n/a		
BCDL 5.0	Code	IRC2015/TPI2014	Matrix-S							
									Weight: 89 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 20=Mechanical, 15=0-5-8, 12=Mechanical
 Max Uplift 12=-240(LC 3)
 Max Grav 20=730(LC 10), 15=1285(LC 1), 12=99(LC 7)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-2277/0, 3-4=-2277/0, 4-5=-2178/0, 5-7=-2178/0, 7-8=0/949, 8-9=0/941, 9-10=-35/391
 BOT CHORD 19-20=0/1521, 18-19=0/2178, 17-18=0/2178, 15-17=0/999, 14-15=-391/35, 13-14=-391/35, 12-13=-391/35
 WEBS 2-20=-1636/0, 2-19=0/816, 3-19=-280/0, 7-15=-1852/0, 7-17=0/1281, 5-17=-370/0, 9-15=-721/0, 10-12=-46/520



- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 3x6 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 240 lb uplift at joint 12.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 7) CAUTION, Do not erect truss backwards.



Job	Truss	Truss Type	Qty	Ply	Lot 3 Cypress Rd	E15828499
J0521-3405	F09	Floor	4	1	Job Reference (optional)	

Comtech, Inc, Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Fri Jun 11 07:16:55 2021 Page 1
ID:Cx08YMfSk??cVMzGzaSRDzyTlJ-j5oi51M6stmKVWoExyz5jcRC1FR?rXY85wAlUnz7Qj6



6-3-2	7-1-12	13-10-12
6-3-2	0-10-10	6-9-0


Plate Offsets (X,Y)-- [4:0-1-8,Edge], [11:0-1-8,Edge]										
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 40.0	Plate Grip DOL	1.00	TC 0.45	Vert(LL)	-0.17	9-10	>991	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.76	Vert(CT)	-0.21	9-10	>777	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.46	Horz(CT)	0.03	8	n/a	n/a		
BCDL 5.0	Code	IRC2015/TPI2014	Matrix-S							
									Weight: 68 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 12=0-5-8, 8=Mechanical
Max Grav 12=744(LC 1), 8=751(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2400/0, 3-4=-2400/0, 4-5=-2363/0, 5-6=-2363/0
BOT CHORD 11-12=0/1566, 10-11=0/2400, 9-10=0/2400, 8-9=0/1572
WEBS 2-12=-1678/0, 2-11=0/954, 3-11=-265/0, 6-8=-1691/0, 6-9=0/854, 5-9=-261/47, 4-9=-410/227

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Plates checked for a plus or minus 1 degree rotation about its center.
 - 3) Refer to girder(s) for truss to truss connections.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) CAUTION, Do not erect truss backwards.




Job	Truss	Truss Type	Qty	Ply	Lot 3 Cypress Rd	E15828500
J0521-3405	FG	Floor Girder	1	1	Job Reference (optional)	

Comtech, Inc, Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Fri Jun 11 07:16:55 2021 Page 1

ID:Cx08Ymjsk??cVMzGzaSRDzyTj-j5oi51M6stmKVWoExyz5jcRl8FaArcX85wAlUnz7Qj6



Scale = 1:8.6

Plate Offsets (X,Y)-- [9:0-1-8,0-1-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.12	Vert(LL)	-0.00	6	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.17	Vert(CT)	-0.01	6	>999	360		
BCLL 0.0	Rep Stress Incr	NO	WB 0.14	Horz(CT)	0.00	5	n/a	n/a		
BCDL 5.0	Code	IRC2015/TPI2014	Matrix-S						Weight: 25 lb	FT = 20%F, 11%E

LUMBER-
 TOP CHORD 2x4 SP No.1(flat)
 BOT CHORD 2x4 SP No.1(flat)
 WEBS 2x4 SP No.3(flat)

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 3-2-8 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 8=Mechanical, 5=0-3-8
 Max Grav 8=411(LC 1), 5=527(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-478/0
 BOT CHORD 7-8=0/478, 6-7=0/478, 5-6=0/478
 WEBS 3-5=-611/0, 2-8=-620/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Plates checked for a plus or minus 1 degree rotation about its center.
 - 3) Refer to girder(s) for truss to truss connections.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) CAUTION, Do not erect truss backwards.
 - 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 658 lb down at 1-10-4 on top chord. The design/selection of such connection device(s) is the responsibility of others.
 - 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 5-8=-10, 1-4=-100
 Concentrated Loads (lb)
 Vert: 3=-619(B)



June 11, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601


ENGINEERING BY
TRENCO
 A MiTek Affiliate
 818 Soundside Road
 Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Lot 3 Cypress Rd	E15828501
J0521-3405	FW1	Floor	1	1		


Comtech, Inc, Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Fri Jun 11 07:16:57 2021 Page 1

ID:Cx08YMfSk??cVMzGzaSRDzyTIJ-gUwTWjOMOU02kqyd2N?Zp1WeE2HYJYaQYEfOZgz7Qj4



Scale = 1:28.7



2-5-0	3-4-4-3-5-12	17-3-0
2-5-0	0-11-4 0-1-8	13-9-4

Plate Offsets (X,Y)-- [1:Edge,0-1-8], [2:0-1-8,Edge], [3:0-1-8,Edge], [25:0-1-8,Edge]


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.09	Vert(LL)	-0.00	29	>999	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.05	Vert(CT)	-0.00	29	>999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.04	Horz(CT)	0.00	16	n/a		
BCDL 5.0	Code	IRC2015/TPI2014	Matrix-S						
								Weight: 83 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 26-27,25-26.
WEBS 2x4 SP No.3(flat)	

REACTIONS. All bearings 13-10-12 except (jt=length) 30=Mechanical.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 30, 16, 26, 25, 24, 23, 21, 20, 19, 18, 17 except 27=315(LC 4), 27=304(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.



June 11, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 3 Cypress Rd	E15828502
J0521-3405	FW2	Floor Supported Gable	1	1	Job Reference (optional)	

Comtech, Inc, Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Fri Jun 11 07:16:58 2021 Page 1
ID:Cx08YMfksk??cVMzGzaSRDzyTIJ-8gUrk3O_9o8uMzXpc4WOLF3qRSdM2_1anuPy56z7Qj3

0'-1-8"

0'-1-8"

Scale = 1:14.4




Plate Offsets (X,Y)-- [15:0-1-8,0-1-8], [16:0-1-8,0-1-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.06	Vert(LL) n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.01	Vert(CT) n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr YES	WB 0.03	Horz(CT) 0.00	8	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-R					Weight: 34 lb	FT = 20%F, 11%E


LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)
OTHERS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6'-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.

REACTIONS. All bearings 7-9-0.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 14, 8, 13, 12, 11, 10, 9

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 2) Plates checked for a plus or minus 1 degree rotation about its center.
 - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 4) Gable studs spaced at 1'-4-0 oc.
 - 5) Non Standard bearing condition. Review required.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10'-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



June 11, 2021


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

* Plate location details available in **MITek 20/20 software or upon request.**

PLATE SIZE

4 X 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TPI 1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing, Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8
dimensions shown in ft-in-sixteenths
(Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITteK® All Rights Reserved



MITek Engineering Reference Sheet: Mill-7473 rev. 5/19/2020



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Rewriting pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.