I ASSUME NO RESPONSIBILITY FOR ANY DISTANCES AFTER START OF CONTRACTOR/BUILDER SHALL CONSULT WITH HOME OWNER ON ALL INTERIOR AND EXTERIOR MOLDINGS, TRIMS, COLORS, FINISHES, CABINET LAYOUTS, AND MANUFACTORS BEFORE CONSTRUCTION BEGINS.
ALL BEAMS AND FRAMING MEMBERS ARE SIZED BY OTHERS.

1.1 This plan has been drawn to comply with the 2018 NC Building Code

- 1.2 Minimum Design Loads for Building and Other Structures ASCE 7-9B
- 2 Roof Dead Load 115 PSF
- 3 Roof Live Load 20 PSF
- 4 Typical Floor Dead Load 10 PSF
- 5 Floor Live Loads
- 5.1 Rooms other than sleeping rooms 40 PSF 5.2 Sleeping Rooms 30 PSF
- 5.3 Stairs 40 PSF
- 5.4 Decks 40 PSF
- 5.5 Exterior Balconies 60 PSF
- Wind Loads 6.1 Ultimate Design Wind Speeds 15 MPH 6.2 Wind Importance Factor, IW 1.00
- 6.3 Exposure B
- 6.4 Walls (Component and Cladding) 25 PSF
- 6.5 Roofs (Component and Cladding)
  - 6.5.1 Roof Slopes 2.25/12 to 7/12 34.8 PSF 6.5.2 Roof Slopes 7/12 to 12/12 21 PSF

It is the sole responsibility of the Contractor and/or Builder to conform to all standards, provisions, requirements, methods of construction and uses of materials provided in buildings and/or structures as required by NC Uniform Building Code, Local Agencies and in accordance with good engineering practices. Verify all dimensions prior to construction.




## FENESTRATION CALCULATIONS


Floor	Height Of Ext. Wall	Area Of Ext. Wall	Ext. Wall	
lst				
2nd	3'	2270	2270	
other				
2270	Total Sq. Ft.	Total Sq. Ft. of Exterior Walls		


Total Fenestration	Total Exterior Walls	Percentage of wall openings
	Exterior waris	
224	2270	10%

Above Grade Walls Surrounding Heated Space


2 TION









Termite Soil Treatment: Treat entire slab area soil or crawl space surface before vapor barrier is installed and slab is poured with a state approved termiticide. Termiticide should be applied by a licensed and certified pest control professional by the state of North Carolina.




## STEM WALL FOUNDATION Detail not to scale



TYPICAL THICKENED SLAB





OPENING SCHEDULE				
SIZE	COUNT	LIBRARY NAME	R.O. SIZE	
2'-4" x 4'-0"	2	Window\Single Hung	R.O. 28" x 48"	
2'-8" x 5'-0"	6	Window\Single Hung	R.O. 32" x 60-1/2""	
2'-8 x 5'-0" Dbl	2	Window\Single Hung	R.O. 64-1/2" x 60-1/2""	
2'-0" x 3'-0"	1	Window\Single Hung	R.O. 24" x 36"	

GENERAL FRAMING NOTES:

ALL LUMBER IN CONTACT WITH CONCRETE OR MASONRY SHALL BE PRESSURE TREATED

FRAMING LUMBER SHALL BE SYP \*2 GRADE AND/OR SPRUCE PINE FIR \*1 AND/OR \*2, KILN DRIED.

WHERE PRE-ENGINEERED JOISTS ARE USED, JOIST MANUFACTURER SHALL PROVIDE SHOP DRAWINGS, WHICH BEAR SEAL OF A N.C. ENGINEER.

STUDS AND JOISTS SHALL NOT BE CUT TO INSTALL PLUMBING OR WIRING WITHOUT ADDING METAL OR WOOD SIDE PANELS TO STRENGTHEN THE MEMBER TO ITS ORIGINAL CAPACITY.

NAIL MULTIPLE MEMBERS WITH 2 ROWS OF 16d NAILS STAGGERED 32" OC AN USE 3-16d NAILS 2" IN AT EACH END. DOUBLE ALL STUDS UNDER ROOF POST DOWNS UNO.

NAIL FLOOR JOISTS TO SILL PLATE WITH 8d TOE NAILS.


ALL EXPOSED FRAMING ON PORCHES AND DECKS SHALL BE PRESSURE TREATED.


PROVIDE WATERPROOFING AND DRAINS AS REQUIRED.

ALL FRAMING TO BE 16" OC UNO. WALL FRAMING DIMENSIONS ARE BASED ON  $2\times4$  STUDS UNO. DOUBLE STUDS UNDER ALL HEADERS.


LYL'S AND TJI'S TO BE SIZED BY OTHERS

EXTERIOR WALLS IN LIVING AREAS ARE 2 × 4






DORMER DETAIL PLAN SCALE: 1'= 1/4"




HANDGRIP PORTION OF ALL HANDRAILS
SHALL NOT BE LESS THAN 1-1/4" NOR MORE THAN 2" IN
CROSS SECTIONAL DIMENSION, OR THE SHAPE SHALL
PROVIDE AN EQUIVALENT GRIPPING SURFACE




12" OYER HANG ALL

SCALE: 1'= 1/8"



ELECTI	ELECTRICAL LEGEND				
ELECTRICAL	COUNT	SYMBOL			
ceiling fan	2				
7" led disk light	12	0			
outdoor ceiling light	2	<u></u>			
foyer light	1	<b>\( \phi\)</b>			
dinning room light	1	000			
10" led disk light	2	<b>(</b>			
fluorescent light	2				
coach light	2	A			
small coach light	2	<u>Z</u>			
flood light	2	QP			
vanity light	3	000			



DATE: 3/2/2020

DATE: 3/2/2020

DRAWN BY:

SCALE: