

Highland Grove
4-Bedroom Septic Proposal
Lot #17

17

47,039 SQ.FT.

This drawing represents a preliminary septic plan made prior to final construction activities. A revised plan may need to be reworked at time of permitting.

*If plumbing is not sufficient a separate pump and tank may be required.

GRAPHIC SCALE
1" = 50'



System: Pump to D-Box
Lines: 1-4 (360')
0.35 LTAR
24" Trench Bottom
Accepted Status System
Repair: Serial Dist.
Lines: 5-8 (360')
0.35 LTAR
24 Trench Bottom
Accepted Status System

Adams
Soil Consulting
919-414-6761
Job #561

