

Non-Itemized QUOTE Estimate
UFP Mid-Atlantic, LLC



REQ. QUOTE DATE	//	ORDER #	
ORDER DATE	//	QUOTE #	21060947
DELIVERY DATE	//	CUSTOMER ACCT #	CAHM1488
DATE OF INVOICE	//	CUSTOMER PO #	
ORDERED BY	.	INVOICE #	
		TERMS	
SUPERINTENDENT	.	SALES REP	488 Jesse Keene
JOBSITE PHONE #		SALES AREA	

CUF JESSE KEENE CUF JESSE KEENE BURLINGTON, NC 27215 (336) 226-9356	JOB NAME: Plan 153 MODEL: TAG:	LOT # SUBDIV: Prime Estate
	DELIVERY INSTRUCTIONS:	JOB CATEGORY: SELECT CODE
	SPECIAL INSTRUCTIONS:	

BUILDING DEPARTMENT	OVERHANG INFO	HEEL HEIGHT	00-04-03	REQ. LAYOUTS	REQ. ENGINEERING	QUOTE	//
SELECT CODE	END CUT	RETURN				LAYOUT	//
	PLUMB	GABLE STUDS	24 IN. OC	JOBSITE 2	JOBSITE 1	CUTTING	//

ROOF TRUSSES

LOADING INFORMATION

TCLL-TCDL-BCLL-BCDL	STRESS INCR.
20.0,10.0,0.0,10.0	1.00

ROOF TRUSS SPACING: 24.0 IN. O.C. (TYP.)

PROFILE	QTY	PITCH		TYPE ID	BASE SPAN	O/A SPAN	LUMBER		OVERHANG		CANTILEVER		STUB	
		PLY	TOP				BOT	TOP	BOT	LEFT	RIGHT	LEFT	RIGHT	LEFT
	1		5.00	0.00	COMMON A1	32-06-00	17-06-00	2 X 4	2 X 4	01-06-00				15-00-00
	4		5.00	0.00	COMMON A2	32-06-00	17-06-00	2 X 4	2 X 4	01-06-00				15-00-00
	3		5.00	0.00	COMMON A3	32-06-00	17-06-00	2 X 4	2 X 4	02-11-08				15-00-00
	1		5.00	0.00	COMMON A4	33-11-08	18-11-08	2 X 4	2 X 4	00-00-08		01-05-08		15-00-00
	2		5.00	2.50	ROOF A5	32-06-00	17-06-00	2 X 4	2 X 4	01-06-00				15-00-00
	8		5.00	2.50	ROOF A6	32-06-00	32-06-00	2 X 4	2 X 4	01-06-00	01-06-00			
	1		5.00	2.50	ROOF A7	32-06-00	32-06-00	2 X 4	2 X 4	01-06-00				
	5		5.00	0.00	COMMON A8	32-06-00	32-06-00	2 X 4	2 X 6	01-06-00				
	1		5.00	0.00	COMMON A9	32-06-00	32-06-00	2 X 4	2 X 4	01-06-00				
	1		5.00	0.00	COMMON B1	22-00-00	22-00-00	2 X 4	2 X 4	01-06-00	01-06-00			
	3		5.00	0.00	COMMON B2	22-00-00	22-00-00	2 X 4	2 X 4	01-06-00	01-06-00			
	8		5.00	0.00	COMMON B3	22-00-00	22-00-00	2 X 4	2 X 4					
	1		5.00	0.00	COMMON C1	11-06-00	11-06-00	2 X 4	2 X 4	01-06-00	01-06-00			
	1 2 Ply		5.00	0.00	COMMON C2	11-06-00	11-06-00	2 X 4	2 X 6					
	2		5.00	0.00	VALLEY V1	14-09-14	14-09-14	2 X 4	2 X 4					
	2		5.00	0.00	VALLEY V2	12-09-14	12-09-14	2 X 4	2 X 4					
	2		5.00	0.00	VALLEY V3	10-09-14	10-09-14	2 X 4	2 X 4					
	2		5.00	0.00	VALLEY V4	08-09-14	08-09-14	2 X 4	2 X 4					
	2		5.00	0.00	VALLEY V5	06-09-14	06-09-14	2 X 4	2 X 4					

Non-Itemized QUOTE Estimate

UFP Mid-Atlantic, LLC



REQ. QUOTE DATE	//	ORDER #	
ORDER DATE	//	QUOTE #	21060947
DELIVERY DATE	//	CUSTOMER ACCT #	CAHM1488
DATE OF INVOICE	//	CUSTOMER PO #	
ORDERED BY	.	INVOICE #	
		TERMS	
SUPERINTENDENT	.	SALES REP	488 Jesse Keene
JOBSITE PHONE #		SALES AREA	

CUF JESSE KEENE CUF JESSE KEENE BURLINGTON, NC 27215 (336) 226-9356	JOB NAME: Plan 153	LOT #	SUBDIV: Prime Estate
	MODEL:	TAG:	JOB CATEGORY: SELECT CODE
	DELIVERY INSTRUCTIONS:		
	SPECIAL INSTRUCTIONS:		

BUILDING DEPARTMENT	OVERHANG INFO	HEEL HEIGHT	00-04-03	REQ. LAYOUTS	REQ. ENGINEERING	QUOTE	BY	DATE
SELECT CODE	END CUT	RETURN				LAYOUT		//
	PLUMB		GABLE STUDS	24 IN. OC	JOBSITE 2	CUTTING	JOBSITE 1	//

ROOF TRUSSES

LOADING INFORMATION

TCLL-TCDL-BCLL-BCDL	STRESS INCR.
20.0,10.0,0.0,10.0	1.00

ROOF TRUSS SPACING: 24.0 IN. O.C. (TYP.)

PROFILE	QTY	PITCH		TYPE ID	BASE SPAN	O/A SPAN	LUMBER		OVERHANG		CANTILEVER		STUB	
		PLY	TOP				BOT	TOP	BOT	LEFT	RIGHT	LEFT	RIGHT	LEFT
	2	5.00	0.00	VALLEY V6	04-09-14	04-09-14	2 X 4	2 X 4						
	1	5.00	0.00	VALLEY V7	07-07-13	07-07-13	2 X 4	2 X 4						

ITEMS

QTY	ITEM TYPE	SIZE	LENGTH FT-IN-16	PART NUMBER	NOTES
2	Truss Literature	11X17 LAYOUT			
5	New USP Hangers	HUS26 USP HANGER			
2	TJ EWP CAR	LVL TJ 1 3/4 x 14 2.0E C	18-00-00		UPDATED 6-2-21
2	TJ EWP CAR	LVL TJ 1 3/4 x 9 1/4 2.0E C	10-00-00		UPDATED 6-2-21

ACCEPTED BY SELLER BY: _____ TITLE: _____ DATE OF ACCEPTANCE: _____	ACCEPTED BY BUYER PURCHASER: _____ BY: _____ TITLE: _____ ADDRESS: _____ PHONE: _____ DATE: _____	SUB-TOTAL	\$10,000.00
		SALES TAX 7.000%	\$700.00
		GRAND TOTAL	\$10,700.00

Pricing provided is effective for 15 days from the quote date. Delivery of items listed from the time of quote should not exceed 60 days. Quote is based on current design values at the time of quote (lumber, EWP, hardware, etc). Should any of these values change, the price will be adjusted accordingly.

If any truss in this system exceeds 60' in length UFP will require the builder, framer or installer to sign an acknowledgement of risk for installation of long span trusses. UFP will provide this document to the customer.