Harnett County Department of Public Health

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Weaver Homes	PROPERTY LOCATION: 226 Spring subdivision Atkins-Lockar	ig mili Church KD(SK12	LOT # 3				
NEW REPAIR EXPANSION		quired prior to Construction Authorization					
Type of Structure: 48' x 54' SFD		1					
Proposed Wastewater System Type: 25% reduction							
Projected Daily Flow: 360 GPD							
Number of bedrooms: 3 Number of Occupants: 6	max						
Basement Yes No							
	on final location and elevations of facilities	_	7				
Type of Water Supply: Community Public Well	Distance from wellfeet	· ·	Five years				
Permit conditions:			No expiration				
White Del a	E/41 Date: 05-17-21	SEE ATTACHED	SITE SKETCH				
Authorized State Agent:: The issuance of this permit by the Health Department in no way guarantees the issue.							
site is subject to revocation if the site plan, plat, or the intended use changes. The I	nprovement Permit shall not be affected by a change in own	ership of the site. This permit is subject to complia	ince with the provisions of				
the Laws and Rules for Sewage Treatment and Disposal and to conditions of this period	it.						
	Construction Authorization						
	(Required for Building Permit)						
The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .		s into this permit and shall be met. Systems shall b	e installed in accordance				
with the attached system layout.	Control of the Contro						
Wasyer Hamas	DRODERTY LOCATION 226	Spring Hill Church PD/9	SD1228\				
ISSUED TO: Weaver Homes		Spring Hill Church RD(S					
5 10 - 401 11 EAL OFF	20	ckamy	101 # 3				
Facility Type: 48' x 54' SFD							
Basement? Yes No Basement Fixtures?	Yes 🔀 No						
Type of Wastewater System** 25% reduction		(Initial) Wastewater Flow: 360	GPD				
(See note below, if applicable)							
25% reduction	(Repair)						
Installation Requirements/Conditions Number	of trenches 3						
Septic Tank Size 1000 gallons Exact le	ngth of each trench 75 feet	Trench Spacing: 9 Feet	on Center				
Pump Tank Size 1000 gallons Trenche	shall be installed on contour at a	Soil Cover: 6inches					
	m Trench Depth of: 18" - 24" inches	(Maximum soil cover shall not ex	xceed				
(Trench	bottoms shall be level to +/-1/4"	36" above the trench bottom)					
in all d	rections)	*					
Pump Requirements:ft. TDH vsGPM	,		inches below pipe				
		Aggregate Depth:	_ inches above pipe				
Conditions:			inches total				
Conditions.							
WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT	FROM ANY RARE OF CERTIC CYCTEM OR	DEDAID ADEA					
WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT.		KEPAIK AKEA.					
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FI	LD AREA.						
**If applicable: I understand the system type specified is differe	nt from the type specified on the application	n. I accept the specifications of this p	permit.				
Owner/Legal Representative Signature:		Date:					
This Construction Authorization is subject to revocation if the site plan, plat, or the i	stended use changes. The Construction Authorization shall not		ip of the site. This				
Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH							
11 11							
Authorized State Agent: Nah De	EHS Date:	05-17-21					
AUTHORIZED STATE AGENT.							
	Construction Authorization Expiration	Date. US-17-20	_				

Harnett County Department of Public Health Site Sketch

Property Lo	ocation: 226 Spri	ing Hill Church RD(SR1238)			
Issued To:	Weaver Homes	Subdivision	Atkins-Lockamy		Lot # 3
Authorized	State Agent:	Mol Phace HI		Date: 05-17-2	:1

