## Harnett County Department of Public Health

## Improvement Permit

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: 5173 Spring Hill Church Rd (SR1238) ISSUED TO: Tom Nash Contracting NEW X REPAIR EXPANSION Site Improvements required prior to Construction Authorization Issuance: Type of Structure: 80' x 60' SFD Proposed Wastewater System Type: low profile chambers Projected Daily Flow: 360 Number of bedrooms: 3 Number of Occupants: 6 Basement Yes May be required based on final location and elevations of facilities X No Pump Required: Yes Type of Water Supply: Community Public Well Distance from well \_\_\_\_\_\_\_feet X Five years Permit valid for: No expiration Permit conditions: REH Date: 05-24-21 Authorized State Agent:: The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. ISSUED TO: Tom Nash Contracting PROPERTY LOCATION: 5173 Spring Hill Church Rd (SR1238) SUBDIVISION Facility Type: 80' x 60' SFD Expansion Repair Basement Fixtures? Yes X No Basement? Yes X No Type of Wastewater System\*\* low profile chambers (Initial) Wastewater Flow: 360 GPD (See note below, if applicable ) low profile chambers Installation Requirements/Conditions Number of trenches 4 Exact length of each trench 75 Trench Spacing: 9 Septic Tank Size 1000 gallons Pump Tank Size \_\_\_\_\_ Trenches shall be installed on contour at a Soil Cover: 6 Maximum Trench Depth of: 8 (Maximum soil cover shall not exceed inches (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: \_\_\_\_\_ ft. TDH vs. inches below pipe inches above pipe Conditions: Must bring in 6" of group III cover for drain lines inches total WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. \*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This SEE ATTACHED SITE SKETCH Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. Authorized State Agent: Nall A RETYS Date: 05-24-21 Construction Authorization Expiration Date: 05-24-26

## Harnett County Department of Public Health Site Sketch

Property Location: 5173 Spring Hill Church Rd (SR12	238)		
Issued To: Tom Nash Contracting	Subdivision		Lot #
Authorized State Agent: Mah W	- REHS	Date:	05-24-21
Authorized State Agent:    January   Landau   La	FUTURE LOW PROFILE  TEPRIT ATLA  19' -75' 19' -75' 19' -75' 19' -75' -75' -75' -75' -70'		05-24-21
- 56	oring Hill Church Rd ->		
	(SR 1238)		

This drawing is for illustrative purposes only. System installation must meet all pertinent laws, rules, and regulations.