

# North Carolina 2018 - R402.1.5 Total UA

**Property**

134 Spruce Hollow Circle  
Spring Lake, NC 28390  
Model: Nicklaus II 2334

**Organization**

Southern Energy Manager  
Justin Smith

**Inspection Status**

Results are projected

Capitol City Homes - Nicklaus II  
2334 plan slab - HERS  
Nicklaus II 2334 slab

**Builder**

Capitol City Homes

**This report is based on a proposed design and does not confirm field enforcement of design elements.**

## Building UA

Elements	NC Reference	As Designed
Ceilings	42.9	38.4
Above-Grade Walls	202.5	180.1
Windows, Doors and Skylights	105.2	99.5
Slab Floor:	71.4	92.3
Framed Floors	21.5	21.0
Foundation Walls	0.0	0.0
Rim Joists	8.4	6.8
<b>Overall UA (Design must be equal or lower):</b>	<b>451.9</b>	<b>438.1</b>

## Requirements

✓	402.1.5	Total UA alternative compliance passes by 3.1%.
✓	402.3.2 Glazed Fenestration SHGC	Average SHGC: 0.29 Max SHGC: 0.30
✓	R402.4.2.2	Air Leakage Testing Air sealing is 0.29 CFM50 / ft <sup>2</sup> Shell Area. It must not exceed 0.30 CFM50 / ft <sup>2</sup> Shell Area.
✓	R402.5	Area-weighted average fenestration SHGC
✓	R402.5	Area-weighted average fenestration U-Factor
✓	R404.1	Lighting Equipment Efficiency
✓	Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met.
✓	R403.3.1	Duct Insulation
✓	403.3.3	Duct Testing

**Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 3.1%.**

Name: Justin Smith  
Organization: Southern Energy Management

Signature: Justin Smith  
Digitally signed: 9/14/21 at 10:36 AM

### Ekotrope RATER - Version 3.2.4.2743

North Carolina 2018 Prescriptive compliance results calculated using Ekotrope RATER's energy and code compliance algorithm, including appropriate amendments. Ekotrope RATER is a RESNET Accredited HERS Rating Tool. All results are based on data entered by Ekotrope users. Ekotrope disclaims all liability for the information shown on this report.

# Energy Code Inspection Checklist



SOUTHERN ENERGY  
MANAGEMENT  
ENERGY EFFICIENCY & SOLAR POWER

## Property

134 Spruce Hollow Circle  
Spring Lake, NC 28390  
Model: Nicklaus II 2334

## Organization

Southern Energy Manager  
Justin Smith

## Inspection Status

Results are projected

Capitol City Homes - Nicklaus II  
2334 plan slab - HERS  
Nicklaus II 2334 slab

## Builder

Capitol City Homes

## General Building Information

Conditioned Area (sq ft)	2,334
Conditioned Volume (cubic ft)	21,214
Insulated Shell Area (sq ft)	5,941

The building energy model in Ekotrope reflects the building assemblies and energy features listed below. Sometimes energy features will change in the field from what has been modeled. The inspection process should identify any changes and ensure that the home continues to meet the applicable energy code.

## Slab



Name: slab(971 s.f., 152 ft. exterior perimeter)  
R-0 perimeter insulation, R-0 under slab insulation.

## Framed Floor



Name: over garage (298 s.f.)  
R-0 continuous insulation, R-19 cavity insulation  
Insulation Grade: I



Name: over ambient (160 s.f.)  
R-0 continuous insulation, R-19 cavity insulation  
Insulation Grade: I

## Foundation Wall

None Present

## Above Grade Wall



Name: 1st floor ambient (1,231 s.f.)  
R-0 continuous insulation, R-19 cavity insulation  
Insulation Grade: I



Name: 1st floor garage (137 s.f.)  
R-0 continuous insulation, R-19 cavity insulation  
Insulation Grade: I

# Energy Code Inspection Checklist



SOUTHERN ENERGY  
MANAGEMENT  
ENERGY EFFICIENCY & SOLAR POWER

## Property

134 Spruce Hollow Circle  
Spring Lake, NC 28390  
Model: Nicklaus II 2334

## Organization

Southern Energy Manager  
Justin Smith

## Inspection Status

Results are projected

Capitol City Homes - Nicklaus II  
2334 plan slab - HERS  
Nicklaus II 2334 slab

## Builder

Capitol City Homes

Name: 2nd floor ambient (1,247 s.f.)  
R-0 continuous insulation, R-15 cavity insulation  
Insulation Grade: I

Name: 2nd floor attic (316 s.f.)  
R-0 continuous insulation, R-15 cavity insulation  
Insulation Grade: I

## Rim Joist

Name: 1st floor ambient (137 s.f.)  
R: 17.30

Name: 1st floor garage (15 s.f.)  
R: 17.30

## Ceiling / Roof

Name: attic (1,429 s.f.)  
R-13 continuous insulation, R-25 cavity insulation  
Insulation Grade: I

## Opaque Door

Name: front door (20 s.f.)  
U: 0.200

Name: garage door (18 s.f.)  
U: 0.200

## Glazing

Name: front shaded (29.7 s.f.), U: 0.350, SHGC: 0.29, Orientation: EAST

Name: front 2nd unshaded (36.5 s.f.), U: 0.350, SHGC: 0.29, Orientation: EAST

Name: right unshaded (29.7 s.f.), U: 0.350, SHGC: 0.29, Orientation: NORTH

# Energy Code Inspection Checklist



## Property

134 Spruce Hollow Circle  
Spring Lake, NC 28390  
Model: Nicklaus II 2334

## Organization

Southern Energy Manager  
Justin Smith

## Inspection Status

Results are projected

Capitol City Homes - Nicklaus II  
2334 plan slab - HERS  
Nicklaus II 2334 slab

## Builder

Capitol City Homes

- Name: right shaded (36.2 s.f.), U: 0.350, SHGC: 0.29, Orientation: NORTH
- Name: right 2nd unshaded (54.5 s.f.), U: 0.350, SHGC: 0.29, Orientation: NORTH
- Name: rear unshaded (29.7 s.f.), U: 0.350, SHGC: 0.29, Orientation: WEST
- Name: rear 2nd unshaded (46.3 s.f.), U: 0.350, SHGC: 0.29, Orientation: WEST

## Skylight

None Present

## Mechanical Ventilation

None Present

## Mechanical Equipment

- whole house heat pump • Electric • 100% Heating Load @ 8.2 HSPF, 100% Cooling Load @ 14 SEER
- Water Heater • Electric • 100% Hot Water Load @ 0.9 UEF

## Air Leakage Control

- Test Status: Blower-door tested  
House is air-sealed as to achieve 1,697 CFM50 (4.80 ACH50) or less at final blower-door test.

Infiltration Requirements for IECC in Climate Zone 4

- 2009 IECC Infiltration limit for the design home is 7 ACH50.
- 2012 IECC Infiltration limit for the design home is 3 ACH50.
- 2015 IECC Infiltration limit for the design home is 3 ACH50.
- 2018 IECC Infiltration limit for the design home is 3 ACH50.

# Energy Code Inspection Checklist



## Property

134 Spruce Hollow Circle  
Spring Lake, NC 28390  
Model: Nicklaus II 2334

## Organization

Southern Energy Manager  
Justin Smith

## Inspection Status

Results are projected

Capitol City Homes - Nicklaus II  
2334 plan slab - HERS  
Nicklaus II 2334 slab

## Builder

Capitol City Homes

## Duct Leakage

### Duct System 1

NOT entirely within conditioned space, testing required

Leakage to Outside specified as: 93 CFM @ 25Pa (3.98 / 100 ft<sup>2</sup>)

Total Leakage specified as: 93 CFM @ 25Pa (Post-Construction)

## Duct Leakage Code Requirements for IECC

### 2009 IECC:

Postconstruction Leakage Test: Duct Leakage to Outdoors  $\leq$  8 CFM<sub>25</sub> / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage  $\leq$  6 CFM<sub>25</sub> / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage  $\leq$  4 CFM<sub>25</sub> / 100 sq ft CFA.

### 2012 IECC Mandatory, 2015 and 2018 IECC Prescriptive Paths:

Postconstruction Leakage Test: Total Duct Leakage  $\leq$  4 CFM<sub>25</sub> / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage  $\leq$  4 CFM<sub>25</sub> / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage  $\leq$  3 CFM<sub>25</sub> / 100 sq ft CFA.

### 2015 and 2018 IECC Performance Paths (Cost Compliance):

Leakage testing is required UNLESS all ducts and air handlers are located entirely within the thermal envelope.

There is no pass/fail threshold for duct leakage on the performance path.

## Project Notes

Initial Inputs by \_\_\_\_\_ JS 01/13/2021 \_\_\_\_\_

- confirm insulation values
- confirm window values
- confirm radiant barrier installed
- confirm mechanical equipment
- confirm ventilation type; currently modeled to none