Harnett County Department of Public Health

Improvement Permit

PROPERTY LOCATION: SUTO BE RED HINCHUKER RD
ISSUED TO: VICTORIA WICKER PROPERTY LOCATION: SCI 103 LTD H. III CHOCKER CD SUBDIVISION Care Mill Estates LOT # Z3 NEW D. Site Improvements required prior to Construction Authorization Issuance:
NEW REPAIR EXPANSION Site Improvements required prior to Construction Authorization Issuance:
The state of the s
Type of Structure: Proposed Wastewater System Type: 25% (1285) System
Projected Daily Flow: 240 GPD
Number of bedrooms: 2 Number of Occupants: 4 max
Basement Ves No
Pump Required: Yes No May be required based on final location and elevations of facilities
Type of Water Supply: Community Public Well Distance from well feet Permit valid for: Five years
Permit conditions: No expiration
Authorized State Agent: Date: 9-23-21 SEE ATTACHED SITE SKETCH
Authorized State Agent: Date: 9-23-21 SEE ATTACHED SITE SKEICH The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This
site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of
the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.
Construction Authorization
(Required for Building Permit)
The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance
with the attached system layout.
ISSUED TO: Victoria Wicker PROPERTY LOCATION: SX 1703 TZSD HI VICHURCH TZD SUBDIVISION CANE MILL ESTATES LOT # 23
SURDIVISION CASE 11:11 F- Atex 10T # 23
/
Basement? Yes No Basement Fixtures? Yes No
Type of Wastewater System** 25% DBD OTTON System (Initial) Wastewater Flow: 240 GPD
(See note below, if applicable) 50% TOSOUTON (Repair)
Installation Requirements/Conditions Number of trenches Z
Septic Tank Size 1000 gallons Exact length of each trench 100 feet Trench Spacing: Feet on Center
Tump tank size
Maximum Trench Depth of: 18-24-18 inches (Maximum soil cover shall not exceed
(Trench bottoms shall be level to $\pm 1/4$ " 36" above the trench bottom)
in all directions)
Pump Requirements:ft. TDH vsGPM
Aggregate Depth: Z inches above pipe
Conditions: Follow Layout, Consumotor to meet on SITE TRIOR 12 inches total
to 70/500/1
WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.
**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.
Owner/Legal Representative Signature: Date:
This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This
Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH
7 11 / ADD 1845
Authorized State Agent. Date: 9-23-21
Authorized State Agent: Date: 9-23-21 Construction Authorization Expiration Date: 9-23-26

Harnett County Department of Public Health Site Sketch

Property Location: 54 1703 RSD ANN CHUNCK TON	
Property Location: 51 1703 RED HIN CHURCH TOD Issued To: Victoria Willer Subdivision Care Mill Estates Lot	# 23
Authorized State Agent: Janes & Manha De 12803 Date: 9-23-	
* System Cayout IS Very Tight, Contractor to meet onsail prion to	INSTALL
* NO WATER ON POWERLENES IN System on Repair Arm	

