

Trenco  
818 Soundside Rd  
Edenton, NC 27932

Re: J0421-2291  
Stout/Lot 17 Forest Ridge/Harnett

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Comtech, Inc - Fayetteville.

Pages or sheets covered by this seal: E15666800 thru E15666809

My license renewal date for the state of North Carolina is December 31, 2021.

North Carolina COA: C-0844



April 27, 2021

Gilbert, Eric

**IMPORTANT NOTE:** The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job	Truss	Truss Type	Qty	Ply	Stout/Lot 17 Forest Ridge/Harnett	E15666800
J0421-2291	F01	Floor	5	1	Job Reference (optional)	

Comtech, Inc., Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Tue Apr 27 15:17:00 2021 Page 1  
ID:ikQyRsNXi14PrYc3UMF2QWzXTAO-vmCG9VC1?HV3aJbbTE8P0OK\_4wTsnOk4vilvLyzMU?1




Plate Offsets (X,Y)-- [6:0-1-8,Edge], [7:0-1-8,Edge], [26:0-1-8,Edge], [27:0-1-8,Edge], [34:0-1-8,0-0-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.85	Vert(LL) -0.26	25-26	>828	480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.93	Vert(CT) -0.36	25-26	>613	360		
BCLL 0.0	Rep Stress Incr YES	WB 0.57	Horz(CT) 0.05	23	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S					Weight: 172 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat) *Except* 32-39: 2x4 SP 2400F 2.0E(flat)	BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

**REACTIONS.** (size) 39=0-3-8, 31=0-3-8, 23=0-3-8  
Max Grav 39=729(LC 3), 31=2075(LC 1), 23=885(LC 4)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**TOP CHORD** 2-3=-1258/0, 3-4=-1912/0, 4-5=-1912/0, 5-6=-1948/210, 6-7=-1549/534, 7-8=-785/924, 8-10=0/1815, 10-11=0/1815, 11-12=-451/147, 12-14=-1906/0, 14-15=-1906/0, 15-16=-2899/0, 16-17=-2899/0, 17-18=-2899/0, 18-19=-2608/0, 19-20=-2608/0, 20-21=-1589/0

**BOT CHORD** 38-39=0/780, 37-38=0/1702, 36-37=-43/2104, 35-36=-534/1549, 34-35=-534/1549, 33-34=-534/1549, 31-33=-1251/121, 30-31=-777/0, 28-30=0/1274, 27-28=0/2408, 26-27=0/2899, 25-26=0/2863, 24-25=0/2203, 23-24=0/954

**WEBS** 2-39=-1036/0, 2-38=0/666, 3-38=-617/15, 3-37=-90/285, 5-37=-261/87, 5-36=-399/0, 6-36=0/836, 6-35=-549/0, 8-31=-1240/0, 8-33=0/1072, 7-33=-1379/0, 7-34=0/642, 21-23=-1268/0, 21-24=0/883, 20-24=-855/0, 20-25=0/550, 18-25=-347/0, 18-26=-224/328, 11-31=-1585/0, 11-30=0/1207, 12-30=-1170/0, 12-28=0/884, 15-28=-708/0, 15-27=0/875, 16-27=-436/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are 3x6 MT20 unless otherwise indicated.
  - 3) Plates checked for a plus or minus 1 degree rotation about its center.
  - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 5) CAUTION, Do not erect truss backwards.



April 27, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Stout/Lot 17 Forest Ridge/Harnett	E15666801
J0421-2291	F02	Floor	5	1	Job Reference (optional)	

Comtech, Inc., Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Tue Apr 27 15:17:01 2021 Page 1  
ID:ikQyRsNXi14PrYc3UMF2QWzXTAO-NzmeNrDfmbdwCSAo0yfeYbtHTKxqWrBD8MVStPzMU?0




Plate Offsets (X,Y)--	[6:0-2-8,Edge], [7:0-3-0,Edge], [10:0-2-12,Edge], [20:0-3-0,Edge], [22:0-3-0,0-0-0], [25:0-3-0,Edge]
-----------------------	--


LOADING (psf)	SPACING-	1-7-3	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.36	Vert(LL)	-0.37	22	>777	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.43	Vert(CT)	-0.50	22	>565	M18SHS	244/190
BCLL 0.0	Rep Stress Incr	YES	WB 0.56	Horz(CT)	0.08	17	n/a		
BCDL 5.0	Code	IRC2015/TPI2014	Matrix-S						
								Weight: 145 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP 2400F 2.0E(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP 2400F 2.0E(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

**REACTIONS.** (size) 28=0-3-8, 17=0-3-8  
Max Grav 28=1036(LC 1), 17=1036(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
**TOP CHORD** 2-3=-1984/0, 3-4=-3483/0, 4-5=-3483/0, 5-6=-4883/0, 6-7=-5585/0, 7-8=-5585/0, 8-9=-5543/0, 9-10=-5543/0, 10-12=-4834/0, 12-13=-3493/0, 13-14=-3493/0, 14-15=-1984/0  
**BOT CHORD** 27-28=0/1136, 26-27=0/2811, 25-26=0/4178, 23-25=0/5416, 22-23=0/5585, 21-22=0/5585, 20-21=0/5349, 19-20=0/4137, 18-19=0/2809, 17-18=0/1137  
**WEBS** 2-28=-1511/0, 2-27=0/1180, 3-27=-1150/0, 3-26=0/914, 5-26=-943/0, 5-25=0/902, 6-25=-707/0, 6-23=-177/572, 7-23=-261/61, 15-17=-1511/0, 15-18=0/1178, 14-18=-1148/0, 14-19=0/930, 12-19=-874/0, 12-20=0/893, 10-20=-682/0, 10-21=0/356, 8-21=-487/336

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) All plates are 3x6 MT20 unless otherwise indicated.
  - 4) Plates checked for a plus or minus 1 degree rotation about its center.
  - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



April 27, 2021

Job	Truss	Truss Type	Qty	Ply	Stout/Lot 17 Forest Ridge/Harnett	E15666802
J0421-2291	F02A	GABLE	1	1	Job Reference (optional)	


Comtech, Inc., Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Tue Apr 27 15:17:02 2021 Page 1  
ID:ikQyRsNXi14PrYc3UMF2QWzXTAO-r9J0aBDHXulnqcl\_afBt5pPPskBQFHgMN0E0QrzMU??

0-1-8



Scale = 1:38.5



<b>LOADING</b> (psf)	<b>SPACING-</b>	<b>CSI.</b>	<b>DEFL.</b>	<b>PLATES</b>	<b>GRIP</b>
TCLL 40.0	1-7-3	TC 0.58	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.80	Vert(LL) -0.24 28-30 >816 480	M18SHS	244/190
BCLL 0.0	Lumber DOL 1.00	WB 0.61	Vert(CT) -0.34 28-30 >594 360		
BCDL 5.0	Rep Stress Incr NO	Matrix-S	Horz(CT) 0.04 19 n/a n/a		
	Code IRC2015/TPI2014			Weight: 138 lb	FT = 20%F, 11%E

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SP No.1(flat) *Except* 1-12: 2x4 SP 2400F 2.0E(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP 2400F 2.0E(flat) *Except* 29-36: 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

**REACTIONS.** All bearings 6-2-0 except (jt=length) 36=0-3-8.  
(lb) - Max Grav All reactions 250 lb or less at joint(s) 19, 23, 22, 21, 20 except 36=1137(LC 1), 24=1322(LC 1), 24=1322(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-2216/0, 3-4=-2216/0, 4-5=-3498/0, 5-6=-3498/0, 6-7=-4165/0, 7-8=-4165/0, 8-9=-3579/0, 9-10=-2156/0, 10-11=-2156/0  
BOT CHORD 35-36=0/1255, 34-35=0/1255, 33-34=0/2960, 32-33=0/2960, 31-32=0/3809, 30-31=0/3816, 28-30=0/3579, 27-28=0/3579, 26-27=0/1173, 24-25=0/1173  
WEBS 2-36=-1637/0, 2-34=0/1279, 4-34=-990/0, 4-32=0/716, 6-32=-414/0, 6-30=0/463, 8-30=0/749, 8-28=-514/0, 9-27=0/806, 9-26=-1820/0, 11-26=0/1279, 11-24=-1532/0

- NOTES-**
- 1) All plates are MT20 plates unless otherwise indicated.
  - 2) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 3) Plates checked for a plus or minus 1 degree rotation about its center.
  - 4) Gable studs spaced at 1-4-0 oc.
  - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 6) CAUTION, Do not erect truss backwards.
  - 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).


**LOAD CASE(S)** Standard  
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00  
Uniform Loads (plf)  
Vert: 19-36=-58(B=-50), 1-18=-80



Job	Truss	Truss Type	Qty	Ply	Stout/Lot 17 Forest Ridge/Harnett	E15666803
J0421-2291	F03	FLOOR	3	1	Job Reference (optional)	

Comtech, Inc., Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Tue Apr 27 15:17:03 2021 Page 1  
ID:ikQyRsNXi14PrYc3UMF2QWzXTAO-KLtOoXEvICteRmKA8Ni6d0yb68cr\_hTWcg\_ZyHzMU?\_



9-3-0	10-4-14	22-2-4	22-6-4
9-3-0	1-1-14	11-9-6	0-4-0
Plate Offsets (X,Y)--	[15:0-3-0,Edge], [16:0-3-0,Edge]		

LOADING (psf)	SPACING-	CSL.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.48	Vert(LL) -0.35	21	>760	480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.46	Vert(CT) -0.48	21	>552	360	M18SHS	244/190
BCLL 0.0	Rep Stress Incr YES	WB 0.83	Horz(CT) -0.03	15	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S						
							Weight: 151 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP 2400F 2.0E(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP 2400F 2.0E(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

**REACTIONS.** (size) 28=0-3-8, 15=0-3-8  
Max Grav 28=1207(LC 1), 15=1207(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-2336/0, 3-4=-4101/0, 4-5=-4101/0, 5-6=-5170/0, 6-7=-5684/0, 7-9=-5524/0, 9-10=-4768/0, 10-11=-4768/0, 11-12=-3345/0, 12-14=-1370/0, 14-15=-1370/0  
BOT CHORD 27-28=0/1397, 26-27=0/3326, 24-26=0/4774, 22-24=0/5684, 21-22=0/5684, 20-21=0/5684, 19-20=0/5293, 18-19=0/4171, 17-18=0/2490  
WEBS 15-17=0/1744, 2-28=-1766/0, 2-27=0/1277, 3-27=-1343/0, 3-26=0/1029, 12-17=-1488/0, 12-18=0/1160, 11-18=-1121/0, 11-19=0/791, 9-19=-697/0, 9-20=0/464, 5-26=-894/0, 5-24=0/615, 6-24=-989/0, 7-20=-676/267, 7-21=-391/260, 6-22=-214/438

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) Plates checked for a plus or minus 1 degree rotation about its center.
  - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 5) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
  - 6) CAUTION, Do not erect truss backwards.



April 27, 2021

Job	Truss	Truss Type	Qty	Ply	Stout/Lot 17 Forest Ridge/Harnett	E15666804
J0421-2291	F03A	Floor	1	1	Job Reference (optional)	

Comtech, Inc, Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Tue Apr 27 15:17:04 2021 Page 1  
ID:ikQyRsNXi14PrYc3UMF2QWzXTAO-oYRn?sFX3W?V3wvNi4DLAEVkJYrj8zfqKj7TjzMU\_z




Plate Offsets (X,Y)-- [6:0-1-8,Edge], [13:Edge,0-1-8], [18:0-1-8,Edge]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.64	Vert(LL) -0.30	18-20	>750	480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.93	Vert(CT) -0.41	18-20	>552	360	M18SHS	244/190
BCLL 0.0	Rep Stress Incr YES	WB 0.81	Horz(CT) 0.05	15	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S						
							Weight: 116 lb	FT = 20%F, 11%E

**LUMBER-**

TOP CHORD 2x4 SP No.1(flat) \*Except\*  
1-8: 2x4 SP 2400F 2.0E(flat)  
BOT CHORD 2x4 SP No.1(flat)  
WEBS 2x4 SP No.3(flat)

**BRACING-**

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.

**REACTIONS.**


(size) 21=0-3-8, 15=0-3-8, 13=0-3-8  
Max Uplift 13=-654(LC 3)  
Max Grav 21=884(LC 3), 15=2074(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2657/0, 3-4=-2657/0, 4-5=-2805/0, 5-6=-2805/0, 6-7=-1667/0, 7-9=-1667/0,  
9-10=0/2044, 10-11=0/2040  
BOT CHORD 20-21=0/1656, 18-20=0/2971, 17-18=0/2805, 16-17=0/2805, 14-15=-1011/0,  
13-14=-1011/0  
WEBS 2-21=-1817/0, 2-20=0/1106, 9-15=-2385/0, 9-16=0/1710, 7-16=-261/45, 6-16=-1255/0,  
4-20=-376/0, 4-18=-451/188, 5-18=-129/267, 11-15=-1383/0, 11-13=0/1221

**NOTES-**

- Unbalanced floor live loads have been considered for this design.
- All plates are MT20 plates unless otherwise indicated.
- All plates are 1.5x3 MT20 unless otherwise indicated.
- Plates checked for a plus or minus 1 degree rotation about its center.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 654 lb uplift at joint 13.
- Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- CAUTION, Do not erect truss backwards.



April 27, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

**Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**



818 Soundside Road  
Edenton, NC 27932





Job	Truss	Truss Type	Qty	Ply	Stout/Lot 17 Forest Ridge/Harnett	E15666806
J0421-2291	F05	Floor	5	1	Job Reference (optional)	

Comtech, Inc, Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Tue Apr 27 15:17:05 2021 Page 1  
ID:ikQyRsNXi14PrYc3UMF2QWzXTAO-Gk?9DCG9qp7Mh4UZFokajR1w7xGbSfp3\_Tg?AzMU\_y

0-1-8



0-1-8  
Scale = 1:31.2




Plate Offsets (X,Y)-- [6:0-1-8,Edge], [17:0-1-8,Edge]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.57	Vert(LL) -0.27	18-19	>838	480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.64	Vert(CT) -0.37	18-19	>612	360	M18SHS	244/190
BCLL 0.0	Rep Stress Incr YES	WB 0.52	Horz(CT) 0.06	14	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S						
							Weight: 100 lb	FT = 20%F, 11%E

**LUMBER-**

TOP CHORD 2x4 SP No.1(flat)  
 BOT CHORD 2x4 SP 2400F 2.0E(flat) \*Except\*  
 21-23: 2x4 SP No.1(flat)  
 WEBS 2x4 SP No.3(flat)

**BRACING-**

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.**

(size) 14=0-3-8, 23=0-3-8  
 Max Grav 14=1023(LC 1), 23=1023(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1892/0, 3-4=-3178/0, 4-5=-3178/0, 5-6=-3824/0, 6-7=-3939/0, 7-8=-3939/0,  
 8-9=-3182/0, 9-11=-3182/0, 11-12=-1893/0  
 BOT CHORD 22-23=0/1112, 20-22=0/2641, 19-20=0/3644, 18-19=0/3939, 17-18=0/3939, 16-17=0/3613,  
 15-16=0/2637, 14-15=0/1113  
 WEBS 2-23=-1478/0, 2-22=0/1085, 3-22=-1042/0, 3-20=0/730, 5-20=-634/0, 5-19=0/402,  
 6-19=-470/171, 12-14=-1480/0, 12-15=0/1084, 11-15=-1035/0, 11-16=0/741,  
 8-16=-586/0, 8-17=0/699, 7-17=-284/0

**NOTES-**

- Unbalanced floor live loads have been considered for this design.
- All plates are MT20 plates unless otherwise indicated.
- All plates are 1.5x3 MT20 unless otherwise indicated.
- Plates checked for a plus or minus 1 degree rotation about its center.
- Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



April 27, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

**ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

**Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road  
 Edenton, NC 27932



Job	Truss	Truss Type	Qty	Ply	Stout/Lot 17 Forest Ridge/Harnett	E15666807
J0421-2291	FW01	GABLE	1	1	Job Reference (optional)	

Comtech, Inc, Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Tue Apr 27 15:17:07 2021 Page 1  
ID:ikQyRsNXi14PrYc3UMF2QWzXTAO-C77vduHQMRN4wOdxNCm2os7K4I?zwd46Wlyn42zMU\_w




Plate Offsets (X,Y)-- [34:0-1-8,Edge], [35:0-1-8,Edge]

LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.22	Vert(LL) -0.06	34-35	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.32	Vert(CT) -0.08	34-35	>999	360		
BCLL 0.0	Rep Stress Incr YES	WB 0.28	Horz(CT) 0.02	27	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S						
							Weight: 155 lb	FT = 20%F, 11%E


**LUMBER-**  
TOP CHORD 2x4 SP No.1(flat)  
BOT CHORD 2x4 SP No.1(flat)  
WEBS 2x4 SP No.3(flat)  
OTHERS 2x4 SP No.3(flat)

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** All bearings 14-9-8 except (jt=length) 27=5-9-8, 32=5-9-8, 32=5-9-8, 31=5-9-8, 30=5-9-8, 29=5-9-8, 28=5-9-8.  
(lb) - Max Uplift All uplift 100 lb or less at joint(s) 40, 31  
Max Grav All reactions 250 lb or less at joint(s) 27, 50, 49, 48, 47, 46, 45, 44, 43, 42, 41, 40, 31, 30, 29, 28 except 32=802(LC 4), 32=802(LC 1), 38=799(LC 1), 38=799(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 14-16=-1116/0, 16-17=-1727/0, 17-18=-1727/0, 18-19=-1727/0, 19-20=-1112/0  
BOT CHORD 37-38=0/696, 35-37=0/1520, 34-35=0/1727, 33-34=0/1518, 32-33=0/691  
WEBS 20-32=-920/0, 20-33=0/585, 19-33=-564/0, 19-34=0/285, 14-38=-926/0, 14-37=0/586, 16-37=-562/0, 16-35=0/282

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 3) Plates checked for a plus or minus 1 degree rotation about its center.
  - 4) Gable studs spaced at 1-4-0 oc.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 40, 31.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 7) CAUTION, Do not erect truss backwards.



April 27, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



Job	Truss	Truss Type	Qty	Ply	Stout/Lot 17 Forest Ridge/Harnett	E15666808
J0421-2291	FW02	GABLE	1	1	Job Reference (optional)	


Comtech, Inc, Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Tue Apr 27 15:17:08 2021 Page 1  
ID:ikQyRsNXi14PrYc3UMF2QWzXTAO-gJhHrE127kVxYXC8xwHHK4fYQ9Q5f8BFlyhKcVzMU\_v

0-1-8

0-1-8

Scale = 1:37.0



1-4-0	2-8-0	4-0-0	5-4-0	6-8-0	8-0-0	9-4-0	10-8-0	12-0-0	13-4-0	14-8-0	16-0-0	17-4-0	18-8-0	20-0-0	21-4-0	22-2-12
1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	0-10-12
<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in	(oc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>						
TCLL 40.0	Plate Grip DOL 1.00		TC 0.06	Vert(LL) n/a	-	n/a	999		MT20	244/190						
TCDL 10.0	Lumber DOL 1.00		BC 0.01	Vert(CT) n/a	-	n/a	999									
BCLL 0.0	Rep Stress Incr YES		WB 0.03	Horz(CT) 0.00	20	n/a	n/a									
BCDL 5.0	Code IRC2015/TPI2014		Matrix-R						Weight: 97 lb	FT = 20%F, 11%E						

**LUMBER-**

TOP CHORD 2x4 SP No.1 (flat)  
BOT CHORD 2x4 SP No.1 (flat)  
WEBS 2x4 SP No.3 (flat)  
OTHERS 2x4 SP No.3 (flat)

**BRACING-**

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.**


All bearings 22-2-12.

(b) - Max Grav All reactions 250 lb or less at joint(s) 38, 20, 37, 36, 35, 34, 33, 31, 30, 29, 28, 27, 26, 25, 24, 23, 22, 21

**FORCES.** (b) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
- 2) Plates checked for a plus or minus 1 degree rotation about its center.
- 3) Gable requires continuous bottom chord bearing.
- 4) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- 5) Gable studs spaced at 1-4-0 oc.
- 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



April 27, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

**ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

**Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Stout/Lot 17 Forest Ridge/Harnett	E15666809
J0421-2291	FW03	GABLE	1	1	Job Reference (optional)	



Comtech, Inc, Fayetteville, NC - 28314,

8.330 s Oct 7 2020 MiTek Industries, Inc. Tue Apr 27 15:17:08 2021 Page 1  
ID:ikQyRsNXi14PrYc3UMF2QWzXTAO-gJhHrE127kVxYXC8xwHHK4fYQ9Q4f8BFlyhKcVzMU\_v

0<sub>1</sub>:8

0<sub>1</sub>:8

Scale = 1:21.3



<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in	(loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	12	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-R						Weight: 58 lb	FT = 20%F, 11%E

**LUMBER-**

TOP CHORD 2x4 SP No.1(flat)  
BOT CHORD 2x4 SP No.1(flat)  
WEBS 2x4 SP No.3(flat)  
OTHERS 2x4 SP No.3(flat)

**BRACING-**

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.**


All bearings 12-11-0.  
(lb) - Max Grav All reactions 250 lb or less at joint(s) 22, 12, 21, 20, 19, 18, 17, 16, 15, 14, 13

**FORCES.**

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- All plates are 1.5x3 MT20 unless otherwise indicated.
- Plates checked for a plus or minus 1 degree rotation about its center.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 1-4-0 oc.
- Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



April 27, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road  
Edenton, NC 27932

# Symbols

## PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

\* Plate location details available in **MITek 20/20 software or upon request.**

## PLATE SIZE

**4 X 4**

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

## LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

## BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

### Industry Standards:

ANSI/TPI 1: National Design Specification for Metal Plate Connected Wood Truss Construction.  
DSB-89: Design Standard for Bracing, Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

# Numbering System

6-4-8  
dimensions shown in ft-in-sixteenths  
(Drawings not to scale)



**JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.**

**CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.**

## PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988  
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITteK® All Rights Reserved



MITek Engineering Reference Sheet: MII-7473 rev. 5/19/2020



# General Safety Notes

## Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Rewriting pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.