

Harnett County Department of Public Health

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: 110 Thorntons Creek Dr. (Old Stage Rd. S
 SUBDIVISION Thorntons Creek LOT # 15

ISSUED TO: Stand Cure Custom Homes Inc.

NEW REPAIR EXPANSION

Type of Structure: 63x65 sfd, 4 beds 3 baths

Proposed Wastewater System Type: 25% Reduction Sys.

Projected Daily Flow: 480 GPD

Number of bedrooms: 4 Number of Occupants: 8 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well NA feet

Permit valid for: Five years No expiration

Permit conditions: _____

Authorized State Agent: [Signature] Date: 11/30/2021 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Stand Cure Custom Homes Inc. PROPERTY LOCATION: 110 Thorntons Creek Dr. (Old Stage Rd
 SUBDIVISION Thorntons Creek LOT # 15

Facility Type: 63x65 sfd, 4 beds 3 baths New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 480 GPD

(See note below, if applicable) 25% REDUCTION SYS. (Repair)

Installation Requirements/Conditions

Septic Tank Size 1250 gallons Number of trenches 3

Pump Tank Size _____ gallons Exact length of each trench 110 feet

Trenches shall be installed on contour at a Trench Spacing: 9 Feet on Center

Maximum Trench Depth of: 22 inches Soil Cover: 10 inches

(Trench bottoms shall be level to +1/4" (Maximum soil cover shall not exceed 36" above the trench bottom)

in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: NA inches below pipe

Conditions: GAVITT TO D-BOX EQUAL DISTRIBUTION NA inches above pipe

NA inches total

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 11/30/2021

ANDREW CORN Construction Authorization Expiration Date: 11/30/2026

