NOTE:

ALL WORK IS TO BE DONE IN ACCORDANCE WITH THE CURRENT VERSION OF THE NORTH CAROLINA BUILDING CODE.

ALL DIMENSIONS ARE TO BE CONFIRMED BY CONTRACTOR

BEFORE CONSTRUCTION AND BEFORE ORDERING MATERIALS.

THE CONTRACTOR MUST VERIFY SIZE AND SPACING OF ALL STRUCTURAL MEMBERS BASED ON SPANS AND LOADS PRIOR TO CONSTRUCTION OR ORDERING MATERIALS.

THE CONTRACTOR MUST VERIFY FOOTING REQUIREMENTS FOR LOADS AND SOIL CONDITIONS AND PROVIDE ADEQUATE FOOTINGS.

FIELD VERIFY LOCATION AND SIZE OF CRAWLSPACE ACCESS.

CONTRACTOR MUST CONSULT W/ HOME OWNER TO DETERMINE MATERIAL / FINISH OF FOUNDATION WALL. ADJUST DIMENSIONS OF FOUNDATION WALL AS REQUIRED SO THAT THE FLOOR PLAN REMAINS UNCHANGED. (I.E. BRICK VENEER, ETC.)

SEALED CRAWLSPACE PER CODE.

PER OWNER'S REQUEST - FLOOR OF CRAWLSPACE TO BE ABOVE EXTERIOR GRADE. CONTRACTOR MUST MAINTAIN AT LEAST 40"
BETWEEN CRAWLSPACE FLOOR AND BOTTOM OF FLOOR JOISTS.

LEGEND

(3) 2x10 GRIDER

4" BRICK VENEER

DOUBLE 2x10 FLOOR JOIST

2x10 FLOOR JOIST

CONCRETE MASONRY UNIT (CMU)

CRAWLSPACE VENTILATION CALC.

NO FOUNDATION VENTS REQUIRED - SEALED CRAWLSPACE PER CODE.

NOTE:

ALL WORK IS TO BE DONE IN ACCORDANCE WITH THE CURRENT VERSION OF THE NORTH CAROLINA BUILDING CODE.

ALL DIMENSIONS ARE TO BE CONFIRMED BY CONTRACTOR BEFORE CONSTRUCTION AND BEFORE ORDERING MATERIALS.

CONTRACTOR MUST CONFIRM SIZES OF ALL STRUCTURAL MEMBERS MEET CODE BASED ON SPANS AND LOADS FOR

GIVEN LOCATIONS BEFORE CONSTRUCTION AND BEFORE ORDERING MATERIALS. CONSULT WITH AN ENGINEER IF NEEDED.

FIELD LOCATE PULL-DOWN ATTIC ACCESS WITH OWNER.

FIELD VERIFY LOCATION AND SIZE OF CRAWLSPACE ACCESS.

2'-8"x3'-2"	1	
2'-0"x3'-4"	1	GLASS BLOCK

WINDOW SCHEDULE

1 TIGHT MULLED

QTY.

5

(3) 2'-8"x5'-2" 2 TIGHT MULLED

SIZE

2'-8"x5'-2"

(2) 2'-8"x5'-2"

FENESTRATION CALC.

EXTERIOR WALL AREA			
PERIMETER 1st FLOOR	168'-8"		
WALL HEIGHT 1st FLOOR	9'-0"		
TOTAL WALL AREA	1518 SQ. FT.		

EXTERIOR WALL OPENINGS

TOTAL FOR WINDOWS 187 SQ. FT.


TOTAL FOR DOORS 120 SQ. FT.

TOTAL AREA OF OPENINGS 307 SQ. FT.

AREA OF OPENINGS MUST BE LESS THAN
15% OF TOTAL AREA OF EXTERIOR WALL.

THEREFORE X = 20.22%

DOOR SCHEDULE SIZE 5'-0"x6'-8" 3' EXTERIOR, FRONT ENTRY W/ SIDE LITES EXTERIOR, GARAGE ENTRY EXTERIOR, LAUNDRY ENTRY 3'-0"x6'-8" 10'-0"x6'-8" EXTERIOR, GLASS DOUBLE SLIDER 2'-8"x6'-8" INTERIOR INTERIOR 2'-6"x6'-8" 2'-0"x6'-8" INTERIOR INTERIOR, DOUBLE DOOR 4'-0"x6'-8"



6" Exterior Walls - Typ.

PLANS FOR:

MCBride Residence

REVISIONS

ALL WORK TO BE DONE SHALL BE IN ACCORDANCE WITH THE CURRENT VERSION OF THE NORTH CAROLINA BUILDING CODE.

THE CONTRACTOR IS
RESPONSIBLE FOR CHECKING ALL
DIMENIONS PRIOR TO
CONSTRUCTION OR ORDERING
MATERIALS. THE CONTRACTOR IS
ALSO RESPONSIBLE FOR
VERIFYING REQUIRED SIZES OF
ALL STRUCTURAL ELEMENTS
(FOOTINGS, BEAMS, JOISTS,

COPYRIGHT © 2021
ALL RIGHTS RESERVED.
REPRODUCTION OF THIS SHEET,
IN WHOLE OR IN PART, IS
STRICTLY PROHIBITED WITHOUT
EXPRESS WRITTEN PERMISSION
OF THE DESIGNER. USE OF PLANS
FOR CONSTRUCTION OF
DUPLICATE BUILDINGS MUST BE
APPROVED BY THE DESIGNER.
PLANS NOT VALID FOR
CONSTRUCTION WITHOUT
APPROPRIATE PROFESSIONAL
SEALS AND APPROVALS.

COLUMNS, RAFTERS, ETC.)

DATE 4-12-2021


DRAWN BY: JMP

JOB NO. 21-01

SHEET NO.

FOUNDATION FRAMING & FLOOR PLAN

A100




FOUNDATION PLAN

Bottom of floor joists to be at least

Scale: 1/4" = 1'-0"
Sealed Crawlspace

40" above grade.

42'-0"



ALL WORK TO BE DONE SHALL BE
IN ACCORDANCE WITH THE
CURRENT VERSION OF THE
NORTH CAROLINA BUILDING

THE CONTRACTOR IS RESPONSIBLE FOR CHECKING ALL CONSTRUCTION OR ORDERING MATERIALS. THE CONTRACTOR IS VERIFYING REQUIRED SIZES OF ALL STRUCTURAL ELEMENTS (FOOTINGS, BEAMS, JOISTS,

REPRODUCTION OF THIS SHEET, STRICTLY PROHIBITED WITHOUT EXPRESS WRITTEN PERMISSION OF THE DESIGNER. USE OF PLANS **DUPLICATE BUILDINGS MUST BE** APPROVED BY THE DESIGNER. APPROPRIATE PROFESSIONAL

4-12-2021