DAVID MILLER, PE

6300 Creedmoor Rd, STE 170#363 Raleigh, NC 27612 (919) 422-8932 (Office); <u>DAVE@DMA-PA.COM</u>

August 19,2021

Weaver Development Company

DBA: Weaver Homes 309 Wagoner Drive Fayetteville, NC 28303 Johnny 910-978–0435

Brooke Weaver; brooke@weaver-homes.com

e-mailed to: johnny@weaver-homes.com; Duston Blackwell 919-606-4696

e-mailed to: cdb1971@gmail.com;

RE: Engineering - Foundation Analysis Lot 3 Williams Farms Subdivision, Erwin NC Project No.:21DDM-0819D

To whom it may concern:

The undersigned arrived on-site 8-19-21 to observe, probe and perform Dynamic Cone Penetrometer (DCP) testing in general accordance with the American Standard Testing Methods (ASTM) special publication 399 on the grey silty sandy fill soil materials at the above referenced site. Based on the observations and test data the grey silty sandy fill soils were adequately compacted at the tested locations.

Sincerely,

David Miller, PE

DEM/21DDM-0819D



1934 Josie Williams Rd. Erwn, NC 28339