North Carolina 2018 - R402.1.5 Total UA

Property

20 Walker Grove Lane Lillington, NC 27546 Model: 2672 Wayne E-D4_1 Community: Walkers Grove

Walkers Grove 18

True_Walkers Grove 18_2672 Wayne E-D4_1_GL_WinPerPlan Organization

Performance Point, LLC. Rick Blair 704-614-7175

Builder

True Homes

ization Inspection Status
nance Point, LLC. Results are projected

This report is based on a proposed design and does not confirm field enforcement of design elements.

Building UA

Elements	NC Reference	As Designed
Ceilings	49.9	44.5
Above-Grade Walls	187.4	191.7
Windows, Doors and Skylights	110.9	95.2
Slab Floor:	89.6	89.6
Framed Floors	0.0	0.0
Foundation Walls	0.0	0.0
Rim Joists	9.4	9.2
Overall UA (Design must be equal or lower):	447.2	430.2

Requirements

402.1.5	Total UA alternative compliance passes by 3.8%.	
402.3.2 Glazed Fenestration SHGC	Average SHGC: 0.30 Max SHGC: 0.30	
R402.4.2.2	Air Leakage Testing	Air sealing is 5.00 ACH at 50 Pa. It must not exceed 5.00 ACH at 50 Pa.
R402.5	Area-weighted average fenestration SHGC	
R402.5	Area-weighted average fenestration U-Factor	
R404.1	Lighting Equipment Efficiency	
Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met.	
R403.3.1	Duct Insulation	
403.3.3	Duct Testing	

Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 3.8%.

Name:	Rick Blair	Signature:	12/152
Organization:	Performance Point, LLC.	Digitally signed:	7/6/21 at 10:36 AM

Property

20 Walker Grove Lane Lillington, NC 27546 Model: 2672 Wayne E-D4 1 Community: Walkers Grove

Walkers Grove 18

True Walkers Grove 18 2672 Wayne E-D4 1 GL WinPerPlan Organization

Performance Point, LLC. Rick Blair 704-614-7175

Builder True Homes Inspection Status Results are projected

General Building Information

Conditioned Area (sq ft) 2.648 Conditioned Volume (cubic ft) 24,306 Insulated Shell Area (sq ft) 6.247.5

The building energy model in Ekotrope reflects the building assemblies and energy features listed below. Sometimes energy features will change in the field from what has been modeled. The inspection process should identify any changes and ensure that the home continues to meet the applicable energy code.

	Name: House Slab (1,664 s.f., 180 ft. exterior perimeter R-10 perimeter insulation, R-0 under slab insulation.		
Framed Floor			
	None Present		
Four	ndation Wall		

Above Grade Wall

None Present

	Name: 2x4 Ambient (2,026 s.f.) R-0 continuous insulation, R-15 cavity insulation Insulation Grade: I
Д	Name: Niche (2 s.f.) R-3 continuous insulation, R-0 cavity insulation Insulation Grade: I
	Name: 2x4 Garage (289.1 s.f.) R-0 continuous insulation, R-15 cavity insulation Insulation Grade: I
	Name: 2x4 Kneewall (433.3 s.f.) R-0 continuous insulation, R-15 cavity insulation Insulation Grade: I

Property

20 Walker Grove Lane Lillington, NC 27546 Model: 2672 Wayne E-D4_1 Community: Walkers Grove

Walkers Grove 18 True_Walkers Grove 18_2672 Wayne E-D4_1_GL_WinPerPlan

Organization Performance Point I

Performance Point, LLC. Rick Blair 704-614-7175

Builder True Homes Inspection Status Results are projected

Rim	Joist		
	Name: Ambient (55.3 s.f.) R: 13.30		
П	Name: Attic (94.6 s.f.) R: 13.30		
П	Name: Garage (19.2 s.f.) R: 13.30		
Ceili	ng / Roof		
	Name: 1st FI Ceiling (680 s.f.) R-0 continuous insulation, R-38 cavity insulation Insulation Grade: I		
	Name: 2nd Fl Ceiling (984 s.f.) R-28.5 continuous insulation, R-9.5 cavity insulation Insulation Grade: I		
Opa	que Door		
	Name: Front Door (20 s.f.) R: 7.00		
П	Name: Garage Entry (17.8 s.f.) R: 7.00		
	Name: Attic Door (17.8 s.f.) R: 5.00		
Glaz	ing		
П	Name: Front (45 s.f.), U: 0.330, SHGC: 0.3, Orientation: SOUTH		

Name: Front SHD (30 s.f.), U: 0.330, SHGC: 0.3, Orientation: SOUTH

Property Organization Inspection Status 20 Walker Grove Lane Performance Point, LLC. Results are projected Lillington, NC 27546 Rick Blair Model: 2672 Wayne E-D4 1 704-614-7175 Community: Walkers Grove Builder Walkers Grove 18 True Homes True Walkers Grove 18 2672 Wayne E-D4 1 GL WinPerPlan Name: Right (45 s.f.), U: 0.330, SHGC: 0.3, Orientation: EAST Name: Back (105 s.f.), U: 0.330, SHGC: 0.3, Orientation: NORTH Name: Left -Laundry 2'6"x5' (12.5 s.f.), U: 0.330, SHGC: 0.3, Orientation: WEST Name: Left - MSTR BA 2'x3' (6 s.f.), U: 0.330, SHGC: 0.3, Orientation: WEST Name: Left Door (17.8 s.f.), U: 0.330, SHGC: 0.3, Orientation: WEST Skylight None Present Mechanical Ventilation None Present Mechanical Equipment Water Heater • Electric • 100% Hot Water Load @ 0.95 Energy Factor Heat Pump / All • Electric • 100% Heating Load @ 8.2 HSPF, 100% Cooling Load @ 14 SEER Air Leakage Control Test Status: Blower-door tested House is air-sealed as to achieve 2,026 CFM50 (5.00 ACH50) or less at final blower-door test.

Infiltration Requirements for IECC in Climate Zone 4

2009 IECC Infiltration limit for the design home is 7 ACH50.

2012 IECC Infiltration limit for the design home is 3 ACH50.

2015 IECC Infiltration limit for the design home is 3 ACH50.

2018 IECC Infiltration limit for the design home is 3 ACH50.

Property

20 Walker Grove Lane Lillington, NC 27546 Model: 2672 Wayne E-D4_1 Community: Walkers Grove

Walkers Grove 18 True_Walkers Grove 18_2672 Wayne E-D4 1 GL WinPerPlan Organization

Performance Point, LLC. Rick Blair 704-614-7175

Builder True Homes **Inspection Status**Results are projected

Duct Leakage

Duct System 1

NOT entirely within conditioned space, testing required Leakage to Outside specified as: 4 CFM25 / 100 ft² Total Leakage specified as: 4 CFM25 / 100 ft² (Post-Construction)

Duct Leakage Code Requirements for IECC

2009 IECC:

Postconstruction Leakage Test: Duct Leakage to Outdoors <= 8 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage <= 6 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

2012 IECC Mandatory, 2015 and 2018 IECC Prescriptive Paths:

Postconstruction Leakage Test: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage <= 3 CFM25 / 100 sq ft CFA.

2015 and 2018 IECC Performance Paths (Cost Compliance):

Leakage testing is required UNLESS all ducts and air handlers are located entirely within the thermal envelope.

There is no pass/fail threshold for duct leakage on the performance path.

Project Notes

HG_05/05/2021___N/S Performance Report True_2672 Wayne E-D4_1

Worst Orientation (SE)

DG_05/06/2021 Revised

Energy Specifications Label

20 Walker Grove Lane

Model: 2672 Wayne E-D4_1 Ekotrope RATER - Version: 4.0.0.2704

Building Envelope Specs

Ceiling: R-38

Above Grade Walls: R-15 Foundation Walls: N/A Exposed Floor: N/A

Slab: R-10

Infiltration: 5 ACH50

Duct Insulation: Supply: R8, Return: R8 Duct Lkg to Outdoors: 4 CFM25 / 100 ft²

Window & Door Specs

U-Value: 0.33, SHGC: 0.3

Door: R-7

Mechanical Equipment Specs

Heating: Air Source Heat Pump • Electric • 8.2

HSPF

Cooling: Air Source Heat Pump • Electric • 14

SEER

Hot Water: Water Heater • Electric • 0.95 Energy

Factor

Average Mechanical Ventilation: 0 CFM

Builder or Design Professional

Signature:

Builder Affidavit

Property

20 Walker Grove Lane Lillington, NC 27546 Model: 2672 Wayne E-D4_1 Community: Walkers Grove

Walkers Grove 18 True_Walkers Grove 18_2672 Wayne E-D4 1 GL WinPerPlan Organization
Performance Point, LLC.
Rick Blair

Rick Blair 704-614-7175

Builder True Homes **Inspection Status**Results are projected

Important Notice to Builder

Builder affirms in this affidavit that all building characteristics described in the Building Summary Report accurately reflect this New Home. Builder agrees to allow the Home Energy Rating System (HERS) Provider and/or Rater to verify building characteristics of this New Home fully at the HERS Rater/Provider's discretion. The HERS Provider and Rater do not create or imply any duty or obligations to Builder or any subsequent owner. Builder is responsible for taking any actions necessary to protect Builder's interest. There is no guarantee or warranty whatsoever expressed or implied from the HERS Provider or Rater.

HERS® Index Score:80

Builder Name: True Ho	omes	Builder Signature:	Ashley Jones
Name:	Rick Blair	Signature:	TUTSZ
Organization:	Performance Point, LLC.	Digitally signed:	7/6/21 at 10:36 AM