

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: 21031298
WAG-18

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by The Building Center.

Pages or sheets covered by this seal: I45482357 thru I45482396

My license renewal date for the state of North Carolina is December 31, 2021.

North Carolina COA: C-0844



April 5, 2021

Johnson, Andrew


IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job 21031298	Truss A01	Truss Type Common	Qty 3	Ply 1	WAG-18	145482357
-----------------	--------------	----------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:20:30 2021 Page 1

ID:kRYsvCFZGIM3FfDJckq8VhyKJWz-iKt?LgDoq4z5bPBSxlQz_gyUDkZUPK1KheOK1JzUml



5x5 =

Scale: 3/16"=1'




Plate Offsets (X,Y)-- [1:0-0-0,0-1-1], [9:Edge,0-1-1]						
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl
TCLL 20.0	Plate Grip DOL	1.15	TC 0.44	Vert(LL)	-0.16 10-12	>999 360
TCDL 10.0	Lumber DOL	1.15	BC 0.88	Vert(CT)	-0.39 10-12	>999 240
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.47	Horz(CT)	0.12 9	n/a n/a
BCDL 10.0	Code IRC2015/TP12014		Matrix-AS			
						PLATES
						MT20
						GRIP
						244/190
						Weight: 190 lb
						FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 6-12, 4-12
WEDGE	
Left: 2x4 SP No.3 , Right: 2x4 SP No.3	

REACTIONS. (size) 1=Mechanical, 9=Mechanical
 Max Horz 1=126(LC 14)
 Max Uplift 1=-135(LC 10), 9=-135(LC 11)
 Max Grav 1=1476(LC 1), 9=1476(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-2699/284, 2-4=-2445/276, 4-5=-1736/270, 5-6=-1736/270, 6-8=-2445/276, 8-9=-2699/284
 BOT CHORD 1-14=-298/2337, 12-14=-173/1925, 10-12=-108/1925, 9-10=-188/2337
 WEBS 5-12=-97/1134, 6-12=-667/200, 6-10=-29/499, 8-10=-328/164, 4-12=-667/200, 4-14=-29/499, 2-14=-328/164

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 15-5-6, Exterior(2) 15-5-6 to 21-5-6, Interior(1) 21-5-6 to 33-10-12, Exterior(2) 33-10-12 to 36-10-12 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=135, 9=135.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.




April 5, 2021

Job 21031298	Truss A01A	Truss Type Common	Qty 7	Ply 1	WAG-18	145482358
-----------------	---------------	----------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:20:31 2021 Page 1

ID:kRYSvcFZGIM3FfDjCkq8VhyKJWz-AWQNZ0DQbO5yDZmeUSxCWtVb07t28g1Twl8tZlZUmok



5x5 =

Scale = 1:68.2





Plate Offsets (X, Y)-- [1:0-0-0,0-0-13], [9:Edge,0-0-13], [12:0-1-12,0-2-0], [13:0-1-12,0-2-0]


LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.70	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.99	Vert(LL) -0.75 13-15 >587 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.93	Vert(CT) -0.90 13-15 >493 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-AS	Horz(CT) 0.10 9 n/a n/a		
	Code IRC2015/TPI2014			Weight: 209 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.1 *Except* 12-13: 2x6 SP No.1	BOT CHORD Rigid ceiling directly applied.
WEBS 2x4 SP No.3	JOINTS 1 Brace at Jt(s): 16
OTHERS 2x4 SP No.3	
WEDGE Left: 2x4 SP No.3 , Right: 2x4 SP No.3	

REACTIONS. (size) 1=Mechanical, 9=Mechanical
 Max Horz 1=126(LC 10)
 Max Uplift 1=-135(LC 10), 9=-135(LC 11)
 Max Grav 1=1476(LC 1), 9=1476(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-2694/267, 2-4=-2116/267, 4-5=-350/114, 5-6=-350/114, 6-8=-2116/267,
 8-9=-2694/267
 BOT CHORD 1-15=-291/2324, 13-15=-291/2324, 12-13=-84/1821, 10-12=-167/2324, 9-10=-167/2324
 WEBS 6-12=0/531, 8-12=-763/236, 8-10=0/268, 4-13=0/531, 2-13=-763/236, 2-15=0/268,
 4-16=-1598/207, 6-16=-1598/207

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 15-5-6, Exterior(2) 15-5-6 to 21-5-6, Interior(1) 21-5-6 to 33-10-12, Exterior(2) 33-10-12 to 36-10-12 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=135, 9=135.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



Job 21031298	Truss A01GE	Truss Type Common Supported Gable	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482359
-----------------	----------------	--------------------------------------	----------	----------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:20:34 2021 Page 1

ID:kRYSvcFZGIM3FDJCKq8VhyKJWz-b56VB1GluTX40VDAaVv8W7FIL8fLElwcGNyA4zUmoh





Plate Offsets (X,Y)--	[7:0-2-8,0-3-0], [23:0-2-8,0-3-0], [39:0-1-10,0-1-8], [49:0-1-10,0-1-8]
-----------------------	---

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.09	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.03	Vert(LL) n/a - n/a 999		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.10	Vert(CT) n/a - n/a 999		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.01 29 n/a n/a		
	Code IRC2015/TPI2014			Weight: 305 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SP No.3	WEBS 1 Row at midpt 15-44, 14-45, 16-43

REACTIONS. All bearings 36-10-12.
 (lb) - Max Horz 1=129(LC 14)
 Max Uplift All uplift 100 lb or less at joint(s) 1, 45, 46, 47, 48, 50, 51, 52, 53, 54, 55, 56, 57, 58, 43, 42, 41, 40, 38, 37, 36, 35, 34, 33, 32, 31, 30
 Max Grav All reactions 250 lb or less at joint(s) 1, 29, 44, 45, 46, 47, 48, 50, 51, 52, 53, 54, 55, 56, 57, 58, 43, 42, 41, 40, 38, 37, 36, 35, 34, 33, 32, 31, 30

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 14-15=-87/265, 15-16=-87/265

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) 0-0-0 to 3-0-0, Exterior(2) 3-0-0 to 15-5-6, Corner(3) 15-5-6 to 21-5-6, Exterior(2) 21-5-6 to 33-10-12, Corner(3) 33-10-12 to 36-10-12 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 1-4-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 45, 46, 47, 48, 50, 51, 52, 53, 54, 55, 56, 57, 58, 43, 42, 41, 40, 38, 37, 36, 35, 34, 33, 32, 31, 30.
 - Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 29.




April 5, 2021

Job 21031298	Truss A02GE	Truss Type GABLE	Qty 1	Ply 1	WAG-18	145482360
-----------------	----------------	---------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,



8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:20:37 2021 Page 1

ID:kRYSvcFZGIM3FfDJCkq8VhyKJWz-goep3lBBEr6xUDorj2cm8lfuYxNY7MIEbCnPzUmoe



5x5 =

Scale = 1:64.9



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.48	Vert(LL)	-0.17	16-18	>999	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.93	Vert(CT)	-0.43	16-18	>633		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.32	Horz(CT)	0.07	76	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-AS						
								Weight: 338 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP DSS *Except* 17-19: 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 6-18, 4-18
OTHERS 2x4 SP No.3	
WEDGE Left: 2x4 SP No.3, Right: 2x4 SP No.3	

REACTIONS. All bearings 8-0-0 except (jt=length) 1=7-0-12, 21=7-0-12, 22=7-0-12, 23=7-0-12, 24=7-0-12, 25=7-0-12, 1=7-0-12.
 (lb) - Max Horz 1=126(LC 10)
 Max Uplift All uplift 100 lb or less at joint(s) 1, 9, 21, 23, 25, 13, 12, 10 except 22=340(LC 1), 15=142(LC 11), 14=806(LC 1)
 Max Grav All reactions 250 lb or less at joint(s) 22, 23, 24, 25, 14, 13, 12, 11, 10 except 1=1137(LC 1), 9=879(LC 1), 21=451(LC 1), 15=1200(LC 1), 1=1137(LC 1), 9=879(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-2062/232, 2-4=-1810/224, 4-5=-1326/228, 5-6=-1326/228, 6-8=-1366/162, 8-9=-1620/177
 BOT CHORD 1-25=-263/1765, 24-25=-263/1765, 23-24=-263/1765, 22-23=-263/1765, 21-22=-263/1765, 20-21=-263/1765, 18-20=-141/1456, 16-18=-37/1253, 15-16=-96/1372, 14-15=-96/1372, 13-14=-96/1372, 12-13=-96/1372, 11-12=-96/1372, 10-11=-96/1372, 9-10=-96/1372
 WEBS 5-18=-60/769, 6-18=-313/161, 8-16=-320/166, 4-18=-542/192, 4-20=-17/283, 2-20=-314/165

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 15-5-6, Exterior(2) 15-5-6 to 21-5-6, Interior(1) 21-5-6 to 33-10-12, Exterior(2) 33-10-12 to 36-10-12 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 4) All plates are 2x4 MT20 unless otherwise indicated.
 - 5) Gable studs spaced at 1-4-0 oc.
 - 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 9, 21, 23, 25, 24=340(LC 1), 15=142(LC 11), 14=806(LC 1).



April 5, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ENGINEERING BY
TRENCO
 A MiTek Affiliate
 818 Soundside Road
 Edenton, NC 27932

Job 21031298	Truss A02GE	Truss Type GABLE	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482360
-----------------	----------------	---------------------	----------	----------	--	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:20:37 2021 Page 2
ID:kRYSvcFZGIM3FfDJCkq8VhyKJWz-?goep3lBBEr6xUDorj2cm8lfuYxNYY7MIEbCnPzUmoe

NOTES-

- 9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
Edenton, NC 27932

Job 21031298	Truss B01	Truss Type Roof Special	Qty 2	Ply 1	WAG-18	145482361
-----------------	--------------	----------------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:20:39 2021 Page 1

ID:kRYSvcFZGIM3FFDJCKq8VhyKJWz-x2vOEIKRjr6pBoNBBy844rZq0kMmt0RxfmY4JrHzUmoc



Scale = 1:44.7





Plate Offsets (X, Y)--	[1:0-2-0,0-0-1], [9:0-2-0,0-3-0]
------------------------	----------------------------------

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.39	Vert(LL)	-0.03	9	>999	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.35	Vert(CT)	-0.08	9-10	>999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.36	Horz(CT)	0.03	7	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-AS						
								Weight: 124 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied.
WEBS 2x4 SP No.3	
SLIDER Left 2x4 SP No.3 -t 2-6-0	

REACTIONS. (size) 1=0-3-8, 7=0-3-8
 Max Horz 1=-131(LC 8)
 Max Uplift 1=-76(LC 10), 7=-78(LC 11)
 Max Grav 1=891(LC 1), 7=891(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-3=-1259/160, 3-4=-950/172, 4-5=-928/167, 5-6=-1174/147, 6-7=-831/130
 BOT CHORD 1-10=-145/1080, 9-10=-145/1080, 8-9=-77/987
 WEBS 3-9=-421/142, 4-9=-43/505, 5-9=-328/121, 6-8=-52/874

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 8-0-14, Exterior(2) 8-0-14 to 14-0-14, Interior(1) 14-0-14 to 19-3-4, Exterior(2) 19-3-4 to 22-3-4 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 7.
 - 6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



Job 21031298	Truss C01	Truss Type ATTIC	Qty 7	Ply 1	WAG-18 Job Reference (optional)	145482362
-----------------	--------------	---------------------	----------	----------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:20:41 2021 Page 2
ID:kRYSvcFZGIM3FDJCkq8VhyKJWz-tR19fRLhFSMXQ5XZ4Y7Yw_wJ09LvUBwyDsZPwAzUmoa

NOTES-

- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 31, 20, 15 except (jt=lb) 34=252.
- 10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 12) Attic room checked for L/360 deflection.

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	WAG-18	145482363
21031298	C01GE	GABLE	1	1		

The Building Center, Gastonia, NC - 28052, 8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:20:59 2021 Page 1
 ID:kRYSvcFZGIM3FfDJCkq8VhyKJWz-Mv7yRbZ_?_d_asv17KRnfnfOTQV6hKNbMfwMYzUmol



Scale: 1/8"=1'




Plate Offsets (X,Y)--	[2:0-2-14,0-2-0], [5:0-6-0,0-2-4], [6:0-3-8,0-1-8], [8:0-2-8,0-3-0], [10:0-6-0,0-2-8], [13:0-2-8,0-3-0], [25:0-2-8,0-3-0], [28:0-2-8,0-2-4], [33:0-1-14,0-1-0], [38:0-2-8,0-2-8], [39:0-2-0,0-0-4], [51:0-1-8,0-1-0], [55:0-1-8,0-1-0], [73:0-1-15,0-1-0], [76:0-1-15,0-1-0], [79:0-1-15,0-1-0], [82:0-1-15,0-1-0]
-----------------------	--

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.60	Vert(LL)	-0.24 18-20	>999	360	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.76	Vert(CT)	-0.36 18-20	>676	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.97	Horz(CT)	0.02 15	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-AS	Attic	-0.11 22-28	1347	360	Weight: 713 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (5-1-5 max.): 5-10.
BOT CHORD 2x4 SP No.1 *Except* 22-28: 2x4 SP No.2, 19-25,25-30: 2x4 SP DSS	BOT CHORD Rigid ceiling directly applied. Except: 3-10-0 oc bracing: 22-28
WEBS 2x4 SP No.3 *Except* 7-29,11-20,35-38: 2x4 SP No.2	WEBS 1 Row at midpt 4-32, 31-37, 28-38, 22-35, 12-20, 5-31
OTHERS 2x4 SP No.3	JOINTS 1 Brace at Jt(s): 36, 37, 38, 39
WEDGE Right: 2x4 SP No.3	

REACTIONS. All bearings 0-3-8.
 (lb) - Max Horz 34=222(LC 6)
 Max Uplift All uplift 100 lb or less at joint(s) 31, 20, 15 except 34=252(LC 25)
 Max Grav All reactions 250 lb or less at joint(s) 34 except 31=2779(LC 2), 20=2048(LC 2), 15=787(LC 23)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-4=-44/424, 4-5=0/827, 5-6=0/823, 7-9=-1015/263, 9-10=-1015/263, 12-14=-808/111, 14-15=-1087/103, 2-34=-143/295
 BOT CHORD 32-33=-335/249, 31-32=-667/179, 29-31=-615/35, 27-29=-661/20, 25-27=0/2078, 21-25=0/1399, 20-21=0/1399, 18-20=0/404, 17-18=-2/897, 15-17=-2/897, 26-28=-1294/0, 24-26=-1294/0, 23-24=-2075/0
 WEBS 4-33=0/429, 4-32=-699/137, 5-32=-59/689, 31-37=-1458/62, 6-37=-406/102, 28-38=-546/174, 7-38=-606/195, 20-22=-771/128, 22-35=-744/141, 11-35=-756/159, 12-20=-720/221, 12-18=-68/687, 14-18=-539/172, 2-33=-391/32, 28-31=-542/182, 28-37=0/1288, 37-38=-766/0, 6-38=0/908, 5-31=-1250/69, 9-39=-385/137, 10-39=-190/1078, 7-39=-249/1010, 26-27=-345/0, 23-25=0/705, 20-23=-1494/0, 27-28=0/2038, 24-27=-810/0

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 8-7-6, Exterior(2) 8-7-6 to 17-1-3, Interior(1) 17-1-3 to 28-9-1, Exterior(2) 28-9-1 to 37-2-15, Interior(1) 37-2-15 to 51-10-8, Exterior(2) 51-10-8 to 54-10-8 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) All plates are 2x4 MT20 unless otherwise indicated.
 - 6) Gable studs spaced at 1-4-0 oc.
- Continued on page 2
 This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.



April 5, 2021

Job	Truss	Truss Type	Qty	Ply	WAG-18	I45482363
21031298	C01GE	GABLE	1	1	Job Reference (optional)	

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:20:59 2021 Page 2
 ID:kRYSvcFZGIM3FDJCKq8VhyKJWz-Mv7yRbZ_?_d_asv17KRnfnfOTQV6hKNbMfwMY7zUmol

NOTES-

- 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
- 9) Ceiling dead load (5.0 psf) on member(s). 38-39, 36-39, 35-36, 37-38
- 10) Bottom chord live load (40.0 psf) and additional bottom chord dead load (0.0 psf) applied only to room. 26-28, 24-26, 23-24, 22-23
- 11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 31, 20, 15 except (jt=lb) 34=252.
- 12) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 14) Attic room checked for L/360 deflection.

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601





818 Soundside Road
 Edenton, NC 27932

Job 21031298	Truss C02	Truss Type MONOPICH	Qty 2	Ply 1	WAG-18 Job Reference (optional)	145482364
-----------------	--------------	------------------------	----------	----------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:00 2021 Page 1

ID:kRYSvcFZGIM3FDJcKq8VhyKJWz-q5hLewacmlrCOUDh2z0C?Cb9qr5QsnlbJgw5azUmoH



Scale = 1:63.3

Plate Offsets (X,Y)--	[2:0-0-0,0-0-9], [8:0-2-8,0-3-4]
-----------------------	----------------------------------


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.48	Vert(LL)	-0.16	7-8	>999	360	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.65	Vert(CT)	-0.23	7-8	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.64	Horz(CT)	0.03	7	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-AS							
									Weight: 121 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 6-7, 5-7

REACTIONS. (size) 2=0-3-8, 7=Mechanical
 Max Horz 2=333(LC 10)
 Max Uplift 2=-50(LC 10), 7=-201(LC 10)
 Max Grav 2=868(LC 1), 7=874(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1309/32, 3-5=-741/0
 BOT CHORD 2-9=-284/1095, 8-9=-284/1095, 7-8=-144/583
 WEBS 3-9=0/263, 3-8=-583/160, 5-8=0/508, 5-7=-815/203

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-10-8 to 2-1-8, Interior(1) 2-1-8 to 17-4-4, Exterior(2) 17-4-4 to 20-4-4 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 7=201.
 - 6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.




April 5, 2021

Job 21031298	Truss C02GE	Truss Type MONOPITCH SUPPORTED	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482365
-----------------	----------------	-----------------------------------	----------	----------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:01 2021 Page 1

ID:kRYSvcFZGIM3FfDJCKq8VhyKJWz-IHEjsGbEXctiqA3PFIUFkCtVdLq9TEupzPTd0zUmoG
9-0-0
9-0-0



Scale = 1:27.3

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.05	Vert(LL)	0.00	1	n/r	120	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.04	Vert(CT)	0.00	1	n/r	90		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.05	Horz(CT)	0.00		n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S							
									Weight: 55 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3


BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 9-0-0.
(lb) - Max Horz 2=153(LC 10)
Max Uplift All uplift 100 lb or less at joint(s) 9, 10, 11, 12, 13, 14
Max Grav All reactions 250 lb or less at joint(s) 9, 2, 10, 11, 12, 13, 14

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-251/83

NOTES-

- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) -0-10-8 to 2-4-0, Exterior(2) 2-4-0 to 5-10-4, Corner(3) 5-10-4 to 8-10-4 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) All plates are 2x4 MT20 unless otherwise indicated.
- 4) Gable requires continuous bottom chord bearing.
- 5) Gable studs spaced at 1-4-0 oc.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 9, 10, 11, 12, 13, 14.



April 5, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job 21031298	Truss C03	Truss Type MONOPITCH	Qty 2	Ply 1	WAG-18 Job Reference (optional)	145482366
-----------------	--------------	-------------------------	----------	----------	------------------------------------	-----------


The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:02 2021 Page 1

ID:kRYSvcFZGIM3FfDJCKq8VhyKJWz-mUo53cbslv?ZRKecoT?UHQHZ_ddKuu612d909SzUmoF



Scale = 1:55.9



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.33	Vert(LL)	-0.02 5-6	>999	360	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.28	Vert(CT)	-0.04 5-6	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.14	Horz(CT)	-0.00 5	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-AS					Weight: 86 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 4-5, 3-5

REACTIONS. (size) 7=0-3-8, 5=Mechanical
 Max Horz 7=215(LC 10)
 Max Uplift 5=-185(LC 10)
 Max Grav 7=496(LC 1), 5=454(LC 17)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-323/0, 2-7=-447/0
 WEBS 3-5=-369/176

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 7-11-4, Exterior(2) 7-11-4 to 10-11-4 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 5=185.
 - 6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



April 5, 2021

Job 21031298	Truss D01	Truss Type MONOPITCH	Qty 9	Ply 1	WAG-18	145482367
-----------------	--------------	-------------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:03 2021 Page 1

ID:kRYSvcFZGIM3FfDJckq8VhyKJWz-EgMTGycV3D7Q3UDoMAWjpdq901zwdNXBHhuaiuzUmoE



Scale = 1:12.7




Plate Offsets (X,Y)-- [2:0-0-5,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.31	Vert(LL)	-0.02	4-7	>999	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.26	Vert(CT)	-0.05	4-7	>999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	2	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-AS						
								Weight: 19 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3


BRACING-
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 2=0-3-8, 4=0-1-8
Max Horz 2=63(LC 6)
Max Uplift 2=-50(LC 6), 4=-36(LC 10)
Max Grav 2=251(LC 1), 4=189(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
- 4) Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 4.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4.
- 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



April 5, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job 21031298	Truss D01GE	Truss Type MONOPITCH SUPPORTED	Qty 2	Ply 1	WAG-18	145482368
					Job Reference (optional)	


The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:03 2021 Page 1

ID:kRYsvfZGIM3FDJcKq8VhyKJWz-EgMTGycV3D7Q3UDoMAWjpdqDr11JdNoBHHuaiuzUmoE



Scale = 1:12.7



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.06	Vert(LL)	0.00	1	n/r	120	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.04	Vert(CT)	0.00	1	n/r	90		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.05	Horz(CT)	0.00		n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-P						Weight: 21 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3


BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 5-0-0.
(lb) - Max Horz 2=63(LC 6)
Max Uplift All uplift 100 lb or less at joint(s) 6, 2, 7, 8
Max Grav All reactions 250 lb or less at joint(s) 6, 2, 7, 8

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) Gable requires continuous bottom chord bearing.
- 4) Gable studs spaced at 1-4-0 oc.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 2, 7, 8.



April 5, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
Edenton, NC 27932

Job 21031298	Truss E01	Truss Type Monopitch	Qty 9	Ply 1	WAG-18	145482369
-----------------	--------------	-------------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:04 2021 Page 1

ID:kRYSvcFZGIM3FDJCKq8VhyKJWz-iswrUld7qXFghdn_wu1yMrNKbRJ_MqnKVxe7ELzUmoD



Scale = 1:17.8

Plate Offsets (X,Y)--		[4:Edge,0-1-14]								
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15		TC 0.32	Vert(LL) -0.02	4-7	>999	360		MT20	244/190
TCDL 10.0	Lumber DOL 1.15		BC 0.27	Vert(CT) -0.05	4-7	>999	240			
BCLL 0.0 *	Rep Stress Incr YES		WB 0.00	Horz(CT) 0.01	2	n/a	n/a			
BCDL 10.0	Code IRC2015/TPI2014		Matrix-AS						Weight: 21 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	3-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS. (size) 2=0-3-8, 4=0-1-8
 Max Horz 2=90(LC 10)
 Max Uplift 2=-25(LC 10), 4=-48(LC 10)
 Max Grav 2=260(LC 1), 4=187(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 4) Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - 5) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 4.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4.
 - 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord.




April 5, 2021

Job 21031298	Truss E01GE	Truss Type GABLE	Qty 1	Ply 1	WAG-18	145482370
					Job Reference (optional)	

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:05 2021 Page 1

ID:kRYSvcFZGIM3FfDJckq8VhyKJWz-B3UDheelbqN7InMBUyYbV2vLrFD5G0UkbnhmzUmoC



Scale = 1:17.8

Plate Offsets (X,Y)--	[4:Edge,0-1-14]							
LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.32	Vert(LL) -0.02	4-11	>999	360	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.27	Vert(CT) -0.05	4-11	>999	240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Horz(CT) 0.01	2	n/a	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-AS					Weight: 25 lb	FT = 20%
	Code IRC2015/TPI2014							

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD 3-0-0 oc bracing.
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	

REACTIONS. (size) 2=0-3-8, 4=0-1-8
 Max Horz 2=90(LC 10)
 Max Uplift 2=-25(LC 10), 4=-48(LC 10)
 Max Grav 2=260(LC 1), 4=187(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 3) Gable studs spaced at 1-4-0 oc.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 6) Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - 7) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 4.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4.
 - 9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord.




April 5, 2021

Job 21031298	Truss F01	Truss Type COMMON	Qty 1	Ply 1	WAG-18	145482371
-----------------	--------------	----------------------	----------	----------	--------	-----------


The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:06 2021 Page 1

ID:kRYSvcFZGIM3FfDJckq8VhyKJWz-fF2cv_eNM8V_wxxN13QRGSgtEsnqgidzF7EIDzUmoB



Scale = 1:36.7



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.27	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.89	Vert(LL) -0.15 8-14 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.23	Vert(CT) -0.31 8-14 >768 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-AS	Horz(CT) 0.03 6 n/a n/a		
	Code IRC2015/TPI2014			Weight: 91 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 WEBS 2x4 SP No.3
 WEDGE
 Left: 2x4 SP No.3 , Right: 2x4 SP No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied.
 BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 2=0-3-8, 6=0-3-8
 Max Horz 2=-74(LC 15)
 Max Uplift 2=-88(LC 10), 6=-88(LC 11)
 Max Grav 2=853(LC 1), 6=853(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1310/195, 3-4=-983/151, 4-5=-983/151, 5-6=-1310/195
 BOT CHORD 2-8=-142/1121, 6-8=-96/1121
 WEBS 4-8=-3/571, 5-8=-366/157, 3-8=-366/157

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 7-0-0, Exterior(2) 7-0-0 to 13-0-0, Interior(1) 13-0-0 to 17-10-8, Exterior(2) 17-10-8 to 20-10-8 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 6.
 - 6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.




April 5, 2021

Job 21031298	Truss F01GE	Truss Type COMMON SUPPORTED GAB	Qty 1	Ply 1	WAG-18	145482372
-----------------	----------------	------------------------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:07 2021 Page 1

ID:kRYSvcFZGIM3FfDJckq8VhyKJWz-7Rc_6Kf?7SdrY5WZb0bf_T?v?eORZAqnCusnrgzUmoA



Scale = 1:36.9




Plate Offsets (X,Y)-- [24:0-2-8,0-3-0]									
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.05	Vert(LL)	-0.00	16	n/r	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	-0.00	16	n/r		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.04	Horz(CT)	0.00	16	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S						
								Weight: 120 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS. All bearings 20-0-0.
 (lb) - Max Horz 2=74(LC 10)
 Max Uplift All uplift 100 lb or less at joint(s) 2, 25, 26, 27, 28, 29, 30, 23, 22, 21, 20, 19, 18, 16
 Max Grav All reactions 250 lb or less at joint(s) 2, 24, 25, 26, 27, 28, 29, 30, 23, 22, 21, 20, 19, 18, 16

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) -0-10-8 to 2-0-0, Exterior(2) 2-0-0 to 7-0-0, Corner(3) 7-0-0 to 13-0-0, Exterior(2) 13-0-0 to 17-10-8, Corner(3) 17-10-8 to 20-10-8 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 4) All plates are 2x4 MT20 unless otherwise indicated.
 - 5) Gable requires continuous bottom chord bearing.
 - 6) Gable studs spaced at 1-4-0 oc.
 - 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 25, 26, 27, 28, 29, 30, 23, 22, 21, 20, 19, 18, 16.



April 5, 2021

Job 21031298	Truss F01GR	Truss Type COMMON GIRDER	Qty 1	Ply 3	WAG-18	145482373
-----------------	----------------	-----------------------------	----------	----------	--------	-----------


The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:09 2021 Page 1

ID:kRYSvcFZGIM3FfDJckq8VhyKJWz-3qjX?hFf3uZnPgyjRd73u458Szm1wf3fCLuvYzUmo8



Scale = 1:36.7



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.59	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.48	Vert(LL) -0.11 9-10 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.66	Vert(CT) -0.22 9-10 >999 240		
BCDL 10.0	Rep Stress Incr NO	Matrix-MSH	Horz(CT) 0.04 6 n/a n/a		
	Code IRC2015/TP12014			Weight: 380 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x8 SP DSS
WEBS 2x4 SP No.3 *Except*
4-9: 2x4 SP No.2


BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-5-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 2=0-3-8, 6=0-3-8
Max Horz 2=-74(LC 32)
Max Uplift 2=-743(LC 8), 6=-878(LC 9)
Max Grav 2=7436(LC 1), 6=8833(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-13346/1315, 3-4=-9470/953, 4-5=-9472/953, 5-6=-13689/1350
BOT CHORD 2-10=-1184/11901, 9-10=-1184/11901, 8-9=-1141/12212, 6-8=-1141/12212
WEBS 4-9=-770/8111, 5-9=-4379/513, 5-8=-327/3767, 3-9=-4020/477, 3-10=-294/3449

- NOTES-**
- 3-ply truss to be connected together with 10d (0.148"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-4-0 oc.
Bottom chords connected as follows: 2x8 - 2 rows staggered at 0-4-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=743, 6=878.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1456 lb down and 155 lb up at 2-0-12, 1456 lb down and 155 lb up at 4-0-12, 1456 lb down and 155 lb up at 6-0-12, 1456 lb down and 155 lb up at 8-0-12, 1456 lb down and 155 lb up at 10-0-12, 1456 lb down and 155 lb up at 12-0-12, 1456 lb down and 155 lb up at 14-0-12, 1456 lb down and 155 lb up at 16-0-12, and 1456 lb down and 155 lb up at 17-6-12, and 1461 lb down and 149 lb up at 19-6-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15



April 5, 2021

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job 21031298	Truss F01GR	Truss Type COMMON GIRDER	Qty 1	Ply 3	WAG-18 Job Reference (optional)	145482373
-----------------	----------------	-----------------------------	----------	-----------------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:09 2021 Page 2
ID:kRYSvcFZGIM3FfDJckq8VhyKJWz-3qjX?hFf3uZnPgyjRd73u458Szm1wf3CLuvYzUmo8

LOAD CASE(S) Standard

Uniform Loads (plf)

Vert: 1-4=-60, 4-7=-60, 11-14=-20

Concentrated Loads (lb)

Vert: 9=-1456(B) 17=-1456(B) 18=-1456(B) 19=-1456(B) 20=-1456(B) 21=-1456(B) 22=-1456(B) 23=-1456(B) 24=-1456(B) 25=-1461(B)

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
Edenton, NC 27932

Job 21031298	Truss PB1	Truss Type GABLE	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482374
-----------------	--------------	---------------------	----------	----------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:12 2021 Page 1
ID:kRYsvCFZGIM3FfDJCKq8VhyKJWz-TPPt91j8x_G8esPXOZAqhXilpf6cER6WLAAyWtzUmo5



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 2-0-0	TC 0.05	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.03	Vert(LL) n/a - n/a 999		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.04	Vert(CT) n/a - n/a 999		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-S	Horz(CT) 0.00 16 n/a n/a		
				Weight: 108 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS. All bearings 20-1-11.
 (lb) - Max Horz 1=114(LC 6)
 Max Uplift All uplift 100 lb or less at joint(s) 1, 16, 2, 24, 26, 27, 28, 29, 22, 21, 20, 19, 18, 17
 Max Grav All reactions 250 lb or less at joint(s) 1, 16, 2, 23, 24, 26, 27, 28, 29, 22, 21, 20, 19, 18, 17, 15

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) 0-3-8 to 3-3-8, Exterior(2) 3-3-8 to 6-3-9, Corner(3) 6-3-9 to 12-3-9, Exterior(2) 12-3-9 to 16-9-13, Corner(3) 16-9-13 to 19-9-13 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 1-4-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 16, 2, 24, 26, 27, 28, 29, 22, 21, 20, 19, 18, 17.
 - See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



Job 21031298	Truss PB2	Truss Type GABLE	Qty 7	Ply 1	WAG-18	145482375
-----------------	--------------	---------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:14 2021 Page 1
ID:kRYSvcFZGIM3FfDJckq8VhyKJWz-QnXdajlOTbWstAYvV_DlMyn2RTIliKqopU3famzUmo3



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.23	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.14	Vert(LL) n/a - n/a 999		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.09	Vert(CT) n/a - n/a 999		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.00 8 n/a n/a		
	Code IRC2015/TPI2014			Weight: 77 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 20-1-11.
(lb) - Max Horz 1=-114(LC 6)
Max Uplift All uplift 100 lb or less at joint(s) 8, 10, 9 except 1=-196(LC 17), 2=-103(LC 10), 13=-105(LC 10)
Max Grav All reactions 250 lb or less at joint(s) 1, 8, 7 except 2=390(LC 17), 11=260(LC 1), 13=376(LC 17), 10=352(LC 22), 9=265(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 3-13=-282/149, 5-10=-268/131

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-3-8 to 3-3-8, Interior(1) 3-3-8 to 6-3-9, Exterior(2) 6-3-9 to 12-3-9, Interior(1) 12-3-9 to 16-9-13, Exterior(2) 16-9-13 to 19-9-13 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 4-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 10, 9 except (jt=lb) 1=196, 2=103, 13=105.
 - See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



April 5, 2021

Job 21031298	Truss R01	Truss Type COMMON	Qty 1	Ply 1	WAG-18	145482376
-----------------	--------------	----------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:15 2021 Page 1

ID:kRYSvcFZGIM3FfDJCkq8VhyKJWz-u_57o3IOEvejVK763hkXI9K4StwPRIGy18oC7CzUmo2



Scale = 1:54.2




Plate Offsets (X,Y)--	[9:0-4-0,0-3-0]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.79	Vert(LL) -0.16 9-10 >999 360	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.85	Vert(CT) -0.33 9-10 >725 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.21	Horz(CT) 0.02 8 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-AS		Weight: 106 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied.
WEBS 2x4 SP No.3	

REACTIONS. (size) 10=0-3-8, 8=0-3-8
 Max Horz 10=-183(LC 8)
 Max Uplift 10=-71(LC 10), 8=-71(LC 11)
 Max Grav 10=850(LC 1), 8=850(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-909/128, 3-4=-697/144, 4-5=-697/144, 5-6=-909/128, 2-10=-749/152, 6-8=-749/152
 BOT CHORD 9-10=-102/652, 8-9=-22/609
 WEBS 4-9=-73/524

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 7-0-0, Exterior(2) 7-0-0 to 13-0-0, Interior(1) 13-0-0 to 17-10-8, Exterior(2) 17-10-8 to 20-10-8 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 10, 8.
- 6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.




Job 21031298	Truss R01GE	Truss Type COMMON SUPPORTED GAB	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482377
-----------------	----------------	------------------------------------	----------	----------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:17 2021 Page 1

ID:kRYSvcFZGIM3FfDJCkq8VhyKJWz-qMCmDknHmWuQkdHUB6m?OaPaqgofvhOFVSHJB4zUmo0



4x4 =

Scale = 1:55.6





Plate Offsets (X,Y)--	[28:0-2-8,0-3-0]								
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.16	Vert(LL)	-0.00	19	n/r	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.10	Vert(CT)	-0.00	19	n/r		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.10	Horz(CT)	0.00	20	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-R						
								Weight: 173 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 10-28
OTHERS 2x4 SP No.3	

REACTIONS. All bearings 20-0-0.
 (lb) - Max Horz 36=183(LC 8)
 Max Uplift All uplift 100 lb or less at joint(s) 20, 29, 30, 31, 32, 33, 34, 27, 26, 25, 24, 23, 22 except 36=160(LC 8), 35=206(LC 10), 21=178(LC 11)
 Max Grav All reactions 250 lb or less at joint(s) 20, 28, 29, 30, 31, 32, 33, 34, 35, 27, 26, 25, 24, 23, 22, 21 except 36=253(LC 10)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) -0-10-8 to 2-0-0, Exterior(2) 2-0-0 to 7-0-0, Corner(3) 7-0-0 to 13-0-0, Exterior(2) 13-0-0 to 17-10-8, Corner(3) 17-10-8 to 20-10-8 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 20, 29, 30, 31, 32, 33, 34, 27, 26, 25, 24, 23, 22 except (jt=lb) 36=160, 35=206, 21=178.



April 5, 2021

Job 21031298	Truss R01GR	Truss Type COMMON GIRDER	Qty 1	Ply 2	WAG-18 Job Reference (optional)	145482378
-----------------	----------------	-----------------------------	----------	----------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:19 2021 Page 1

ID:kRYSvcFZGIM3FfDJCKq8VhyKJWz-mIKWdQoXl788_xRtlXoTT?UovUO1NOVYymmQGzzUmo_



4x8 ||

Scale = 1:54.6




Plate Offsets (X, Y)--	[2:0-0-0,0-3-7], [6:Edge,0-3-7], [9:0-4-0,0-4-8]
------------------------	--

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.70	in (loc) l/defl L/d	MT20	137/130
TCDL 10.0	Plate Grip DOL 1.15	BC 0.43	Vert(LL) -0.11 9-11 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.96	Vert(CT) -0.22 9-11 >999 240		
BCDL 10.0	Rep Stress Incr NO	Matrix-MSH	Horz(CT) 0.04 6 n/a n/a		
	Code IRC2015/TPI2014			Weight: 322 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-6-12 oc purlins.
BOT CHORD 1-1/2X7-1/4 LP-LSL TC 1.75E	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 4-9: 2x4 SP No.2	
WEDGE Left: 2x6 SP No.2 , Right: 2x6 SP No.2	

REACTIONS.
(size) 2=0-3-8, 6=0-3-8
Max Horz 2=183(LC 26)
Max Uplift 2=-724(LC 8), 6=-863(LC 9)
Max Grav 2=7421(LC 1), 6=8848(LC 1)

FORCES.
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-9001/889, 3-4=-6436/714, 4-5=-6436/714, 5-6=-9166/904
BOT CHORD 2-11=-703/6822, 9-11=-703/6822, 8-9=-633/6950, 6-8=-633/6950
WEBS 4-9=-807/7820, 5-9=-2786/406, 5-8=-299/3349, 3-9=-2614/388, 3-11=-276/3130

- NOTES-**
- 2-ply truss to be connected together with 10d (0.148"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 1-1/2x7-1/4 - 2 rows staggered at 0-7-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; Lumber DOL=1.33 plate grip DOL=1.33
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=724, 6=863.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1456 lb down and 155 lb up at 2-0-12, 1456 lb down and 155 lb up at 4-0-12, 1456 lb down and 155 lb up at 6-0-12, 1456 lb down and 155 lb up at 8-0-12, 1456 lb down and 155 lb up at 10-0-12, 1456 lb down and 155 lb up at 12-0-12, 1456 lb down and 155 lb up at 14-0-12, 1456 lb down and 155 lb up at 16-0-12, and 1456 lb down and 155 lb up at 17-6-12, and 1461 lb down and 149 lb up at 19-6-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

Continued on page 2



April 5, 2021

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p>	<p>ENGINEERING BY TRENCO A MiTek Affiliate</p> <p>818 Soundside Road Edenton, NC 27932</p>
--	---

Job 21031298	Truss R01GR	Truss Type COMMON GIRDER	Qty 1	Ply 2	WAG-18 Job Reference (optional)	145482378
-----------------	----------------	-----------------------------	----------	-----------------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:19 2021 Page 2
ID:kRYSvcFZGIM3FfDJcKq8VhyKJWz-mIKWdQoXI788_xRtiXoTT?UovUO1NOVYymmQGzzUmo_

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-4=-60, 4-7=-60, 12-15=-20

Concentrated Loads (lb)

Vert: 10=-1456(F) 9=-1456(F) 17=-1461(F) 18=-1456(F) 19=-1456(F) 20=-1456(F) 21=-1456(F) 22=-1456(F) 23=-1456(F) 24=-1456(F)

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job 21031298	Truss V1	Truss Type Valley	Qty 1	Ply 1	WAG-18	145482379
-----------------	-------------	----------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:20 2021 Page 1

ID:kRYSvcFZGIM3FDJcKq8VhyKJWz-Exuurmp93RG?b503sFJi?D149up363nhBQWznPzUmnz



Scale = 1:28.0





Plate Offsets (X,Y)-- [7:0-2-8,0-3-0]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.22	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.12	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.06	Horz(CT)	0.00	5	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S						
								Weight: 60 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 16-5-0.
 (lb) - Max Horz 1=52(LC 14)
 Max Uplift All uplift 100 lb or less at joint(s) 1, 5, 8, 6
 Max Grav All reactions 250 lb or less at joint(s) 1, 5 except 7=265(LC 1), 8=362(LC 21), 6=362(LC 22)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 WEBS 2-8=-271/131, 4-6=-271/131

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-7-9 to 3-7-9, Interior(1) 3-7-9 to 5-3-0, Exterior(2) 5-3-0 to 11-3-0, Interior(1) 11-3-0 to 12-10-7, Exterior(2) 12-10-7 to 15-10-7 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 3) Gable requires continuous bottom chord bearing.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5, 8, 6.



April 5, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job 21031298	Truss V2	Truss Type Valley	Qty 1	Ply 1	WAG-18	145482380
-----------------	-------------	----------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:30 2021 Page 1

ID:kRYSvcFZGIM3FfDJCKq8VhyKJWz-ysVgxBxQiWXaodn_RLV2PKRoBwEMSaQ9UzV8qzUmp



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.18	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.12	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.05	Horz(CT)	0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S						Weight: 43 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3


BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6'-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.

REACTIONS. All bearings 12-5-0.
 (lb) - Max Horz 1=38(LC 11)
 Max Uplift All uplift 100 lb or less at joint(s) 1, 8, 6
 Max Grav All reactions 250 lb or less at joint(s) 1, 5 except 7=287(LC 1), 8=295(LC 21), 6=295(LC 22)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TC DL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 3) Gable requires continuous bottom chord bearing.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6'-0" between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 8, 6.



April 5, 2021

Job 21031298	Truss V3	Truss Type Valley	Qty 1	Ply 1	WAG-18	145482381
-----------------	-------------	----------------------	----------	----------	--------	-----------


The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:35 2021 Page 1

ID:kRYSvcFZGIM3FDJCKq8VhyKJWz-lqIz_u?ZX29tvOfyEu5D6N9ewxwM7rqueFeGp2zUmnk



Scale = 1:15.5



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.25	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.13	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.04	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-P						Weight: 27 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=8-5-0, 3=8-5-0, 4=8-5-0
 Max Horz 1=25(LC 10)
 Max Uplift 1=27(LC 10), 3=32(LC 11)
 Max Grav 1=147(LC 1), 3=147(LC 1), 4=286(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TC DL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 3) Gable requires continuous bottom chord bearing.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.



April 5, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
 Edenton, NC 27932

Job 21031298	Truss V4	Truss Type Valley	Qty 1	Ply 1	WAG-18	145482382
-----------------	-------------	----------------------	----------	----------	--------	-----------


The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:36 2021 Page 1

ID:kRYsvCFZGIM3FfDJckq8VhyKJWz-m0syCE0BIMHkWYE8occcSfbhsqKGesli2svOqLUzUmnj



Scale = 1:8.4



0-0-8	4-6-0
0-0-8	4-5-8

LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES	GRIP			
TCLL	20.0	Plate Grip DOL	2-0-0	TC	0.04	Vert(LL)	n/a	(loc)	-	l/defl	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.13	Vert(CT)	n/a		-	n/a	999			
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	3	n/a	n/a				
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-P									Weight: 12 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 4-6-0 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=4-5-0, 3=4-5-0
 Max Horz 1=11(LC 10)
 Max Uplift 1=-12(LC 10), 3=-12(LC 11)
 Max Grav 1=130(LC 1), 3=130(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 3) Gable requires continuous bottom chord bearing.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.



Job 21031298	Truss V5	Truss Type Valley	Qty 1	Ply 1	WAG-18	145482383
-----------------	-------------	----------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:38 2021 Page 1

ID:kRYsvCFZGIM3FDJcKq8VhyKJWz-jP_idw1SqzXSmsOXv1ewk0n9h8xBKAcLKDtWQNZUmmh



4x4 =

Scale = 1:46.8




Plate Offsets (X,Y)--	[10:0-2-8,0-3-0]
-----------------------	------------------

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.21	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.19	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.17	Horz(CT)	0.00	7	n/a		
BCDL 10.0	Code	IRC2015/TPI2014	Matrix-S					Weight: 85 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS. All bearings 18-6-10.
 (lb) - Max Horz 1=-150(LC 6)
 Max Uplift All uplift 100 lb or less at joint(s) 7 except 1=-112(LC 8), 11=-151(LC 10), 12=-114(LC 10), 9=-151(LC 11), 8=-114(LC 11)
 Max Grav All reactions 250 lb or less at joint(s) 1, 7 except 10=373(LC 20), 11=426(LC 17), 12=280(LC 1), 9=425(LC 18), 8=280(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 3-11=-284/192, 5-9=-284/192

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-4-13 to 3-4-13, Interior(1) 3-4-13 to 6-3-5, Exterior(2) 6-3-5 to 12-3-5, Interior(1) 12-3-5 to 15-1-12, Exterior(2) 15-1-12 to 18-1-12 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7 except (jt=lb) 1=112, 11=151, 12=114, 9=151, 8=114.




April 5, 2021

Job 21031298	Truss V6	Truss Type Valley	Qty 1	Ply 1	WAG-18	145482384
-----------------	-------------	----------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:48 2021 Page 1

ID:kRYSvcFZGIM3FfDJCkq8VhyKJWz-QKaUjL9jT2o1yO9SV7qG87Bs2ANYgippdnlSmnzUmnX



Scale = 1:42.5

Plate Offsets (X,Y)--	[7:0-2-8,0-3-0]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.22	Vert(LL) n/a - n/a 999	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.12	Vert(CT) n/a - n/a 999		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.12	Horz(CT) 0.00 5 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-S		Weight: 71 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS. All bearings 16-1-13.
 (lb) - Max Horz 1=129(LC 7)
 Max Uplift All uplift 100 lb or less at joint(s) 1 except 8=-157(LC 10), 6=-157(LC 11)
 Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7 except 8=383(LC 17), 6=383(LC 18)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 WEBS 2-8=-290/194, 4-6=-290/193

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-4-13 to 3-4-13, Interior(1) 3-4-13 to 5-0-14, Exterior(2) 5-0-14 to 11-0-14, Interior(1) 11-0-14 to 12-8-15, Exterior(2) 12-8-15 to 15-8-15 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 3) Gable requires continuous bottom chord bearing.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1 except (jt=lb) 8=157, 6=157.




April 5, 2021

Job 21031298	Truss V7	Truss Type Valley	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482385
-----------------	-------------	----------------------	----------	----------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:51 2021 Page 1

ID:kRYsvCFZGIM3FDJCKq8VhykJKWz-qvGcLNBmzAcps00AFNzmlpOzNOI3?FJIW6N6zUmnU



Scale = 1:36.5


LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.18	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.12	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.09	Horz(CT)	0.00	5	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-S					Weight: 59 lb	FT = 20%
	Code IRC2015/TPI2014							

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS. All bearings 13-8-6.
 (lb) - Max Horz 1=109(LC 7)
 Max Uplift All uplift 100 lb or less at joint(s) 1, 5 except 8=137(LC 10), 6=137(LC 11)
 Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7 except 8=326(LC 17), 6=326(LC 18)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-8=-254/171, 4-6=-254/171

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-4-13 to 3-4-13, Interior(1) 3-4-13 to 3-10-8, Exterior(2) 3-10-8 to 9-10-8, Interior(1) 9-10-8 to 10-4-3, Exterior(2) 10-4-3 to 13-4-3 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 3) Gable requires continuous bottom chord bearing.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 8=137, 6=137.



April 5, 2021

Job 21031298	Truss V8	Truss Type Valley	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482386
-----------------	-------------	----------------------	----------	----------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,


8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:22:04 2021 Page 1

ID:kRYSvcFZGIM3FDJcKq8VhyKJWz-yPYX4pLiympmsNWRU60oVscYdqIQyfAJGAILszUmnH



4x4 =

Scale = 1:30.1



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.19	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.12	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.06	Horz(CT)	0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S						Weight: 46 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 11-4-3.
 (lb) - Max Horz 1--89(LC 8)
 Max Uplift All uplift 100 lb or less at joint(s) 1, 5 except 8--135(LC 10), 6--135(LC 11)
 Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7 except 8=314(LC 17), 6=314(LC 18)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-8=-255/174, 4-6=-255/174

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 8=135, 6=135.



April 5, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
 Edenton, NC 27932

Job 21031298	Truss V9	Truss Type Valley	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482387
-----------------	-------------	----------------------	----------	----------	------------------------------------	-----------


The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:22:13 2021 Page 1

ID:kRYSvcFZGIM3FDJCkq8VhyKJWz-B8bxzuSPajyUSEZFTm7fOj54Fug116UNArH9zUmn8



Scale = 1:25.2



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.33	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.17	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.05	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-P					Weight: 34 lb	FT = 20%
	Code IRC2015/TPI2014							

LUMBER-
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3


BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=8-11-6, 3=8-11-6, 4=8-11-6
 Max Horz 1=-69(LC 6)
 Max Uplift 1=-31(LC 11), 3=-40(LC 11)
 Max Grav 1=187(LC 1), 3=187(LC 1), 4=278(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 3) Gable requires continuous bottom chord bearing.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.



April 5, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
 Edenton, NC 27932

Job 21031298	Truss V10	Truss Type Valley	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482388
-----------------	--------------	----------------------	----------	----------	------------------------------------	-----------


The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:21 2021 Page 1

ID:kRYSvcFZGIM3FDJcKq8VhyKJWz-j8SH26qnlOsDFbFQyrxYQaGvH9qrWZqQ4FXJszUmy



Scale = 1:19.0



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.15	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.08	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Code	IRC2015/TPI2014	Matrix-P					Weight: 24 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=6-6-10, 3=6-6-10, 4=6-6-10
Max Horz 1=-48(LC 6)
Max Uplift 1=-22(LC 11), 3=-28(LC 11)
Max Grav 1=132(LC 1), 3=132(LC 1), 4=196(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 3) Gable requires continuous bottom chord bearing.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.




Job 21031298	Truss V11	Truss Type Valley	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482389
-----------------	--------------	----------------------	----------	----------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:22 2021 Page 1

ID:kRYSvcFZGIM3FfDJCKq8VhyKJWz-BK0fGSrPb2WjrOASzGMA5e6TihUHazE_ek74slzUmnx



Scale = 1:11.4

Plate Offsets (X,Y)-- [2:0-2-0,Edge]		CSI.				DEFL.				PLATES	GRIP		
LOADING (psf)	SPACING- 2-0-0	TC	0.05	in (loc)	l/defl	L/d	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCLL 20.0	Plate Grip DOL 1.15	BC	0.13	Vert(CT)	n/a	-	n/a	999	Horz(CT)	0.00	3	n/a	n/a
TCDL 10.0	Lumber DOL 1.15	WB	0.00	Weight: 13 lb	FT = 20%								
BCLL 0.0 *	Rep Stress Incr YES	Matrix-P											
BCDL 10.0	Code IRC2015/TPI2014												

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 4-1-13 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=4-1-3, 3=4-1-3
 Max Horz 1=28(LC 9)
 Max Uplift 1=-10(LC 10), 3=-10(LC 11)
 Max Grav 1=134(LC 1), 3=134(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 3) Gable requires continuous bottom chord bearing.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.




April 5, 2021

Job 21031298	Truss V12	Truss Type GABLE	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482390
-----------------	--------------	---------------------	----------	----------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:23 2021 Page 1

ID:kRYSvcFZGIM3FfDJCkq8VhyKJWz-fWa1Tos1MMeaSYkeXNtPdrfdk5s1JOa7tOkeOkzUmw



Scale = 1:48.5

Plate Offsets (X,Y)--	[21:0-2-8,0-3-0]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.07	Vert(LL) n/a - n/a 999	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.04	Vert(CT) n/a - n/a 999		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.12	Horz(CT) 0.00 13 n/a n/a		
BCDL 10.0	Code IRC2015/TP12014	Matrix-S		Weight: 129 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS. All bearings 18-5-14.
 (lb) - Max Horz 1=149(LC 6)
 Max Uplift All uplift 100 lb or less at joint(s) 1, 13, 20, 21, 22, 23, 24, 18, 17, 16, 15, 14
 Max Grav All reactions 250 lb or less at joint(s) 1, 13, 19, 20, 21, 22, 23, 24, 18, 17, 16, 15, 14

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-4-13 to 3-4-13, Interior(1) 3-4-13 to 6-2-15, Exterior(2) 6-2-15 to 12-2-15, Interior(1) 12-2-15 to 15-1-1, Exterior(2) 15-1-1 to 18-1-1 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 3) All plates are 2x4 MT20 unless otherwise indicated.
 - 4) Gable requires continuous bottom chord bearing.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 13, 20, 21, 22, 23, 24, 18, 17, 16, 15, 14.




April 5, 2021

Job 21031298	Truss V13	Truss Type Valley	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482391
-----------------	--------------	----------------------	----------	----------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:24 2021 Page 1

ID:kRYsvFZGIM3FfDJCkq8VhyKJWz-7i7Ph8sg7gmR4iJq54OeA3Ci7VBz2ruH62UBwAzUmnv



Scale = 1:42.3

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.22	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.12	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.12	Horz(CT)	0.00	5	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-S					Weight: 71 lb	FT = 20%
	Code IRC2015/TPI2014							

LUMBER-
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3


BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 16-0-8.
 (lb) - Max Horz 1=-129(LC 6)
 Max Uplift All uplift 100 lb or less at joint(s) 1 except 9=-157(LC 10), 6=-156(LC 11)
 Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7 except 9=381(LC 17), 6=381(LC 18)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-9=-289/193, 4-6=-289/193

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-4-13 to 3-4-13, Interior(1) 3-4-13 to 5-0-9, Exterior(2) 5-0-9 to 11-0-9, Interior(1) 11-0-9 to 12-8-4, Exterior(2) 12-8-4 to 15-8-4 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1 except (jt=lb) 9=157, 6=156.



April 5, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
 Edenton, NC 27932

Job 21031298	Truss V14	Truss Type Valley	Qty 1	Ply 1	WAG-18	145482392
-----------------	--------------	----------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:25 2021 Page 1
ID:kRYSvcFZGIM3FfDJCkq8VhyKJWz-bvhnuUtluzvisu1fovtiGkxXvXDniZQLiDkSdzUmmu



Scale = 1:36.3

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.18	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.12	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.09	Horz(CT)	0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S						Weight: 58 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 13-7-11.
(lb) - Max Horz 1=-109(LC 6)
Max Uplift All uplift 100 lb or less at joint(s) 1, 5 except 8=-136(LC 10), 6=-136(LC 11)
Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7 except 8=325(LC 17), 6=325(LC 18)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-8=-253/171, 4-6=-253/170

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-4-13 to 3-4-13, Interior(1) 3-4-13 to 3-10-2, Exterior(2) 3-10-2 to 9-10-2, Interior(1) 9-10-2 to 10-3-7, Exterior(2) 10-3-7 to 13-3-7 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 8=136, 6=136.



April 5, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
Edenton, NC 27932

Job 21031298	Truss V15	Truss Type Valley	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482393
-----------------	--------------	----------------------	----------	----------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:26 2021 Page 1

ID:kRYSvcFZGIM3FDJckq8VhykJWz-35FA5puweH19J0TDCVQ6FUH67IsPWmFaZMzl?3zUmnt



Scale = 1:30.0

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.19	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.12	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.06	Horz(CT)	0.00	5	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-S					Weight: 46 lb	FT = 20%
	Code IRC2015/TPI2014							


LUMBER-
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 11-2-14.
 (lb) - Max Horz 1--88(LC 6)
 Max Uplift All uplift 100 lb or less at joint(s) 1, 5 except 8--136(LC 10), 6--136(LC 11)
 Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7 except 8=315(LC 17), 6=315(LC 18)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-8=-256/175, 4-6=-256/175

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 8=136, 6=136.



April 5, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job 21031298	Truss V16	Truss Type Valley	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482394
-----------------	--------------	----------------------	----------	----------	------------------------------------	-----------

The Building Center, Gastonia, NC - 28052,


8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:27 2021 Page 1

ID:kRYSvcFZGIM3FDJCkq8VhyKJWz-XHpYJ9vYPb90xA2PmDyLohqEmiBzFDjjo0irXVzUmns



4x4 =

Scale = 1:25.1



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.32	Vert(LL)	n/a	-	n/a	999	MT20	244/190
BCDL 10.0	Lumber DOL	1.15	BC 0.17	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.05	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-P						Weight: 33 lb	FT = 20%


LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=8-10-2, 3=8-10-2, 4=8-10-2
Max Horz 1=-68(LC 6)
Max Uplift 1=-31(LC 11), 3=-39(LC 11)
Max Grav 1=186(LC 1), 3=186(LC 1), 4=276(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TC DL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 3) Gable requires continuous bottom chord bearing.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.



April 5, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job 21031298	Truss V17	Truss Type Valley	Qty 1	Ply 1	WAG-18 Job Reference (optional)	145482395
-----------------	--------------	----------------------	----------	----------	------------------------------------	-----------


The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:27 2021 Page 1

ID:kRYSvcFZGIM3FDJcKq8VhyKJWz-XHpYJ9vYPb90xA2PmDyLohqHRiCGFD3jo0irXVzUmns



Scale = 1:18.9



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.15	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.08	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code	IRC2015/TPI2014	Matrix-P						Weight: 24 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=6-5-5, 3=6-5-5, 4=6-5-5
 Max Horz 1=48(LC 9)
 Max Uplift 1=-22(LC 11), 3=-28(LC 11)
 Max Grav 1=130(LC 1), 3=130(LC 1), 4=194(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
 - 3) Gable requires continuous bottom chord bearing.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.




April 5, 2021

Job 21031298	Truss V18	Truss Type Valley	Qty 1	Ply 1	WAG-18	145482396
-----------------	--------------	----------------------	----------	----------	--------	-----------

The Building Center, Gastonia, NC - 28052,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 2 11:21:28 2021 Page 1

ID:kRYSvcFZGIM3FDJCkq8VhyKJWz-?UNwVVvAAuHtZKdcKwTaKvMUp6Xm_gjs1gSO3yzUmnr



Scale = 1:11.3

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.05	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.13	Vert(LL) n/a - n/a 999		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Vert(CT) n/a - n/a 999		
BCDL 10.0	Rep Stress Incr YES	Matrix-P	Horz(CT) 0.00 3 n/a n/a		
	Code IRC2015/TPI2014			Weight: 12 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2


BRACING-
 TOP CHORD Structural wood sheathing directly applied or 4-1-2 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=4-0-8, 3=4-0-8
 Max Horz 1=-28(LC 8)
 Max Uplift 1=-10(LC 10), 3=-10(LC 11)
 Max Grav 1=131(LC 1), 3=131(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=5.0psf; BCDL=5.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 3) Gable requires continuous bottom chord bearing.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.



April 5, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component


Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
 Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

* Plate location details available in **MITek 20/20 software** or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TFP 1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8
dimensions shown in ft-in-sixteenths
(Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TFP 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITteK® All Rights Reserved



MITek Engineering Reference Sheet: Mill-7473 rev. 5/19/2020



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TFP 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TFP 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Rewriting pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TFP 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.