

# North Carolina 2018 - R402.1.5 Total UA

## Property

23 Walker Grove Lane  
Lillington, NC 27546  
Model: 2630 Huntley E-D2\_1  
Community: Walkers Grove

Walkers Grove 1  
True\_Walkers Grove 1\_2630  
Huntley E-D2\_1\_GR\_WinPerPlan

## Organization

Performance Point, LLC.  
Rick Blair  
704-614-7175

## Builder

True Homes

## Inspection Status

Results are projected

**This report is based on a proposed design and does not confirm field enforcement of design elements.**

## Building UA

Elements	NC Reference	As Designed
Ceilings	48.0	41.4
Above-Grade Walls	195.6	196.5
Windows, Doors and Skylights	115.0	101.4
Slab Floor:	80.4	80.4
Framed Floors	22.2	22.4
Foundation Walls	0.0	0.0
Rim Joists	11.4	11.2
<b>Overall UA (Design must be equal or lower):</b>	<b>472.6</b>	<b>453.3</b>

## Requirements

✓	402.1.5	Total UA alternative compliance passes by 4.1%.
✓	402.3.2 Glazed Fenestration SHGC	Average SHGC: 0.30 Max SHGC: 0.30
✓	R402.4.2.2	Air Leakage Testing Air sealing is 5.00 ACH at 50 Pa. It must not exceed 5.00 ACH at 50 Pa.
✓	R402.5	Area-weighted average fenestration SHGC
✓	R402.5	Area-weighted average fenestration U-Factor
✓	R404.1	Lighting Equipment Efficiency
✓	Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met.
✓	R403.3.1	Duct Insulation
✓	403.3.3	Duct Testing

**Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 4.1%.**

Name: Rick Blair

Signature: 

Organization: Performance Point, LLC.

Digitally signed: 7/6/21 at 10:30 AM

## Ekotrope RATER - Version 4.0.0.2704

North Carolina 2018 Prescriptive compliance results calculated using Ekotrope RATER's energy and code compliance algorithm, including appropriate amendments. Ekotrope RATER is a RESNET Accredited HERS Rating Tool. All results are based on data entered by Ekotrope users. Ekotrope disclaims all liability for the information shown on this report.

# Energy Code Inspection Checklist

## Property

23 Walker Grove Lane  
Lillington, NC 27546  
Model: 2630 Huntley E-D2\_1  
Community: Walkers Grove

Walkers Grove 1  
True\_Walkers Grove 1\_2630  
Huntley E-D2\_1\_GR\_WinPerPlan

## Organization

Performance Point, LLC.  
Rick Blair  
704-614-7175

## Builder

True Homes

## Inspection Status

Results are projected

## General Building Information

Conditioned Area (sq ft)	2,725
Conditioned Volume (cubic ft)	24,563
Insulated Shell Area (sq ft)	6,271.8

The building energy model in Ekotrope reflects the building assemblies and energy features listed below. Sometimes energy features will change in the field from what has been modeled. The inspection process should identify any changes and ensure that the home continues to meet the applicable energy code.

## Slab



Name: House Slab(1,126 s.f., 166 ft. exterior perimeter)  
R-10 perimeter insulation, R-0 under slab insulation.

## Framed Floor



Name: Cantilever (25 s.f.)  
R-0 continuous insulation, R-19 cavity insulation  
Insulation Grade: I



Name: Over Garage (448 s.f.)  
R-0 continuous insulation, R-19 cavity insulation  
Insulation Grade: I

## Foundation Wall

None Present

## Above Grade Wall



Name: 2x4 Ambient (2,461.8 s.f.)  
R-0 continuous insulation, R-15 cavity insulation  
Insulation Grade: I



Name: Niche (2 s.f.)  
R-3 continuous insulation, R-0 cavity insulation  
Insulation Grade: I

# Energy Code Inspection Checklist

## Property

23 Walker Grove Lane  
Lillington, NC 27546  
Model: 2630 Huntley E-D2\_1  
Community: Walkers Grove

## Organization

Performance Point, LLC.  
Rick Blair  
704-614-7175


## Inspection Status


Results are projected

Walkers Grove 1  
True\_Walkers Grove 1\_2630  
Huntley E-D2\_1\_GR\_WinPerPlan

## Builder


True Homes

 Name: 2x4 Garage (378.1 s.f.)  
R-0 continuous insulation, R-15 cavity insulation  
Insulation Grade: I

 Name: 2x4 Kneewall (27.4 s.f.)  
R-0 continuous insulation, R-13 cavity insulation  
Insulation Grade: I


## Rim Joist

 Name: Ambient (139.8 s.f.)  
R: 13.30

 Name: Attic (13.2 s.f.)  
R: 13.30


 Name: Garage (51.5 s.f.)  
R: 13.30

## Ceiling / Roof


 Name: Ceiling (1,599 s.f.)  
R-28.5 continuous insulation, R-9.5 cavity insulation  
Insulation Grade: I

## Opaque Door

 Name: Front door (20 s.f.)  
R: 7.00

 Name: Garage entry (17.8 s.f.)  
R: 7.00

## Glazing

 Name: Front (60 s.f.), U: 0.330, SHGC: 0.3, Orientation: WEST

 Name: Front Shd (30 s.f.), U: 0.330, SHGC: 0.3, Orientation: WEST

# Energy Code Inspection Checklist

## Property

23 Walker Grove Lane  
Lillington, NC 27546  
Model: 2630 Huntley E-D2\_1  
Community: Walkers Grove

## Organization

Performance Point, LLC.  
Rick Blair  
704-614-7175

## Inspection Status

Results are projected

Walkers Grove 1  
True\_Walkers Grove 1\_2630  
Huntley E-D2\_1\_GR\_WinPerPlan

## Builder

True Homes

Name: Right (21 s.f.), U: 0.330, SHGC: 0.3, Orientation: SOUTH

Name: Back (91 s.f.), U: 0.330, SHGC: 0.3, Orientation: EAST

Name: Back Master BR Fxd (16 s.f.), U: 0.330, SHGC: 0.3, Orientation: EAST

Name: Back kitchen Fxd (10 s.f.), U: 0.330, SHGC: 0.3, Orientation: EAST

Name: Back door (17.8 s.f.), U: 0.330, SHGC: 0.3, Orientation: EAST

Name: Left (45 s.f.), U: 0.330, SHGC: 0.3, Orientation: NORTH

## Skylight

None Present

## Mechanical Ventilation

None Present

## Mechanical Equipment

Water Heating • Electric • 100% Hot Water Load @ 0.95 Energy Factor

Heating / All • Electric • 100% Heating Load @ 8.2 HSPF, 100% Cooling Load @ 14 SEER

## Air Leakage Control

Test Status: Blower-door tested  
House is air-sealed as to achieve 2,047 CFM50 (5.00 ACH50) or less at final blower-door test.

Infiltration Requirements for IECC in Climate Zone 4

2009 IECC Infiltration limit for the design home is 7 ACH50.

2012 IECC Infiltration limit for the design home is 3 ACH50.

2015 IECC Infiltration limit for the design home is 3 ACH50.

2018 IECC Infiltration limit for the design home is 3 ACH50.

# Energy Code Inspection Checklist

## Property

23 Walker Grove Lane  
Lillington, NC 27546  
Model: 2630 Huntley E-D2\_1  
Community: Walkers Grove

Walkers Grove 1  
True\_Walkers Grove 1\_2630  
Huntley E-D2\_1\_GR\_WinPerPlan

## Organization

Performance Point, LLC.  
Rick Blair  
704-614-7175

## Builder

True Homes

## Inspection Status

Results are projected

## Duct Leakage

### Duct System 1

NOT entirely within conditioned space, testing required

Leakage to Outside specified as: 4 CFM25 / 100 ft<sup>2</sup>

Total Leakage specified as: 4 CFM25 / 100 ft<sup>2</sup> (Post-Construction)

## Duct Leakage Code Requirements for IECC

### 2009 IECC:

Postconstruction Leakage Test: Duct Leakage to Outdoors  $\leq$  8 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage  $\leq$  6 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage  $\leq$  4 CFM25 / 100 sq ft CFA.

### 2012 IECC Mandatory, 2015 and 2018 IECC Prescriptive Paths:

Postconstruction Leakage Test: Total Duct Leakage  $\leq$  4 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage  $\leq$  4 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage  $\leq$  3 CFM25 / 100 sq ft CFA.

### 2015 and 2018 IECC Performance Paths (Cost Compliance):

Leakage testing is required UNLESS all ducts and air handlers are located entirely within the thermal envelope.

There is no pass/fail threshold for duct leakage on the performance path.

## Project Notes

JM\_05/03/2021\_\_Performance Report

**True\_2630 Huntley E-D2\_1**

Used worst orientation (W)

Game Room

DG\_05/06/2021

Revised

## Energy Specifications Label

*23 Walker Grove Lane*

Model: 2630 Huntley E-D2\_1

Ekotrope RATER - Version: 4.0.0.2704

### Building Envelope Specs

Ceiling: R-38

Above Grade Walls: R-15

Foundation Walls: N/A

Exposed Floor: R-19

Slab: R-10

Infiltration: 5 ACH50

Duct Insulation: Supply: R8, Return: R8

Duct Lkg to Outdoors: 4 CFM25 / 100 ft<sup>2</sup>

### Window & Door Specs

U-Value: 0.33, SHGC: 0.3

Door: R-7

### Mechanical Equipment Specs

Heating: Air Source Heat Pump • Electric • 8.2

HSPF

Cooling: Air Source Heat Pump • Electric • 14

SEER

Hot Water: Water Heater • Electric • 0.95 Energy

Factor

Average Mechanical Ventilation: 0 CFM

### Builder or Design Professional

Signature: \_\_\_\_\_

# Builder Affidavit

**Property**

23 Walker Grove Lane  
Lillington, NC 27546  
Model: 2630 Huntley E-D2\_1  
Community: Walkers Grove

Walkers Grove 1  
True\_Walkers Grove 1\_2630  
Huntley E-D2\_1\_GR\_WinPerPlan

**Organization**

Performance Point, LLC.  
Rick Blair  
704-614-7175

**Builder**

True Homes

**Inspection Status**

Results are projected

## Important Notice to Builder

Builder affirms in this affidavit that all building characteristics described in the Building Summary Report accurately reflect this New Home. Builder agrees to allow the Home Energy Rating System (HERS) Provider and/or Rater to verify building characteristics of this New Home fully at the HERS Rater/Provider's discretion. The HERS Provider and Rater do not create or imply any duty or obligations to Builder or any subsequent owner. Builder is responsible for taking any actions necessary to protect Builder's interest. There is no guarantee or warranty whatsoever expressed or implied from the HERS Provider or Rater.

HERS® Index Score:81

Builder Name: True Homes

Builder Signature: Ashley Jones

Name: Rick Blair

Signature: RB

Organization: Performance Point, LLC.

Digitally signed: 7/6/21 at 10:30 AM