

RE: J0721-4528
Weaver / 75 Thomas Farm / Harnett

Trenco
818 Soundside Rd
Edenton, NC 27932

Site Information:

Customer: Project Name: J0721-4528
Lot/Block: Model:
Address: Subdivision:
City: State:

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: IRC2015/TPI2014 Design Program: MiTek 20/20 8.4
Wind Code: N/A Wind Speed: N/A mph
Roof Load: N/A psf Floor Load: 55.0 psf

This package includes 12 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date
1	E15917758	F1	7/26/2021
2	E15917759	F2	7/26/2021
3	E15917760	F3	7/26/2021
4	E15917761	F4	7/26/2021
5	E15917762	F4A	7/26/2021
6	E15917763	F5	7/26/2021
7	E15917764	F7	7/26/2021
8	E15917765	F7A	7/26/2021
9	E15917766	KW4	7/26/2021
10	E15917767	KW5	7/26/2021
11	E15917768	KW6	7/26/2021
12	E15917769	KW7	7/26/2021

The truss drawing(s) referenced above have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Comtech, Inc - Fayetteville.

Truss Design Engineer's Name: Gilbert, Eric

My license renewal date for the state of North Carolina is December 31, 2021.

North Carolina COA: C-0844

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to TRENCO. Any project specific information included is for TRENCO customers file reference purpose only, and was not taken into account in the preparation of these designs. TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



July 26, 2021

Job	Truss	Truss Type	Qty	Ply	Weaver / 75 Thomas Farm / Harnett	E15917758
J0721-4528	F1	Floor	3	1	Job Reference (optional)	

Comtech, Inc, Fayetteville, NC - 28314,

8.430 s Jun 2 2021 MiTek Industries, Inc. Thu Jul 8 14:06:58 2021 Page 1
 ID:6QM6oUdKO1fjINWahDSvtyxoet-WfP3n4HxpQB9UfgdNlvyxGsgw4tgW33YjyYRklz_64h




Plate Offsets (X,Y)--	[13:0-1-8,Edge], [23:0-1-8,Edge], [24:0-1-8,Edge], [26:0-1-8,Edge], [33:0-1-8,Edge], [34:0-1-8,Edge]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.88	Vert(LL) -0.30 27-28 >747 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.78	Vert(CT) -0.39 27-28 >568 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.74	Horz(CT) 0.03 25 n/a n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S		Weight: 183 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1 (flat)	TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1 (flat) *Except*	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
22-29: 2x4 SP 2400F 2.0E (flat)	
WEBS 2x4 SP No.3 (flat)	

REACTIONS. All bearings 0-3-8 except (jt=length) 35=0-3-0, 22=0-2-8.
 (lb) - Max Uplift All uplift 100 lb or less at joint(s) except 22=-230(LC 6)
 Max Grav All reactions 250 lb or less at joint(s) 22 except 32=1949(LC 3), 35=583(LC 5), 25=1578(LC 11)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1280/416, 3-4=-1280/416, 4-5=-1280/416, 5-6=0/2174, 6-8=0/2174, 8-9=-1609/0, 9-11=-1609/0, 11-12=-2405/0, 12-13=-2405/0, 13-14=-1943/0, 14-15=-1943/0, 15-16=0/1257, 16-17=0/1250, 17-18=-106/539, 18-19=-106/539, 19-20=-106/539
BOT CHORD 34-35=-78/1002, 33-34=-416/1280, 32-33=-1101/519, 30-32=-274/291, 28-30=0/2276, 27-28=0/1943, 26-27=0/1943, 25-26=0/569, 24-25=-849/0, 23-24=-539/106, 22-23=-291/137
WEBS 6-32=-299/0, 16-25=-280/0, 2-35=-1098/87, 2-34=-373/307, 5-32=-1700/0, 5-33=0/1243, 4-33=-415/0, 8-32=-2177/0, 8-30=0/1554, 9-30=-259/0, 11-30=-837/0, 11-28=0/306, 12-28=-413/0, 15-25=-1992/0, 15-26=0/1541, 14-26=-445/0, 13-28=-3/796, 20-22=-178/388, 13-27=-410/0, 17-25=-722/0, 17-24=0/632, 18-24=-358/0, 20-23=-445/0, 19-23=0/254

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 22.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 230 lb uplift at joint 22.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 7) CAUTION, Do not erect truss backwards.



<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE. Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p>	<p>ENGINEERING BY TRENCO A MiTek Affiliate</p> <p>818 Soundside Road Edenton, NC 27932</p>
--	--

Comtech, Inc, Fayetteville, NC - 28314,

8.430 s Jun 2 2021 MiTek Industries, Inc. Thu Jul 8 14:07:00 2021 Page 1
ID:6QM6oUdKO1fjJINWahDSvtyxoet-T2XpBJL2Rsjyq0VAyQ1hx_XuX4_wKrBF1YPez_64f




Plate Offsets (X, Y)--	[1:Edge,0-1-8], [3:0-1-8,Edge], [13:0-1-8,Edge], [23:0-1-8,Edge], [24:0-1-8,Edge], [26:0-1-8,Edge], [33:0-1-8,Edge], [34:0-1-8,Edge]
------------------------	--

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.94	Vert(LL) -0.31	27-28	>723	480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.91	Vert(CT) -0.41	27-28	>540	360	M18SHS	244/190
BCLL 0.0	Rep Stress Incr NO	WB 0.95	Horz(CT) 0.03	25	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S						
							Weight: 198 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat) *Except* 1-7,10-21: 2x4 SP 2400F 2.0E(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat) *Except* 22-29: 2x4 SP 2400F 2.0E(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. All bearings 0-3-8 except (jt=length) 35=0-3-0, 22=0-2-8.
 (lb) - Max Uplift All uplift 100 lb or less at joint(s) except 22=-260(LC 6)
 Max Grav All reactions 250 lb or less at joint(s) 22 except 35=650(LC 5), 32=2556(LC 3), 25=1660(LC 11)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	BOT CHORD	WEBS
2-3=-1101/389, 3-4=-1094/391, 4-5=-1094/391, 5-6=0/2880, 6-8=0/2850, 8-9=-2128/0, 9-11=-2116/0, 11-12=-2684/0, 12-13=-2684/0, 13-14=-2120/0, 14-15=-2120/0, 15-16=0/1367, 16-17=0/1359, 17-18=-28/601, 18-19=-28/601, 19-20=-28/601	34-35=0/1166, 33-34=-391/1094, 32-33=-1442/28, 30-32=0/685, 28-30=0/2649, 27-28=0/2120, 26-27=0/2120, 25-26=0/571, 24-25=-941/0, 23-24=-601/28, 22-23=-324/92	6-32=-267/0, 16-25=-295/0, 2-35=-1266/0, 2-34=-783/0, 3-34=0/278, 5-32=-2081/0, 5-33=0/1554, 4-33=-551/0, 20-22=-119/431, 17-25=-755/0, 17-24=0/686, 18-24=-404/0, 20-23=-496/0, 19-23=0/298, 8-32=-3450/0, 8-30=0/1655, 9-30=-350/0, 11-30=-656/0, 12-28=-494/0, 15-25=-2110/0, 15-26=0/1722, 14-26=-511/0, 13-28=0/983, 13-27=-436/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 4) Plates checked for a plus or minus 1 degree rotation about its center.
 - 5) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 22.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 260 lb uplift at joint 22.
 - 7) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 8) CAUTION, Do not erect truss backwards.
 - 9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 169 lb down at 1-9-12, 169 lb down at 3-9-12, and 169 lb down at 14-2-12, and 550 lb down at 15-9-8 on top chord. The design/selection of such connection device(s) is the responsibility of others.
 - 10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

Continued on page 2



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



Job	Truss	Truss Type	Qty	Ply	Weaver / 75 Thomas Farm / Harnett	E15917759
J0721-4528	F2	Floor Girder	1	1	Job Reference (optional)	

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jun 2 2021 MiTek Industries, Inc. Thu Jul 8 14:07:00 2021 Page 2
 ID:6QM6oUdKO1fjjjNWahDSvtyxoet-T2XpBlJBL2Rsjyq0VAyQ1hx_XuX4_wKrBF1YPez_64f

LOAD CASE(S) Standard

1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00

Uniform Loads (plf)

Vert: 22-35=-10, 1-21=-100

Concentrated Loads (lb)

Vert: 7=-89(F) 38=-89(F) 39=-89(F) 40=-470(F)

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
 Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Weaver / 75 Thomas Farm / Harnett	E15917760
J0721-4528	F3	Floor	3	1	Job Reference (optional)	

Comtech, Inc, Fayetteville, NC - 28314,

8.430 s Jun 2 2021 MiTek Industries, Inc. Thu Jul 8 14:07:03 2021 Page 1
 ID:6QM6oUdKO1jflINWahDSvtyxoet-tdCyqnL4ezqRaQYbAlV7eJZYM5fCBJAhtDGC?zz_64c



LOADING (psf)	SPACING-	CS.I.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.71	Vert(LL) -0.34	31	>837	480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.50	Vert(CT) -0.45	31	>619	360	M18SHS	244/190
BCLL 0.0	Rep Stress Incr YES	WB 0.81	Horz(CT) 0.04	25	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S						
							Weight: 200 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP 2400F 2.0E(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP 2400F 2.0E(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 44=0-3-0, 39=0-3-8, 25=0-3-0
 Max Uplift 44=-129(LC 4)
 Max Grav 44=539(LC 3), 39=2485(LC 1), 25=1121(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-857/329, 3-4=-1035/1110, 4-5=-1035/1110, 5-6=-1035/1110, 6-7=-97/2188,
 7-8=0/3492, 8-9=0/3492, 9-11=0/707, 11-12=-1859/0, 12-13=-1859/0, 13-15=-3379/0,
 15-16=-4599/0, 16-17=-4599/0, 17-18=-4980/0, 18-19=-4980/0, 19-20=-4622/0,
 20-21=-3590/0, 21-22=-3590/0, 22-23=-2106/0
 BOT CHORD 43-44=-161/567, 42-43=-598/1089, 41-42=-1110/1035, 40-41=-1730/627, 39-40=-2595/0,
 38-39=-1908/0, 36-38=-126/855, 35-36=0/2755, 32-35=0/4080, 31-32=0/4888,
 30-31=0/4980, 29-30=0/4980, 27-29=0/4229, 26-27=0/2949, 25-26=0/1224
 WEBS 2-44=-752/215, 7-39=-1418/0, 2-43=-234/404, 7-40=0/1005, 3-43=-322/374,
 6-40=-1091/0, 3-42=-750/0, 6-41=0/1194, 4-42=-4/309, 5-41=-551/0, 9-39=-2109/0,
 9-38=0/1705, 11-38=-1686/0, 11-36=0/1394, 13-36=-1249/0, 13-35=0/897, 15-35=-994/0,
 15-32=0/709, 17-32=-621/0, 23-25=-1627/0, 23-26=0/1226, 22-26=-1173/0,
 22-27=0/871, 20-27=-868/0, 20-29=0/572, 19-29=-728/110, 19-30=-263/305,
 17-31=-157/574

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) All plates are 3x4 MT20 unless otherwise indicated.
 - 4) Plates checked for a plus or minus 1 degree rotation about its center.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 129 lb uplift at joint 44.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 7) CAUTION, Do not erect truss backwards.



Job	Truss	Truss Type	Qty	Ply	Weaver / 75 Thomas Farm / Harnett	E15917761
J0721-4528	F4	Floor	5	1	Job Reference (optional)	

Comtech, Inc, Fayetteville, NC - 28314,

8.430 s Jun 2 2021 MiTek Industries, Inc. Thu Jul 8 14:07:04 2021 Page 1
 ID:6QM6oUdKO1jjiNWahDSvtyxoet-LpmK17MiPGylCa7nk?0MBX6IMVvlwvBR6t?mYPz_64b




Plate Offsets (X,Y)--		[4:0-1-8,Edge], [16:0-1-8,Edge], [17:0-1-8,Edge], [21:0-1-8,Edge]	
LOADING (psf)	SPACING-	CSI.	DEFL.
TCLL 40.0	2-0-0	TC 0.63	in (loc) l/defl L/d
TCDL 10.0	Plate Grip DOL 1.00	BC 0.89	Vert(LL) -0.27 15-16 >704 480
BCLL 0.0	Lumber DOL 1.00	WB 0.63	Vert(CT) -0.36 15-16 >531 360
BCDL 5.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.05 14 n/a n/a
	Code IRC2015/TPI2014		
			PLATES MT20
			GRIP 244/190
			Weight: 124 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat) *Except* 7-13: 2x4 SP 2400F 2.0E(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 22=Mechanical, 19=0-3-8, 14=0-3-0
 Max Grav 22=465(LC 3), 19=1431(LC 1), 14=853(LC 7)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-792/0, 3-4=-792/0, 4-5=0/494, 5-6=0/494, 6-8=-2584/0, 8-9=-2584/0,
 9-10=-2584/0, 10-11=-2527/0, 11-12=-2527/0
 BOT CHORD 21-22=0/741, 20-21=0/792, 19-20=0/792, 17-19=0/1472, 16-17=0/2584, 15-16=0/2776,
 14-15=0/1591
 WEBS 5-19=-278/0, 2-22=-810/0, 4-19=-1028/0, 6-19=-1803/0, 6-17=0/1333, 8-17=-449/0,
 12-14=-1745/0, 12-15=0/1035, 10-15=-311/0, 10-16=-530/136, 9-16=-106/344

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.



July 8, 2021

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p>	<p>818 Soundside Road Edenton, NC 27932</p>
--	---

Comtech, Inc, Fayetteville, NC - 28314,

0-1-8





Plate Offsets (X, Y)-- [4:0-1-8,Edge], [5:0-1-8,Edge], [19:0-1-8,Edge], [20:0-1-8,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.95	Vert(LL)	-0.29 18-19	>660	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.94	Vert(CT)	-0.39 18-19	>490	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.69	Horz(CT)	0.03 17	n/a	n/a		
BCDL 5.0	Code	IRC2015/TPI2014	Matrix-S						
								Weight: 134 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1 (flat)	TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1 (flat)	BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 2x4 SP No.3 (flat)	

REACTIONS. All bearings 9-0-4 except (jt=length) 17=0-3-0.
 (lb) - Max Uplift All uplift 100 lb or less at joint(s) 25 except 23=-186(LC 4), 24=-135(LC 4)
 Max Grav All reactions 250 lb or less at joint(s) 29, 28, 27, 26, 23, 24, 25 except 22=1537(LC 1), 22=1537(LC 1), 17=782(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 7-8=0/1020, 8-9=0/1026, 9-11=-1995/0, 11-12=-1995/0, 12-13=-1995/0, 13-14=-2224/0, 14-15=-2224/0
 BOT CHORD 23-24=-492/0, 22-23=-492/0, 20-22=0/691, 19-20=0/1995, 18-19=0/2318, 17-18=0/1441
 WEBS 8-22=-266/0, 7-22=-713/0, 7-24=0/423, 15-17=-1580/0, 15-18=0/866, 9-22=-1894/0, 9-20=0/1444, 11-20=-466/0, 13-19=-555/0, 12-19=-9/291

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 3) Plates checked for a plus or minus 1 degree rotation about its center.
 - 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 25 except (jt=lb) 23=186, 24=135.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.



July 8, 2021

Job	Truss	Truss Type	Qty	Ply	Weaver / 75 Thomas Farm / Harnett	E15917763
J0721-4528	F5	Floor	1	1	Job Reference (optional)	

Comtech, Inc, Fayetteville, NC - 28314,

8.430 s Jun 2 2021 MiTek Industries, Inc. Thu Jul 8 14:07:07 2021 Page 1
ID:6QM6oUdKO1jjiNWahDSvtyxoet-IOSTF9OaiBK131sMP8a3p9kFAixA7BstorEQ8kz_64Y

0-1-8




Plate Offsets (X,Y)-- [4:0-1-8,Edge], [15:0-1-8,Edge], [16:0-1-8,Edge], [18:0-1-8,Edge]


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.66	Vert(LL)	-0.22 19-21	>799	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.88	Vert(CT)	-0.29 19-21	>612	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.57	Horz(CT)	0.03 17	n/a	n/a		
BCDL 5.0	Code	IRC2015/TPI2014	Matrix-S					Weight: 105 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1 (flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1 (flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3 (flat)	

REACTIONS. (size) 22=Mechanical, 17=0-3-8, 14=0-2-8
Max Uplift 14=-106(LC 3)
Max Grav 22=742(LC 3), 17=1336(LC 1), 14=205(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2078/0, 3-4=-2078/0, 4-5=-1931/0, 5-6=-1931/0, 6-8=0/819, 8-9=0/813, 9-10=-150/287, 10-11=-150/287, 11-12=-150/287
BOT CHORD 21-22=0/1346, 19-21=0/1931, 18-19=0/1931, 17-18=0/850, 16-17=-482/47, 15-16=-287/150
WEBS 8-17=-265/0, 9-17=-550/0, 12-15=-264/0, 9-16=0/443, 10-16=-293/0, 6-17=-1712/0, 6-18=0/1207, 5-18=-364/0, 2-22=-1475/0, 2-21=0/810, 3-21=-330/0, 4-21=-151/288

- NOTES-**
- Unbalanced floor live loads have been considered for this design.
 - All plates are 1.5x3 MT20 unless otherwise indicated.
 - Plates checked for a plus or minus 1 degree rotation about its center.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate at joint(s) 14.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 14=106.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.



Job	Truss	Truss Type	Qty	Ply	Weaver / 75 Thomas Farm / Harnett	E15917764
J0721-4528	F7	Floor	3	1	Job Reference (optional)	

Comtech, Inc. Fayetteville, NC - 28314, 8.430 s Jun 2 2021 MiTek Industries, Inc. Thu Jul 8 14:07:08 2021 Page 1
 ID:6QM6oUdKO1fjJINWahDSvtyxoet-Ea0rtVPDVTvSkhBRyZr5ILNGZt6TosIN11VzzhAz_64X




Plate Offsets (X,Y)-- [2:0-1-8,Edge], [3:0-1-8,Edge], [9:0-1-8,0-1-8], [10:0-1-8,0-1-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.08	Vert(LL)	-0.00	7	>999	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.05	Vert(CT)	-0.00	7	>999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.05	Horz(CT)	0.00	5	n/a		
BCDL 5.0	Code	IRC2015/TPI2014	Matrix-S					Weight: 25 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1 (flat)	TOP CHORD Structural wood sheathing directly applied or 3-9-8 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1 (flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 (flat)	

REACTIONS. (size) 8=0-3-0, 5=Mechanical
 Max Grav 8=189(LC 1), 5=189(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Plates checked for a plus or minus 1 degree rotation about its center.
 - 3) Refer to girder(s) for truss to truss connections.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



July 8, 2021

Job	Truss	Truss Type	Qty	Ply	Weaver / 75 Thomas Farm / Harnett	E15917765
J0721-4528	F7A	Floor Girder	1	1	Job Reference (optional)	

Comtech, Inc. Fayetteville, NC - 28314, 8.430 s Jun 2 2021 MiTek Industries, Inc. Thu Jul 8 14:07:08 2021 Page 1
 ID:6QM6oUdKO1fjjiNWahDSvtxoeT-Ea0rtVPDVTvSkhBRYzr5ILNGYy6Q8sjY11VzzhAz_64X




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [9:0-1-8,0-1-8], [10:0-1-8,0-1-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.14	Vert(LL)	-0.01	6	>999	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.20	Vert(CT)	-0.01	6	>999		
BCLL 0.0	Lumber DOL 1.00	WB 0.16	Horz(CT)	0.00	5	n/a		
BCDL 5.0	Rep Stress Incr NO	Matrix-S					Weight: 29 lb	FT = 20%F, 11%E
	Code IRC2015/TPI2014							


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1 (flat)	TOP CHORD Structural wood sheathing directly applied or 3-9-8 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1 (flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 (flat)	

REACTIONS. (size) 8=0-3-0, 5=Mechanical
 Max Grav 8=449(LC 1), 5=570(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-540/0
 BOT CHORD 7-8=0/540, 6-7=0/540, 5-6=0/540
 WEBS 3-5=-683/0, 2-8=-690/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Plates checked for a plus or minus 1 degree rotation about its center.
 - 3) Refer to girder(s) for truss to truss connections.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 671 lb down at 1-11-4 on top chord. The design/selection of such connection device(s) is the responsibility of others.
 - 6) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 5-8=-10, 1-4=-100
 Concentrated Loads (lb)
 Vert: 3=-642(F)



July 8, 2021

Job	Truss	Truss Type	Qty	Ply	Weaver / 75 Thomas Farm / Harnett	E15917766
J0721-4528	KW4	GABLE	1	1	Job Reference (optional)	


Comtech, Inc, Fayetteville, NC - 28314,

8.430 s Jun 2 2021 MiTek Industries, Inc. Thu Jul 8 14:07:09 2021 Page 1
 ID:6QM6oUdKO1jfjINWahDSvtyxoet-imaD4qQrEpablL0kXZcXuapl?WpFbCqAF9jXdDz_64W

0-1/8

0-1/8

Scale = 1:41.2



0-5-2 1-9-2 3-1-2 4-5-2 5-9-2 7-1-2 8-5-2 9-9-2 11-1-2 12-5-2 13-9-2 15-1-2 16-5-2 17-9-2 19-1-2 20-5-2 21-9-2 23-1-2 24-5-2 24-10-4
 0-5-2 1-4-0 1-4-0 1-4-0 1-4-0 1-4-0 1-4-0 1-4-0 1-4-0 1-4-0 1-4-0 1-4-0 1-4-0 1-4-0 1-4-0 1-4-0 1-4-0 1-4-0 1-4-0 0-5-2


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	23	n/a		
BCDL 5.0	Code	IRC2015/TPI2014	Matrix-R						
								Weight: 110 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 24-10-4.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 42, 23, 32, 33, 35, 36, 37, 38, 39, 40, 41, 31, 30, 29, 28, 27, 26, 25, 24

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 2) Plates checked for a plus or minus 1 degree rotation about its center.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 5) Gable studs spaced at 1-4-0 oc.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



July 8, 2021

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p>	<p>ENGINEERING BY</p> <p>TRENCO</p> <p>A MiTek Affiliate</p> <p>818 Soundside Road Edenton, NC 27932</p>
--	--

Job	Truss	Truss Type	Qty	Ply	Weaver / 75 Thomas Farm / Harnett	E15917767
J0721-4528	KW5	GABLE	1	1	Job Reference (optional)	


Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jun 2 2021 MiTek Industries, Inc. Thu Jul 8 14:07:10 2021 Page 1
ID:6QM6oUdKO1jfiNWahDSvtyxoet-Az7bIART_6iSwVbx4G7mQoMwn9ZkF5JUpS4I3z_64V

0-1/8

0-1/8

Scale = 1:33.2



0-7-14	1-11-14	3-3-14	4-7-14	5-11-14	7-3-14	8-7-14	9-11-14	11-3-14	12-7-14	13-11-14	15-3-14	16-7-14	17-11-14	19-3-14	19-11-12
0-7-14	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	1-4-0	0-7-14

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	19	n/a	n/a		
BCDL 5.0	Code	IRC2015/TPI2014	Matrix-R						Weight: 89 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 19-11-12.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 36, 19, 27, 28, 29, 31, 32, 33, 34, 35, 26, 25, 24, 23, 22, 21, 20

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 2) Plates checked for a plus or minus 1 degree rotation about its center.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 5) Gable studs spaced at 1-4-0 oc.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



July 8, 2021

Job	Truss	Truss Type	Qty	Ply	Weaver / 75 Thomas Farm / Harnett	E15917768
J0721-4528	KW6	GABLE	1	1	Job Reference (optional)	


Comtech, Inc, Fayetteville, NC - 28314,

8.430 s Jun 2 2021 MiTek Industries, Inc. Thu Jul 8 14:07:11 2021 Page 1
 ID:6QM6oUdKO1jffjNWahDSvtyxoet-e9hzVWR5lQqlyfA7e_e?z?u5ZJVm36MTJTcdHVz_64U

0-1-8

0-1-8

Scale = 1:17.4



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	10	n/a		
BCDL 5.0	Code	IRC2015/TPI2014	Matrix-R					Weight: 48 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 10-7-8.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 18, 10, 14, 15, 16, 17, 13, 12, 11

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 2) Plates checked for a plus or minus 1 degree rotation about its center.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 5) Gable studs spaced at 1-4-0 oc.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



July 8, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
 Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Weaver / 75 Thomas Farm / Harnett	E15917769
J0721-4528	KW7	Floor Supported Gable	1	1	Job Reference (optional)	

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jun 2 2021 MiTek Industries, Inc. Thu Jul 8 14:07:11 2021 Page 1
 ID:6QM6oUdKO1jjiNWahDSvtyxoet-e9hzVWR5IQqYfA7e_e?z?u5aJvk36MTJTCdHVz_64U



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.06	Vert(LL)	n/a - n/a	999	MT20	244/190	
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(CT)	n/a - n/a	999	Weight: 20 lb FT = 20%F, 11%E		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00 5	n/a			
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-R							

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1 (flat)	TOP CHORD	Structural wood sheathing directly applied or 3-9-8 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1 (flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3 (flat)		
OTHERS	2x4 SP No.3 (flat)		

REACTIONS. All bearings 3-9-8.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 8, 5, 7, 6

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- 1) Plates checked for a plus or minus 1 degree rotation about its center.
 - 2) Gable requires continuous bottom chord bearing.
 - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 4) Gable studs spaced at 1-4-0 oc.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.




July 8, 2021

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

* Plate location details available in **MITek 20/20 software** or upon request.

PLATE SIZE

4 X 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TFP 1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing, Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate
BCSI: Connected Wood Trusses.

Numbering System

6-4-8
dimensions shown in ft-in-sixteenths
(Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TFP 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITteK® All Rights Reserved



MITek Engineering Reference Sheet: Mill-7473 rev. 5/19/2020



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TFP 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TFP 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Rewriting pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TFP 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.