## Harnett County Department of Public Health

## Improvement Permit

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: 92 Glenmont Creek PI (401S) ISSUED TO: H&H Constructors SUBDIVISION Williams Farm REPAIR [ EXPANSION NEW X Site Improvements required prior to Construction Authorization Issuance: Type of Structure: 41' x 47' SFD Proposed Wastewater System Type: 25% reduction Projected Daily Flow: 480 Number of bedrooms: 4 Number of Occupants: 8 Basement Yes May be required based on final location and elevations of facilities × No Pump Required: Yes Type of Water Supply: Community Public Well Distance from well feet X Five years Permit valid for: No expiration Permit conditions: Date: 09-20-21 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit... Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958. and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. ISSUED TO: H&H Constructors PROPERTY LOCATION: 92 Glenmont Creek PI (401S) SUBDIVISION Williams Farm Facility Type: 41' x 47' SFD Expansion Repair Basement? Yes X No Basement Fixtures? Yes X No Type of Wastewater System\*\* 25% reduction (Initial) Wastewater Flow: 480 GPD (See note below, if applicable ) 25% reduction Installation Requirements/Conditions Number of trenches 3 Septic Tank Size 1000 gallons Exact length of each trench 60 Trench Spacing: 9 Pump Tank Size gallons Trenches shall be installed on contour at a Soil Cover: 6 Maximum Trench Depth of: 24 (Maximum soil cover shall not exceed inches (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: \_\_\_\_\_\_ft. TDH vs. \_\_\_ inches below pipe inches above pipe Conditions: inches total WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. \*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH Date: 09-20-21 Construction Authorization Expiration Date: 09-20-26

## Harnett County Department of Public Health Site Sketch

Property Location: 92 Glenmont Cre	ek PI (401S)		
Issued To: H&H Constructors	Subdivision	Williams Farm	Lot # 32
Authorized State Agent:	h M REH		Date: 09-20-21
	Drainago	way	
220.00	FUTURA 25 CADUCTION PRODUCTION	60'   60'	N 09°AA(50)
S 02°06'35" E	5.00 COV. PORCH 7.67' 28.33' PROPOSED TOPSAIL 8.55	-60'   210.44'   00'25	
This download is feet 111.	PROP CONC DRIVE	n must meet all pertine	nt laws rules and regulations
This drawing is for illustrative purp	poses only. System installation	must meet an pertine	nt laws, rules, and regulations.