

Job 21053233	Truss A1	Truss Type Truss	Qty 5	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:08

Page: 1

ID:0761kpzV3L0ziW9xvme2LTz6QbJ-q3h0WgPY0kl2RcrT0aloXaUtX7HvKu0ZDT3PoWz6Op7




Plate Offsets (X, Y): [3:0-3-0,0-3-0], [7:0-3-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.62	Vert(LL)	0.23	12-14	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.95	Vert(CT)	-0.44	12-14	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.57	Horz(CT)	0.11	8	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 191 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 2-8-6 oc purlins.
BOT CHORD 2x4 SP No.1 *Except* B2:2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 6-12, 4-12

REACTIONS	(lb/size)	2=1540/0-3-8, (min. 0-1-13), 8=1540/0-3-8, (min. 0-1-13)
Max Horiz	2=-170 (LC 11)	
Max Uplift	2=-225 (LC 10), 8=-225 (LC 11)	

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-2780/755, 3-4=-2532/718, 4-5=-1757/597, 5-6=-1757/597, 6-7=-2532/718, 7-8=-2780/755
BOT CHORD	2-14=-549/2443, 14-21=-348/1966, 21-22=-348/1966, 13-22=-348/1966, 12-13=-348/1966, 11-12=-348/1966, 11-23=-348/1966, 23-24=-348/1966, 10-24=-348/1966, 8-10=-549/2443
WEBS	5-12=-345/1183, 6-12=-694/311, 6-10=-79/557, 7-10=-369/244, 4-12=-694/311, 4-14=-79/557, 3-14=-369/244

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone, cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 225 lb uplift at joint 2 and 225 lb uplift at joint 8.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard

Job 21053233	Truss A2	Truss Type Truss	Qty 3	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:08

Page: 1

ID:DioRMr?NMG0YZ\_uWavClz5z6QbG-mRpnxMQoYL?mhv\_s8?oGc?ZD2xx\_oashnYWPz6Op5




Plate Offsets (X, Y): [3:0-3-0,0-3-0], [7:0-3-0,0-3-0], [8:Edge,0-0-2]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.62	Vert(LL)	0.25	9-11	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.98	Vert(CT)	-0.46	9-11	>959	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.57	Horz(CT)	0.11	8	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 190 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 2-8-8 oc purlins.
BOT CHORD	2x4 SP No.1 *Except* B2:2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS	2x4 SP No.3	WEBS	1 Row at midpt
WEDGE	Right: 2x4 SP No.2		6-11, 4-11

REACTIONS	(lb/size)	
	2=1531/0-3-8, (min. 0-1-13), 8=1469/ Mechanical, (min. 0-1-8)	
	Max Horiz	2=182 (LC 10)
	Max Uplift	2=-225 (LC 10), 8=-199 (LC 11)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-2759/751, 3-4=-2511/714, 4-5=-1737/594, 5-6=-1738/594, 6-7=-2455/705, 7-8=-2706/740
BOT CHORD	2-13=-587/2424, 13-20=-386/1948, 20-21=-386/1948, 19-21=-386/1948, 11-12=-386/1948, 10-11=-383/1929, 10-22=-383/1929, 22-23=-383/1929, 9-23=-383/1929, 8-9=-573/2348
WEBS	5-11=-342/1169, 6-11=-669/306, 6-9=-68/507, 7-9=-331/236, 4-11=-693/311, 4-13=-78/556, 3-13=-370/244

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 225 lb uplift at joint 2 and 199 lb uplift at joint 8.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard

Job 21053233	Truss A3L	Truss Type Truss	Qty 2	Ply 2	Job Reference (optional)
-----------------	--------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:09

Page: 1

ID:dHTZ?1t1GfBm6QRc5G1Sbkz6QbD-Eem99iRQJf7d13Z2iiJV9C6QqLI6XHF?wRH3Prz6Op4




Plate Offsets (X, Y): [3:0-3-0,0-3-0], [5:0-1-15,Edge], [7:0-1-15,Edge], [9:0-3-0,0-3-0], [14:0-4-0,0-4-12], [18:0-4-0,0-4-12]

Loading	(psf)	Spacing		CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	2-0-0	TC	0.49	Vert(LL)	0.23	16-18	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.92	Vert(CT)	-0.35	16	>999	180	MT18HS	244/190
BCLL	0.0*	Rep Stress Incr	NO	WB	0.41	Horz(CT)	0.12	10	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 513 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 4-2-13 oc purlins, except 2-0-0 oc purlins (5-9-15 max.): 5-7.
BOT CHORD	2x6 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		
<b>REACTIONS</b>	(lb/size) 2=3529/0-3-8, (min. 0-2-1), 10=3529/0-3-8, (min. 0-2-1)		
	Max Horiz 2=-134 (LC 9)		
	Max Uplift 2=-1206 (LC 8), 10=-1206 (LC 9)		

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-7141/2518, 3-4=-6086/2267, 4-5=-5069/1962, 5-6=-4557/1815, 6-7=-4557/1814, 7-8=-5069/1961, 8-9=-6086/2266, 9-10=-7141/2516
BOT CHORD	2-25=-2297/6354, 25-26=-2297/6354, 20-26=-2297/6354, 20-27=-2292/6332, 27-28=-2292/6332, 19-28=-2292/6332, 19-29=-1978/5390, 29-30=-1978/5390, 18-30=-1978/5390, 17-18=-1699/4784, 17-31=-1699/4784, 16-31=-1699/4784, 16-32=-1699/4784, 15-32=-1699/4784, 14-15=-1699/4784, 14-33=-1843/5390, 33-34=-1843/5390, 13-34=-1843/5390, 13-35=-2156/6332, 35-36=-2156/6332, 12-36=-2156/6332, 12-37=-2161/6354, 37-38=-2161/6354, 10-38=-2161/6354
WEBS	3-20=-1677/54, 3-19=-1102/367, 4-19=-899/1173, 4-18=-1277/511, 5-18=-799/1995, 6-18=-609/292, 6-16=-242/593, 6-14=-609/291, 7-14=-799/1995, 8-14=-1277/511, 8-13=-399/1173, 9-13=-1102/366, 9-12=-1677/54

- NOTES**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.  
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.  
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
  - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section.  
Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
  - Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - All plates are MT20 plates unless otherwise indicated.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-00-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1206 lb uplift at joint 2 and 1206 lb uplift at joint 10.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - Use USP JUS26 (With 4-10d nails into Girder & 4-10d nails into Truss) or equivalent spaced at 2-0-0 oc max. starting at 2-6-12 from the left end to 34-5-4 to connect truss(es) A10 (1 ply 2x4 SP), A9 (1 ply 2x4 SP), A8 (1 ply 2x4 SP), A7 (1 ply 2x4 SP), A6 (1 ply 2x4 SP), A5 (1 ply 2x4 SP), A4 (1 ply 2x4 SP), A5 (1 ply 2x4 SP), A6 (1 ply 2x4 SP), A7 (1 ply 2x4 SP), A8 (1 ply 2x4 SP), A9 (1 ply 2x4 SP), A10 (1 ply 2x4 SP) to front face of bottom chord.
  - Fill all nail holes where hanger is in contact with lumber.
- LOAD CASE(S)** Standard
- 1) Dead + Roof Live (balanced); Lumber Increase=1.15, Plate Increase=1.15

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



Job 21053233	Truss A3L	Truss Type Truss	Qty 2	Ply 2	Job Reference (optional)
-----------------	--------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:09

Page: 2

ID:dHTZ?t1GfBm6QRc5G1Sbkz6QbD-EeM99iRQJf7dl3Z2iiJV9C6QqLI6XHF?wRH3Prz6Op4

Uniform Loads (lb/ft)

Vert: 1-5=-60, 5-7=-60, 7-11=-60, 2-10=-20

Concentrated Loads (lb)

Vert: 18=-232 (F), 16=-232 (F), 14=-232 (F), 25=-247 (F), 26=-232 (F), 27=-232 (F), 28=-232 (F), 29=-232 (F), 30=-232 (F), 31=-232 (F), 32=-232 (F), 33=-232 (F), 34=-232 (F), 35=-232 (F), 36=-232 (F), 37=-232 (F), 38=-247 (F)

PRELIMINARY DRAWINGS  
LOADS AND WEBS MAY CHANGE

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



Job 21053233	Truss A4	Truss Type Truss	Qty 10	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	-----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:11

Page: 1

ID: o761kpzV3L0ziW9xvme2LTz6QbJ-A0UvaOThrGNLYNjRp7LzEdBg186S?9yINImAUjz6Op2




Plate Offsets (X, Y): [5:Edge,0-7-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.89	Vert(LL)	+0.06	4-5	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.41	Vert(CT)	-0.13	4-5	>610	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.53	Horz(CT)	-0.01	4	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 47 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 8-9-11 oc bracing.
WEBS	2x4 SP No.3		
<b>REACTIONS</b>	(lb/size)	4=252/ Mechanical, (min. 0-1-8), 5=333/0-3-0, (min. 0-1-8)	
	Max Horiz	5=298 (LC 7)	
	Max Uplift	4=-150 (LC 7), 5=-6 (LC 6)	
	Max Grav	4=327 (LC 17), 5=360 (LC 18)	
<b>FORCES</b>	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.		
TOP CHORD	2-5=-285/146, 2-3=-276/154		
BOT CHORD	4-5=-443/560		
WEBS	2-4=-658/506		

- NOTES**
- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone, cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 6 lb uplift at joint 5 and 150 lb uplift at joint 4.
  - 6) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard

Job 21053233	Truss A5	Truss Type Truss	Qty 4	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:11

Page: 1

ID:o76lkpzV3L0ziW9xvme2LTz6QbJ-A0UvaOThrGNLYNjRp7LzEdBj88h?DcINImAUjz6Op2




Plate Offsets (X, Y): [2:0-3-0,0-1-4], [3:0-1-0,Edge], [4:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.68	Vert(LL)	+0.03	6-7	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.27	Vert(CI)	-0.07	6-7	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.29	Horz(CI)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 62 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end
BOT CHORD	2x4 SP No.2	BOT CHORD	verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.
WEBS	2x4 SP No.3		Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS	(lb/size)	
	5=252/ Mechanical, (min. 0-1-8), 7=333/0-3-8, (min. 0-1-8)	
	Max Horiz 7=267 (LC 7)	
	Max Uplift 5=-131 (LC 7), 7=-18 (LC 10)	
	Max Grav 5=286 (LC 17), 7=335 (LC 18)	

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-7=-278/149, 2-3=-265/94, 4-5=-388/143
BOT CHORD	6-7=-336/406
WEBS	2-6=-460/380, 3-6=-274/223, 4-6=-141/411

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Provide adequate drainage to prevent water ponding.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 6) Refer to girder(s) for truss to truss connections.
  - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 18 lb uplift at joint 7 and 131 lb uplift at joint 5.
  - 8) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

**LOAD CASE(S)** Standard


Job 21053233	Truss A6	Truss Type Truss	Qty 4	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:11

Page: 1

ID:Gjg9z7qf8qJgk7TU9Hugz6Qbl-A0UvaOThrGNLYNjRp7LzEdBmX8AH?FoInImAUJz6Op2



Scale = 1:40

Plate Offsets (X, Y): [2:0-0-12,0-1-8], [3:0-1-0,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.48	Vert(LL)	+0.01	6-7	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.17	Vert(CI)	-0.03	6-7	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.15	Horz(CI)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 55 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD
BOT CHORD 2x4 SP No.2	BOT CHORD
WEBS 2x4 SP No.3	

Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.  
Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS	(lb/size)
	5=252/ Mechanical, (min. 0-1-8), 7=333/0-3-0, (min. 0-1-8)
	Max Horiz 7=228 (LC 7)
	Max Uplift 5=-110 (LC 7), 7=-33 (LC 10)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-7=-288/153
BOT CHORD	6-7=-259/275
WEBS	2-6=-278/257, 3-5=-263/101

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone, cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 33 lb uplift at joint 7 and 110 lb uplift at joint 5.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss A7	Truss Type Truss	Qty 4	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:12

Page: 1

ID:GJggx9z7qf8qJgk7TU9Hugz6Qbl-A0UvaOThrGNLYNjRp7LzEdBpC8BG?GmINImAUjz6Op2



Scale = 1:36.4

Plate Offsets (X, Y): [2:0-0-12,0-1-8], [3:0-1-0,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	+0.01	6-7	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.11	Vert(CT)	-0.01	6-7	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.09	Horz(CT)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 50 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD
BOT CHORD 2x4 SP No.2	BOT CHORD
WEBS 2x4 SP No.3	

Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.  
Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS	(lb/size)	5=252/ Mechanical, (min. 0-1-8), 7=333/0-3-8, (min. 0-1-8)
Max Horiz	7=188 (LC 7)	
Max Uplift	5=-92 (LC 7), 7=-42 (LC 10)	

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-7=-297/155

- NOTES**
- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TODL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Provide adequate drainage to prevent water ponding.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 42 lb uplift at joint 7 and 92 lb uplift at joint 5.
  - 7) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.






Job 21053233	Truss A8	Truss Type Truss	Qty 4	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:12

Page: 1

ID:GJgX9z7qf8qJgk7TU9Hugz6Qbl-fD2InkTJcaVC9XldNrsCnrk?QYXMKjFRcPWk0Az6Op1



Scale = 1:32.8

Plate Offsets (X, Y): [2:0-1-4,0-1-8], [3:0-1-0,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	-0.01	5-6	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.12	Vert(CI)	-0.01	5-6	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.08	Horz(CI)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 44 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS	(lb/size)	5=252/ Mechanical, (min. 0-1-8), 7=333/0-3-0, (min. 0-1-8)
	Max Horiz	7=149 (LC 7)
	Max Uplift	5=-77 (LC 7), 7=-45 (LC 10)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-7=-310/156

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Provide adequate drainage to prevent water ponding.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 6) Refer to girder(s) for truss to truss connections.
  - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 45 lb uplift at joint 7 and 77 lb uplift at joint 5.
  - 8) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss A9	Truss Type Truss	Qty 4	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFPI Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:12

Page: 1

ID:GJggx9z7qf8qJgk7TU9Hugz6Qbl-fD2lnkTJcaVC9XldNrsCnrkzgyWLkj?RcPWk0Az6Op1



Scale = 1:31.6

Plate Offsets (X, Y): [2:0-1-4,0-1-8], [3:0-1-12,0-1-12]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.32	Vert(LL)	+0.01	5-6	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.18	Vert(C)	-0.03	5-6	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.09	Horz(C)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 40 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS	(lb/size)	5=252/ Mechanical, (min. 0-1-8), 7=333/0-3-8, (min. 0-1-8)
Max Horiz	7=109 (LC 9)	
Max Uplift	5=65 (LC 7), 7=42 (LC 10)	

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-7=333/153

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Provide adequate drainage to prevent water ponding.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 6) Refer to girder(s) for truss to truss connections.
  - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 42 lb uplift at joint 7 and 65 lb uplift at joint 5.
  - 8) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

**LOAD CASE(S)** Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.






Job 21053233	Truss A11	Truss Type Truss	Qty 8	Ply 1	Job Reference (optional)
-----------------	--------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:12

Page: 1

ID:o761kpzV3L0ziW9xvme2LTz6QbJ-fD2lnkTJcaVC9XldNrsCnrk1fYYQkkQRcPWk0Az6Op1



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	0.00	4-7	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.05	Vert(CT)	0.00	4-7	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 10 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 2-6-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
<b>REACTIONS</b>	
(lb/size) 2=170/0-3-8, (min. 0-1-8), 3=57/ Mechanical, (min. 0-1-8), 4=29/ Mechanical, (min. 0-1-8)	
Max Horiz 2=67 (LC 10)	
Max Uplift 2=-36 (LC 10), 3=-32 (LC 10)	
Max Grav 2=170 (LC 1), 3=57 (LC 1), 4=43 (LC 3)	
<b>FORCES</b>	
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	

- NOTES**
- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone, cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown. Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 32 lb uplift at joint 3 and 36 lb uplift at joint 2.
  - 6) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- LOAD CASE(S)** Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss B1	Truss Type Truss	Qty 3	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:13

Page: 1

ID:Radcov?pSBHJxryobmDrz6RC6-7Pcg\_4UxNtd2ngtpxYNRJ2H?aymkt1tbq3FHYcz6Op0



Scale = 1:88.8

Plate Offsets (X, Y): [2:0-8-0,0-1-4], [3:0-4-0,0-4-8], [8:0-3-6,Edge], [11:0-4-0,0-4-8], [12:0-2-12,0-2-8], [13:0-6-0,0-7-12], [16:0-6-0,0-2-8], [17:3-11-2,0-2-8], [18:1-8-11,0-2-8], [19:0-6-0,0-7-12], [20:0-6-0,0-3-4]

Loading	(psf)	Spacing	2-3-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.95	Vert(LL)	-0.55	16-18	>641	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.55	Vert(CI)	-0.85	16-18	>411	180	MT18HS	244/190
BCLL	0.0*	Rep Stress Incr	NO	WB	0.69	Horz(CI)	0.02	12	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH		Attic	-0.27	16-18	>627	360		Weight: 366 lb FT = 20%

LUMBER	BRACING
TOP CHORD 2x6 SP 2400F 2.0E	TOP CHORD 2-0-0 oc purlins (3-10-14 max.) (Switched from sheeted: Spacing > 2-0-0).
BOT CHORD 2x10 SP 2400F 2.0E *Except* B3,B2:1-1/2x4-3/4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* W3,W4:2x4 SP No.2	WEBS 1 Row at midpt 10-13
REACTIONS	JOINTS 1 Brace at Jt(s): 6, 8, 20
(lb/size) 2=1590/0-3-8, (min. 0-1-9), 12=917/ Mechanical, (min. 0-1-8), 14=1048/0-3-8, (min. 0-1-8)	
Max Horiz 2=327 (LC 9)	
Max Uplift 2=187 (LC 10), 12=82 (LC 10), 14=327 (LC 11)	
Max Grav 2=1893 (LC 22), 12=920 (LC 22), 14=1785 (LC 23)	
FORCES	
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD 2-3=-2858/331, 3-4=-3154/528, 4-5=-1537/937, 5-6=-185/1268, 6-7=-220/1633, 7-8=-220/1633, 8-9=-157/1182, 9-10=-1600/345, 10-11=-1291/303, 11-12=-1143/257	
BOT CHORD 2-19=-307/2580, 19-27=-95/1699, 18-27=-95/1699, 17-18=-95/1699, 16-17=-95/1699, 15-16=-95/1699, 15-28=-95/1699, 14-28=-95/1699, 13-14=-95/1699, 12-13=-200/958	
WEBS 4-18=-252/543, 10-16=-25/1454, 5-20=3230/516, 9-20=3230/516, 3-19=-870/342, 10-13=-1514/0, 11-13=-704/304, 4-19=-493/1509	

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - All plates are MT20 plates unless otherwise indicated.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Ceiling dead load (5.0 psf) on member(s). 4-5, 9-10, 5-20, 9-20
  - Bottom chord live load (40.0 psf) and additional bottom chord dead load (0.0 psf) applied only to room. 16-18
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 2, 82 lb uplift at joint 12 and 327 lb uplift at joint 14.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - Attic room checked for L/360 deflection.

LOAD CASE(S) Standard


Job 21053233	Truss B2	Truss Type Truss	Qty 6	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:13

Page: 1

ID:xpin1UxFL3R\_YF\_63DeEIgZ6RC4-7Pcg\_4UxNtd2ngtpxYNRJ2H?eymjT\_vbq3FHYcz6Op0



Scale = 1:87.2

Plate Offsets (X, Y):	[2:0-8-0,0-1-4], [3:0-4-0,0-4-8], [8:0-3-6,Edge], [11:0-4-0,0-4-8], [14:0-3-4,0-2-12], [16:0-6-0,0-2-4], [17:3-11-2,0-2-8], [19:0-6-0,0-7-12], [19:1-8-11,0-2-8], [20:0-6-0,0-3-4]
-----------------------	--

Loading	(psf)	Spacing	2-3-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.95	Vert(LL)	-0.54	16-18	>684	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.56	Vert(CT)	-0.84	16-18	>440	180	MT18HS	244/190
BCLL	0.0*	Rep Stress Incr	NO	WB	0.88	Horz(CT)	0.02	13	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH		Attic	-0.27	16-18	>631	360		
											Weight: 370 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x6 SP 2400F 2.0E	TOP CHORD 2-0-0 oc purlins (3-11-6 max.)
BOT CHORD 2x10 SP 2400F 2.0E *Except* B3,B2:1-1/2x4-3/4 SP No.2	(Switched from sheeted: Spacing > 2-0-0).
WEBS 2x4 SP No.3 *Except* W3,W4:2x4 SP No.2	Rigid ceiling directly applied or 10-0-0 oc bracing.
	1 Row at midpt 10-14
	1 Brace at Jt(s): 6, 8, 20
<b>REACTIONS</b>	<b>JOINTS</b>
(lb/size) 2=1587/0-3-8, (min. 0-1-9), 13=612/ Mechanical, (min. 0-1-8), 14=1355/0-5-8, (min. 0-1-14)	
Max Horiz 2=327 (LC 9)	
Max Uplift 2=-184 (LC 10), 13=-159 (LC 7), 14=-416 (LC 11)	
Max Grav 2=1891 (LC 22), 13=612 (LC 1), 14=2271 (LC 23)	
<b>FORCES</b>	
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD 2-3=-2854/328, 3-4=-3149/525, 4-5=-1540/334, 5-6=-181/261, 6-7=-214/1625, 7-8=-214/1625, 8-9=-151/1177, 9-10=-1598/343, 10-11=-968/374, 11-12=-821/387, 12-13=-841/362	
BOT CHORD 2-19=-304/2576, 19-27=-89/1698, 18-27=-89/1698, 17-18=-89/1698, 16-17=-89/1698, 16-28=-89/1698, 15-28=-89/1698, 14-15=-89/1698, 13-14=-295/686	
WEBS 4-19=-497/1505, 4-18=-260/547, 10-16=0/170, 5-20=-3221/504, 9-20=-3221/504, 3-19=-868/341, 11-14=-736/261, 10-14=-2178/112	

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - All plates are MT20 plates unless otherwise indicated.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Ceiling dead load (5.0 psf) on member(s). 4-5, 9-10, 5-20, 9-20
  - Bottom chord live load (40.0 psf) and additional bottom chord dead load (0.0 psf) applied only to room. 16-18
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 184 lb uplift at joint 2, 159 lb uplift at joint 13 and 416 lb uplift at joint 14.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

Job 21053233	Truss B3	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:13

Page: 1

ID: ?Radcoy628BtJxriyobmDrz6RC6-7Pcg\_4UxNtd2ngtpxYNRJ2H0kymDT?Rbq3FHYcz6Op0




Plate Offsets (X, Y): [5:0-5-8,Edge], [6:Edge,0-4-4], [8:0-3-6,Edge], [9:Edge,0-4-4], [13:0-2-12,0-2-8], [14:0-6-0,0-7-12], [17:0-6-0,0-2-8], [18:3-11-2,0-2-8], [19:1-8-11,0-2-8], [20:0-6-0,0-7-12]

Loading	(psf)	Spacing	2-3-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.88	Vert(LL)	-0.47	17-19	>743	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.52	Vert(CT)	-0.73	17-19	>478	180	MT18HS	244/190
BCLL	0.0*	Rep Stress Incr	NO	WB	0.66	Horz(CT)	0.03	13	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH		Attic	-0.24	17-19	>698	360		Weight: 366 lb FT = 20%

LUMBER		BRACING	
TOP CHORD	2x6 SP 2400F 2.0E	TOP CHORD	2-0-0 oc purlins (4-3-6 max.)
BOT CHORD	2x10 SP 2400F 2.0E *Except* B3,B2:1-1/2x4-3/4 SP No.2	BOT CHORD	(Switched from sheeted: Spacing > 2-0-0). Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3 *Except* W3:2x4 SP No.2, W4:2x4 SP No.1	WEBS	1 Row at midpt 10-14
		WEBS	2 Rows at 1/3 pts 6-9
REACTIONS			
	(lb/size) 2=1621/0-3-8, (min. 0-1-10), 13=1031/ Mechanical, (min. 0-1-8), 15=903/0-3-8, (min. 0-1-8)		
	Max Horiz 2=315 (LC 9)		
	Max Uplift 2=-189 (LC 10), 13=-102 (LC 10), 15=-314 (LC 11)		
	Max Grav 2=1930 (LC 22), 13=1094 (LC 22), 15=1567 (LC 23)		
FORCES			
	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.		
TOP CHORD	2-3=-2896/315, 3-4=-2762/344, 4-5=-3261/549, 5-6=-4654/354, 6-7=-146/1405, 7-8=-185/1759, 8-9=-126/1335, 9-10=-1702/361, 10-11=-1606/341, 11-12=-1321/277, 12-13=-1460/251		
BOT CHORD	2-20=-295/2594, 20-27=-116/1816, 19-27=-116/1816, 18-19=-116/1816, 17-18=-116/1816, 16-17=-116/1816, 16-28=-116/1816, 15-28=-116/1816, 14-15=-116/1816, 13-14=-215/1223		
WEBS	5-19=-172/657, 10-17=-19/1436, 4-20=-850/341, 5-20=-474/1372, 11-14=-697/301, 10-14=-1285/0, 6-9=-3476/478		

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - All plates are MT20 plates unless otherwise indicated.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Ceiling dead load (5.0 psf) on member(s). 5-6, 9-10, 6-9
  - Bottom chord live load (40.0 psf) and additional bottom chord dead load (0.0 psf) applied only to room. 17-19
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 189 lb uplift at joint 2, 102 lb uplift at joint 13 and 314 lb uplift at joint 15.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - Attic room checked for L/360 deflection.

**LOAD CASE(S)** Standard

Job 21053233	Truss B4G	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	--------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:14

Page: 1

ID:Q0FIEqy16NZrAOZldw9TqUz6RC3-bbA2CQVZ8BivPqS0UGugsGpHXM8rCXSk3j?q42z6Op?




Plate Offsets (X, Y):	[11:0-4-7,0-3-6], [18:0-4-7,0-3-6], [33:1-9-0,0-2-8], [39:0-4-0,0-2-4], [40:0-2-4,0-2-4], [41:0-4-0,0-2-4], [42:0-4-0,0-2-4], [45:0-2-4,0-2-4], [46:0-2-4,0-2-4]
-----------------------	--

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.49	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.37	Vert(CT)	n/a	-	n/a	999	MT18HS	244/190
BCLL	0.0*	Rep Stress Incr	YES	WB	0.48	Horz(CT)	0.01	26	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 382 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x6 SP No.2	TOP CHORD Structural wood sheathing directly applied or 5-9-11 oc purlins, except 2-0-0 oc purlins (5-9-15 max.): 11-18.
BOT CHORD 2x10 SP No.2 *Except* B2:1-1/2x4-3/4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.2 *Except* W1:2x4 SP No.3	JOINTS 1 Brace at Jt(s): 39, 40, 41, 43, 45, 47
OTHERS 2x4 SP No.3	
<b>REACTIONS</b>	
All bearings 37-0-0.	
(lb) - Max Horiz 2=228 (LC 9)	
Max Uplift All uplift 100 (lb) or less at joint(s) 2, 26, 28, 29, 36, 37 except 27=-127 (LC 11), 30=-687 (LC 16), 35=-687 (LC 16), 38=-118 (LC 10)	
Max Grav All reactions 250 (lb) or less at joint(s) 26, 30, 35, 37 except 2=394 (LC 1), 26=323 (LC 1), 27=308 (LC 23), 29=657 (LC 2), 31=1094 (LC 16), 34=1093 (LC 16), 36=359 (LC 22), 38=292 (LC 22)	
<b>FORCES</b>	
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD 2-3=-401/246, 3-4=-393/220, 4-5=-334/231, 5-6=-451/257, 6-7=-478/295, 7-8=-528/308, 8-9=-442/308, 9-10=-568/363, 10-11=-1143/568, 11-12=-1096/559, 12-13=-1096/559, 13-14=-1096/559, 14-15=-1096/559, 15-16=-1096/559, 16-17=-1096/559, 17-18=-1096/559, 18-19=-1143/568, 19-20=-568/363, 20-21=-442/308, 21-22=-528/278, 22-23=-478/239, 23-24=-451/206, 24-25=-394/160, 25-26=-401/176	
BOT CHORD 2-38=-190/309, 37-38=-190/309, 36-37=-190/309, 35-36=-190/309, 34-35=-190/309, 33-34=-218/403, 32-33=-218/403, 31-32=-218/403, 30-31=-142/300, 29-30=-142/300, 28-29=-142/300, 27-28=-142/300, 26-27=-142/300	
WEBS 9-34=-340/143, 20-31=-340/110, 10-42=-319/692, 41-42=-320/693, 39-41=-320/693, 39-40=-320/693, 40-45=-320/693, 45-46=-320/693, 19-46=-319/692	

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only.
  - Provide adequate drainage to prevent water ponding.
  - All plates are MT20 plates unless otherwise indicated.
  - All plates are 3x6 MT20 unless otherwise indicated.
  - Gable requires continuous bottom chord bearing.
  - Gable studs spaced at 2-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 26, 2, 36, 37, 29, 28 except (jt=lb) 35=687, 38=117, 30=687, 27=126.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - Attic room checked for L/360 deflection.

LOAD CASE(S)	Standard
--------------	----------

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.





Job 21053233	Truss C1	Truss Type Truss	Qty 4	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFPI Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:14

Page: 1

ID:fTmkZ5rs?vY\_CAYm9F0bWoz6RcB-bbA2CQVZ8BivPqS0UGugsGpH\_M61CUzk3j?q42z6Op?




Plate Offsets (X, Y): [2:0-0-12,0-1-8], [8:0-0-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.46	Vert(LL)	0.14	12-13	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.49	Vert(CT)	-0.18	12-13	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.70	Horz(CT)	0.01	10	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 158 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 5-8-15 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	

REACTIONS	(lb/size)
10=917/0-3-8, (min. 0-1-8), 14=917/0-3-8, (min. 0-1-8)	
Max Horiz 14=-336 (LC 8)	
Max Uplift 10=-100 (LC 11), 14=-100 (LC 10)	

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-944/178, 3-4=-847/210, 4-5=-910/400, 5-6=910/400, 6-7=-849/210, 7-8=-944/178, 2-14=-852/240, 8-10=-852/240
BOT CHORD	13-14=-309/440, 13-15=-25/514, 15-16=-25/514, 12-16=-25/514
WEBS	5-12=-253/526, 6-12=-386/326, 5-13=-253/527, 4-13=-386/327, 2-13=0/523, 8-12=-6/533

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone, cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint 14 and 100 lb uplift at joint 10.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard


Job 21053233	Truss C1G	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	--------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:15

Page: 1

ID:7fK6mQsUIDhrqKXyXq2?z6RCA-3okQPIWBV/tm1\_1C2zQvPTMUUmWdx4BuInkOdVz6Op\_



Scale = 1:67.3

Plate Offsets (X, Y):	[3:0-3-0,0-3-0], [8:0-3-0,Edge], [13:0-3-0,0-3-0]
-----------------------	---

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.35	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.21	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.13	Horz(CT)	0.01	16	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MR							Weight: 177 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3	WEBS	1 Row at midpt
OTHERS	2x4 SP No.3		7-23, 9-22, 6-24, 10-21

REACTIONS	
All bearings 21-6-0.	
(lb) - Max Horiz	28=336 (LC 9)
Max Uplift	All uplift 100 (lb) or less at joint(s) 18, 26 except 16=-139 (LC 9), 17=-288 (LC 11), 20=-114 (LC 11), 21=-163 (LC 11), 24=-160 (LC 10), 25=-115 (LC 10), 27=-297 (LC 10), 28=-173 (LC 8)
Max Grav	All reactions 250 (lb) or less at joint(s) 17, 18, 20, 21, 22, 23, 24, 25, 26 except 16=323 (LC 11), 27=251 (LC 8), 28=341 (LC 10)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-28=-250/155, 2-3=-367/246, 6-7=-223/269, 5-10=-223/269, 13-14=-350/228
BOT CHORD	27-28=-166/263, 26-27=-166/264, 25-26=-166/264, 24-25=-166/264, 23-24=-166/264, 22-23=-166/264, 21-22=-166/264, 20-21=-166/264, 19-20=-166/264, 18-19=-166/264, 17-18=-166/264, 16-17=-164/263

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only.
  - All plates are 1.5x3 MT20 unless otherwise indicated.
  - Gable requires continuous bottom chord bearing.
  - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - Gable studs spaced at 2-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 26, 18 except (jt=lb) 28=173, 16=139, 24=159, 25=115, 27=296, 21=162, 20=114, 17=288.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S)	Standard
--------------	----------

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



Job 21053233	Truss C2	Truss Type Truss	Qty 3	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFPI Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:15

Page: 1

ID:7fK6mQsUIDhrqKXyjjXq2?z6RCA-3okQPIWBvVtm1\_1C2zQvPTMSImSGxw1uInkOdVz6Op\_




Plate Offsets (X, Y): [1:0-0-12,0-1-8], [6:0-0-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.46	Vert(LL)	0.14	10-11	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.49	Vert(CT)	-0.18	10-11	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.74	Horz(CT)	0.01	8	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 156 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 5-8-3 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	

REACTIONS	(lb/size)
	8=919/0-3-8, (min. 0-1-8), 12=846/0-3-8, (min. 0-1-8)
	Max Horiz 12=-326 (LC 6)
	Max Uplift 8=-100 (LC 11), 12=-88 (LC 11)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	1-2=-946/209, 2-3=-914/405, 3-4=-911/401, 4-5=-851/211, 5-6=-946/179, 1-12=-781/187, 6-8=-854/241
BOT CHORD	11-12=-283/416, 11-13=-24/515, 13-14=-24/515, 10-14=-24/516
WEBS	3-10=-253/526, 4-10=-387/326, 3-11=-258/536, 2-11=-400/339, 1-11=-12/538, 6-10=-6/535

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone, cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 88 lb uplift at joint 12 and 100 lb uplift at joint 8.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard


Job 21053233	Truss C3L	Truss Type Truss	Qty 1	Ply 2	Job Reference (optional)
-----------------	--------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:15

Page: 1

ID:BYknwZ2uDqZj7dAr5clL9Az6RBx-3okQPIWBvVm1\_1C2zQvPTMPZmLixuwuInkOdVz6Op



Scale = 1:69.6

Loading	(psf)	Spacing		CSI	DEFLL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	2-0-0	TC	0.67	Vert(LL)	-0.08	7-9	>999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	1.15	Vert(CT)	-0.14	7-9	>999	MT18HS	244/190
BCLL	0.0*	Rep Stress Incr	NO	WB	0.85	Horz(CT)	0.02	6	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH						Weight: 339 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 5-3-8 oc purlins, except end verticals.
BOT CHORD	2x6 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3 *Except* W1:2x4 SP No.2		

REACTIONS	(lb/size)	
	6=4753/0-3-8, (min. 0-2-13), 11=4175/0-3-8, (min. 0-2-7)	
	Max Horiz 11=304 (LC 5)	
	Max Uplift 6=-707 (LC 8), 11=-906 (LC 9)	

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	1-2=-4330/961, 2-3=-3227/783, 3-4=-3227/783, 4-5=-4906/820, 4-11=-3482/751, 5-6=-3925/643
BOT CHORD	11-12=-433/818, 12-13=-433/818, 10-13=-433/818, 10-14=-699/2984, 14-15=-699/2984, 9-15=-699/2984, 9-16=-490/3390, 16-17=-490/3390, 8-17=-490/3390, 8-18=-490/3390, 7-18=-490/3390, 7-19=-174/813, 19-20=-174/813, 6-20=-174/813
WEBS	3-9=-954/4100, 4-9=-1945/404, 4-7=-174/2338, 2-9=-1227/559, 2-10=-392/1402, 1-10=-427/2375, 5-7=-375/2622

- NOTES**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.  
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.  
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
  - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section.  
Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
  - Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - All plates are MT20 plates unless otherwise indicated.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 906 lb uplift at joint 11 and 707 lb uplift at joint 6.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Use USP JUS26 (With 4-10d nails into Girder & 4-10d nails into Truss) or equivalent spaced at 2-0-0 oc max. starting at 1-5-4 from the left end to 19-5-4 to connect truss(es) B2 (1 ply 2x10 SP), B1 (1 ply 2x10 SP), B3 (1 ply 2x10 SP) to back face of bottom chord.
  - Fill all nail holes where hanger is in contact with lumber.
- LOAD CASE(S)** Standard
- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-3=-60, 3-5=-60, 6-11=-20  
Concentrated Loads (lb)  
Vert: 10=-590 (B), 12=-590 (B), 13=-590 (B), 14=-590 (B), 15=-590 (B), 16=-590 (B), 17=-894 (B), 18=-894 (B), 19=-894 (B), 20=-1009 (B)

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



Job 21053233	Truss D1	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:15

Page: 1

ID:bsuUzmt6WXpiST68Hg23bDz6RC9-3okQPIWBvVtm1\_1C2zQvPTMWlmPXx3GuInkOdVz6Op\_




Plate Offsets (X, Y): [2:Edge,0-2-4], [2:0-1-15,0-4-4], [6:Edge,0-2-4], [6:0-1-15,0-4-4], [8:0-4-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	-0.08	8-14	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.66	Vert(CI)	-0.17	8-14	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.19	Horz(CI)	0.02	6	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 83 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 5-5-5 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	
WEDGE Left: 2x4 SP No.2 Right: 2x4 SP No.2	
<b>REACTIONS</b>	
(lb/size) 2=774/0-3-8, (min. 0-1-8), 6=774/0-3-8, (min. 0-1-8)	
Max Horiz 2=-87 (LC 11)	
Max Uplift 2=-120 (LC 10), 6=-120 (LC 11)	
<b>FORCES</b>	
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD 2-3=-1120/335, 3-4=-853/251, 4-5=-853/251, 5-6=-1120/335	
BOT CHORD 2-8=-196/963, 6-8=-196/963	
WEBS 4-8=-65/490, 5-8=-312/188, 3-8=-312/188	

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 120 lb uplift at joint 2 and 120 lb uplift at joint 6.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- LOAD CASE(S)** Standard

Job 21053233	Truss D1G	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	--------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:16

Page: 1

ID:bsuUzmt6WXpiST68Hg23bDz6RC9-X\_lod5Xpgo?de8cOchx8xhvJR9vNgWP1X1Ux8xz6Ooz




Plate Offsets (X, Y):	[2:Edge,0-1-4], [2:0-1-15,0-4-4], [14:Edge,0-1-4], [14:0-1-15,0-4-4]
-----------------------	--

Loading	(psf)	Spacing		2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL		1.15	TC	0.08	Vert(LL)	0.00	21	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL		1.15	BC	0.05	Vert(CT)	0.00	21	>999	180		
BCLL	0.0*	Rep Stress Incr	YES		WB	0.13	Horz(CT)	0.00	14	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014		Matrix-MSH							Weight: 110 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		
OTHERS	2x4 SP No.3		
WEDGE	Left: 2x4 SP No.2 Right: 2x4 SP No.2		

REACTIONS	
All bearings 6-8-8, except 14=6-8-12, 19=6-8-12, 17=6-8-12, 16=6-8-12, 33=6-8-12, 22=0-3-8, 20=0-3-8	
(lb) - Max Horiz	2=-87 (LC 11), 30=-87 (LC 11)
Max Uplift	All uplift 100 (lb) or less at joint(s) 2, 14, 16, 19, 23, 24, 25, 30, 33
Max Grav	All reactions 250 (lb) or less at joint(s) 2, 14, 16, 17, 19, 20, 22, 23, 24, 25, 30, 33

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only.
  - All plates are 1.5x3 MT20 unless otherwise indicated.
  - Gable studs spaced at 2-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 14, 23, 24, 25, 19, 16, 2, 14.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard


Job 21053233	Truss E1	Truss Type Truss	Qty 14	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	-----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:16

Page: 1

ID:i4fz8PqcTIIgzsoN2qz7QNz6RCD-X\_lod5Xpgo?de8cOchx8xhve59nXgOD1X1Ux8xz6Ooz



Scale = 1:33.2

Plate Offsets (X, Y): [2:0-2-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.42	Vert(LL)	0.06	6-9	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.55	Vert(CT)	-0.13	6-9	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.65	Horz(CT)	0.02	5	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 52 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 5-1-5 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS	(lb/size)	2=537/0-3-0, (min. 0-1-8), 5=472/ Mechanical, (min) 0-1-8)
Max Horiz	2=132 (LC 9)	
Max Uplift	2=-134 (LC 6), 5=-104 (LC 10)	

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-1073/330
BOT CHORD	2-6=-305/1021, 5-6=-305/1021
WEBS	3-6=0/266, 3-5=-1040/368

- NOTES**
- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust), Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 134 lb uplift at joint 2 and 104 lb uplift at joint 5.
  - 6) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss E1G	Truss Type Truss	Qty 2	Ply 1	Job Reference (optional)
-----------------	--------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:16

Page: 1

ID:32SsB6ulHqxZ3dhLqNZI7Qz6RC8-X\_lod5Xpgo?de8cOchx8xvhv79sjgYc1X1Ux8xz6Ooz



Scale = 1:32.9

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	n/a	-	n/a	999	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.22	Vert(CT)	n/a	-	n/a	999	
BCLL	0.0*	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.00	8	n/a	n/a	
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH						Weight: 52 lb	FT = 20%

**LUMBER**

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3
OTHERS	2x4 SP No.3

**BRACING**

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS**

All bearings 12-0-0.

(lb) - Max Horiz 2=132 (LC 9), 13=132 (LC 9)

Max Uplift All uplift 100 (lb) or less at joint(s) 2, 8, 9, 10, 11, 12, 13

Max Grav All reactions 250 (lb) or less at joint(s) 2, 8, 9, 10, 11, 13 except 12=405 (LC 1)

**FORCES**

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

WEBS 3-12=-265/154

- NOTES**
- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TC DL=6.0psf; BC DL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Truss designed for wind loads in the plane of the truss only.
  - 3) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 4) Gable requires continuous bottom chord bearing.
  - 5) Gable studs spaced at 2-0-0 oc.
  - 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 7) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 2, 12, 11, 10, 9, 2.
  - 9) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.






Job 21053233	Truss FTG1	Truss Type Truss	Qty 1	Ply 2	Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:16

Page: 1

ID:xYAySgkLrIP0dBra8qF6hz6RCL-X\_lod5Xpgo?de8cOchx8xvhG9sMgTw1X1Ux8xz6Ooz



Scale = 1:32.9

Plate Offsets (X, Y): [5:0-2-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	0.05	7-8	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.24	Vert(CI)	-0.10	7-8	>999	180		
BCLL	0.0*	Rep Stress Incr		WB	0.35	Horz(CI)	0.01	6	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 202 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	2-0-0 oc purlins (6-0-0 max.): 1-5, except end verticals.
BOT CHORD	2x6 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS	(lb/size)	
	5=163/0-3-8, (min. 0-1-8), 6=540/0-3-8, (min. 0-1-8), 10=703/0-3-8, (min. 0-1-8)	
	Max Horiz	10=-61 (LC 4)
	Max Uplift	5=-75 (LC 4), 6=-72 (LC 5), 10=-147 (LC 4)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	1-10=-621/169, 1-2=-1743/363, 2-3=-1743/363
BOT CHORD	7-8=-386/1775, 6-7=-386/1775
WEBS	1-8=-350/1702, 2-8=-360/174, 3-6=-174/359

- NOTES**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.  
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.  
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
  - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section.  
Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 147 lb uplift at joint 10, 72 lb uplift at joint 6 and 75 lb uplift at joint 5.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard


Job 21053233	Truss FTG2	Truss Type Truss	Qty 1	Ply 2	Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:17

Page: 1

ID:fTmkZ5rs7vY\_CAYm9F0bWoz6RCB-X\_lod5Xpgo?de8cOchx8xhvVG9otgLu1X1Ux8xz6Ooz



Loading	(psf)	Spacing	2-0-0	CSI	DEFLL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.99	Vert(L)	-0.08	13-14	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.46	Vert(CT)	-0.16	13-14	>999	180		
BCLL	0.0*	Rep Stress Incr	NO	WB	0.87	Horz(CT)	0.02	9	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 658 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	2-0-0 oc purlins (5-11-7 max.): 1-8, except end verticals.
BOT CHORD	2x6 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3	WEBS	1 Row at midpt
<b>REACTIONS</b>	(lb/size)	9=2792/0-3-8, (min. 0-1-11), 17=2424/0-3-8, (min. 0-1-11), 19=1531/0-3-8, (min. 0-1-8)	
	Max Horiz	19=-377 (LC 4)	
	Max Uplift	9=-237 (LC 5), 17=-183 (LC 5), 19=-422 (LC 4)	
	Max Grav	9=2830 (LC 2), 17=2855 (LC 15), 19=1570 (LC 2)	
<b>FORCES</b>	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.		
TOP CHORD	1-19=-1484/432, 1-20=-586/115, 20-21=-566/115, 21-22=-586/115, 2-22=-586/115, 2-23=-593/134, 23-24=-593/134, 3-24=-593/134, 3-25=-1492/155, 25-26=-1492/155, 4-26=-1492/155, 4-27=-2102/181, 5-27=-2102/181, 5-28=-2102/181, 28-29=-2102/181, 6-29=-2102/181, 6-30=-2101/181, 30-31=-2101/181, 7-31=-2101/181, 8-9=-279/91		
BOT CHORD	19-34=-323/295, 18-34=-323/295, 17-18=-229/600, 17-35=-211/1483, 16-35=-211/1483, 15-16=-210/2072, 12-15=-208/2056, 11-12=-208/2056, 11-36=-184/1355, 10-36=-184/1355, 10-37=-184/1355, 9-37=-184/1355		
WEBS	1-18=-410/1225, 2-18=-1014/353, 2-17=-400/175, 3-17=-2494/56, 3-16=-28/1743, 4-16=-1964/83, 11-13=-1271/121, 6-13=-1201/163, 7-11=-56/1563, 7-10=0/353, 7-9=-2865/207, 14-15=0/498, 4-14=0/674		

- NOTES**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.  
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.  
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
  - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section.  
Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TC DL=6.0psf; BC DL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 422 lb uplift at joint 19, 183 lb uplift at joint 17 and 237 lb uplift at joint 9.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 276 lb down and 16 lb up at 1-0-12, 273 lb down and 13 lb up at 3-0-12, 278 lb down and 4 lb up at 5-0-12, 278 lb down and 4 lb up at 20-11-4, 273 lb down and 13 lb up at 22-11-4, 273 lb down and 16 lb up at 24-11-4, and 273 lb down and 14 lb up at 26-11-4, and 282 lb down and 22 lb up at 28-11-4 on top chord. The design/selection of such connection device(s) is the responsibility of others.
- LOAD CASE(S)** Standard
- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-8=-60, 9-19=-20, 13-14=-20

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



Job 21053233	Truss FTG2	Truss Type Truss	Qty 1	Ply 2	Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:17

Page: 2

ID:fTmkZ5rs?vY\_CAym9F0bWoz6RCB-X\_lod5Xpgo?de8cOchx8xhvVG9otgLu1X1Ux8xz6Ooz

Concentrated Loads (lb)

Vert: 6=-273, 20=-276, 21=-273, 22=-273, 23=-273, 24=-273, 25=-273, 26=-273, 27=-273, 28=-273, 29=-273, 30=-273, 31=-273, 32=-273, 33=-282

PRELIMINARY DRAWINGS  
LOADS AND WEBS MAY CHANGE

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss G1G	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	--------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:17

Page: 1

ID:32SsB6ulHqxZ3dhLqNZI7Qz6RC8-?ArBqRXSR68UGIBbAOSNUuRtmZEAP?JAIhDUgNz6Ooy



Scale = 1:33.9

Plate Offsets (X, Y): [4'-0-2-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.17	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.07	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00	8	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MR							Weight: 36 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6'-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	

**REACTIONS** All bearings 6-2-8.  
 (lb) - Max Horiz 11=130 (LC 9)  
 Max Uplift All uplift 100 (lb) or less at joint(s) 8, 9, 10, 11  
 Max Grav All reactions 250 (lb) or less at joint(s) 8, 9, 10, 11

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust), Vasc=103mph, TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only.
  - Gable requires continuous bottom chord bearing.
  - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - Gable studs spaced at 2'-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-0-0 tall by 2'-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 11, 8, 10, 9.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard

Job 21053233	Truss G1L	Truss Type Truss	Qty 1	Ply 2	Job Reference (optional)
-----------------	--------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:17

Page: 1

ID:Eu5bw3p\_i\_APLiEBU6Suu9z6RCE-?ArBqRXSR68UGlBbAOSNUuRu0Z8xPuRAIHdUgNz6Ooy




Plate Offsets (X, Y): [1:Edge,0-3-2], [3:Edge,0-3-2]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.09	Vert(LL)	+0.01	4-10	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.47	Vert(CI)	-0.02	4-10	>999	180		
BCLL	0.0*	Rep Stress Incr	NO	WB	0.46	Horz(CI)	0.00	1	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 70 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	2x6 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		
WEDGE	Left: 2x6 SP No.2 Right: 2x6 SP No.2		

REACTIONS	(lb/size)	
	1=2775/0-3-8, (min. 0-1-10), 3=2073/0-3-8, (min. 0-1-8)	
	Max Horiz 1=-80 (LC 6)	
	Max Uplift 1=-393 (LC 9), 3=-293 (LC 8)	

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	1-2=-1757/300, 2-3=-1756/299
BOT CHORD	1-11=-168/1224, 4-11=-168/1224, 4-12=168/1224, 3-12=-168/1224
WEBS	2-4=-333/2238

- NOTES**
- 2-ply truss to be connected together with 10d 0.131"x3" nails as follows:  
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.  
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-7-0 oc.  
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
  - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section.  
Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
  - Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TC DL=6.0psf; BC DL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 393 lb uplift at joint 1 and 293 lb uplift at joint 3.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Use USP HUS26 (With 14-16d nails into Girder & 6-16d nails into Truss) or equivalent spaced at 2-0-0 oc max. starting at 0-8-0 from the left end to 4-8-0 to connect truss(es) A2 (1 ply 2x4 SP) to back face of bottom chord.
  - Fill all nail holes where hanger is in contact with lumber.
- LOAD CASE(S)** Standard
- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-2=-60, 2-3=-60, 5-8=-20  
Concentrated Loads (lb)  
Vert: 7=-1453 (B), 11=-1449 (B), 12=-1449 (B)


Job 21053233	Truss M1	Truss Type Truss	Qty 8	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:17

Page: 1

ID:XYAySgkblrIP0dBra8qF6hz6RCL-?ArBqRXSR68UGlBbAOSNUuRq\_ZCTP?gAlhDugNz6Ooy



Scale = 1:32.3

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.35	Vert(L)	0.03	4-7	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.25	Vert(CT)	-0.05	4-7	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.01	2	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 20 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 5-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS	(lb/size)	2=260/0-3-0, (min. 0-1-8), 4=188/0-1-8, (min. 0-1-8)
Max Horiz	2=101 (LC 9)	
Max Uplift	2=55 (LC 10), 4=48 (LC 10)	

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less, except when shown.

- NOTES**
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph, TCCL=6.0psf, BCDL=6.0psf, h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone, cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - Provide mechanical connection (by others) of truss to bearing plate at joint(s) 4.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 55 lb uplift at joint 2 and 48 lb uplift at joint 4.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S)	Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss M2L	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	--------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:18

Page: 1

ID:i4fz8PqcTIIgZsoN2qz7QNz6RCD-TNPZ2nY4CQGLuSlnj5zc06\_3xzaG8S9K\_Lz2Cpz6Oox



Scale = 1:37.7

Plate Offsets (X, Y):	[3:0-1-4,0-2-8]
-----------------------	-----------------

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	0.00	6-9	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	0.00	6-9	>999	180		
BCLL	0.0*	Rep Stress Incr		WB	0.05	Horz(CT)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 27 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 5-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.
BOT CHORD	2x6 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS	(lb/size)	
	2=270/0-3-0, (min. 0-1-8), 5=205/ Mechanical, (min. 0-1-8)	
	Max Horiz	2=66 (LC 7)
	Max Uplift	2=-61 (LC 8), 5=-43 (LC 5)

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TODL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; and vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 61 lb uplift at joint 2 and 43 lb uplift at joint 5.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.
  - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S)	Standard
1)	Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
	Uniform Loads (lb/ft)
	Vert: 1-3=-60, 3-4=-60, 5-7=-20
	Concentrated Loads (lb)
	Vert: 6=-14 (B), 3=-13 (B)

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss M3L	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	--------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:18

Page: 1

ID:i4fz8PqcTIIlGzsoN2qz7QNz6RCD-TNPZ2nY4CQGLuSlnj5zc06\_3xzaF8S7K\_Lz2Cpz6Oox



Scale = 1:37.7

Plate Offsets (X, Y):	[3:0-1-4,0-2-8]
-----------------------	-----------------

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	0.00	6-9	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.08	Vert(CI)	0.00	6-9	>999	180		
BCLL	0.0*	Rep Stress Incr		WB	0.05	Horz(CI)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 27 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 5-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.
BOT CHORD	2x6 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS	(lb/size)	
	2=274/0-3-0, (min. 0-1-8), 5=212/ Mechanical, (min. 0-1-8)	
	Max Horiz	2=66 (LC 7)
	Max Uplift	2=-62 (LC 8), 5=-43 (LC 5)

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TODL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; and vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 62 lb uplift at joint 2 and 43 lb uplift at joint 5.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.
  - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S)	Standard
1)	Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
	Uniform Loads (lb/ft)
	Vert: 1-3=-60, 3-4=-60, 5-7=-20
	Concentrated Loads (lb)
	Vert: 6=-19 (F), 3=-18 (F)

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.






Job 21053233	Truss M4	Truss Type Truss	Qty 4	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:18

Page: 1

ID:32SsB6ulHqxZ3dhLqNZI7Qz6RC8-TNPZ2nY4CQGLuSlnj5zc06\_3gzaQ8SvK\_Lz2Cpz6Oox



Scale = 1:30.8

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.10	Vert(L)	0.00	4-7	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.07	Vert(CT)	-0.01	4-7	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	2	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 13 lb	FT = 20%

**LUMBER**

TOP CHORD 2x4 SP No.2  
 BOT CHORD 2x4 SP No.2  
 WEBS 2x4 SP No.3

**BRACING**

TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (lb/size) 2=185/0-3-0, (min. 0-1-8), 4=104/0-1-8, (min. 0-1-8)  
 Max Horiz 2=65 (LC 9)  
 Max Uplift 2=43 (LC 10), 4=26 (LC 10)

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES**

- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph, TCDL=6.0psf, BCDL=6.0psf, h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone, cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate at joint(s) 4.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 43 lb uplift at joint 2 and 26 lb uplift at joint 4.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss M5	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:18

Page: 1

ID:xYAySgkbLrIPdBra8qF6hz6RCL-TNPZ2nY4CQGLuSlnj5zc06\_3ZzaL8SvK\_Lz2Cpz6Oox



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.11	Vert(L)	0.00	4-7	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	-0.01	4-7	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 11 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
<b>REACTIONS</b>	
(lb/size) 2=188/0-3-0, (min. 0-1-8), 3=73/ Mechanical, (min. 0-1-8), 4=34/ Mechanical, (min. 0-1-8)	
Max Horiz 2=64 (LC 10)	
Max Uplift 2=-37 (LC 10), 3=-41 (LC 10)	
Max Grav 2=188 (LC 1), 3=73 (LC 1), 4=53 (LC 3)	
<b>FORCES</b>	
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	

- NOTES**
- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone, cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown. Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 41 lb uplift at joint 3 and 37 lb uplift at joint 2.
  - 6) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- LOAD CASE(S)** Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss M6	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:18

Page: 1

ID: xYAySgkbLrIP0dBra8qF6hz6RCL-TNPZ2nY4CQGLuSlnj5zc06\_3Kza68SvK\_Lz2Cpz6Oox



Scale = 1:21.8

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.12	Vert(L)	0.00	3-6	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.09	Vert(CT)	-0.01	3-6	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	1	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 9 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
<b>REACTIONS</b>	
(lb/size) 1=118/0-3-8, (min. 0-1-8), 2=78/ Mechanical, (min. 0-1-8), 3=39/ Mechanical, (min. 0-1-8)	
Max Horiz 1=49 (LC 10)	
Max Uplift 1=-11 (LC 10), 2=-42 (LC 10)	
Max Grav 1=118 (LC 1), 2=78 (LC 1), 3=55 (LC 3)	

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- 1) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone, cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown. Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 11 lb uplift at joint 1 and 42 lb uplift at joint 2.
  - 6) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss PB2	Truss Type Truss	Qty 9	Ply 1	Job Reference (optional)
-----------------	--------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:18

Page: 1

ID:32SsB6ulHqxZ3dhLqNZI7Qz6RC8-TNPZ2nY4CQGLuSlnj5zco6\_4lzbY8SkK\_Lz2Cpz6Oox



Scale = 1:27.6

Loading	(psf)	Spacing	2-3-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.03	Vert(L)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr		NO	0.01	Horz(CT)	0.00	4	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 14 lb	FT = 20%

**LUMBER**  
TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
OTHERS 2x4 SP No.3

**BRACING**  
TOP CHORD 2-0-0 oc purlins  
(Switched from sheeted: Spacing > 2-0-0).  
Rigid ceiling directly applied or 10-0-0 oc bracing.  
BOT CHORD

**REACTIONS** All bearings 3-3-1.  
(lb) - Max Horiz 2=-41 (LC 8), 7=-41 (LC 8)  
Max Uplift All uplift 100 (lb) or less at joint(s) 2, 4, 6, 7, 11  
Max Grav All reactions 250 (lb) or less at joint(s) 2, 4, 6, 7, 11

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only.
  - Gable requires continuous bottom chord bearing.
  - Gable studs spaced at 4-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4, 6, 2, 4.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - See standard piggyback truss connection detail for connection to base truss.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

**LOAD CASE(S)** Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss V1	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:18

Page: 1

ID:XYAySgkbLrIP0dBra8qF6hz6RCL-TNPZ2nY4CQGLuSlnj5zc06\_33zaT8RtK\_Lz2Cpz6Oox



Scale = 1:29.9

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.07	Vert(L)	n/a	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.07	Vert(TL)	n/a	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.07	Horiz(TL)	0.00	3	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH						Weight: 20 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 5'-0-8 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 6'-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS
All bearings 5-0-8.
(lb) - Max Horiz 1=60 (LC 7)
Max Uplift All uplift 100 (lb) or less at joint(s) 1, 3, 4, 9
Max Grav All reactions 250 (lb) or less at joint(s) 1, 3, 9 except 4=404 (LC 7)

FORCES
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-4=-310/87

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Gable requires continuous bottom chord bearing.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-06"-00 tall by 2'-00"-00 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3, 4, 3.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S)
Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss V2	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:19

Page: 1

ID:xYAYsgkbLrIP0dBra8qF6hz6RCL-xZzxF7ZiyjOCVbKzHpUrZJDXNxtsv9TD?ibGz6Oow



Scale = 1:28.8

Plate Offsets (X, Y): [2:0-2-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.06	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 10 lb	FT = 20%

**LUMBER**

TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2

**BRACING**

TOP CHORD Structural wood sheathing directly applied or 3-0-8 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (lb/size) 1=122/3-0-8, (min. 0-1-8), 3=122/3-0-8, (min. 0-1-8)  
Max Horiz 1=35 (LC 7)  
Max Uplift 1=-13 (LC 10), 3=-13 (LC 11)

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES**

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-00-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 13 lb uplift at joint 1 and 13 lb uplift at joint 3.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.






Job 21053233	Truss V4	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:19

Page: 1

ID:XE0FOSvN283QhnGXO44Xgez6RC7-xZzx7ZijjOCVbKzHpUrZJXBYNvtstRTD?blGz6Oow



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.22	Vert(L)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.19	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.17	Horiz(TL)	0.00	7	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 95 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SP No.3	WEBS 1 Row at midpt 4-11

REACTIONS
All bearings 18-7-8.
(lb) - Max Horiz 1=235 (LC 7)
Max Uplift All uplift 100 (lb) or less at joint(s) 7, 8, 11, 18 except 1=163 (LC 8), 10=-292 (LC 11), 12=-257 (LC 10), 13=-148 (LC 10)
Max Grav All reactions 250 (lb) or less at joint(s) 1, 7, 18 except 8=271 (LC 1), 10=474 (LC 18), 11=523 (LC 20), 12=461 (LC 17), 13=276 (LC 17)

FORCES
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-313/273, 2-3=-276/238, 3-4=-312/342, 4-6=-313/308
WEBS 4-11=-366/213, 3-12=-360/302, 2-13=-306/230, 5-10=-371/316, 6-8=-273/214

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone, cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - All plates are 1.5x3 MT20 unless otherwise indicated.
  - Gable requires continuous bottom chord bearing.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7, 11, 8, 7 except (jt=lb) 1=162, 12=256, 13=147, 10=292.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S)
Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.






Job 21053233	Truss V5	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:19

Page: 1

ID:XE0F0SvN283QhnGXO44Xgez6RC7-xZzxF7ZijyOCVbKzHpUrZJXBHNV?sriTD?blGz6Oow



Scale = 1:50.4

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.23	Vert(L)	n/a	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.18	Vert(TL)	n/a	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.29	Horiz(TL)	0.00	5	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH						Weight: 77 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS
All bearings 15-11-8.
(lb) - Max Horiz 1--201 (LC 6)
Max Uplift All uplift 100 (lb) or less at joint(s) 1 except 6--252 (LC 11), 8--257 (LC 10)
Max Grav All reactions 250 (lb) or less at joint(s) 1, 5 except 6=483 (LC 13), 7=439 (LC 17), 8=489 (LC 17)

FORCES
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 3-7--255/0, 2-8--358/288, 4-6--358/286

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust), Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Gable requires continuous bottom chord bearing.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1 except (jt=lb) 8=257, 6=252.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S)
Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss V6	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:19

Page: 1

ID:XE0FOSvN283QhnGXO44Xgez6RC7-xZzF7ZiyjOCVbKzHpUrZJXC5NvJsuATD?iblGz6Oow



Scale = 1:45.1

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.18	Vert(L)	n/a	-	n/a	999	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.16	Vert(TL)	n/a	-	n/a	999	
BCLL	0.0*	Rep Stress Incr	YES	WB	0.13	Horiz(TL)	0.00	5	n/a	n/a	
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH						Weight: 62 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS
All bearings 13-3-8.
(lb) - Max Horiz 1=-167 (LC 6)
Max Uplift All uplift 100 (lb) or less at joint(s) 1, 5 except 6=211 (LC 11), 8=216 (LC 10)
Max Grav All reactions 250 (lb) or less at joint(s) 1, 5 except 6=380 (LC 13), 7=355 (LC 17), 8=385 (LC 17)

FORCES
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-8=-322/262, 4-6=-322/259

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust), Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Gable requires continuous bottom chord bearing.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 8=216, 6=210.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S)
Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss V7	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:19

Page: 1

ID: ?Radcov?pSBHJxryjobmDrz6RC6-xZzxF7ZiyjOCVbKzHpUrZJXBxNwusufTD?blGz6Oow



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.19	Vert(TL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.12	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.10	Horiz(TL)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 46 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS
All bearings 10-7-8.
(lb) - Max Horiz 1=-133 (LC 6)
Max Uplift All uplift 100 (lb) or less at joint(s) 1, 5 except 6=-196 (LC 11), 8=206 (LC 10)
Max Grav All reactions 250 (lb) or less at joint(s) 1, 5, 7 except 6=344 (LC 18), 8=352 (LC 17)

FORCES
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-8=-379/323, 4-6=-379/320

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust), Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Gable requires continuous bottom chord bearing.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 8=204, 6=197.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S)
Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss V8	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:20

Page: 1

ID:?Radcov?pSBHJxryjobmDrz6RC6-QIXJStKj1W37lvArW?46X3N?nFDbLcdRfS9Hiz6Oov



Scale = 1:35.4

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.17	Vert(L)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.18	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.12	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 32 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 7-11-8 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS	(lb/size)
	1=52/7-11-8, (min. 0-1-8), 3=52/7-11-8, (min. 0-1-8), 4=532/7-11-8, (min. 0-1-8)
	Max Horiz 1=-98 (LC 6)
	Max Uplift 1=-2 (LC 22), 3=-2 (LC 21), 4=-124 (LC 10)
	Max Grav 1=78 (LC 21), 3=78 (LC 22), 4=532 (LC 1)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS	2-4=-394/187

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Gable requires continuous bottom chord bearing.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 2 lb uplift at joint 1, 2 lb uplift at joint 3 and 124 lb uplift at joint 4.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 21053233	Truss V9	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	-------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:20

Page: 1

ID:?Radcov?pSBHJxrjyobmDrz6RC6-QIXJSTaKj1W37lvArW?46X3PinGjbMldRfS9Hiz6Oov



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.06	Vert(L)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.08	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.04	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 21 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 5-3-8 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
OTHERS	2x4 SP No.3		

REACTIONS	(lb/size)	1=59/5-3-8, (min. 0-1-8), 3=59/5-3-8, (min. 0-1-8), 4=306/5-3-8, (min. 0-1-8)
Max Horiz	1=64 (LC 9)	
Max Uplift	1=-1 (LC 11), 3=-4 (LC 11), 4=-59 (LC 10)	
Max Grav	1=70 (LC 21), 3=70 (LC 22), 4=306 (LC 1)	

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior, (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Gable requires continuous bottom chord bearing.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1 lb uplift at joint 1, 4 lb uplift at joint 3 and 59 lb uplift at joint 4.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.





Job 21053233	Truss V10	Truss Type Truss	Qty 1	Ply 1	Job Reference (optional)
-----------------	--------------	---------------------	----------	----------	--------------------------

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, David Gantt

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Mon Jun 14 11:16:20

Page: 1

ID:32SsB6ulHqxZ3dhLqNZI7Qz6RC8-QIXJSTaKj1W37lvArW?46X3PwnHKbMPdRfS9Hiz6Oov



Scale = 1:32

Plate Offsets (X, Y): [2:0-2-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFI	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.04	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 8 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 2-7-8 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS**

(lb/size)	1=105/2-7-8, (min. 0-1-8), 3=105/2-7-8, (min. 0-1-8)
Max Horiz	1=29 (LC 6)
Max Uplift	1=12 (LC 10), 3=12 (LC 11)

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Gable requires continuous bottom chord bearing.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-00-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 12 lb uplift at joint 1 and 12 lb uplift at joint 3.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.

