

Trenco  
818 Soundside Rd  
Edenton, NC 27932

Re: 21030657-02  
Cameron Woods Lot 19 - 2913 Elev B-Floor Truss

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Carter Components (Lexington, NC).

Pages or sheets covered by this seal: T24503242 thru T24503262

My license renewal date for the state of North Carolina is December 31, 2021.

North Carolina COA: C-0844



June 28, 2021

---

Lee, Julius

**IMPORTANT NOTE:** The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

|                    |             |                     |          |          |   |
|--------------------|-------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>L3 | Truss Type<br>GABLE | Qty<br>1 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503242<br>Job Reference (optional) |
|--------------------|-------------|---------------------|----------|----------|---|


Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:14 2021 Page 1  
ID:Co\_LqUbt4ATaJKEajxSMZzY4vF-cQl1XJ\_LiwJDWAEBDuWvK2VrELIVb4kLOMLqZU1mjJ

0-1-8

0-3-0

Scale = 1:25.4



|                       |       |                 |       |       |       |       |        |        |        |        |        |
|-----------------------|-------|-----------------|-------|-------|-------|-------|--------|--------|--------|--------|--------|
| 1-0-8                 | 2-4-8 | 3-8-8           | 5-0-8 | 6-4-8 | 7-8-8 | 9-0-8 | 10-4-8 | 11-8-8 | 13-0-8 | 14-4-8 | 15-5-0 |
| 1-0-8                 | 1-4-0 | 1-4-0           | 1-4-0 | 1-4-0 | 1-4-0 | 1-4-0 | 1-4-0  | 1-4-0  | 1-4-0  | 1-4-0  | 1-0-8  |
| Plate Offsets (X,Y)-- |       | [14:0-2-0,Edge] |       |       |       |       |        |        |        |        |        |

|                      |                      |       |             |              |          |        |     |               |                 |
|----------------------|----------------------|-------|-------------|--------------|----------|--------|-----|---------------|-----------------|
| <b>LOADING</b> (psf) | <b>SPACING-</b>      | 2-0-0 | <b>CSI.</b> | <b>DEFL.</b> | in (loc) | l/defl | L/d | <b>PLATES</b> | <b>GRIP</b>     |
| TCLL 40.0            | Plate Grip DOL       | 1.00  | TC 0.08     | Vert(LL)     | n/a      | -      | n/a | MT20          | 244/190         |
| TCDL 10.0            | Lumber DOL           | 1.00  | BC 0.01     | Vert(CT)     | n/a      | -      | n/a |               |                 |
| BCLL 0.0             | Rep Stress Incr      | YES   | WB 0.03     | Horz(CT)     | 0.00     | 14     | n/a |               |                 |
| BCDL 5.0             | Code IRC2018/TPI2014 |       | Matrix-R    |              |          |        |     |               |                 |
|                      |                      |       |             |              |          |        |     | Weight: 70 lb | FT = 20%F, 11%E |


**LUMBER-**  
TOP CHORD 2x4 SP No.2(flat)  
BOT CHORD 2x4 SP No.2(flat)  
WEBS 2x4 SP No.3(flat)  
OTHERS 2x4 SP No.3(flat)

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** All bearings 15-5-0.  
(lb) - Max Grav All reactions 250 lb or less at joint(s) 26, 14, 20, 21, 22, 23, 24, 25, 19, 18, 17, 16, 15

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- All plates are 1.5x3 MT20 unless otherwise indicated.
  - Gable requires continuous bottom chord bearing.
  - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - Gable studs spaced at 1-4-0 oc.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



June 28, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road  
Edenton, NC 27932



|                    |                |                     |          |          |   |
|--------------------|----------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3GRA | Truss Type<br>FLOOR | Qty<br>1 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503244 |
|--------------------|----------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:11 2021 Page 1  
ID:Co\_LqIUb4tATaJKEajxSMZy4vF-Cr3uulxSQ?xefiWcYIzCiPtBO87DOb\_vIO79y9z1mjM



|                        |                                |             |                                  |               |                 |
|------------------------|--------------------------------|-------------|----------------------------------|---------------|-----------------|
| Plate Offsets (X, Y)-- | [2:0-3-0,Edge], [3:0-3-0,Edge] |             |                                  |               |                 |
| <b>LOADING</b> (psf)   | <b>SPACING-</b> 2-0-0          | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b> | <b>GRIP</b>     |
| TCLL 40.0              | Plate Grip DOL 1.00            | TC 0.76     | Vert(LL) -0.04 6 >999 480        | MT20          | 244/190         |
| TCDL 10.0              | Lumber DOL 1.00                | BC 0.69     | Vert(CT) -0.05 6 >999 360        |               |                 |
| BCLL 0.0               | Rep Stress Incr NO             | WB 0.54     | Horz(CT) 0.02 5 n/a n/a          |               |                 |
| BCDL 5.0               | Code IRC2018/TPI2014           | Matrix-S    |                                  | Weight: 38 lb | FT = 20%F, 11%E |


|                             |   |
|-----------------------------|---|
| <b>LUMBER-</b>              | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.1(flat) | TOP CHORD Structural wood sheathing directly applied or 5-6-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.2(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)      |   |

**REACTIONS.** (size) 8=0-5-8, 5=Mechanical  
Max Grav 8=854(LC 1), 5=1162(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 4-5=-462/0, 2-3=-1951/0  
BOT CHORD 7-8=0/1951, 6-7=0/1951, 5-6=0/1951  
WEBS 3-5=-2069/0, 2-8=-2069/0

**NOTES-**  
1) Unbalanced floor live loads have been considered for this design.  
2) Refer to girder(s) for truss to truss connections.  
3) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.  
4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

**LOAD CASE(S)** Standard  
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00  
Uniform Loads (plf)  
Vert: 5-8=-10, 1-4=-100  
Concentrated Loads (lb)  
Vert: 9=-719 10=-719





June 28, 2021

|                    |              |                     |          |          |   |
|--------------------|--------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3A | Truss Type<br>FLOOR | Qty<br>3 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503245 |
|--------------------|--------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:02 2021 Page 1  
ID:Co\_LqlUbt4ATaJKEajxSMZzY4vF-z71V?DqpXEpw4KktWMJ5rW?ieV\_9nVBaeURB8Az1mjV




|                       |  |                  |                                  |
|-----------------------|--|------------------|----------------------------------|
| Plate Offsets (X,Y)-- | [4:0-1-8,Edge], [5:0-1-8,Edge], [9:0-3-0,Edge] | 15-1-0<br>15-1-0 | 15-5-0<br>0-4-0                  |
| <b>LOADING</b> (psf)  | <b>SPACING-</b> 2-0-0                          | <b>CSI.</b>      | <b>DEFL.</b> in (loc) l/defl L/d |
| TCLL 40.0             | Plate Grip DOL 1.00                            | TC 0.50          | Vert(LL) -0.15 13 >999 480       |
| TCDL 10.0             | Lumber DOL 1.00                                | BC 0.94          | Vert(CT) -0.20 13 >888 360       |
| BCLL 0.0              | Rep Stress Incr YES                            | WB 0.58          | Horz(CT) 0.01 9 n/a n/a          |
| BCDL 5.0              | Code IRC2018/TPI2014                           | Matrix-S         |                                  |
|                       |  |                  | <b>PLATES</b> MT20               |
|                       |  |                  | <b>GRIP</b> 244/190              |
|                       |  |                  | Weight: 82 lb FT = 20%F, 11%E    |

|                             |   |
|-----------------------------|---|
| <b>LUMBER-</b>              | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.2(flat) | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.2(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 2-2-0 oc bracing: 13-14. |
| WEBS 2x4 SP No.3(flat)      |   |

**REACTIONS.** (size) 16=0-3-8, 9=0-3-8  
Max Grav 16=813(LC 1), 9=819(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-2180/0, 3-4=-2180/0, 4-5=-2485/0, 5-6=-2448/0, 6-7=-2448/0, 7-8=-939/0, 8-9=-936/0  
BOT CHORD 15-16=0/1362, 14-15=0/2485, 13-14=0/2485, 12-13=0/2485, 11-12=0/1889  
WEBS 9-11=0/1218, 2-16=-1529/0, 2-15=0/927, 4-15=-583/0, 7-11=-1080/0, 7-12=0/633, 6-12=-250/31, 5-12=-377/213

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) Attach ribbon block to truss with 3-10d nails applied to flat face.
  - 3) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 5) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
  - 6) CAUTION, Do not erect truss backwards.





June 28, 2021

|  |   |
|--|---|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information</b> available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p> | <p>ENGINEERING BY<br/><b>TRENCO</b><br/>A MiTek Affiliate</p> <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|---|

|                    |               |                     |          |          |   |
|--------------------|---------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3GR | Truss Type<br>FLOOR | Qty<br>1 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503246 |
|--------------------|---------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:10 2021 Page 1  
ID:Co\_LqUbt4ATaJKEajxSMZzY4vF-kfWWhyxqfhp2ZxQ\_2SzACKy2kkWf38UkNcQjz1mjN



|       |        |        |        |        |        |         |
|-------|--------|--------|--------|--------|--------|---------|
| 6-3-8 | 7-1-8  | 7-11-8 | 8-4-12 | 10-7-6 | 15-3-4 | 18-10-8 |
| 6-3-8 | 0-10-0 | 0-10-0 | 0-5-4  | 2-2-10 | 4-7-14 | 3-7-4   |

Plate Offsets (X,Y)-- [4:0-3-0,Edge], [5:0-3-0,Edge], [9:0-3-0,Edge], [12:Edge,0-1-8]

| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc)    | l/defl | L/d | PLATES | GRIP    |
|---------------|----------------------|-------|----------|----------|-------------|--------|-----|--------|---------|
| TCLL 40.0     | Plate Grip DOL       | 1.00  | TC 0.99  | Vert(LL) | -0.39 15-16 | >574   | 480 | MT20   | 244/190 |
| TCDL 10.0     | Lumber DOL           | 1.00  | BC 0.84  | Vert(CT) | -0.54 15-16 | >416   | 360 | MT18HS | 244/190 |
| BCLL 0.0      | Rep Stress Incr      | NO    | WB 0.84  | Horz(CT) | 0.09 12     | n/a    | n/a |        |         |
| BCDL 5.0      | Code IRC2018/TPI2014 |       | Matrix-S |          |             |        |     |        |         |

Weight: 121 lb FT = 20%F, 11%E


| LUMBER-                           | BRACING-  |
|-----------------------------------|---|
| TOP CHORD 2x4 SP No.2(flat)       | TOP CHORD Structural wood sheathing directly applied or 3-7-9 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP 2400F 2.0E(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)            |   |

**REACTIONS.** (size) 19=0-3-8, 12=0-3-8  
Max Grav 19=1217(LC 1), 12=1868(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-3694/0, 3-4=-3710/0, 4-5=-5105/0, 5-6=-6013/0, 6-7=-6013/0, 7-9=-5186/0, 9-10=-5034/0  
BOT CHORD 18-19=0/2139, 17-18=0/5105, 16-17=0/5105, 15-16=0/5105, 13-15=0/5769, 12-13=0/2579  
WEBS 9-13=-1457/0, 10-12=-3132/0, 10-13=0/3018, 2-19=-2404/0, 2-18=0/1761, 3-18=0/387, 4-18=-1876/0, 7-13=-647/0, 7-15=0/272, 6-15=-484/0, 5-15=0/1267

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) The Fabrication Tolerance at joint 14 = 11%
  - 4) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 6) CAUTION, Do not erect truss backwards.
  - 7) Use MiTek MSH422 (With 10d nails into Girder & 6-10d nails into Truss) or equivalent at 15-3-4 from the left end to connect truss(es) to front face of top chord.
  - 8) Fill all nail holes where hanger is in contact with lumber.
  - 9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard  
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00  
Uniform Loads (plf)  
Vert: 12-19=-10, 1-11=-100  
Concentrated Loads (lb)  
Vert: 9=-1062(F)



June 28, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**ENGINEERING BY**  
**TRENCO**  
A MiTek Affiliate  
818 Soundside Road  
Edenton, NC 27932


|                    |              |                     |          |          |   |
|--------------------|--------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3B | Truss Type<br>FLOOR | Qty<br>1 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503247 |
|--------------------|--------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:03 2021 Page 1  
ID:Co\_LqlUbt4ATaJKEajxSMZzY4vF-RJbtDzRiXxniUu444qKjNjYi0vMiWxOjt8Bkgdz1mjU



0-3-0  
Scale = 1:31.1




| LOADING (psf) | SPACING-             | CSI.     | DEFL.                         | PLATES        | GRIP            |
|---------------|----------------------|----------|-------------------------------|---------------|-----------------|
| TCLL 40.0     | 2-0-0                | TC 0.97  | in (loc) l/defl L/d           | MT20          | 244/190         |
| TCDL 10.0     | Plate Grip DOL 1.00  | BC 0.79  | Vert(LL) -0.35 15-16 >642 480 | MT20HS        | 187/143         |
| BCLL 0.0      | Lumber DOL 1.00      | WB 0.65  | Vert(CT) -0.48 15-16 >467 360 |               |                 |
| BCDL 5.0      | Rep Stress Incr YES  | Matrix-S | Horz(CT) 0.06 12 n/a n/a      |               |                 |
|               | Code IRC2018/TPI2014 |          |                               | Weight: 98 lb | FT = 20%F, 11%E |

| LUMBER-  | BRACING-  |
|--|---|
| TOP CHORD 2x4 SP No.2(flat)  | TOP CHORD Structural wood sheathing directly applied, except end verticals. |
| BOT CHORD 2x4 SP 2400F 2.0E(flat) *Except*<br>12-14: 2x4 SP No.1(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.              |
| WEBS 2x4 SP No.3(flat)   |   |

**REACTIONS.** (size) 19=0-3-8, 12=0-3-8  
Max Grav 19=1015(LC 1), 12=1008(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-2919/0, 3-4=-2919/0, 4-5=-3652/0, 5-6=-3965/0, 6-8=-3965/0, 8-9=-2987/0, 9-10=-2987/0  
 BOT CHORD 18-19=0/1748, 17-18=0/3652, 16-17=0/3652, 15-16=0/3652, 13-15=0/3690, 12-13=0/1786  
 WEBS 4-17=0/324, 5-16=-316/8, 2-19=-1963/0, 2-18=0/1327, 4-18=-1082/0, 10-12=-1990/0, 10-13=0/1361, 8-13=-796/0, 8-15=0/371, 6-15=-299/0, 5-15=-183/625

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 4) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



June 28, 2021

|  |  |
|--|--|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</b><br/>         Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information</b> available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p> | <p>ENGINEERING BY<br/> <b>TRENCO</b><br/>         A MiTek Affiliate</p> <p>818 Soundside Road<br/>         Edenton, NC 27932</p> |
|--|--|




|                    |              |                     |          |          |   |
|--------------------|--------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3C | Truss Type<br>FLOOR | Qty<br>4 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503248 |
|--------------------|--------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:03 2021 Page 1  
ID:Co\_LqlUbt4ATaJKEajxSMZzY4vF-RJbtDzrIXxniUu444qKNjYmQvM2WYzjt8Bkgdz1mjU



Scale = 1:31.0




|                        |                                |             |                                  |               |                 |
|------------------------|--------------------------------|-------------|----------------------------------|---------------|-----------------|
| Plate Offsets (X, Y)-- | [4:0-1-8,Edge], [5:0-1-8,Edge] |             |                                  |               |                 |
| <b>LOADING</b> (psf)   | <b>SPACING-</b> 2-0-0          | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b> | <b>GRIP</b>     |
| TCLL 40.0              | Plate Grip DOL 1.00            | TC 0.95     | Vert(LL) -0.32 15-16 >678 480    | MT20          | 244/190         |
| TCDL 10.0              | Lumber DOL 1.00                | BC 0.77     | Vert(CT) -0.44 15-16 >493 360    | MT20HS        | 187/143         |
| BCLL 0.0               | Rep Stress Incr YES            | WB 0.64     | Horz(CT) 0.06 12 n/a n/a         |               |                 |
| BCDL 5.0               | Code IRC2018/TPI2014           | Matrix-S    |                                  |               |                 |
|                        |                                |             |                                  | Weight: 96 lb | FT = 20%F, 11%E |

|  |   |
|--|---|
| <b>LUMBER-</b>   | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.2(flat)  | TOP CHORD Structural wood sheathing directly applied, except end verticals. |
| BOT CHORD 2x4 SP 2400F 2.0E(flat) *Except*<br>12-14: 2x4 SP No.1(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.              |
| WEBS 2x4 SP No.3(flat)   |   |

**REACTIONS.** (size) 19=0-3-8, 12=Mechanical  
Max Grav 19=998(LC 1), 12=1004(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-2859/0, 3-4=-2859/0, 4-5=-3551/0, 5-6=-3834/0, 6-7=-3834/0, 7-9=-2898/0,  
9-10=-2898/0  
BOT CHORD 18-19=0/1716, 17-18=0/3551, 16-17=0/3551, 15-16=0/3551, 13-15=0/3583, 12-13=0/1718  
WEBS 4-17=-0/304, 5-16=-329/11, 2-19=-1928/0, 2-18=0/1294, 4-18=-1031/0, 10-12=-1935/0,  
10-13=0/1336, 7-13=-776/0, 7-15=0/370, 6-15=-301/0, 5-15=-178/618

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) Attach ribbon block to truss with 3-10d nails applied to flat face.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 7) CAUTION, Do not erect truss backwards.



June 28, 2021

|  |   |
|--|---|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information</b> available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p> | <p>ENGINEERING BY<br/><b>TRENCO</b><br/>A MiTek Affiliate</p> <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|---|



|                    |              |                     |          |          |   |
|--------------------|--------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>L3E | Truss Type<br>GABLE | Qty<br>1 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503249 |
|--------------------|--------------|---------------------|----------|----------|---|



Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:16 2021 Page 1  
ID:Co\_LqIUb4ATaJKEajxSMZzY4vF-Yptny??bEXZxmUOaLJZNPTaBk9\_z3zEesfqwdNz1mjH

0-3-0

0-1-8

Scale = 1:21.1




| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d | PLATES | GRIP          |                 |
|---------------|----------------------|-------|----------|----------|----------|--------|-----|--------|---------------|-----------------|
| TCLL 40.0     | Plate Grip DOL       | 1.00  | TC 0.08  | Vert(LL) | n/a      | -      | n/a | 999    | MT20          | 244/190         |
| TCDL 10.0     | Lumber DOL           | 1.00  | BC 0.01  | Vert(CT) | n/a      | -      | n/a | 999    |               |                 |
| BCLL 0.0      | Rep Stress Incr      | YES   | WB 0.03  | Horz(CT) | 0.00     | 12     | n/a | n/a    |               |                 |
| BCDL 5.0      | Code IRC2018/TPI2014 |       | Matrix-R |          |          |        |     |        |               |                 |
|               |                      |       |          |          |          |        |     |        | Weight: 60 lb | FT = 20%F, 11%E |

|                             |   |
|-----------------------------|---|
| <b>LUMBER-</b>              | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.2(flat) | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.2(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)      |   |
| OTHERS 2x4 SP No.3(flat)    |   |

**REACTIONS.** All bearings 12-11-0.  
(lb) - Max Grav All reactions 250 lb or less at joint(s) 22, 12, 17, 18, 19, 20, 21, 16, 15, 14, 13

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 2) Gable requires continuous bottom chord bearing.
  - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 4) Gable studs spaced at 1-4-0 oc.
  - 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



June 28, 2021



|  |   |
|--|---|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information</b> available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p> | <p>ENGINEERING BY</p> <p><b>TRENCO</b></p> <p>A MiTek Affiliate</p> <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|---|



|                    |              |                     |          |          |   |
|--------------------|--------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3F | Truss Type<br>FLOOR | Qty<br>2 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503251 |
|--------------------|--------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:07 2021 Page 1  
ID:Co\_LqUbt4ATaJKEajxSMZzY4vF-J4qO3wuyMmRCB5CrJwuGYZiTnWjLSqJnm9ypOz1mjQ



|                       |                                 |                    |                 |                 |
|-----------------------|---------------------------------|--------------------|-----------------|-----------------|
| Plate Offsets (X,Y)-- | [6:0-1-8,Edge], [15:0-1-8,Edge] | 12-11-0<br>12-11-0 | 16-1-0<br>3-2-0 | 16-4-8<br>0-3-8 |
|-----------------------|---------------------------------|--------------------|-----------------|-----------------|


|                      |                      |       |             |                |          |        |     |               |                 |
|----------------------|----------------------|-------|-------------|----------------|----------|--------|-----|---------------|-----------------|
| <b>LOADING</b> (psf) | <b>SPACING-</b>      | 2-0-0 | <b>CSI.</b> | <b>DEFL.</b>   | in (loc) | l/defl | L/d | <b>PLATES</b> | <b>GRIP</b>     |
| TCLL 40.0            | Plate Grip DOL 1.00  |       | TC 0.86     | Vert(LL) -0.27 | 15-17    | >569   | 480 | MT20          | 244/190         |
| TCDL 10.0            | Lumber DOL 1.00      |       | BC 0.81     | Vert(CT) -0.37 | 15-17    | >408   | 360 |               |                 |
| BCLL 0.0             | Rep Stress Incr YES  |       | WB 0.37     | Horz(CT) 0.03  | 10       | n/a    | n/a |               |                 |
| BCDL 5.0             | Code IRC2018/TPI2014 |       | Matrix-S    |                |          |        |     |               |                 |
|                      |                      |       |             |                |          |        |     | Weight: 87 lb | FT = 20%F, 11%E |

|  |   |
|--|---|
| <b>LUMBER-</b>   | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.2(flat) *Except*<br>1-7: 2x4 SP No.1(flat)         | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.2(flat) *Except*<br>11-16: 2x4 SP 2400F 2.0E(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)   |   |

**REACTIONS.** (size) 18=0-3-8, 10=0-3-0, 13=0-3-8  
Max Grav 18=721(LC 1), 10=348(LC 7), 13=721(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-1859/0, 3-4=-1859/0, 4-5=-1555/0, 5-6=-1555/0, 6-8=-402/0, 8-9=-384/0, 9-10=-380/0  
BOT CHORD 17-18=0/1194, 15-17=0/1990, 14-15=0/1555, 13-14=0/1555, 12-13=0/402  
WEBS 10-12=0/494, 6-14=0/296, 2-18=-1339/0, 2-17=0/753, 4-15=-519/0, 6-13=-1478/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) Attach ribbon block to truss with 3-10d nails applied to flat face.
  - 3) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 5) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
  - 6) CAUTION, Do not erect truss backwards.





June 28, 2021

|  |   |
|--|---|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information</b> available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p> | <p>ENGINEERING BY</p> <p><b>TRENCO</b></p> <p>A MiTek Affiliate</p> <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|---|

|                    |              |                     |          |          |   |
|--------------------|--------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3G | Truss Type<br>FLOOR | Qty<br>1 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503252 |
|--------------------|--------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:08 2021 Page 1  
ID:Co\_LqUbt4ATaJKEajxSMZzY4vF-nHOmGGva74Z3oFn1tdQV4nFePw2OBDIS0QuVLqz1mjP




| LOADING (psf) | SPACING-             | CSI.     | DEFL.                         | PLATES        | GRIP            |
|---------------|----------------------|----------|-------------------------------|---------------|-----------------|
| TCLL 40.0     | 2-0-0                | TC 0.87  | in (loc) l/defl L/d           | MT20          | 244/190         |
| TCDL 10.0     | Plate Grip DOL 1.00  | BC 0.89  | Vert(LL) -0.20 15-16 >807 480 |               |                 |
| BCLL 0.0      | Lumber DOL 1.00      | WB 0.60  | Vert(CT) -0.28 15-16 >590 360 |               |                 |
| BCDL 5.0      | Rep Stress Incr YES  | Matrix-S | Horz(CT) 0.03 12 n/a n/a      |               |                 |
|               | Code IRC2018/TPI2014 |          |                               | Weight: 92 lb | FT = 20%F, 11%E |

| LUMBER-  | BRACING-   |
|--|--|
| TOP CHORD 2x4 SP No.2(flat) *Except*<br>4-11: 2x4 SP No.1(flat)        | TOP CHORD Structural wood sheathing directly applied or 3-1-0 oc purlins, except end verticals.    |
| BOT CHORD 2x4 SP No.2(flat) *Except*<br>12-17: 2x4 SP 2400F 2.0E(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:<br>6-0-0 oc bracing: 12-13. |
| WEBS 2x4 SP No.3(flat)   |  |

**REACTIONS.** (size) 19=0-3-8, 12=0-3-8, 13=0-3-8  
Max Uplift 12=34(LC 3)  
Max Grav 19=722(LC 3), 12=161(LC 4), 13=1056(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-1849/0, 3-5=-1849/0, 5-6=-1759/0, 6-7=-1759/0, 7-8=-1168/0, 8-9=0/277, 9-10=0/277  
BOT CHORD 18-19=0/1184, 16-18=0/2016, 15-16=0/1204, 14-15=0/1168, 13-14=0/1168  
WEBS 7-15=-679/0, 8-14=0/379, 2-19=-1328/0, 2-18=0/754, 5-16=-297/2, 6-16=-536/0, 7-16=0/1270, 8-13=-1678/0, 10-13=-364/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) Attach ribbon block to truss with 3-10d nails applied to flat face.
  - 3) One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 12. This connection is for uplift only and does not consider lateral forces.
  - 4) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 6) CAUTION, Do not erect truss backwards.





June 28, 2021

|  |   |
|--|---|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information</b> available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p> | <p>ENGINEERING BY</p> <p><b>TRENCO</b></p> <p>A MiTek Affiliate</p> <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|---|


|                    |               |                     |          |          |   |
|--------------------|---------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3GA | Truss Type<br>FLOOR | Qty<br>4 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503253 |
|--------------------|---------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:09 2021 Page 1  
ID:Co\_LqlUbt4ATaJKEajxSMZzY4vF-FTy8UcwCuNhwQPMERKkxd\_nsXKPrwgXcF4e3tGz1mjO



Scale = 1:28.5



|                        |                                |             |                                  |               |                 |
|------------------------|--------------------------------|-------------|----------------------------------|---------------|-----------------|
| Plate Offsets (X, Y)-- | [6:0-1-8,Edge], [7:0-1-8,Edge] |             |                                  |               |                 |
| <b>LOADING</b> (psf)   | <b>SPACING</b> 2-0-0           | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b> | <b>GRIP</b>     |
| TCLL 40.0              | Plate Grip DOL 1.00            | TC 0.65     | Vert(LL) -0.20 15-16 >988 480    | MT20          | 244/190         |
| TCDL 10.0              | Lumber DOL 1.00                | BC 0.81     | Vert(CT) -0.31 15-16 >659 360    | MT20HS        | 187/143         |
| BCLL 0.0               | Rep Stress Incr NO             | WB 0.61     | Horz(CT) 0.05 12 n/a n/a         |               |                 |
| BCDL 5.0               | Code IRC2018/TPI2014           | Matrix-S    |                                  | Weight: 90 lb | FT = 20%F, 11%E |


|  |   |
|--|---|
| <b>LUMBER-</b>   | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP 2400F 2.0E(flat)                                      | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.1(flat) *Except*<br>12-17: 2x4 SP 2400F 2.0E(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)   |   |

**REACTIONS.** (size) 19=0-3-8, 12=Mechanical  
Max Grav 19=1017(LC 1), 12=961(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-2848/0, 3-4=-2848/0, 4-5=-3464/0, 5-6=-3464/0, 6-7=-3128/0, 7-8=-2711/0, 8-10=-2711/0  
BOT CHORD 18-19=0/1725, 16-18=0/3404, 15-16=0/3148, 14-15=0/3128, 13-14=0/3107, 12-13=0/1637  
WEBS 6-15=-453/0, 7-14=0/457, 2-19=-1937/0, 2-18=0/1272, 3-18=-253/0, 4-18=-630/0, 5-16=-464/0, 6-16=0/890, 10-12=-1844/0, 10-13=0/1216, 8-13=-60/354, 7-13=-1195/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) Attach ribbon block to truss with 3-10d nails applied to flat face.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 6) Load case(s) 1, 2, 3, 4, 5, 6 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - 7) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 8) CAUTION, Do not erect truss backwards.

|  |
|--|
| <b>LOAD CASE(S)</b> Standard   |
| 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00<br>Uniform Loads (plf)<br>Vert: 12-19=-10, 1-5=-115, 5-11=-100                      |
| 2) Dead: Lumber Increase=1.00, Plate Increase=1.00<br>Uniform Loads (plf)<br>Vert: 12-19=-10, 1-5=-115, 5-11=-100  |
| 3) 1st chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00<br>Uniform Loads (plf)<br>Vert: 12-19=-10, 1-5=-115, 5-7=-100, 7-11=-20 |



June 28, 2021

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**ENGINEERING BY**  
**TRENCO**  
A MiTek Affiliate  
818 Soundside Road  
Edenton, NC 27932

|             |       |            |     |     |  |
|-------------|-------|------------|-----|-----|--|
| Job         | Truss | Truss Type | Qty | Ply | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss |
| 21030657-02 | F3GA  | FLOOR      | 4   | 1   | T24503253                                      |
|             |       |            |     |     | Job Reference (optional)                       |

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:09 2021 Page 2  
 ID:Co\_LqIUbt4ATaJKEajxSMZzY4vF-FTy8UcwCuNhwQPMERKxkd\_nsXKPrwgXcF4e3tGz1mjO

**LOAD CASE(S)** Standard

- 4) 2nd chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00  
 Uniform Loads (plf)  
 Vert: 12-19=-10, 1-5=-35, 5-6=-20, 6-11=-100
- 5) 3rd chase Dead: Lumber Increase=1.00, Plate Increase=1.00  
 Uniform Loads (plf)  
 Vert: 12-19=-10, 1-5=-115, 5-7=-100, 7-11=-20
- 6) 4th chase Dead: Lumber Increase=1.00, Plate Increase=1.00  
 Uniform Loads (plf)  
 Vert: 12-19=-10, 1-5=-35, 5-6=-20, 6-11=-100

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

**Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road  
 Edenton, NC 27932




|                    |               |                     |          |          |   |
|--------------------|---------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3CA | Truss Type<br>FLOOR | Qty<br>5 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503254 |
|--------------------|---------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:04 2021 Page 1  
ID:Co\_LqlUbt4ATaJKEajxSMZzY4vF-vV8FQvs33r3eJeTGenLZwx40cJhHFMft5owlC3z1mjT



Scale = 1:31.0



|                        |                                |             |                                  |               |                 |
|------------------------|--------------------------------|-------------|----------------------------------|---------------|-----------------|
| Plate Offsets (X, Y)-- | [4:0-1-8,Edge], [5:0-1-8,Edge] |             |                                  |               |                 |
| <b>LOADING</b> (psf)   | <b>SPACING-</b> 2-0-0          | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b> | <b>GRIP</b>     |
| TCLL 40.0              | Plate Grip DOL 1.00            | TC 0.60     | Vert(LL) -0.27 15-16 >799 480    | MT20          | 244/190         |
| TCDL 22.0              | Lumber DOL 1.00                | BC 0.83     | Vert(CT) -0.46 15-16 >477 360    | MT20HS        | 187/143         |
| BCLL 0.0               | Rep Stress Incr YES            | WB 0.77     | Horz(CT) 0.07 12 n/a n/a         |               |                 |
| BCDL 5.0               | Code IRC2018/TPI2014           | Matrix-S    |                                  | Weight: 96 lb | FT = 20%F, 11%E |


**LUMBER-**  
TOP CHORD 2x4 SP 2400F 2.0E(flat)  
BOT CHORD 2x4 SP 2400F 2.0E(flat) \*Except\*  
12-14: 2x4 SP No.1(flat)  
WEBS 2x4 SP No.3(flat)

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 19=0-3-8, 12=Mechanical  
Max Grav 19=1216(LC 1), 12=1223(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-3481/0, 3-4=-3481/0, 4-5=-4325/0, 5-6=-4674/0, 6-7=-4674/0, 7-9=-3529/0, 9-10=-3529/0  
BOT CHORD 18-19=0/2095, 17-18=0/4325, 16-17=0/4325, 15-16=0/4325, 13-15=0/4361, 12-13=0/2094  
WEBS 4-17=0/298, 5-16=-324/0, 2-19=-2353/0, 2-18=0/1569, 4-18=-1227/0, 10-12=-2358/0, 10-13=0/1626, 9-13=-274/0, 7-13=-942/0, 7-15=0/433, 6-15=-400/0, 5-15=-88/710

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) Attach ribbon block to truss with 3-10d nails applied to flat face.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 7) CAUTION, Do not erect truss backwards.



June 28, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road  
Edenton, NC 27932


|                    |              |                     |          |          |   |
|--------------------|--------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3H | Truss Type<br>FLOOR | Qty<br>5 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503255 |
|--------------------|--------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:12 2021 Page 1  
ID:Co\_LqUbt4ATaJKEajxSMZzY4vF-g2dH6ey4BI3VHs4o6TURFdPKrXTB73u2x2sjUzb1mjL



Scale = 1:26.8




|                       |  |             |                                  |               |                 |
|-----------------------|--|-------------|----------------------------------|---------------|-----------------|
| Plate Offsets (X,Y)-- | [6:0-1-8,Edge], [13:0-1-8,Edge], [15:0-4-8,Edge] |             |                                  |               |                 |
| <b>LOADING</b> (psf)  | <b>SPACING-</b> 2-0-0                            | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b> | <b>GRIP</b>     |
| TCLL 40.0             | Plate Grip DOL 1.00                              | TC 0.78     | Vert(LL) -0.22 13-14 >870 480    | MT20          | 244/190         |
| TCDL 10.0             | Lumber DOL 1.00                                  | BC 0.64     | Vert(CT) -0.31 13-14 >617 360    |               |                 |
| BCLL 0.0              | Rep Stress Incr YES                              | WB 0.50     | Horz(CT) 0.04 10 n/a n/a         |               |                 |
| BCDL 5.0              | Code IRC2018/TPI2014                             | Matrix-S    |                                  | Weight: 83 lb | FT = 20%F, 11%E |

|                                   |   |
|-----------------------------------|---|
| <b>LUMBER-</b>                    | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.1(flat)       | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP 2400F 2.0E(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)            |   |

**REACTIONS.** (size) 15=0-3-8, 10=Mechanical  
Max Grav 15=863(LC 1), 10=869(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-2394/0, 3-4=-2394/0, 4-5=-2703/0, 5-6=-2703/0, 6-7=-2360/0, 7-8=-2360/0  
BOT CHORD 14-15=0/1464, 13-14=0/2804, 12-13=0/2703, 11-12=0/2703, 10-11=0/1461  
WEBS 6-12=-27/377, 2-15=-1643/0, 2-14=0/1054, 4-14=-464/0, 4-13=-291/258, 8-10=-1645/0, 8-11=0/1019, 7-11=-122/282, 6-11=-1012/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) Attach ribbon block to truss with 3-10d nails applied to flat face.
  - 3) Refer to girder(s) for truss to truss connections.
  - 4) Bearing at joint(s) 15 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 7) CAUTION, Do not erect truss backwards.





June 28, 2021

|   |   |
|---|---|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</b><br/>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information</b> available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p> | <p>ENGINEERING BY<br/><b>TRENCO</b><br/>A MiTek Affiliate</p> <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|---|---|

|                    |               |                     |          |          |   |
|--------------------|---------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3DA | Truss Type<br>FLOOR | Qty<br>2 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503256 |
|--------------------|---------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:06 2021 Page 1  
ID:Co\_LqUbt4ATaJKEajxSMZy4vF-ruG?rauJbSJLZxdfCN1?MAOU7M3JlR9Z6PPHyz1mjR




| LOADING (psf) | SPACING-             | CSI.     | DEFL.                         | PLATES        | GRIP            |
|---------------|----------------------|----------|-------------------------------|---------------|-----------------|
| TCLL 40.0     | 2-0-0                | TC 0.45  | in (loc) l/defl L/d           | MT20          | 244/190         |
| TCDL 22.0     | Plate Grip DOL 1.00  | BC 0.88  | Vert(LL) -0.11 12 >999 480    |               |                 |
| BCLL 0.0      | Lumber DOL 1.00      | WB 0.47  | Vert(CT) -0.18 11-12 >908 360 |               |                 |
| BCDL 5.0      | Rep Stress Incr YES  | Matrix-S | Horz(CT) 0.04 9 n/a n/a       |               |                 |
|               | Code IRC2018/TPI2014 |          |                               | Weight: 75 lb | FT = 20%F, 11%E |

|                             |   |
|-----------------------------|---|
| <b>LUMBER-</b>              | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.2(flat) | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.2(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)      |   |

**REACTIONS.** (size) 14=0-3-8, 9=0-3-8  
Max Grav 14=926(LC 1), 9=918(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-2417/0, 3-4=-2417/0, 4-5=-2659/0, 5-6=-2431/0, 6-7=-2431/0  
BOT CHORD 13-14=0/1539, 12-13=0/2659, 11-12=0/2659, 10-11=0/2659, 9-10=0/1571  
WEBS 2-14=-1727/0, 2-13=0/994, 3-13=-266/0, 4-13=-526/0, 7-9=-1746/0, 7-10=0/974, 6-10=-259/0, 5-10=-523/0

- NOTES-**
- Unbalanced floor live loads have been considered for this design.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.





June 28, 2021

|  |  |
|--|--|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information</b> available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p> | <p>ENGINEERING BY</p> <p>A MiTek Affiliate</p> <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|--|

|                    |               |                     |          |          |   |
|--------------------|---------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3JA | Truss Type<br>FLOOR | Qty<br>4 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503257 |
|--------------------|---------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:13 2021 Page 1  
ID:Co\_LqlUbt4ATaJKEajxSMZzY4vF-8EBfJ\_zjycBMv0f?gA?gnqyYvxIBsRLBAicG02z1mjK



|                       |   |             |                                  |               |             |  |                                |
|-----------------------|---|-------------|----------------------------------|---------------|-------------|--|--------------------------------|
| Plate Offsets (X,Y)-- | [12:0-3-0,Edge], [16:0-1-8,Edge], [17:0-1-8,Edge] |             |                                  |               |             |  |                                |
| <b>LOADING</b> (psf)  | <b>SPACING-</b> 2-0-0                             | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b> | <b>GRIP</b> |  |                                |
| TCLL 40.0             | Plate Grip DOL 1.00                               | TC 0.63     | Vert(LL) -0.32 15-16 >731 480    | MT20          | 244/190     |  |                                |
| TCDL 10.0             | Lumber DOL 1.00                                   | BC 0.85     | Vert(CT) -0.46 15-16 >506 360    | MT20HS        | 187/143     |  |                                |
| BCLL 0.0              | Rep Stress Incr NO                                | WB 0.81     | Horz(CT) 0.01 12 n/a n/a         |               |             |  |                                |
| BCDL 5.0              | Code IRC2018/TPI2014                              | Matrix-S    |                                  |               |             |  | Weight: 103 lb FT = 20%F, 11%E |


|                |  |                 |   |
|----------------|--|-----------------|---|
| <b>LUMBER-</b> |  | <b>BRACING-</b> |   |
| TOP CHORD      | 2x4 SP No.1(flat) *Except*<br>1-9: 2x4 SP 2400F 2.0E(flat)   | TOP CHORD       | Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD      | 2x4 SP No.1(flat) *Except*<br>13-18: 2x4 SP 2400F 2.0E(flat) | BOT CHORD       | Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS           | 2x4 SP No.3(flat)  |                 |   |

**REACTIONS.** (size) 20=0-3-8, 12=0-3-0  
Max Grav 20=1177(LC 1), 12=1137(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-3456/0, 3-4=-3456/0, 4-5=-4579/0, 5-6=-4579/0, 6-7=-4579/0, 7-8=-3892/0, 8-10=-3892/0, 10-11=-1309/0, 11-12=-1305/0  
BOT CHORD 19-20=0/2028, 17-19=0/4307, 16-17=0/4579, 15-16=0/4481, 14-15=0/2782  
WEBS 11-14=-266/0, 12-14=0/1698, 5-17=-462/3, 2-20=-2278/0, 2-19=0/1617, 3-19=-271/0, 4-19=-964/0, 4-17=-45/733, 10-14=-1673/0, 10-15=0/1258, 7-15=-667/0, 7-16=-202/542

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) Attach ribbon block to truss with 3-10d nails applied to flat face.
  - 4) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 5) Load case(s) 1, 2, 3, 4, 5, 6 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 7) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
  - 8) CAUTION, Do not erect truss backwards.

|   |  |
|---|--|
| <b>LOAD CASE(S)</b> Standard  |  |
| 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00<br>Uniform Loads (plf)<br>Vert: 13-20=-10, 1-6=-115, 6-22=-100, 12-22=-115           |  |
| 2) Dead: Lumber Increase=1.00, Plate Increase=1.00<br>Uniform Loads (plf)<br>Vert: 13-20=-10, 1-6=-115, 6-22=-100, 12-22=-115                                   |  |
| 3) 1st chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00<br>Uniform Loads (plf)<br>Vert: 13-20=-10, 1-6=-115, 6-22=-20, 12-22=-35 |  |



June 28, 2021

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**ENGINEERING BY**  
**TRENCO**  
A MiTek Affiliate  
818 Soundside Road  
Edenton, NC 27932

|                    |               |                     |          |          |   |
|--------------------|---------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3JA | Truss Type<br>FLOOR | Qty<br>4 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503257<br>Job Reference (optional) |
|--------------------|---------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:13 2021 Page 2  
ID:Co\_LqlUbt4ATaJKEajxSMZzY4vF-8EBfJ\_zjycBMv0f?gA?gnqyYvxlBsRLBAicG02z1mjK

**LOAD CASE(S)** Standard

- 4) 2nd chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00  
Uniform Loads (plf)  
Vert: 13-20=-10, 1-5=-35, 5-6=-115, 6-22=-100, 12-22=-115
- 5) 3rd chase Dead: Lumber Increase=1.00, Plate Increase=1.00  
Uniform Loads (plf)  
Vert: 13-20=-10, 1-6=-115, 6-22=-20, 12-22=-35
- 6) 4th chase Dead: Lumber Increase=1.00, Plate Increase=1.00  
Uniform Loads (plf)  
Vert: 13-20=-10, 1-5=-35, 5-6=-115, 6-22=-100, 12-22=-115

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

**Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road  
Edenton, NC 27932

|                    |              |                     |          |          |   |
|--------------------|--------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>L3S | Truss Type<br>GABLE | Qty<br>1 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503258 |
|--------------------|--------------|---------------------|----------|----------|---|


Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:17 2021 Page 1  
ID:Co\_LqIUbt4ATaJKEajxSMZzY4vF-0?RA9L0D?rioNdzmv04cyg7MNYKDoQTn5JaUApz1mjG

0-3-8

0-3-8

Scale = 1:13.3



|       |        |        |             |        |       |        |        |       |
|-------|--------|--------|-------------|--------|-------|--------|--------|-------|
| 0-3-8 | 0-11-0 | 1-10-0 | 2-0-0 2-3-0 | 4-11-0 | 5-4-0 | 6-3-0  | 6-10-8 | 7-2-0 |
| 0-3-8 | 0-7-8  | 0-11-0 | 0-2-0 0-3-0 | 2-8-0  | 0-5-0 | 0-11-0 | 0-7-8  | 0-3-8 |

Plate Offsets (X,Y)-- [2:0-3-0,Edge]


|                      |                      |       |             |              |          |        |     |               |                 |
|----------------------|----------------------|-------|-------------|--------------|----------|--------|-----|---------------|-----------------|
| <b>LOADING</b> (psf) | <b>SPACING-</b>      | 2-0-0 | <b>CSI.</b> | <b>DEFL.</b> | in (loc) | l/defl | L/d | <b>PLATES</b> | <b>GRIP</b>     |
| TCLL 40.0            | Plate Grip DOL       | 1.00  | TC 0.09     | Vert(LL)     | -0.00    | 10     | n/r | MT20          | 244/190         |
| TCDL 10.0            | Lumber DOL           | 1.00  | BC 0.01     | Vert(CT)     | -0.00    | 10     | n/r |               |                 |
| BCLL 0.0             | Rep Stress Incr      | YES   | WB 0.03     | Horz(CT)     | -0.00    | 12     | n/a |               |                 |
| BCDL 5.0             | Code IRC2018/TPI2014 |       | Matrix-R    |              |          |        |     |               |                 |
|                      |                      |       |             |              |          |        |     | Weight: 40 lb | FT = 20%F, 11%E |

|                             |   |
|-----------------------------|---|
| <b>LUMBER-</b>              | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.2(flat) | TOP CHORD Structural wood sheathing directly applied or 7-2-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.2(flat) | BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.                                   |
| WEBS 2x4 SP No.3(flat)      |   |
| OTHERS 2x4 SP No.3(flat)    |   |

**REACTIONS.** All bearings 7-2-0.  
(lb) - Max Grav All reactions 250 lb or less at joint(s) 20, 12, 16, 17, 19, 15, 13, 18, 14

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 2) Gable requires continuous bottom chord bearing.
  - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 4) Gable studs spaced at 1-4-0 oc.
  - 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



June 28, 2021



|  |   |
|--|---|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information</b> available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p> | <p>ENGINEERING BY<br/><b>TRENCO</b><br/>A MiTek Affiliate</p> <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|---|



|                    |              |                     |          |          |   |
|--------------------|--------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3D | Truss Type<br>FLOOR | Qty<br>8 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503259 |
|--------------------|--------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:05 2021 Page 1  
ID:Co\_LqIUbt4ATaJKEajxSMZzY4vF-NiideFthq9BUxn2SCVsoT8dEPJ3u\_vu0KSgrkVz1mjS




|                        |                                  |             |                                  |               |                 |
|------------------------|----------------------------------|-------------|----------------------------------|---------------|-----------------|
| Plate Offsets (X, Y)-- | [4:0-1-8, Edge], [5:0-1-8, Edge] |             |                                  |               |                 |
| <b>LOADING</b> (psf)   | <b>SPACING-</b> 2-0-0            | <b>CSI.</b> | <b>DEFL.</b> in (loc) l/defl L/d | <b>PLATES</b> | <b>GRIP</b>     |
| TCLL 40.0              | Plate Grip DOL 1.00              | TC 0.41     | Vert(LL) -0.11 12 >999 480       | MT20          | 244/190         |
| TCDL 10.0              | Lumber DOL 1.00                  | BC 0.75     | Vert(CT) -0.15 11-12 >999 360    |               |                 |
| BCLL 0.0               | Rep Stress Incr YES              | WB 0.39     | Horz(CT) 0.04 9 n/a n/a          |               |                 |
| BCDL 5.0               | Code IRC2018/TPI2014             | Matrix-S    |                                  |               |                 |
|                        |                                  |             |                                  | Weight: 75 lb | FT = 20%F, 11%E |

|                             |   |
|-----------------------------|---|
| <b>LUMBER-</b>              | <b>BRACING-</b>   |
| TOP CHORD 2x4 SP No.2(flat) | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.2(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)      |   |

**REACTIONS.** (size) 14=0-3-8, 9=0-3-8  
Max Grav 14=760(LC 1), 9=754(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-1986/0, 3-4=-1986/0, 4-5=-2183/0, 5-6=-1998/0, 6-7=-1998/0  
BOT CHORD 13-14=0/1261, 12-13=0/2183, 11-12=0/2183, 10-11=0/2183, 9-10=0/1286  
WEBS 2-14=-1414/0, 2-13=0/822, 4-13=-466/30, 7-9=-1430/0, 7-10=0/806, 5-10=-464/42

**NOTES-**  
1) Unbalanced floor live loads have been considered for this design.  
2) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.  
3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



June 28, 2021

|  |   |
|--|---|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information</b> available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p> | <p>ENGINEERING BY<br/><b>TRENCO</b><br/>A MiTek Affiliate</p> <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|---|

|                    |              |                     |          |          |   |
|--------------------|--------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>L3D | Truss Type<br>GABLE | Qty<br>1 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503260<br>Job Reference (optional) |
|--------------------|--------------|---------------------|----------|----------|---|


Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:15 2021 Page 1  
ID:Co\_LqlUbt4ATaJKEajxSMZzY4vF-4dJPKf?zTDR48KpNnb28tF10xeeKX\_Ud05N5wz1mjl

0-1-8

0-3-0

Scale = 1:23.3



|                      |                      |                |                          |                |                |                |                |                 |                 |                 |                               |
|----------------------|----------------------|----------------|--------------------------|----------------|----------------|----------------|----------------|-----------------|-----------------|-----------------|-------------------------------|
| 0-5-8<br>0-5-8       | 1-9-8<br>1-4-0       | 3-1-8<br>1-4-0 | 4-5-8<br>1-4-0           | 5-9-8<br>1-4-0 | 7-1-8<br>1-4-0 | 8-5-8<br>1-4-0 | 9-9-8<br>1-4-0 | 11-1-8<br>1-4-0 | 12-5-8<br>1-4-0 | 13-9-8<br>1-4-0 | 14-3-0<br>0-5-8               |
| <b>LOADING</b> (psf) | <b>SPACING-</b>      | 2-0-0          | <b>CSI.</b>              | <b>DEFL.</b>   | in (loc)       | l/defl         | L/d            | <b>PLATES</b>   | <b>GRIP</b>     |                 |                               |
| TCLL 40.0            | Plate Grip DOL 1.00  | TC 0.08        | Vert(LL) n/a - n/a       | 999            | MT20           | 244/190        |                |                 |                 |                 |                               |
| TCDL 10.0            | Lumber DOL 1.00      | BC 0.02        | Vert(CT) n/a - n/a       | 999            |                |                |                |                 |                 |                 |                               |
| BCLL 0.0             | Rep Stress Incr YES  | WB 0.03        | Horz(CT) 0.00 14 n/a n/a |                |                |                |                |                 |                 |                 |                               |
| BCDL 5.0             | Code IRC2018/TPI2014 | Matrix-R       |                          |                |                |                |                |                 |                 |                 | Weight: 67 lb FT = 20%F, 11%E |


**LUMBER-**  
 TOP CHORD 2x4 SP No.2(flat)  
 BOT CHORD 2x4 SP No.2(flat)  
 WEBS 2x4 SP No.3(flat)  
 OTHERS 2x4 SP No.3(flat)

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** All bearings 14-3-0.  
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 24, 14, 19, 20, 21, 22, 23, 18, 17, 16, 15

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 2) Gable requires continuous bottom chord bearing.
  - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 4) Gable studs spaced at 1-4-0 oc.
  - 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



June 28, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601





818 Soundside Road  
 Edenton, NC 27932

|                    |              |                     |          |          |   |
|--------------------|--------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>F3J | Truss Type<br>FLOOR | Qty<br>6 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503261 |
|--------------------|--------------|---------------------|----------|----------|---|

Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:13 2021 Page 1  
ID:Co\_LqlUbt4ATaJKEajxSMZzY4vF-8EBfJ\_zjycBMv0f?gA?gnqyTaxjLsS\_BAicG02z1mjK



|                       |   |
|-----------------------|---|
| Plate Offsets (X,Y)-- | [12:0-3-0,Edge], [16:0-1-8,Edge], [17:0-1-8,Edge] |
|-----------------------|---|


| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc)    | l/defl | L/d | PLATES         | GRIP            |
|---------------|----------------------|-------|----------|----------|-------------|--------|-----|----------------|-----------------|
| TCLL 40.0     | Plate Grip DOL       | 1.00  | TC 0.91  | Vert(LL) | -0.39 15-16 | >608   | 480 | MT20           | 244/190         |
| TCDL 10.0     | Lumber DOL           | 1.00  | BC 0.96  | Vert(CT) | -0.54 15-16 | >436   | 360 | MT20HS         | 187/143         |
| BCLL 0.0      | Rep Stress Incr      | YES   | WB 0.77  | Horz(CT) | -0.01 12    | n/a    | n/a |                |                 |
| BCDL 5.0      | Code IRC2018/TPI2014 |       | Matrix-S |          |             |        |     |                |                 |
|               |                      |       |          |          |             |        |     | Weight: 103 lb | FT = 20%F, 11%E |

| LUMBER-  | BRACING-  |
|--|---|
| TOP CHORD 2x4 SP No.2(flat) *Except*<br>1-9: 2x4 SP No.1(flat) | TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.1(flat)                                    | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:                          |
| WEBS 2x4 SP No.3(flat)   | 2-2-0 oc bracing: 15-16.  |

**REACTIONS.** (size) 20=0-3-8, 12=0-3-0  
Max Grav 20=1067(LC 1), 12=1074(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-3161/0, 3-4=-3161/0, 4-5=-4262/0, 5-6=-4262/0, 6-7=-4262/0, 7-8=-3703/0,  
8-10=-3703/0, 10-11=-1242/0, 11-12=-1239/0  
BOT CHORD 19-20=0/1844, 17-19=0/3975, 16-17=0/4262, 15-16=0/4229, 14-15=0/2655  
WEBS 12-14=0/1613, 5-17=-471/0, 2-20=-2071/0, 2-19=0/1492, 4-19=-217/58,  
10-14=-1605/0, 10-15=0/1187, 7-15=-595/0, 7-16=-280/464

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) Attach ribbon block to truss with 3-10d nails applied to flat face.
  - 4) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 6) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
  - 7) CAUTION, Do not erect truss backwards.



June 28, 2021

|  |   |
|--|---|
| <p><b>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</b></p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see <b>ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information</b> available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p> | <p>818 Soundside Road<br/>Edenton, NC 27932</p> |
|--|---|

|                    |              |                     |          |          |   |
|--------------------|--------------|---------------------|----------|----------|---|
| Job<br>21030657-02 | Truss<br>L3J | Truss Type<br>GABLE | Qty<br>1 | Ply<br>1 | Cameron Woods Lot 19 - 2913 Elev B-Floor Truss<br>T24503262<br>Job Reference (optional) |
|--------------------|--------------|---------------------|----------|----------|---|


Carter Components (Lexington), Lexington, NC - 27295,

8.510 s Jun 18 2021 MiTek Industries, Inc. Mon Jun 28 11:09:17 2021 Page 1  
ID:Co\_LqIUbt4ATaJKEajxSMZzY4vF-0?RA9L0D?rioNdzmV04cyg7MSYKDoQU5JaUApz1mjG

0-1-8

0-3-8

Scale = 1:32.8



| LOADING (psf) | SPACING-             | 2-0-0 | CSI.     | DEFL.    | in (loc) | l/defl | L/d | PLATES        | GRIP            |
|---------------|----------------------|-------|----------|----------|----------|--------|-----|---------------|-----------------|
| TCLL 40.0     | Plate Grip DOL       | 1.00  | TC 0.08  | Vert(LL) | -0.00    | 18     | n/r | MT20          | 244/190         |
| TCDL 10.0     | Lumber DOL           | 1.00  | BC 0.01  | Vert(CT) | -0.00    | 18     | n/r |               |                 |
| BCLL 0.0      | Rep Stress Incr      | YES   | WB 0.03  | Horz(CT) | 0.00     | 20     | n/a |               |                 |
| BCDL 5.0      | Code IRC2018/TPI2014 |       | Matrix-R |          |          |        |     | Weight: 90 lb | FT = 20%F, 11%E |

**LUMBER-**  
TOP CHORD 2x4 SP No.2(flat)  
BOT CHORD 2x4 SP No.2(flat)  
WEBS 2x4 SP No.3(flat)  
OTHERS 2x4 SP No.3(flat)


**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

**REACTIONS.** All bearings 20-0-0.  
(lb) - Max Grav All reactions 250 lb or less at joint(s) 37, 20, 29, 30, 31, 32, 33, 34, 35, 36, 28, 26, 25, 24, 23, 22, 21

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- All plates are 1.5x3 MT20 unless otherwise indicated.
- Attach ribbon block to truss with 3-10d nails applied to flat face.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 1-4-0 oc.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- CAUTION, Do not erect truss backwards.



June 28, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

**ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**


**Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road  
Edenton, NC 27932

# Symbols

## PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

\* Plate location details available in **MITek 20/20 software** or upon request.

## PLATE SIZE

**4 X 4**


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

## LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

## BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

### Industry Standards:

ANSI/TPI 1: National Design Specification for Metal Plate Connected Wood Truss Construction.  
DSB-89: Design Standard for Bracing.  
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

# Numbering System

6-4-8  
dimensions shown in ft-in-sixteenths  
(Drawings not to scale)



**JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.**

**CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.**

## PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988  
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITteK® All Rights Reserved



MITek Engineering Reference Sheet: Mill-7473 rev. 5/19/2020



# General Safety Notes

## Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Rewriting pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.