



Job 21020034KHUDSON- F	Truss PB06	Truss Type Piggyback	Qty 2	Ply 3	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	---------------	-------------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:46

Page: 1

ID: xvfr8eR?7FbDNolgUTwBw8zhTm-EJUaptdsv0?iOIEbzHsanAF3EROPs2rt2ppgUDzHslv



Scale = 1:21.7

Loading	(psf)	Spacing	4-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	NO	WB	0.01	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 64 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING

TOP CHORD 2-0-0 oc purlins (6-0-0 max.)
 (Switched from sheeted: Spacing > 2-0-0).
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS All bearings 5-1-4.

(lb) - Max Horiz 2=-95 (LC 12), 7=-95 (LC 12)
 Max Uplift All uplift 100 (lb) or less at joint(s) 2, 4, 7, 11
 Max Grav All reactions 250 (lb) or less at joint(s) except 2=402 (LC 21),
 4=402 (LC 22), 6=373 (LC 21), 7=402 (LC 21), 11=402 (LC 22)

FORCES

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

- 3-ply truss to be connected together as follows:
 Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
 Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 4. This connection is for uplift only and does not consider lateral forces.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



Job 21020034KHUDSON-F	Truss PB06A	Truss Type Piggyback	Qty 12	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
--------------------------	----------------	-------------------------	-----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:48

Page: 1

ID: xvfr8eR?7FbDNolgUTwBw8zhTm-74k5fEgNyFW8tVYNC6wXx0QlI2joshTzRntd_zHslr



Scale = 1:21.7

Loading	(psf)	Spacing	2-0-0	CSI	0.11	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.11	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 21 lb	FT = 20%

LUMBER
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING
 TOP CHORD
 BOT CHORD

Structural wood sheathing directly applied or 6-0-0 oc purlins.
 Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS All bearings 5-1-4.
 (lb) - Max Horiz 2=-47 (LC 12), 7=-47 (LC 12)
 Max Uplift All uplift 100 (lb) or less at joint(s) 2, 4, 7, 11
 Max Grav All reactions 250 (lb) or less at joint(s) 2, 4, 6, 7, 11

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 4-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 4. This connection is for uplift only and does not consider lateral forces.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



Job 21020034KHUDSON- F	Truss PB06B	Truss Type Piggyback	Qty 4	Ply 2	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	----------------	-------------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:49

Page: 1

ID:P5DDM_SduZk4_yKs2BSQTLzhTI-bHITsag?jZe?Vf7ZmqRmUEyWzS5aXI5cC4XQ9QzHslq



Scale = 1:21.7

Loading	(psf)	Spacing	2-6-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	NO	WB	0.01	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 43 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD 2-0-0 oc purlins (6-0-0 max.)
(Switched from sheeted: Spacing > 2-0-0).
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS All bearings 5-1-4.
(lb) - Max Horiz 2=-59 (LC 12), 7=-59 (LC 12)
Max Uplift All uplift 100 (lb) or less at joint(s) 2, 4, 7, 11
Max Grav All reactions 250 (lb) or less at joint(s) 6 except 2=252 (LC 21),
4=252 (LC 22), 7=252 (LC 21), 11=252 (LC 22)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- 2-ply truss to be connected together as follows:
Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 4-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 4. This connection is for uplift only and does not consider lateral forces.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



Job 21020034KHUDSON-F	Truss PB06C	Truss Type Piggyback	Qty 2	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
--------------------------	----------------	-------------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:49

Page: 1

ID:P5DDM_SduZk4_yKs2BSQTLzhTI-bHITsag?jZe?Vf7ZmqRmUEYwVS5yXlxcC4XQ9QzHslq



Scale = 1:21.7

Loading	(psf)	Spacing	2-0-0	CSI	0.11	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.11	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 21 lb	FT = 20%

LUMBER
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING
 TOP CHORD
 BOT CHORD

Structural wood sheathing directly applied or 6-0-0 oc purlins.
 Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS All bearings 5-1-4.
 (lb) - Max Horiz 2=-47 (LC 12), 7=-47 (LC 12)
 Max Uplift All uplift 100 (lb) or less at joint(s) 2, 4, 7, 11
 Max Grav All reactions 250 (lb) or less at joint(s) 2, 4, 6, 7, 11

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 4. This connection is for uplift only and does not consider lateral forces.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard

Job 21020034KHUDSON- F	Truss T01	Truss Type Attic Girder	Qty 2	Ply 3	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	--------------	----------------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:50

Page: 2

ID:AdiE1jYe?0kxyBxPWsbln1zhhTd-bHITsag?jZe?Vf7ZmqRmUEyiaS0GXAccC4XQ9QzHslq

16) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

Job 21020034KHUDSON- F	Truss T02	Truss Type Attic	Qty 5	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	--------------	---------------------	----------	----------	---




Plate Offsets (X, Y): [2:0-4-0,0-1-1], [6:0-2-11,0-2-0], [7:0-4-0,0-2-13], [8:0-4-0,0-2-13], [9:0-2-11,0-2-0], [11:0-2-4,0-1-8], [13:0-3-8,0-7-4]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP		
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.86	Vert(LL)	-0.52	13-15	>728	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.63	Vert(CT)	-0.88	13-15	>431	180	MT20HS	187/143
TCDL	10.0	Rep Stress Incr	YES	WB	0.93	Horz(CT)	0.02	12	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH		Attic	-0.32	13-15	>602	360		
BCDL	10.0											
										Weight: 276 lb	FT = 20%	

LUMBER
TOP CHORD 2x6 SP No.2 *Except* T4,T1:2x6 SP 2400F 2.0E
BOT CHORD 2x10 SP 2400F 2.0E
WEBS 2x4 SP No.3 *Except* W3:2x4 SP No.2
REACTIONS (lb/size) 2=1500/0-3-8, (min. 0-1-8), 12=1530/0-3-8, (min. 0-1-11)
Max Horiz 2=304 (LC 13)
Max Uplift 2=-12 (LC 14)
Max Grav 2=1842 (LC 52), 12=2061 (LC 50)

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-4-4 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 7-8.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 16-17, 11-12
JOINTS 1 Brace at Jt(s): 16, 17
MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-21=-2734/0, 3-21=-2617/0, 3-22=-2372/0, 22-23=-2268/0, 4-23=-2221/0, 4-24=-1712/53, 5-24=-1692/55, 5-6=-1600/77, 6-7=-635/244, 7-25=-505/295, 8-25=-505/295, 8-9=-703/219, 9-10=-1741/76, 10-26=-2078/0, 26-27=-2088/0, 11-27=-2175/0, 11-12=-2779/0
BOT CHORD 2-15=-55/2426, 14-15=0/1771, 13-14=0/1771
WEBS 3-15=-824/189, 4-15=0/994, 10-13=-174/674, 6-16=-1994/0, 16-17=-1989/0, 9-17=-2008/0, 11-13=0/2275

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-3-6, Interior (1) 2-3-6 to 11-0-6, Exterior(2R) 11-0-6 to 26-5-4, Interior (1) 26-5-4 to 28-3-6, Exterior(2E) 28-3-6 to 31-5-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Ceiling dead load (5.0 psf) on member(s). 4-6, 9-10, 6-16, 16-17, 9-17; Wall dead load (5.0psf) on member(s). 4-15, 10-13
 - Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 13-15
 - One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2. This connection is for uplift only and does not consider lateral forces.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - Attic room checked for L/360 deflection.

Job 21020034KHUDSON- F	Truss T02	Truss Type Attic	Qty 5	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	--------------	---------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:50

Page: 2

ID: eqFdF3ZGmKsoaLWb4Z6XKFzhTc-3Tss4whdUsms6ohlKXz?1RVvWrJDGXxlQkG_hszHslp

LOAD CASE(S) Standard


Job 21020034KHUDDSON-F	Truss T03	Truss Type Attic	Qty 4	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
---------------------------	--------------	---------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:51

Page: 1

ID:60p?SPZuXd_fBU5neHdmsSzhhTb-XFPEHGfFAujkyGxtFUEZf16lFgr?03vf00XEJzHslo



Scale = 1:67.5

Plate Offsets (X, Y): [2:0-4-0,0-1-1], [6:0-2-11,0-2-0], [7:0-4-0,0-2-13], [8:0-4-0,0-2-13], [9:0-2-11,0-2-0], [13:0-4-0,0-1-1], [16:0-3-8,0-7-0], [19:0-3-8,0-4-12]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.73	Vert(LL)	-0.44	16-19	>860	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.54	Vert(CT)	-0.72	16-19	>526	180	MT20HS	187/143
TCDL	10.0	Rep Stress Incr	YES	WB	0.66	Horz(CT)	0.03	13	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH		Attic	-0.28	16-19	>690	360		
BCDL	10.0											
											Weight: 319 lb	FT = 20%

LUMBER

TOP CHORD 2x6 SP 2400F 2.0E *Except* T3:2x6 SP No.2
 BOT CHORD 2x10 SP 2400F 2.0E
 WEBS 2x4 SP No.3 *Except* W3:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-7-1 oc purlins, except
 2-0-0 oc purlins (6-0-0 max.): 7-8.
 BOT CHORD Rigid ceiling directly applied or 9-8-5 oc bracing.
 WEBS 1 Row at midpt 20-21
 JOINTS 1 Brace at Jt(s): 20, 21

REACTIONS

(lb/size) 2=1650/0-3-8, (min. 0-1-11), 13=1063/0-3-8, (min. 0-1-8),
 15=864/0-3-8, (min. 0-1-8)
 Max Horiz 2=257 (LC 13)
 Max Uplift 2=-49 (LC 14), 13=-182 (LC 14), 15=-182 (LC 15)
 Max Grav 2=2020 (LC 52), 13=1184 (LC 46), 15=1658 (LC 42)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-28=-3154/0, 3-28=-3037/15, 3-29=-2773/0, 29-30=-2625/0, 4-30=-2605/0, 4-5=-2013/100, 5-6=-1913/124,
 6-7=-568/339, 7-31=-384/486, 8-31=-384/486, 8-9=-600/285, 9-10=-1916/131, 10-11=-2003/120, 11-32=-2616/93,
 32-33=-2637/82, 12-33=-2774/77, 12-34=-1685/353, 13-34=-1759/331
 BOT CHORD 2-19=-81/2807, 18-19=0/2190, 17-18=0/2190, 16-17=0/2190, 15-16=-235/1457, 13-15=-235/1457
 WEBS 3-19=-778/187, 4-19=0/1098, 11-16=-49/1069, 12-16=0/1380, 12-15=-2120/56, 6-20=-2600/51, 20-21=-2589/56,
 9-21=-2606/55

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-10-10, Interior (1) 2-10-10 to 10-2-2, Exterior(2R) 10-2-2 to 27-5-6, Interior (1) 27-5-6 to 34-8-14, Exterior(2E) 34-8-14 to 38-6-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Ceiling dead load (5.0 psf) on member(s). 4-6, 9-11, 6-20, 20-21, 9-21; Wall dead load (5.0psf) on member(s).4-19, 11-16
- Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 16-19
- One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2, 15, and 13. This connection is for uplift only and does not consider lateral forces.

Job 21020034KHUDSON- F	Truss T03	Truss Type Attic	Qty 4	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	--------------	---------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:51

Page: 2

ID:60p?SPZuXd_fBU5neHdmsSzhTb-XfPEHGIFFAujkyGxtFUEZf16IFgr?03vf00XEJzHslo

- 13) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 15) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard


Job 21020034KHUDSON-F	Truss T04	Truss Type Attic	Qty 3	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
--------------------------	--------------	---------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:52

Page: 1

ID:3Pxt4b93FENRoEAlifEytzhTz-?szcVcjt0U0ZM6r8Ry?T6saGRf0wkT02u2l5mlzHsln



Scale = 1:66.6

Plate Offsets (X, Y): [2:0-4-0,0-1-1], [6:0-2-11,0-2-0], [7:0-4-0,0-2-13], [8:0-4-0,0-2-13], [9:0-2-11,0-2-0], [13:0-4-0,0-1-1], [15:0-3-8,0-7-0], [18:0-3-8,0-4-12]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP		
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.77	Vert(LL)	-0.45	15-18	>843	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.55	Vert(CT)	-0.74	15-18	>514	180	MT20HS	187/143
TCDL	10.0	Rep Stress Incr	YES	WB	0.68	Horz(CT)	0.03	13	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH		Attic	-0.28	15-18	>685	360		
BCDL	10.0											
										Weight: 317 lb	FT = 20%	

LUMBER

TOP CHORD 2x6 SP 2400F 2.0E *Except* T3,T5:2x6 SP No.2
 BOT CHORD 2x10 SP 2400F 2.0E
 WEBS 2x4 SP No.3 *Except* W3:2x4 SP No.2

REACTIONS (lb/size) 2=1640/0-3-8, (min. 0-1-11), 13=956/0-3-8, (min. 0-1-8),
 14=929/0-3-8, (min. 0-1-8)
 Max Horiz 2=253 (LC 11)
 Max Uplift 2=-48 (LC 14), 13=-172 (LC 14), 14=-170 (LC 15)
 Max Grav 2=2008 (LC 52), 13=1081 (LC 46), 14=1726 (LC 42)

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-1-0 oc purlins, except
 2-0-0 oc purlins (6-0-0 max.): 7-8.
 BOT CHORD Rigid ceiling directly applied or 9-6-8 oc bracing.
 WEBS 1 Row at midpt 19-20
 JOINTS 1 Brace at Jt(s): 19, 20

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-27=-3124/0, 3-27=-3007/12, 3-28=-2744/0, 28-29=-2660/0, 29-30=-2594/0, 4-30=-2574/0, 4-5=-1987/98,
 5-6=-1885/122, 6-7=-562/363, 7-31=-381/505, 8-31=-381/505, 8-9=-600/293, 9-10=-1898/129, 10-11=-1986/120,
 11-32=-2562/89, 32-33=-2583/78, 12-33=-2720/73, 12-34=-1553/341, 13-34=-1627/322
 BOT CHORD 2-18=-87/2777, 17-18=0/2154, 16-17=0/2154, 15-16=0/2154, 14-15=-242/1343, 13-14=-242/1343
 WEBS 3-18=-785/188, 4-18=0/1090, 11-15=-45/1001, 12-15=0/1461, 12-14=-2189/40, 6-19=-2590/47, 19-20=-2580/52,
 9-20=-2598/51

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-10-10, Interior (1) 2-10-10 to 10-2-2, Exterior(2R) 10-2-2 to 27-5-6, Interior (1) 27-5-6 to 33-10-6, Exterior(2E) 33-10-6 to 37-7-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Ceiling dead load (5.0 psf) on member(s).4-6, 9-11, 6-19, 19-20, 9-20; Wall dead load (5.0psf) on member(s).4-18, 11-15
- Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 15-18
- One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2, 14, and 13. This connection is for uplift only and does not consider lateral forces.

Job 21020034KHUDSON- F	Truss T04	Truss Type Attic	Qty 3	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	--------------	---------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:52

Page: 2

ID:3Pxt4b93FENRoEAlifEytzhTZ-?szcVcjt0U0ZM6r8Ry?T6saGRf0wkT02u2l5mlzHsln

- 13) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 15) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard


Job 21020034KHUDSON- F	Truss T05	Truss Type Attic Girder	Qty 2	Ply 2	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	--------------	----------------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:52

Page: 1

ID:?n3WlmcPbsU5g6OZi7ii1zhTX-?szcVejt0U0ZM6r8Ry?T6saDlf1BkYn2u2l5mlzHsln



Scale = 1:66.6

Plate Offsets (X, Y): [2:0-4-0,0-1-1], [6:0-2-11,0-2-0], [7:0-4-0,0-2-13], [8:0-4-0,0-2-13], [9:0-2-11,0-2-0], [17:0-3-8,0-6-4]

Loading	(psf)	Spacing	3-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP		
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.97	Vert(LL)	-0.33	17-20	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.47	Vert(CT)	-0.55	17-20	>682	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.46	Horz(CT)	0.02	14	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH		Attic	-0.20	17-20	>960	360		
BCDL	10.0											
											Weight: 662 lb	FT = 20%

LUMBER

TOP CHORD 2x6 SP No.2 *Except* T1:2x6 SP 2400F 2.0E
 BOT CHORD 2x10 SP 2400F 2.0E
 WEBS 2x4 SP No.3 *Except* W4:2x4 SP No.2

BRACING

TOP CHORD 2-0-0 oc purlins (6-0-0 max.)
 (Switched from sheeted: Spacing > 2-0-0).
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 JOINTS 1 Brace at Jt(s): 7, 8, 22, 23

REACTIONS (lb/size) 2=2455/0-3-8, (min. 0-1-8), 14=1416/0-3-8, (min. 0-1-8),
 16=1415/0-3-8, (min. 0-1-8)
 Max Horiz 2=379 (LC 9)
 Max Uplift 2=-72 (LC 12), 14=-254 (LC 12), 16=-256 (LC 13)
 Max Grav 2=3021 (LC 50), 14=1606 (LC 50), 16=2520 (LC 40)

FORCES

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-4800/80, 3-30=-4116/0, 30-31=-3998/0, 4-31=-3898/0, 4-5=-2975/145, 5-6=-2822/181, 6-7=-918/391,
 7-32=-655/546, 8-32=-655/546, 8-9=-960/348, 9-10=-2820/188, 10-11=-2951/185, 11-33=-3983/146, 12-33=-4159/120,
 12-13=-2287/535, 13-14=-2521/476
 BOT CHORD 2-21=-170/4253, 20-21=-170/4253, 19-20=0/3205, 18-19=0/3205, 17-18=0/3205, 16-17=-139/2667, 15-16=-338/2006,
 14-15=-325/2068
 WEBS 3-21=-117/489, 3-20=-1360/345, 4-20=0/1688, 11-17=-99/1806, 12-17=0/1406, 12-16=-3254/0, 13-16=-439/164,
 13-15=0/335, 6-22=-3648/62, 22-23=-3631/69, 9-23=-3655/68

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
 Bottom chords connected as follows: 2x10 - 2 rows staggered at 0-9-0 oc.
 Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Ceiling dead load (5.0 psf) on member(s).4-6, 9-11, 6-22, 22-23, 9-23; Wall dead load (5.0psf) on member(s).4-20, 11-17
- Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 17-20

Job 21020034KHUDSON- F	Truss T05	Truss Type Attic Girder	Qty 2	Ply 2	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	--------------	----------------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:52

Page: 2

ID:?n3WlmcPbsU5g6OZi7ii1IzhTX-?szcVcjt0U0ZM6r8Ry?T6saDlf1BkYn2u2l5mlzHsln

- 13) One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2, 16, and 14. This connection is for uplift only and does not consider lateral forces.
- 14) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 15) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 16) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

Job 21020034KHudson-F	Truss T06	Truss Type Attic Structural Gable	Qty 1	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
--------------------------	--------------	--------------------------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:53

Page: 1

ID:PMkewofHtnngXZ78YFFPfxzhTU-T2X_ijjVnn8QzGQK?gWie47R13KiTuhC6iVelBzHslm




Plate Offsets (X, Y): [2:0-4-0,0-1-1], [6:0-2-11,0-2-0], [7:0-4-0,0-2-13], [11:0-4-0,0-2-13], [13:0-2-11,0-2-0], [26:0-3-8,0-7-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP		
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.78	Vert(LL)	-0.43	26-29	>839	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.58	Vert(CT)	-0.70	26-29	>508	180	MT20HS	187/143
TCDL	10.0	Rep Stress Incr	YES	WB	0.93	Horz(CT)	0.03	21	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH		Attic	-0.27	26-29	>716	360		
BCDL	10.0											
										Weight: 338 lb FT = 20%		

LUMBER
TOP CHORD 2x6 SP 2400F 2.0E *Except* T3,T5:2x6 SP No.2
BOT CHORD 2x10 SP 2400F 2.0E
WEBS 2x4 SP No.3 *Except* W3:2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-0-12 oc purlins, except
2-0-0 oc purlins (6-0-0 max.): 7-11.
BOT CHORD Rigid ceiling directly applied or 9-8-5 oc bracing.
JOINTS 1 Brace at Jt(s): 30, 31, 32

REACTIONS All bearings 8-0-0. except 2=0-3-8
(lb) - Max Horiz 2=253 (LC 11)
Max Uplift All uplift 100 (lb) or less at joint(s) 2, 21, 22, 23 except 24=-133 (LC 14), 25=-871 (LC 46)
Max Grav All reactions 250 (lb) or less at joint(s) 22, 23 except 2=2005 (LC 52), 21=948 (LC 52), 24=1327 (LC 52), 25=624 (LC 42)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-41=-3117/8, 3-41=-3000/27, 3-42=-2734/0, 4-43=-2650/0, 4-44=-2584/0, 4-45=-2564/0, 4-5=-1980/109, 5-6=-1881/132, 6-7=-597/337, 7-8=-425/483, 8-9=-425/483, 9-10=-425/483, 10-11=-425/483, 11-12=-529/373, 12-13=-673/254, 13-14=-1891/138, 14-15=-1978/130, 15-45=-2620/116, 45-46=-2648/112, 16-46=-2737/99, 16-17=-1780/237, 17-18=-1522/249, 18-19=-1622/244, 19-47=-1530/203, 20-47=-1580/191, 20-21=-1599/171
BOT CHORD 2-29=-99/2772, 28-29=0/2151, 27-28=0/2151, 26-27=0/2151, 25-26=-119/1479, 24-25=-112/1319, 23-24=-112/1319, 22-23=-112/1319, 21-22=-112/1319
WEBS 3-29=-782/187, 4-29=0/1071, 15-26=-76/1111, 6-31=-2554/58, 30-31=-2554/58, 30-32=-2554/58, 32-33=-2554/58, 13-33=-2560/58, 12-33=-8/286, 17-34=-511/0, 24-34=-514/0, 16-25=-1952/0, 25-34=-21/398, 18-34=-15/392, 16-26=0/1439

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-10-10, Interior (1) 2-10-10 to 10-2-2, Exterior(2R) 10-2-2 to 27-5-6, Interior (1) 27-5-6 to 33-10-6, Exterior(2E) 33-10-6 to 37-7-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

Job 21020034KHUDSON- F	Truss T06	Truss Type Attic Structural Gable	Qty 1	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	--------------	--------------------------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:53

Page: 2

ID:PMkewofHtntgXZ78YFFFPfzhTU-T2X_ijjVnn8QzGQK?gWie47R13KiTuhC6iVeIBzHslm

- 12) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 13) Ceiling dead load (5.0 psf) on member(s). 4-6, 13-15, 6-31, 30-31, 30-32, 32-33, 13-33; Wall dead load (5.0psf) on member(s).4-29, 15-26
- 14) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 26-29
- 15) One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2, 24, 23, 22, and 21. This connection is for uplift only and does not consider lateral forces.
- 16) One RT16A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 25. This connection is for uplift only and does not consider lateral forces.
- 17) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 18) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 19) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard


Job 21020034KHUDSON- F	Truss T07	Truss Type Common Supported Gable	Qty 1	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	--------------	--------------------------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:54

Page: 1

ID:tHmbZKSFfssxc6v3uczf?ZzhTk-T2X_ijjVnn8QzGQK?gWie47cz3T8T3yC6iVelBzHslm



Scale = 1:55.9
Plate Offsets (X, Y): [2:0-2-12,0-0-3], [20:0-2-12,0-2-11]

Loading	(psf)	Spacing	2-0-0	CSI	0.08	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20 244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999	
TCDL	10.0	Rep Stress Incr	YES	WB	0.21	Horz(CT)	0.01	22	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH							
BCDL	10.0										Weight: 219 lb FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3
SLIDER Left 2x4 SP No.3 -- 0-11-14, Right 2x4 SP No.3 -- 0-11-14

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 11-30, 10-31, 12-28


REACTIONS All bearings 29-11-0.
(lb) - Max Horiz 2=248 (LC 13), 38=248 (LC 13)
Max Uplift All uplift 100 (lb) or less at joint(s) 20, 23, 24, 25, 26, 27, 28, 31, 32, 33, 34, 35, 36, 42 except 2=112 (LC 12), 22=104 (LC 15), 37=122 (LC 14), 38=112 (LC 12)
Max Grav All reactions 250 (lb) or less at joint(s) 2, 20, 22, 23, 24, 25, 26, 27, 30, 32, 33, 34, 35, 36, 37, 38, 42 except 28=258 (LC 22), 31=258 (LC 21)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-1-8, Exterior(2N) 2-1-8 to 11-11-8, Corner(3R) 11-11-8 to 17-11-8, Exterior(2N) 17-11-8 to 27-9-8, Corner(3E) 27-9-8 to 30-9-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2, 31, 32, 33, 34, 35, 36, 37, 28, 27, 26, 25, 24, 23, 22, and 20. This connection is for uplift only and does not consider lateral forces.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job 21020034KHudson-F	Truss T08	Truss Type Common	Qty 7	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
--------------------------	--------------	----------------------	----------	----------	---



Scale = 1:55.9

Plate Offsets (X, Y): [2:0-3-13,Edge], [5:0-4-0,Edge], [7:0-4-0,Edge], [10:0-3-13,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP		
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.98	Vert(LL)	-0.25	12-14	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.82	Vert(CT)	-0.37	12-14	>960	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.37	Horz(CT)	0.04	10	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 159 lb	FT = 20%

LUMBER	TOP CHORD	2x4 SP No.1 *Except* T1:2x4 SP 2400F 2.0E	BRACING	TOP CHORD	Structural wood sheathing directly applied.
BOT CHORD	2x4 SP No.1		BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.	
WEBS	2x4 SP No.2 *Except* W1:2x4 SP No.3				
OTHERS	2x4 SP No.3				
SLIDER	Left 2x4 SP No.3 -- 1-6-0, Right 2x4 SP No.3 -- 1-6-0				

REACTIONS (lb/size) 2=1249/0-3-8, (min. 0-1-12), 10=1249/0-3-8, (min. 0-1-12)
 Max Horiz 2=248 (LC 13)
 Max Uplift 2=-119 (LC 14), 10=-119 (LC 15)
 Max Grav 2=1462 (LC 24), 10=1462 (LC 25)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1320/0, 3-4=-1902/183, 4-23=-1788/231, 5-23=-1672/243, 5-6=-1659/264, 6-7=-1659/264, 7-24=-1672/243, 8-24=-1788/231, 8-9=-1902/183, 9-10=-1156/0
 BOT CHORD 2-25=-288/1683, 25-26=-182/1683, 14-26=-182/1683, 14-27=0/1101, 13-27=0/1101, 13-28=0/1101, 12-28=0/1101, 12-29=-31/1515, 29-30=-31/1515, 10-30=-31/1515
 WEBS 6-12=-161/922, 8-12=-465/283, 6-14=-161/922, 4-14=-465/283

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 11-11-8, Exterior(2R) 11-11-8 to 17-11-8, Interior (1) 17-11-8 to 27-9-8, Exterior(2E) 27-9-8 to 30-9-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 10. This connection is for uplift only and does not consider lateral forces.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job 21020034KHUDSON-F	Truss T09	Truss Type Attic Girder	Qty 2	Ply 2	Kelly's Account-Lamco-McNeill Job Reference (optional)
--------------------------	--------------	----------------------------	----------	----------	---




Plate Offsets (X, Y): [2:0-4-0,0-1-1], [6:0-2-11,0-2-0], [7:0-4-0,0-2-13], [8:0-4-0,0-2-13], [9:0-2-11,0-2-0], [15:0-3-8,0-7-4]

Loading	(psf)	Spacing	3-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.94	Vert(LL)	-0.38	15-17	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.54	Vert(CT)	-0.64	15-17	>593	180	MT20HS	187/143
TCDL	10.0	Rep Stress Incr	NO	WB	0.69	Horz(CT)	0.02	13	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH		Attic	-0.22	15-17	>848	360		
BCDL	10.0											
											Weight: 586 lb	FT = 20%

LUMBER

TOP CHORD 2x6 SP No.2 *Except* T1:2x6 SP 2400F 2.0E
 BOT CHORD 2x10 SP 2400F 2.0E
 WEBS 2x4 SP No.3 *Except* W4:2x4 SP No.2

BRACING

TOP CHORD 2-0-0 oc purlins (6-0-0 max.), except end verticals (Switched from sheeted: Spacing > 2-0-0).
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 JOINTS 1 Brace at Jt(s): 7, 8, 12, 19, 20

REACTIONS (lb/size) 2=2250/0-3-8, (min. 0-1-8), 13=2295/0-3-8, (min. 0-1-8)
 Max Horiz 2=456 (LC 11)
 Max Uplift 2=-18 (LC 12)
 Max Grav 2=2762 (LC 50), 13=3092 (LC 48)

FORCES

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-4423/2, 3-24=-3519/0, 24-25=-3373/0, 4-25=-3301/0, 4-5=-2566/39, 5-6=-2398/75, 6-7=-999/341, 7-26=-798/376, 8-26=-798/376, 8-9=-1080/321, 9-10=-2582/89, 10-27=-3148/0, 11-27=-3323/0, 11-12=-1003/7, 12-13=-2400/0
 BOT CHORD 2-18=-120/3921, 17-18=-120/3921, 16-17=0/2634, 15-16=0/2634, 14-15=-15/791
 WEBS 3-18=-208/954, 3-17=-1671/415, 4-17=0/1483, 10-15=-103/1225, 11-15=0/3493, 11-14=-4689/0, 6-19=-2871/0, 19-20=-2862/0, 9-20=-2889/0, 12-14=0/2007, 8-20=0/253

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc.
 Bottom chords connected as follows: 2x10 - 2 rows staggered at 0-9-0 oc.
 Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Ceiling dead load (5.0 psf) on member(s). 4-6, 9-10, 6-19, 19-20, 9-20; Wall dead load (5.0psf) on member(s). 4-17, 10-15
- Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 15-17
- One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at Jt(s) 2. This connection is for uplift only and does not consider lateral forces.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

Job 21020034KHUDSON- F	Truss T09	Truss Type Attic Girder	Qty 2	Ply 2	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	--------------	----------------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:54

Page: 2


ID:tZI078fve5?X9jiK5ymeB8zhTT-xE5Mvik8Y5GHbQ?WZN1xBHfaHThYCPiLLMEBqezHsll

- 16) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 17) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

Job 21020034KHUDSON- F	Truss T10	Truss Type Attic Structural Gable	Qty 1	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	--------------	--------------------------------------	----------	----------	---

Carter Components, Sanford, NC, user Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:55 Page: 1
ID:mKYXzVjQIJYdL?5KorbM_zhhTP-QRf7elmJPO8Daaj65YAKVCxgs9wx_3Ua0_IN4zHslk



Scale = 1:60.4

Plate Offsets (X, Y): [13:0-3-0,0-3-8], [17:0-3-0,0-3-8], [29:0-5-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP		
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.13	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.17	Horz(CT)	0.00	26	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
										Weight: 407 lb	FT = 20%	

LUMBER
TOP CHORD 2x6 SP No.2
BOT CHORD 2x10 SP 2400F 2.0E
WEBS 2x4 SP No.3 *Except* W3:2x4 SP No.2
OTHERS 2x4 SP No.3

REACTIONS All bearings 31-7-0.
(lb) - Max Horiz 2=304 (LC 13)
Max Uplift All uplift 100 (lb) or less at joint(s) 2, 26, 27, 30, 32, 33, 34, 36, 37, 39, 40, 41, 42 except 28=134 (LC 15), 38=105 (LC 14)
Max Grav All reactions 250 (lb) or less at joint(s) 2, 26, 27, 31, 32, 33, 34, 36, 37, 39, 40, 41, 42 except 28=386 (LC 54), 30=383 (LC 54), 38=255 (LC 52)

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 13-17.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 33-43, 34-44, 36-45, 10-37, 32-48, 31-49, 20-30
JOINTS 1 Brace at Jt(s): 43, 44, 46, 48, 51

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-3-6, Interior (1) 2-3-6 to 11-0-6, Exterior(2R) 11-0-6 to 26-5-4, Interior (1) 26-5-4 to 28-3-6, Exterior(2E) 28-3-6 to 31-5-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - Provide adequate drainage to prevent water ponding.
 - All plates are 3x6 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2, 38, 26, 33, 34, 36, 37, 39, 40, 41, 42, 32, 30, 28, and 27. This connection is for uplift only and does not consider lateral forces.
 - Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 2.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - Attic room checked for L/360 deflection.

Job 21020034KHUDSON- F	Truss T10	Truss Type Attic Structural Gable	Qty 1	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	--------------	--------------------------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:55

Page: 2

ID:mKYXzVjQjVydL?5KorbM_zhhTP-QRfi7elmJPO8Daaj65YAKVCxgs9wx_3Ua0_IN4zHsk

LOAD CASE(S) Standard


Job 21020034KHUDDSON- F	Truss T11	Truss Type Common Supported Gable	Qty 1	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
-------------------------------	--------------	--------------------------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:56

Page: 1

ID:lsSkBLV7xnEWTZdeH0WMdBzhTh-udD7K_mO4iW?kq9vgo3PGil6QGUDgQ2epgjlVWzHslj



Scale = 1:48.7

Plate Offsets (X, Y): [16:Edge,0-6-6]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.13	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.25	Horz(CT)	0.00	16	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MR								
BCDL	10.0											
											Weight: 150 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 WEBS 2x4 SP No.3
 OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
 WEBS 1 Row at midpt 8-22

REACTIONS

All bearings 20-11-0.
 (lb) - Max Horiz 27=243 (LC 13)
 Max Uplift All uplift 100 (lb) or less at joint(s) 16, 18, 20, 21, 23, 24, 25, 27 except 17=-144 (LC 15), 26=-152 (LC 14)
 Max Grav All reactions 250 (lb) or less at joint(s) 16, 17, 18, 20, 24, 25, 26, 27 except 21=271 (LC 22), 22=265 (LC 15), 23=271 (LC 21)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES


(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 7-8=-182/300, 8-9=-182/300
 WEBS 8-22=-314/134

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-1-8, Exterior(2N) 2-1-8 to 7-5-8, Corner(3R) 7-5-8 to 13-5-8, Exterior(2N) 13-5-8 to 18-9-8, Corner(3E) 18-9-8 to 21-9-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 27, 16, 23, 24, 25, 26, 21, 20, 18, and 17. This connection is for uplift only and does not consider lateral forces.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job 21020034KHudson-F	Truss T12	Truss Type Common	Qty 7	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
--------------------------	--------------	----------------------	----------	----------	---



Scale = 1:50.8

Plate Offsets (X, Y): [2:Edge,0-3-0], [6:Edge,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	0.61	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.61	Vert(LL)	-0.08 10-11	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.54	Vert(CT)	-0.12 11-12	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.71	Horz(CT)	0.02 8	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH							
BCDL	10.0									Weight: 140 lb	FT = 20%

LUMBER
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 WEBS 2x4 SP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 4-9-13 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 8=886/0-3-8, (min. 0-1-8), 12=886/0-3-8, (min. 0-1-8)
 Max Horiz 12=243 (LC 13)
 Max Uplift 8=-78 (LC 15), 12=-78 (LC 14)
 Max Grav 8=988 (LC 6), 12=988 (LC 5)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-481/180, 3-13=-1039/188, 13-14=-943/201, 4-14=-909/224, 4-15=-909/224, 15-16=-943/201, 5-16=-1039/188,
 5-6=-480/180, 2-12=-461/177, 6-8=-461/177
 BOT CHORD 11-12=-101/889, 11-17=0/605, 17-18=0/605, 10-18=0/605, 9-10=-3/779, 8-9=-3/779
 WEBS 4-10=-149/555, 5-10=-295/241, 4-11=-149/555, 3-11=-295/241, 3-12=-748/5, 5-8=-748/4

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 7-5-8, Exterior(2R) 7-5-8 to 13-5-8, Interior (1) 13-5-8 to 18-9-8, Exterior(2E) 18-9-8 to 21-9-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 12 and 8. This connection is for uplift only and does not consider lateral forces.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job 21020034KHudson-F	Truss T13	Truss Type Common	Qty 4	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
--------------------------	--------------	----------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:57

Page: 1

ID:EFaUc1WOTPUeJtn0PRZqiczhTf-MpnVYJn0r0esStk5EVbepwH9fgjFPlen1KTsRyzHsl



Scale = 1:50.8

Plate Offsets (X, Y): [2:Edge,0-3-0], [6:Edge,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.61	Vert(LL)	-0.08	9-10	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.54	Vert(CT)	-0.12	9-10	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.74	Horz(CT)	0.02	7	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 138 lb	FT = 20%

LUMBER
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 WEBS 2x4 SP No.3

BRACING
 TOP CHORD Structural wood sheathing directly applied or 4-9-8 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 7=823/0-3-8, (min. 0-1-8), 11=888/0-3-8, (min. 0-1-8)
 Max Horiz 11=236 (LC 13)
 Max Uplift 7=-58 (LC 15), 11=-78 (LC 14)
 Max Grav 7=935 (LC 6), 11=988 (LC 5)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-480/180, 3-12=-1041/188, 12-13=-944/202, 4-13=-910/225, 4-14=-914/227, 14-15=-949/204, 5-15=-1045/190,
 5-6=-423/132, 2-11=-461/177, 6-7=-359/123
 BOT CHORD 10-11=-114/880, 10-16=0/596, 16-17=0/596, 9-17=0/596, 8-9=-17/785, 7-8=-17/785
 WEBS 4-9=-152/563, 5-9=-303/245, 4-10=-149/556, 3-10=-295/241, 3-11=-750/5, 5-7=-784/35

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 7-5-8, Exterior(2R) 7-5-8 to 13-5-8, Interior (1) 13-5-8 to 17-9-4, Exterior(2E) 17-9-4 to 20-9-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 11 and 7. This connection is for uplift only and does not consider lateral forces.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard




Job 21020034KHudson-F	Truss V02	Truss Type Valley	Qty 1	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
--------------------------	--------------	----------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:57

Page: 1

ID:EFaUc1WOTPUeJtn0PRZqiczhhTf-MpnVYJn0r0esStk5EVbepwHIPgrvPwCn1KTsRyzHsli



Scale = 1:21.7

Plate Offsets (X, Y): [2:0-2-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.05	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP							Weight: 7 lb	FT = 20%
BCDL	10.0											

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING
TOP CHORD
BOT CHORD

Structural wood sheathing directly applied or 2-6-2 oc purlins.
Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=100/2-6-2, (min. 0-1-8), 3=100/2-6-2, (min. 0-1-8)
Max Horiz 1=-21 (LC 10)
Max Uplift 1=-9 (LC 14), 3=-9 (LC 15)
Max Grav 1=113 (LC 20), 3=113 (LC 21)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 9 lb uplift at joint 1 and 9 lb uplift at joint 3.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job 21020034KHudson-F	Truss V05	Truss Type Valley	Qty 1	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
--------------------------	--------------	----------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:57

Page: 1

ID:EFaUc1WOTPUeJtn0PRZqiczhTf-MpnVYJn0r0esStk5EVbepwHG?gpCPwQn1KTsRyzHsl



Scale = 1:25.9

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.14	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.16	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.05	Horiz(TL)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 21 lb	FT = 20%

LUMBER
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING
 TOP CHORD
 BOT CHORD

Structural wood sheathing directly applied or 5-8-8 oc purlins.
 Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 1=50/5-8-8, (min. 0-1-8), 3=50/5-8-8, (min. 0-1-8), 4=357/5-8-8, (min. 0-1-8)
 Max Horiz 1=-52 (LC 10)
 Max Uplift 3=-5 (LC 15), 4=-46 (LC 14)
 Max Grav 1=97 (LC 20), 3=97 (LC 21), 4=373 (LC 20)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 5 lb uplift at joint 3.
 - One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 4. This connection is for uplift only and does not consider lateral forces.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job 21020034KHudson- F	Truss V08	Truss Type Valley	Qty 1	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
------------------------------	--------------	----------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:57

Page: 1

ID:EFaUc1WOTPUeJtn0PRZqiczhhTf-MpnVYJn0r0esStk5EVbepwHCKgIRPun1KTsRyzHsl



Scale = 1:30.1

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.44	Vert(LL)	n/a	-	n/a	999	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.40	Vert(TL)	n/a	-	n/a	999	
TCDL	10.0	Rep Stress Incr	YES	WB	0.15	Horiz(TL)	0.00	3	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP							
BCDL	10.0									Weight: 34 lb	FT = 20%

LUMBER
 TOP CHORD 2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 OTHERS 2x4 SP No.3

BRACING
 TOP CHORD
 BOT CHORD

Structural wood sheathing directly applied or 8-10-14 oc purlins.
 Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 1=20/8-10-14, (min. 0-1-8), 3=20/8-10-14, (min. 0-1-8),
 4=673/8-10-14, (min. 0-1-8)
 Max Horiz 1=-83 (LC 10)
 Max Uplift 1=-53 (LC 21), 3=-53 (LC 20), 4=-112 (LC 14)
 Max Grav 1=75 (LC 20), 3=75 (LC 21), 4=726 (LC 20)

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-9=-136/251, 2-9=-119/339, 2-10=-119/339, 3-10=-136/251
 WEBS 2-4=-546/271

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Exterior(2R) 3-0-5 to 5-11-3, Exterior(2E) 5-11-3 to 8-11-3 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 53 lb uplift at joint 1 and 53 lb uplift at joint 3.
 - One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 4. This connection is for uplift only and does not consider lateral forces.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job 21020034KHudson-F	Truss V12	Truss Type Valley	Qty 1	Ply 1	Kelly's Account-Lamco-McNeill Job Reference (optional)
--------------------------	--------------	----------------------	----------	----------	---

Carter Components, Sanford, NC, user

Run: 8.42 S Dec 30 2020 Print: 8.500 S Apr 2 2021 MiTek Industries, Inc. Mon May 10 16:42:58

Page: 1

ID:IR8sqNX0Eic4K1MDy943FqzhTe-q0LtfneckMj41JloD6L7qSN4BJ8NXxG_CP_PzHsh



Scale = 1:32.4

Loading	(psf)	Spacing	2-0-0	CSI	0.10	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.10	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.04	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.06	Horiz(TL)	0.00	7	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH							Weight: 59 lb	FT = 20%
BCDL	10.0											

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD
BOT CHORD

Structural wood sheathing directly applied or 6-0-0 oc purlins.
Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS All bearings 12-1-5.
(lb) - Max Horiz 1=114 (LC 12)
Max Uplift All uplift 100 (lb) or less at joint(s) 1, 8, 9, 11, 12
Max Grav All reactions 250 (lb) or less at joint(s) 1, 7, 8, 10, 12 except
9=268 (LC 21), 11=268 (LC 20)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) 0-0-5 to 3-0-5, Corner(3R) 3-0-5 to 9-1-10, Corner(3E) 9-1-10 to 12-1-10 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1.
 - One RT7A MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 11, 12, 9, and 8. This connection is for uplift only and does not consider lateral forces.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard