



Agri-Waste Technology, Inc.
501 N Salem Street, Suite 203, Apex, NC 27502
agriwaste.com | 919.859.0669



AOWE As-Built Overview

Client Information		Property Information	
Name	Ashley Becker	Address	145 Stonemason Dr Holly Springs, NC 27540
Phone number	919-818-6735	PIN	0626-80-0039 Harnett County
Email Address	abecker8818@gmail.com	Water Supply	Public
Facility Type	SFR 3-bedrooms	New/Repair/ Expansion?	New

System Information		Leach Field	
Daily Design Flow	360gpd	Total Leach Line Length	300
# of Bedrooms	3	# of Laterals	3
LTAR	0.3	Trench Width	3'
Initial System Type	IIIb - accepted	Maximum Trench Depth	18-24"
Repair System Classification	IIIb - T&J Panel	Manufacturer/Product	EZ Flow
Subsurface Operator Required?	No	Distribution Device	Manifold

Septic Tank		Pump System	
Septic Tank Min. Capacity	1,000	Pump Tank Min. Capacity	1,000
Tank Manufacturer	Mitchell	Tank Manufacturer	Mitchell
Leak Test Required	Yes	Leak Test Required	No
Seam	Mid	Seam	Top
Material	Concrete	Material	Concrete
Access Risers	EZ Set	Access Risers	EZ Set
Effluent Filter	Polylok	Pump Size	1/3 HP
Other		Pump Manufacturer/Type	Zoeller N151



Engineers and Soil Scientists

Agri-Waste Technology, Inc.
501 N Salem Street, Suite 203, Apex, NC 27502
agriwaste.com | 919.859.0669

Maintenance Requirements

- Pump septic tank every 3-5 years or as necessary to ensure proper function.
- Clean effluent filter every 6 months or as necessary to ensure proper function.
- Please do not allow any traffic, construction, excavation, utilities, material storage, or any other disturbance to take place on the designated septic area or repair area. These activities may damage your septic system.

Additional Notes:

Local health department shall inspect Type IIIb systems every 5 years.

A handwritten signature in black ink, appearing to be 'Jeff N...', written over a horizontal line.

AOWE Signature

01/03/2024

Date



Engineers and Soil Scientists

Agri-Waste Technology, Inc.
501 N Salem Street, Suite 203, Apex, NC 27502
agriwaste.com | 919.859.0669

Owners Acceptance of Wastewater System

I, Ashley Becker (Owner), accept the system as designed by

Agri-Waste Technology, Inc (AOWE), and installed by

Lynn Environmental (Contractor).

Ashley Becker
Owner

1/3/24
Date