

North Carolina 2018 - R402.1.5 Total UA



Property

Fayetteville, NC 27501
 Model: Kenzie
 Community: NA

Organization

Southern Energy Manager
 Justin Smith

Inspection Status

Results are projected

Template - H & H - Fayetteville -
 Kenzie plan slab - CZ 4 - ecoSelect
 Kenzie plan slab

Builder

H&H Homes

This report is based on a proposed design and does not confirm field enforcement of design elements.

Building UA

Elements	NC Reference	As Designed
Ceilings	35.1	31.4
Above-Grade Walls	157.9	122.7
Windows, Doors and Skylights	102.9	97.2
Slab Floor:	63.2	81.5
Framed Floors	17.2	18.4
Foundation Walls	0.0	0.0
Rim Joists	7.6	6.7
Overall UA (Design must be equal or lower):	383.9	357.9

Requirements

✓	402.1.5	Total UA alternative compliance passes by 6.8%.
✓	402.3.2 Glazed Fenestration SHGC	Average SHGC: 0.27 Max SHGC: 0.30
✓	R402.4.2.2	Air Leakage Testing Air sealing is 4.80 ACH at 50 Pa. It must not exceed 5.00 ACH at 50 Pa.
✓	R402.5	Area-weighted average fenestration SHGC
✓	R402.5	Area-weighted average fenestration U-Factor
✓	R404.1	Lighting Equipment Efficiency
✓	Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met.
✓	R403.3	Duct Insulation
✓	403.3.3	Duct Testing

Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 6.8%.

Name: Justin Smith
 Organization: Southern Energy Management

Signature: Justin Smith
 Digitally signed: 8/11/20 at 9:29 AM

Ekotrope RATER - Version 3.2.3.2500

North Carolina 2018 Prescriptive compliance results calculated using Ekotrope RATER's energy and code compliance algorithm, including appropriate amendments. Ekotrope RATER is a RESNET Accredited HERS Rating Tool. All results are based on data entered by Ekotrope users. Ekotrope disclaims all liability for the information shown on this report.

Energy Code Inspection Checklist



SOUTHERN ENERGY
MANAGEMENT
ENERGY EFFICIENCY & SOLAR POWER

Property

Fayetteville, NC 27501
Model: Kenzie
Community: NA

Organization

Southern Energy Manager
Justin Smith

Inspection Status

Results are projected

Template - H & H - Fayetteville -
Kenzie plan slab - CZ 4 - ecoSelect
Kenzie plan slab

Builder


H&H Homes

General Building Information


Conditioned Area (sq ft)	1,974
Conditioned Volume (cubic ft)	18,368
Insulated Shell Area (sq ft)	4,820

The building energy model in Ekotrope reflects the building assemblies and energy features listed below. Sometimes energy features will change in the field from what has been modeled. The inspection process should identify any changes and ensure that the home continues to meet the applicable energy code.

Slab

 Name: slab(804 s.f., 136 ft. exterior perimeter)
R-0 perimeter insulation, R-0 under slab insulation.


Framed Floor


 Name: over garage (366 s.f.)
R-0 continuous insulation, R-19 cavity insulation
Insulation Grade: II


Foundation Wall

None Present

Above Grade Wall

 Name: 1st floor ambient (883 s.f.)
R-0 continuous insulation, R-19 cavity insulation
Insulation Grade: II

 Name: 1st floor garage (341 s.f.)
R-0 continuous insulation, R-19 cavity insulation
Insulation Grade: II

 Name: 2nd floor ambient (1,120 s.f.)
R-0 continuous insulation, R-19 cavity insulation
Insulation Grade: II

Rim Joist

Energy Code Inspection Checklist



SOUTHERN ENERGY
MANAGEMENT
ENERGY EFFICIENCY & SOLAR POWER

Property

Fayetteville, NC 27501
Model: Kenzie
Community: NA

Organization

Southern Energy Manager
Justin Smith

Inspection Status

Results are projected

Template - H & H - Fayetteville -
Kenzie plan slab - CZ 4 - ecoSelect
Kenzie plan slab

Builder

H&H Homes

Name: 1st floor ambient (98 s.f.)
R: 15.40

Name: 1st floor garage (38 s.f.)
R: 15.40

Ceiling / Roof

Name: Attic (1,170 s.f.)
R-13 continuous insulation, R-25 cavity insulation
Insulation Grade: I

Opaque Door

Name: front entry (20 s.f.)
U: 0.200

Name: garage entry (18 s.f.)
U: 0.200

Glazing

Name: front shaded (11 s.f.), U: 0.350, SHGC: 0.27, Orientation: SOUTH_EAST

Name: front 2nd unshaded (54 s.f.), U: 0.350, SHGC: 0.27, Orientation: SOUTH_EAST

Name: left unshaded (30 s.f.), U: 0.350, SHGC: 0.27, Orientation: SOUTH_WEST

Name: left 2nd unshaded (15 s.f.), U: 0.350, SHGC: 0.27, Orientation: SOUTH_WEST

Name: right unshaded (30 s.f.), U: 0.350, SHGC: 0.27, Orientation: NORTH_EAST

Name: right 2nd unshaded (23 s.f.), U: 0.350, SHGC: 0.27, Orientation: NORTH_EAST

Name: rear unshaded (30 s.f.), U: 0.350, SHGC: 0.27, Orientation: NORTH_WEST

Energy Code Inspection Checklist



Property

Fayetteville, NC 27501
Model: Kenzie
Community: NA

Organization

Southern Energy Manager
Justin Smith

Inspection Status

Results are projected

Template - H & H - Fayetteville -
Kenzie plan slab - CZ 4 - ecoSelect
Kenzie plan slab

Builder

H&H Homes

Name: rear shaded (33 s.f.), U: 0.350, SHGC: 0.27, Orientation: NORTH_WEST

Name: rear 2nd unshaded (30 s.f.), U: 0.350, SHGC: 0.27, Orientation: NORTH_WEST

Skylight

None Present

Mechanical Ventilation

None Present

Mechanical Equipment

whole house heat pump • Electric • 100% Heating Load @ 8.2 HSPF, 100% Cooling Load @ 14 SEER

Water Heating • Natural Gas • 100% Hot Water Load @ 0.59 Energy Factor

Air Leakage Control

Test Status: Blower-door tested
House is air-sealed as to achieve 1,469 CFM50 (4.80 ACH50) or less at final blower-door test.

Infiltration Requirements for IECC in Climate Zone 4

2009 IECC Infiltration limit for the design home is 7 ACH50.

2012 IECC Infiltration limit for the design home is 3 ACH50.

2015 IECC Infiltration limit for the design home is 3 ACH50.

2018 IECC Infiltration limit for the design home is 3 ACH50.

Duct Leakage

Duct System 1

NOT entirely within conditioned space, testing required

Leakage to Outside specified as: 78 CFM @ 25Pa (3.95 / 100 s.f.)

Total Leakage specified as: 78 CFM @ 25Pa (Post-Construction)

Energy Code Inspection Checklist



SOUTHERN ENERGY
MANAGEMENT
ENERGY EFFICIENCY & SOLAR POWER

Property

Fayetteville, NC 27501
Model: Kenzie
Community: NA

Organization

Southern Energy Manager
Justin Smith

Inspection Status

Results are projected

Template - H & H - Fayetteville -
Kenzie plan slab - CZ 4 - ecoSelect
Kenzie plan slab

Builder

H&H Homes

Duct Leakage Code Requirements for IECC

2009 IECC:

Postconstruction Leakage Test: Duct Leakage to Outdoors ≤ 8 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage ≤ 6 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage ≤ 4 CFM25 / 100 sq ft CFA.

2012 IECC and 2015 IECC Prescriptive Path:

Postconstruction Leakage Test: Total Duct Leakage ≤ 4 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage ≤ 4 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage ≤ 3 CFM25 / 100 sq ft CFA.

2015 Performance Path (Cost Compliance):

Leakage testing is required UNLESS all ducts and air handlers are located entirely within the thermal envelope.

There is no pass/fail threshold for duct leakage on the performance path.

Project Notes

-updated JS 08/11/20

- uninsulated slab modeled
- wall insulation modeled to Grade 2
- confirm attic insulation and hvac specs
- ventilation modeled as none
- confirm cfl lighting %
- modeled to worst case orientation