NOTICE TO CONTRACTOR All construction must comply with current NC Building Codes and is subject to field inspection and verification. APPROVED Limited building only review Permit holder responsible for full compliance with the code COUNTY 10/04/2021 NORTH CAROLINA

GRADE ELEVATIONS SHOWN DO NOT NECESSARILY REFER TO THIS OR ANY OTHER LOT. THEY ARE FOR DIAGRAMMATIC PURPOSES ONLY AND MAY VARY, BUILDER IS RESPONSIBLE FOR ADAPTING THIS PLAN TO SUIT THE EXISTING TOPOGRAPHY OF THE SITE.

ROOF VENTILATION TO BE DETERMINED BY BUILDER AS PER CODE.

ALL EGRESS OR RESCUE WINDOWS FROM SLEEPING ROOMS MUST HAVE A MIN. NET CLEAR OPENING OF 4.0 SQ FT. THE MIN NET CLEAR OPENING HEIGHT DIMENSION SHALL BE 22". THE MIN NET CLEAR OPENING WIDTH SHALL BE 20".

EACH EGRESS WINDOW FROM SLEEPING ROOMS MUST HAVE A SILL HIGHT OF NO MORE THAN 44" FROM THE FLOOR, ALL WINDOW SIZES ARE NOMINAL AND ARE TO BE VERIFIED WITH MANUFACTURER FOR AVAILABILITY AND CONFORMITY TO STATE AND LOCAL CODE REQUIREMENTS.

PORCHES, BALCONIES, OR RAISED FLOOR SURFACES LOCATED MORE THAN 30"
ABOVE THE FLOOR OR GRADE BELOW SHALL HAVE GUARDRAILS NOT LESS THAN 32" IN HEIGHT.

### I ASSUME NO RESPONSIBILITY FOR ANY DISTANCES AFTER START OF

CONTRACTOR/BUILDER SHALL CONSULT WITH HOME OWNER ON ALL INTERIOR AND EXTERIOR MOLDINGS, TRIMS, COLORS, FINISHES, CABINET LAYOUTS, AND MANUFACTORS BEFORE CONSTRUCTION BEGINS.
ALL BEAMS AND FRAMING MEMBERS ARE SIZED BY OTHERS.

1.1 This plan has been drawn to comply with the 2018 NC Building Code

1.2 Minimum Design Loads for Building and Other Structures ASCE 7-9B

2 Roof Dead Load 115 PSF

3 Roof Live Load 20 PSF 4 Typical Floor Dead Load 10 PSF

5 Floor Live Loads

5.1 Rooms other than sleeping rooms 40 PSF

5.2 Sleeping Rooms 30 PSF

5.3 Stairs 40 PSF

5.4 Decks 40 PSF

5.5 Exterior Balconies 60 PSF

6 Wind Loads 6.1 Ultimate Design Wind Speeds 15 MPH

6.2 Wind Importance Factor, IW 1.00

6.3 Exposure B


6.4 Walls (Component and Cladding) 25 PSF

6.5 Roofs (Component and Cladding)

6.5.1 Roof Slopes 2.25/12 to 7/12 34.8 PSF

6.5.2 Roof Slopes 7/12 to 12/12 21 PSF

It is the sole responsibility of the Contractor and/or Builder to conform to all standards, provisions, requirements, methods of construction and uses of materials provided in buildings and/or structures as required by NC Uniform Building Code, Local Agencies and in accordance with good engineering practices. Verify all dimensions prior to construction.



FRONT ELEVATION



RIGHT ELEVATION

FOUNDATION NOTES: ALL FOOTINGS SHALL BEAR ON ORIGINAL UNDISTURBED SOIL. THE 28 DAY COMPRESSIVE STRENGTH OF ALL FOOTINGS IS 3000 PSI PROVIDE WATER PROOFING AND PERIMETER DRAINS AS REQUIRED.


FOUNDATION CONCRETE MIX TO HAVE 1-1/2" MAX AGGREGATE SIZE, CONCRETE FILL MIX TO HAVE 1/2" MAX AGGREGATE SIZE.

FOOTING WIDTHS ARE BASED ON A LOAD-BEARING SOIL CAPACITY OF 2000 PSI.


PROVIDE 6 MIL POLY VAPOR BARRIER TO COVER GROUND SURFACE IN CRAWL SPACE

ALL ANCHOR BOLTS TO BE 12" LONG, 1/2" DIA. A36 UNO ANCHOR BOLTS SHALL BE SPACE AT A MAX OF 6' OC AND NO MORE THAN I' FROM EA CORNER.


Termite Soil Treatment: Treat entire slab area soil or crawl space surface before vapor barrier is installed and slab is poured with a state approved termiticide. Termiticide should be applied by a licensed and certified pest control professional by the state of North Carolina.



# STEM WALL FOUNDATION Detail not to scale




# TYPICAL THICKENED SLAB



### FOUNDATION NUTS, BOLTS, WASHERS 6'-0, OC 1'-0 FROM EACH CORNER

### NOTE: DOUBLE BAND OVER FOUNDATION VENT. DO NOT SPLICE WITHIN 12" OF OPENING LEDGER JOIST OVER OPENING



FOUNDATION PLAN

ALL LUMBER IN CONTACT WITH CONCRETE OR MASONRY SHALL BE

FRAMING LUMBER SHALL BE SYP \*2 GRADE AND/OR SPRUCE PINE FIR \*1 AND/OR \*2, KILN DRIED.

WHERE PRE-ENGINEERED JOISTS ARE USED, JOIST MANUFACTURER SHALL PROVIDE SHOP DRAWINGS, WHICH BEAR SEAL OF A N.C. ENGINEER.

STUDS AND JOISTS SHALL NOT BE CUT TO INSTALL PLUMBING OR WIRING WITHOUT ADDING METAL OR WOOD SIDE PANELS TO STRENGTHEN THE MEMBER TO ITS ORIGINAL CAPACITY.

NAIL MULTIPLE MEMBERS WITH 2 ROWS OF 16d NAILS STAGGERED 32" OC AN USE 3-16d NAILS 2" IN AT EACH END. DOUBLE ALL STUDS UNDER ROOF POST DOWNS UNO.

NAIL FLOOR JOISTS TO SILL PLATE WITH 8d TOE NAILS.

ALL EXPOSED FRAMING ON PORCHES AND DECKS SHALL BE PRESSURE TREATED.

PROVIDE WATERPROOFING AND DRAING AS REQUIRED.

ALL FRAMING TO BE 16" OC UNO. WALL FRAMING DIMENSIONS ARE BASED ON  $2 \times 4$ STUDS UNO. DOUBLE STUDS UNDER ALL HEADERS.

LYL'S AND TJI'S TO BE SIZED BY OTHERS

EXTERIOR WALLS IN LIVING AREAS ARE 2 × 4

OPENING SCHEDULE						
SIZE	COUNT	LIBRARY NAME	R.O. WIDTH	R.O. HEIGHT		
2'-8" x 2'-8"	3	Window	32"	32"		
2'-0" x 4'-0"	2	Window\Single Hung	24"	48"		
2'-8" x 5'-0"	5	Window\Single Hung	32"	60-1/2"		
2'-4" x 4'-0" Twin	1	Window\Single Hung	56"	48"		
2'-8" x 5'-0" Twin	4	Window\Single Hung	64-1/2""	60-1/2"		
4'-0" x 1'-0"	1	Window\Transom	48"	12"		


OPENING SCHEDULE SIZE COUNT LIBRARY NAME R.O. WIDTH R.O. HEIGHT

2'-8" x 5'-0" 1 Window\Single Hung 32"

		611		
	ACCE96			
STOR	AGE	STOR	AGE	
	ACCESS 2'-	ACCE66	_	
			]	
		,		<u>-</u> C
- L - II		N - 11	- L - II	"C-'cc
5'-0"	12	2'-0"	5'-0"	
	= "			
	<u>2</u>   <u>5</u>   <u>5</u>			
		<b>-</b>		
	Bo	<u>ONUS</u>		
11	2'-8'	× 5'-0"	-T"	-
		3'-2"		
/		<i>J = </i> 6		

# OPTIONAL BONUS ROOM

AREA SCHEDULE				
NAME	AREA			
Bonus Room	176.2 sq ft.			
Storage	321.0 sq ft.			






# SECTION A SCALE: 1'= 1/4"

OPEN BALUSTRADE BALCONY / STAIR RAILINGS
NOT LESS THAN 36" IN HEIGHT
WITH PATTERN / SPACING SUCH
THAT A SPHERE 4" IN DIA,
CANNOT PASS THROUGH

ALL HANDRAILS SHALL BE CONTINUOUS THE FULL LENGTH
OF THE STAIRS. HANDGRIP PORTION OF ALL HANDRAILS
SHALL NOT BE LESS THAN 1-1/4" NOR MORE THAN 2" IN
CROSS SECTIONAL DIMENSION, OR THE SHAPE SHALL
PROVIDE AN EQUIVALENT GRIPPING SURFACE


STAIR RAILING NOT TO SCALE

STAIR / BALUSTER
STYLES ARE DIAGRAMMATIC
ONLY -- CONTRACTOR TO
COORDINATE STYLES
WITH OWNER / FINISHES




2 × 10

 $2 \times 12$ 



2 × 10 3-PLY

2 × 10



# ROOF NOTES:

TRUSSES, BRACINGS, BRIDGING AND CONNECTORS ARE TO BE DESIGNED BY THE TRUSS MANUFACTURER.

IDENTIFY LUMBER BY OFFICIAL GRADE MARKINGS.

DO NOT CUT OR REMOVE CHORDS OR OTHER TRUSS MEMBERS.
DO NOT NOTCH OR DRILL TRUSS MEMBERS.

WHERE PRE-ENGINEERED ROOF TRUSSES ARE USED, TRUSS
MANUFACTURER SHALL PROVIDE SHOP DRAWINGS, WHICH BEAR SEAL
OF A N. C. REGISTERED ENGINEER.

PAGE #:

Diane Rives Designs
6205 Mockingbird Lane
5anford, N.C. 21332
919-111-6091
golfwoman@charter.net

Diane Rives De 6205 Mockingk Sanford, N.C. 7

SCALE: 1'= 1/4"

DRAWN BY:

DATE: 1/13/2021

OOF LAYOUT

ROOF PLAN


SCALE: 1'= 1/4"


12" OVER HANG ALL














BONUS ROOM

## THIS LAYOUT IS TO BE USED AS A TRUSS PLACEMENT GUIDE ONLY. PLEASE REFER TO BUILDING PLANS FOR BUILDING CONSTRUCTION AND DETAILS, SUCH AS PLUMBING OR DUCT DROPS.


24-08-00

16-06-00

12-00-00

### PROPOSED DESIGN-NOT FOR CONSTRUCTION





- 2. Adjust truss locations as needed for plumbing and mechanical clearance. Unless otherwise noted, trusses may be shifted as long as O.C. spacing shown is not exceeded.
  3. Do not cut, drill, or otherwise
- damage any part of any truss without prior approval from Peak Truss.
  4. Do not approve drawings if any
- information herein is unclear. Once ordered trusses will be fabricated as approved.

  5. Please contact Peak Truss
- Builders with any questions. We are available to help any way we can. We can be reached at 919-545-5555 or sales@peaktruss.com

Roof Truss Loading per 2018 NC Residential Code

Bottom Chord Live Load Bottom Chord Dead Load

20# PSF 10# PSF 10# PSF

Date

storage load wherever a 42"x24" box will fit between the webs.


Brooklyn RH V2 W Harrington Ave Broadway NC


Q-2101667

**Aron Meeks Designer:** 

Lamco Custom Builders LLC

Hill, NC 27562





Peak Truss
Builders, LLC
PO Box 340, New Hill, NC 27562

Lamco Custom Builders LLC

Date Quoted:

Designer:

Aron Meeks

Brooklyn RH V2 W Harrington Ave Broadway NC Job #

Q-2101667