

RE: Pinehurst Floor
 Pinehurst

Trenco
 818 Soundside Rd
 Edenton, NC 27932

Site Information:

Customer: D.R. HORTON - RAL - 055 Project Name: Pinehurst Floor
 Lot/Block: Model: PINEHURST / B
 Address: Subdivision:
 City: FUQUAY-VARINA State: NC

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):


Design Code: IRC2015/TPI2014 Design Program: MiTek 20/20 8.5
 Wind Code: N/A Wind Speed: N/A mph
 Roof Load: N/A psf Floor Load: 55.0 psf

This package includes 22 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I47722472	F1	9/1/2021	21	I47722492	F15E	9/1/2021
2	I47722473	F2	9/1/2021	22	I47722493	F16	9/1/2021
3	I47722474	F3	9/1/2021				
4	I47722475	F4	9/1/2021				
5	I47722476	F5	9/1/2021				
6	I47722477	F6	9/1/2021				
7	I47722478	F7	9/1/2021				
8	I47722479	F7E	9/1/2021				
9	I47722480	F8	9/1/2021				
10	I47722481	F9	9/1/2021				
11	I47722482	F10	9/1/2021				
12	I47722483	F10E	9/1/2021				
13	I47722484	F11	9/1/2021				
14	I47722485	F12	9/1/2021				
15	I47722486	F12E	9/1/2021				
16	I47722487	F13	9/1/2021				
17	I47722488	F14	9/1/2021				
18	I47722489	F14E	9/1/2021				
19	I47722490	F14GR	9/1/2021				
20	I47722491	F15	9/1/2021				

The truss drawing(s) referenced above have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by 84 Components - #2383.
 Truss Design Engineer's Name: Sevier, Scott
 My license renewal date for the state of North Carolina is December 31, 2021.
 North Carolina COA: C-0844


IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to TRENCO. Any project specific information included is for TRENCO customers file reference purpose only, and was not taken into account in the preparation of these designs. TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



Job Pinehurst Floor	Truss F1	Truss Type FLOOR GIRDER	Qty 1	Ply 1	Pinehurst Job Reference (optional)	147722472
------------------------	-------------	----------------------------	----------	----------	---------------------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:17 2021 Page 1
ID:SMVEKygkLeYRH9FtFyqHoHyi35J-jZdRIHP6ZklG3tvcvkel3rkzINGC2zahrP?dFsyi1z8



Scale = 1:8.9




Plate Offsets (X, Y)--	[2:0-1-8,Edge], [3:0-2-0,Edge], [5:Edge,0-1-8], [8:Edge,0-1-8]
------------------------	--

LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.71	Vert(LL) -0.02 6-7 >999 480	MT20	197/144
TCDL 10.0	Lumber DOL 1.00	BC 0.67	Vert(CT) -0.03 6-7 >999 360		
BCLL 0.0	Rep Stress Incr NO	WB 0.59	Horz(CT) 0.01 5 n/a n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-P		Weight: 35 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 4-8-8 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 8=0-3-8, 5=0-3-8
Max Grav 8=1792(LC 1), 5=1528(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-8=-373/0, 2-3=-2065/0
BOT CHORD 7-8=0/2065, 6-7=0/2029, 5-6=0/2029
WEBS 3-5=-2455/0, 2-8=-2498/0

- NOTES-**
- As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 922 lb down at 1-1-12, 493 lb down at 1-5-4, and 922 lb down at 3-1-12, and 493 lb down at 3-5-4 on top chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).


LOAD CASE(S) Standard
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 5-8=10, 1-4=100
Concentrated Loads (lb)
Vert: 3=1415(F=-493, B=922) 9=1415(F=-493, B=922)



September 1, 2021

Job Pinehurst Floor	Truss F2	Truss Type FLOOR GIRDER	Qty 1	Ply 1	Pinehurst Job Reference (optional)	147722473
------------------------	-------------	----------------------------	----------	----------	---------------------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334, 8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:34 2021 Page 1



Scale = 1:8.5

Plate Offsets (X, Y)--	[4:Edge,0-1-8], [5:Edge,0-1-8]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.81	Vert(LL) 0.00 5 **** 480	MT20	197/144
TCDL 10.0	Lumber DOL 1.00	BC 0.62	Vert(CT) -0.03 4-5 >999 360		
BCLL 0.0	Rep Stress Incr NO	WB 0.48	Horz(CT) 0.01 4 n/a n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-P		Weight: 27 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 3-10-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 5=0-3-8, 4=0-3-8
Max Grav 5=1679(LC 1), 4=1587(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-5=-714/0, 3-4=-622/0
BOT CHORD 4-5=0/1733
WEBS 2-5=-1975/0, 2-4=-1975/0

NOTES-
1) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
3) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 936 lb down at 0-10-4, 493 lb down at 1-1-12, and 929 lb down at 2-10-4, and 514 lb down at 3-1-12 on top chord. The design/selection of such connection device(s) is the responsibility of others.
4) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 4-5=-10, 1-3=-100
Concentrated Loads (lb)
Vert: 6=-1428(F=-493, B=-936) 7=-1444(F=-514, B=-929)



September 1, 2021

Job	Truss	Truss Type	Qty	Ply	Pinehurst	147722474
Pinehurst Floor	F3	FLOOR GIRDER	1	1		

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:35 2021 Page 1
ID:SMVEKygkleYRH9FtFyqHoHyi35J-B0jEXRdPKG0iDe_MpWyzndU3rdLyG1sK_CMatqi1ys



Scale = 1:30.7




Plate Offsets (X,Y)--	[2:0-6-0,Edge], [5:0-1-8,Edge], [6:0-3-0,0-0-0], [10:0-6-0,Edge], [12:Edge,0-3-0], [14:0-3-4,Edge], [15:0-1-8,Edge], [17:0-4-4,Edge], [19:Edge,0-3-0], [20:0-1-8,0-0-8]
-----------------------	---

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.64	Vert(LL)	-0.30 14-15	>720	480	MT20	197/144
TCDL 10.0	Lumber DOL	1.00	BC 0.95	Vert(CT)	-0.42 14-15	>515	360		
BCLL 0.0	Rep Stress Incr	NO	WB 0.92	Horz(CT)	0.06 12	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S					Weight: 149 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 19=0-3-8, 12=0-3-8
Max Grav 19=1054(LC 1), 12=1279(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-4214/0, 4-5=-4214/0, 5-6=-5323/0, 6-7=-5323/0, 7-8=-4883/0, 8-10=-4883/0
BOT CHORD 17-19=0/2427, 16-17=0/5323, 15-16=0/5323, 14-15=0/5443, 12-14=0/3072
WEBS 10-12=-3293/0, 2-19=-2595/0, 10-14=0/1925, 2-17=0/1899, 8-14=-385/0, 7-14=-598/0, 5-17=-1347/0, 7-15=-533/274

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - 3) All plates are 3x6 MT20 unless otherwise indicated.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) CAUTION, Do not erect truss backwards.
 - 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 434 lb down at 14-8-12 on top chord. The design/selection of such connection device(s) is the responsibility of others.
 - 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 12-19=-10, 1-11=-100
Concentrated Loads (lb)
Vert: 21=-354(F)




Job Pinehurst Floor	Truss F4	Truss Type FLOOR GIRDER	Qty 1	Ply 1	Pinehurst Job Reference (optional)	147722475
------------------------	-------------	----------------------------	----------	----------	---------------------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:36 2021 Page 1

ID:SMVEKygkleYRH9FtFyqHoHyi35J-fDGclnd15Z8ZroZYNDUCKr1B01v1?iQUds68PGyi1yr



Scale = 1:8.6

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 40.0	Plate Grip DOL	1.00	TC 0.81	Vert(LL)	0.00	4	****	480	MT20	197/144
BCLL 0.0	Lumber DOL	1.00	BC 0.05	Vert(CT)	-0.00	3-4	>999	360		
BCDL 5.0	Rep Stress Incr	NO	WB 0.00	Horz(CT)	0.00	3	n/a	n/a		
	Code IRC2015/TPI2014		Matrix-P						Weight: 20 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 2-7-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 4=0-7-0, 3=Mechanical
Max Grav 4=491(LC 1), 3=454(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-4=-479/0, 2-3=-442/0

- NOTES-**
- As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - Refer to girder(s) for truss to truss connections.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 688 lb down at 1-2-12 on top chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).


LOAD CASE(S) Standard

- Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 3-4=-10, 1-2=-100
Concentrated Loads (lb)
Vert: 5=-688(B)




Job Pinehurst Floor	Truss F5	Truss Type FLOOR GIRDER	Qty 1	Ply 1	Pinehurst Job Reference (optional)	147722476
------------------------	-------------	----------------------------	----------	----------	---------------------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334, 8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:36 2021 Page 1



Scale = 1:8.6



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 40.0	Plate Grip DOL	1.00	TC 0.49	Vert(LL)	0.00	5	****	480	MT20	197/144
TCDL 10.0	Lumber DOL	1.00	BC 0.30	Vert(CT)	-0.02	4-5	>999	360		
BCLL 0.0	Rep Stress Incr	NO	WB 0.20	Horz(CT)	0.00	4	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-P							
									Weight: 25 lb	FT = 20%F, 11%E

LUMBER-

TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)
 BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)
 WEBS 2x4 SP No.3(flat)

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-5-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 5=Mechanical, 4=0-7-0
 Max Grav 5=754(LC 1), 4=1013(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-5=-301/0, 3-4=-561/0
 BOT CHORD 4-5=0/706
 WEBS 2-5=-830/0, 2-4=-830/0

NOTES-

- As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
- Refer to girder(s) for truss to truss connections.
- Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 696 lb down at 0-11-12, and 723 lb down at 2-11-12 on top chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (plf)
 Vert: 4-5=-10, 1-3=-100
 Concentrated Loads (lb)
 Vert: 6=-696(B) 7=-723(B)



September 1, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



818 Soundside Road
 Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Pinehurst	147722477
Pinehurst Floor	F6	FLOOR GIRDER	1	1		

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:37 2021 Page 1
ID:SMVEKygklyeYRH9FtFyqHoHyi35J-8Pq?y7efstGQTx8lwx?Rt2ZJgR4hkw6dSWrhxyi1yq



Scale = 1:30.7




Plate Offsets (X,Y)--	[2:0-6-0,Edge], [5:0-1-8,Edge], [6:0-3-0,0-0-0], [10:0-6-0,Edge], [12:Edge,0-3-0], [14:0-3-0,Edge], [15:0-1-8,Edge], [17:0-4-8,Edge], [19:Edge,0-3-0], [20:0-1-8,0-0-8]
-----------------------	---

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 1.00	Vert(LL)	-0.32 14-15	>681	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.74	Vert(CT)	-0.44 14-15	>488	360		
BCLL 0.0	Rep Stress Incr	NO	WB 1.00	Horz(CT)	0.06 12	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S						
								Weight: 149 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 19=0-3-8, 12=0-3-8
Max Grav 19=1111(LC 1), 12=1521(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-4504/0, 4-5=-4504/0, 5-6=-5809/0, 6-7=-5809/0, 7-8=-5728/0, 8-10=-5728/0
BOT CHORD 17-19=0/2575, 16-17=0/5809, 15-16=0/5809, 14-15=0/6088, 12-14=0/3760
WEBS 10-12=-4030/0, 2-19=-2754/0, 10-14=0/2093, 2-17=0/2050, 8-14=-520/0, 7-14=-384/0, 5-17=-1553/0, 7-15=-700/104

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - 3) All plates are 3x6 MT20 unless otherwise indicated.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) CAUTION, Do not erect truss backwards.
 - 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 733 lb down at 14-8-12 on top chord. The design/selection of such connection device(s) is the responsibility of others.
 - 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 12-19=-10, 1-11=-100
Concentrated Loads (lb)
Vert: 21=-653(B)



Job	Truss	Truss Type	Qty	Ply	Pinehurst	147722478
Pinehurst Floor	F7	Floor	3	1		

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:38 2021 Page 1
ID:SMVEKygkleYRH9FtFyqHoHyi35J-cbON9TfldBOH45jUeWgPG6dwrTUTRtngAbET9yiyp



Scale = 1:30.6




Plate Offsets (X,Y)-- [1:Edge,0-0-12], [4:0-1-8,Edge], [13:0-1-8,Edge], [18:0-1-8,0-0-12]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.40	Vert(LL)	-0.33 12-13	>659	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.52	Vert(CT)	-0.47 12-13	>465	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.71	Horz(CT)	0.07 11	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S					Weight: 90 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP DSS(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP DSS(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 17=0-3-8, 11=0-3-8
Max Grav 17=986(LC 1), 11=992(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-3359/0, 3-4=-3359/0, 4-5=-4219/0, 5-6=-4219/0, 6-7=-3380/0, 7-9=-3380/0
BOT CHORD 15-17=0/2011, 14-15=0/4219, 13-14=0/4219, 12-13=0/4120, 11-12=0/2022
WEBS 9-11=-2203/0, 2-17=-2185/0, 9-12=0/1486, 2-15=0/1475, 3-15=-257/26, 6-12=-810/0, 4-15=-1123/0, 6-13=-259/535

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 4) CAUTION, Do not erect truss backwards.



September 1, 2021

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p>	<p>ENGINEERING BY</p> <p>A MiTek Affiliate</p> <p>818 Soundside Road Edenton, NC 27932</p>
--	--

Job	Truss	Truss Type	Qty	Ply	Pinehurst	147722479
Pinehurst Floor	F7E	Floor Supported Gable	1	1		

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:39 2021 Page 1
ID:SMVEKygkleYRH9FtFyqHoHyi35J-4oylNpgwOUW8iFH72M1vyTftbExZC3hwvqKo0byi1yo

0-1-8

Scale = 1:30.5




Plate Offsets (X, Y)-- [1:Edge,0-0-12], [33:0-1-8,0-0-12]	
LOADING (psf)	SPACING- 2-0-0
TCLL 40.0	Plate Grip DOL 1.00
TCDL 10.0	Lumber DOL 1.00
BCLL 0.0	Rep Stress Incr YES
BCDL 5.0	Code IRC2015/TPI2014
CSI.	DEFL. in (loc) l/defl L/d
TC 0.08	Vert(LL) n/a - n/a 999
BC 0.01	Vert(CT) n/a - n/a 999
WB 0.03	Horz(CT) 0.00 17 n/a n/a
Matrix-R	
PLATES	GRIP
MT20	197/144
Weight: 77 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 18-3-8.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 32, 17, 31, 30, 28, 27, 26, 25, 24, 23, 22, 21, 20, 19, 18

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - 2) All plates are 1.5x4 MT20 unless otherwise indicated.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 5) Gable studs spaced at 1-4-0 oc.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 7) CAUTION, Do not erect truss backwards.



September 1, 2021

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p>	<p>ENGINEERING BY</p> <p>TRENCO</p> <p>A MiTek Affiliate</p> <p>818 Soundside Road Edenton, NC 27932</p>
--	---


Job	Truss	Truss Type	Qty	Ply	Pinehurst	147722480
Pinehurst Floor	F8	Floor	3	1		

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:39 2021 Page 1
ID:SMVEKygkIeYRH9FtFyqHoHyi35J-4oylNpgwOUW8iFH72M1vyTfosEloCymwvqKo0byi1yo



Scale = 1:24.3



14-7-0
14-7-0

Plate Offsets (X,Y)--	[1:Edge,0-0-12], [5:0-1-8,Edge], [15:0-1-8,0-0-12]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.45	Vert(LL) -0.17 10-11 >999 480	MT20	197/144
TCDL 10.0	Lumber DOL 1.00	BC 0.83	Vert(CT) -0.23 10-11 >758 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.47	Horz(CT) 0.05 9 n/a n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S		Weight: 75 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 14=0-3-8, 9=Mechanical
Max Grav 14=782(LC 1), 9=788(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2439/0, 3-4=-2439/0, 4-5=-2711/0, 5-6=-2457/0, 6-7=-2457/0
BOT CHORD 13-14=0/1546, 12-13=0/2711, 11-12=0/2711, 10-11=0/2711, 9-10=0/1546
WEBS 7-9=-1685/0, 2-14=-1679/0, 7-10=0/997, 2-13=0/977, 6-10=-254/0, 5-10=-468/72, 4-13=-488/54

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - 3) Refer to girder(s) for truss to truss connections.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) CAUTION, Do not erect truss backwards.



September 1, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	Pinehurst	147722481
Pinehurst Floor	F9	Floor	3	1		

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:40 2021 Page 1
ID:SMVEKygkIeYRH9FtFyqHoHyi35J-Y_W7a8hY8oe?KPsKc3Y8UhBzce4_xPj38U4LY1yi1yn



Scale = 1:24.8



14-10-8
14-10-8

Plate Offsets (X,Y)--	[1:Edge,0-0-12], [5:0-1-8,Edge], [15:0-1-8,0-0-12]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.45	Vert(LL) -0.18 11 >999 480	MT20	197/144
TCDL 10.0	Lumber DOL 1.00	BC 0.83	Vert(CT) -0.24 11 >727 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.49	Horz(CT) 0.05 9 n/a n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S		Weight: 76 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 14=0-3-8, 9=0-3-8
Max Grav 14=798(LC 1), 9=804(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2518/0, 3-4=-2518/0, 4-5=-2829/0, 5-6=-2529/0, 6-7=-2529/0
BOT CHORD 13-14=0/1582, 12-13=0/2829, 11-12=0/2829, 10-11=0/2829, 9-10=0/1583
WEBS 7-9=-1725/0, 2-14=-1718/0, 7-10=0/1035, 2-13=0/1025, 6-10=-254/0, 5-10=-514/53, 4-13=-524/43

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 4) CAUTION, Do not erect truss backwards.



September 1, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Pinehurst	147722482
Pinehurst Floor	F10	Floor	4	1		

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:17 2021 Page 1
 ID:SMVEKygkIeYRH9FtFyqHoHyi35J-zdRIHP6ZklG3tcvikel3rk0NNHz2x7hrP?dFsyi1z8



Scale = 1:31.5




Plate Offsets (X,Y)-- [1:Edge,0-0-12], [4:0-1-8,Edge], [13:0-1-8,Edge], [18:0-1-8,0-0-12]


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.51	Vert(LL)	-0.40 12-13	>564	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.62	Vert(CT)	-0.56 12-13	>401	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.74	Horz(CT)	0.07 11	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S					Weight: 92 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP DSS(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP DSS(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 17=0-3-8, 11=Mechanical
 Max Grav 17=1016(LC 1), 11=1022(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-3485/0, 3-4=-3485/0, 4-5=-4463/0, 5-6=-4463/0, 6-7=-3518/0, 7-9=-3518/0
 BOT CHORD 15-17=0/2080, 14-15=0/4463, 13-14=0/4463, 12-13=0/4320, 11-12=0/2092
 WEBS 9-11=-2280/0, 2-17=-2260/0, 9-12=0/1560, 2-15=0/1538, 3-15=-258/53, 6-12=-878/0,
 4-15=-1281/0, 6-13=-229/619

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - 3) Refer to girder(s) for truss to truss connections.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) CAUTION, Do not erect truss backwards.



September 1, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
 Edenton, NC 27932


Job Pinehurst Floor	Truss F10E	Truss Type Floor Supported Gable	Qty 1	Ply 1	Pinehurst Job Reference (optional)	147722483
------------------------	---------------	-------------------------------------	----------	----------	---------------------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:18 2021 Page 1
ID:SMVEKygleYRH9FtFyqHoHyi35J-BIBpzdPIK1t7h1B5JR9_b2HInnmPnZTq43IBnJy1z7

0-1-8

Scale: 3/8"=1'



19-1-8
19-1-8

Plate Offsets (X, Y)-- [1:Edge,0-0-12], [34:0-1-8,0-0-12]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.09	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.00	BC 0.03	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	18	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-R						
								Weight: 81 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)
WEBS 2x4 SP No.3(flat)
OTHERS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 19-1-8.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 33, 18, 32, 31, 29, 28, 27, 26, 25, 24, 23, 22, 21, 20, 19

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - All plates are 1.5x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.



September 1, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601
ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Pinehurst	147722484
Pinehurst Floor	F11	Floor	4	1		

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:19 2021 Page 1
 ID:SMVEKygleYRH9FfYqHoHyi35J-fxIBAzQN5L?_IAmHt9gD8GqPJA?aWrH_JjUkJlyi1z6



Scale: 3/8"=1'




Plate Offsets (X,Y)--	[1:Edge,0-0-12], [14:0-1-8,Edge], [19:0-1-8,0-0-12]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.36	Vert(LL) -0.34 13-14 >657 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.48	Vert(CT) -0.48 13-14 >473 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.76	Horz(CT) 0.07 12 n/a n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S		Weight: 96 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP DSS(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP DSS(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 18=0-3-8, 12=0-3-8
 Max Grav 18=1032(LC 1), 12=1038(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-3584/0, 3-4=-3584/0, 4-5=-4700/0, 5-6=-4700/0, 6-7=-4700/0, 7-8=-3585/0, 8-10=-3585/0
 BOT CHORD 16-18=0/2117, 15-16=0/4421, 14-15=0/4700, 13-14=0/4429, 12-13=0/2123
 WEBS 10-12=-2314/0, 2-18=-2301/0, 10-13=0/1599, 2-16=0/1606, 7-13=-924/0, 4-16=-916/0, 7-14=-161/614, 4-15=-122/602

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 4) CAUTION, Do not erect truss backwards.



<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE. Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p>	<p>ENGINEERING BY TRENCO A MiTek Affiliate</p> <p>818 Soundside Road Edenton, NC 27932</p>
--	--

Job	Truss	Truss Type	Qty	Ply	Pinehurst	147722486
Pinehurst Floor	F12E	Floor Supported Gable	1	1		

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:23 2021 Page 1
ID:SMVEKygkleYRH9FtFyqHoHyi35J-Yj_i0KTf9aVPno326_l9l6_8doTlSqjZELSySWyi1z2

0-1r8

Scale = 1:27.9




Plate Offsets (X,Y)--	[31:0-1-8,0-0-12]						
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d
TCLL 40.0	Plate Grip DOL	1.00	TC 0.08	Vert(LL)	n/a	-	n/a 999
TCDL 10.0	Lumber DOL	1.00	BC 0.02	Vert(CT)	n/a	-	n/a 999
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	16	n/a n/a
BCDL 5.0	Code IRC2015/TPI2014		Matrix-R				
							PLATES
							MT20
							GRIP
							197/144
							Weight: 71 lb
							FT = 20%F, 11%E

LUMBER-

TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)
 BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)
 WEBS 2x4 SP No.3(flat)
 OTHERS 2x4 SP No.3(flat)

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 16-9-8.
 (lb) - Max Grav All reactions 250 lb or less at joint(s) 30, 16, 29, 28, 26, 25, 24, 23, 22, 21, 20, 19, 18, 17

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
- All plates are 1.5x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 1-4-0 oc.
- Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- CAUTION, Do not erect truss backwards.



September 1, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	Pinehurst	147722487
Pinehurst Floor	F13	Floor	4	1		

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:25 2021 Page 1
 ID:SMVEKygkIeYRH9FtFyqHoHyi35J-U56SR0V8hBm705DRDPndNX3N3b?wwd_shfx2XPyi1z0



Scale = 1:28.1



FASTEN TRUSS TO BEARING FOR THE UPLIFT REACTION SHOWN WHILE PERMITTING NO UPWARD MOVEMENT OF THE BEARING.

	12-7-12	12-7-12	12-9-4	16-9-8
			0-1-8	4-0-4
Plate Offsets (X,Y)--	[4:0-1-8,Edge], [13:0-1-8,Edge], [18:0-1-8,0-0-12]			

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.53	Vert(LL)	-0.10 14-15	>999	480	MT20	197/144
TCDL 10.0	Lumber DOL	1.00	BC 0.68	Vert(CT)	-0.13 14-15	>999	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.49	Horz(CT)	0.02 12	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S						
								Weight: 86 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 11-12.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 17=Mechanical, 11=0-3-8, 12=0-3-8
 Max Uplift 11=233(LC 3)
 Max Grav 17=593(LC 3), 11=119(LC 4), 12=1312(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1579/0, 3-4=-1579/0, 4-5=-1328/0, 5-6=-1328/0, 6-8=0/1120, 8-9=0/1115
 BOT CHORD 15-17=0/1097, 14-15=0/1328, 13-14=0/1328, 12-13=0/389, 11-12=-622/25
 WEBS 2-17=-1196/0, 6-12=-1608/0, 2-15=0/527, 6-13=0/1039, 3-15=-268/0, 5-13=-282/0, 4-15=-66/414, 9-11=-20/679, 9-12=-780/0

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - 3) Refer to girder(s) for truss to truss connections.
 - 4) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 11. This connection is for uplift only and does not consider lateral forces.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.



September 1, 2021

Job	Truss	Truss Type	Qty	Ply	Pinehurst	147722488
Pinehurst Floor	F14	Floor	7	1		

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:27 2021 Page 1
 ID:SMVEKygkIeYRH9FtFyqHoHyi35J-QUEDsiWOC0rGPNqLq5Ty9mOPkWOSS99yQ9bHyi1z_



Scale: 3/8"=1'




Plate Offsets (X,Y)--	[1:Edge,0-0-12], [14:0-1-8,Edge], [19:0-1-8,0-0-12]
-----------------------	---


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.35	Vert(LL)	-0.33 13-14	>673	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.48	Vert(CT)	-0.46 13-14	>483	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.75	Horz(CT)	0.07 12	n/a	n/a		
BCDL 5.0	Code IRC2015/TPI2014		Matrix-S					Weight: 95 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP DSS(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP DSS(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 18=0-3-8, 12=0-3-8
 Max Grav 18=1020(LC 1), 12=1027(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-3532/0, 3-4=-3532/0, 4-5=-4592/0, 5-6=-4592/0, 6-7=-4592/0, 7-8=-3533/0, 8-10=-3533/0
 BOT CHORD 16-18=0/2090, 15-16=0/4343, 14-15=0/4592, 13-14=0/4352, 12-13=0/2097
 WEBS 10-12=-2285/0, 2-18=-2271/0, 10-13=0/1571, 2-16=0/1578, 7-13=-896/0, 4-16=-887/0, 7-14=-175/583, 4-15=-123/569

- NOTES-**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 4) CAUTION, Do not erect truss backwards.



September 1, 2021


<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE. Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p>	 818 Soundside Road Edenton, NC 27932
--	---

Job	Truss	Truss Type	Qty	Ply	Pinehurst	147722489
Pinehurst Floor	F14E	Floor Supported Gable	1	1		
						Job Reference (optional)

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:29 2021 Page 1
ID:SMVEKygkleYRH9FtFyqHoHyi35J-NsLzHOYekQGZVjWCSFsZYNEA2CW3sXBScGvGfAyi1yy

Scale = 1:20.4



LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.00	BC	0.02	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	12	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-R							Weight: 54 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)
WEBS 2x4 SP No.3(flat)
OTHERS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 12-4-0.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 21, 12, 20, 19, 18, 17, 16, 15, 14, 13

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - All plates are 1.5x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



September 1, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Pinehurst	147722490
Pinehurst Floor	F14GR	FLOOR GIRDER	1	2	Job Reference (optional)	

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:32 2021 Page 1
ID:SMVEKygleYRH9FtFyqHoHyi35J-nR16vPaX1Le8MAFn8NPGA?sdRQNJ3lLulE8wGVyi1yv



Scale = 1:30.8




Plate Offsets (X,Y)--	[5:0-3-0,Edge], [6:0-3-0,0-0-0], [14:0-1-8,Edge], [19:0-1-8,0-0-8]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.33	Vert(LL) -0.28 13-14 >792 480	MT20	197/144
TCDL 10.0	Lumber DOL 1.00	BC 0.76	Vert(CT) -0.38 13-14 >591 360		
BCLL 0.0	Rep Stress Incr NO	WB 0.58	Horz(CT) 0.07 12 n/a n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-S		Weight: 238 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 18=0-3-8, 12=0-3-8
Max Grav 18=1400(LC 1), 12=1500(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-5284/0, 4-5=-5284/0, 5-6=-6733/0, 6-7=-6733/0, 7-8=-5615/0, 8-10=-5615/0
BOT CHORD 16-18=0/3146, 15-16=0/6733, 14-15=0/6733, 13-14=0/6668, 12-13=0/3353
WEBS 10-12=-3610/0, 2-18=-3379/0, 10-13=0/2445, 2-16=0/2310, 8-13=-442/41, 4-16=-295/78, 7-13=-1137/0, 5-16=-1671/44, 7-14=-152/370

- NOTES-**
- 1) Fasten trusses together to act as a single unit as per standard industry detail, or loads are to be evenly applied to all plies.
 - 2) Unbalanced floor live loads have been considered for this design.
 - 3) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - 4) All plates are 3x6 MT20 unless otherwise indicated.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.
 - 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 184 lb down at 2-1-12, 157 lb down and 137 lb up at 4-1-12, 157 lb down and 137 lb up at 6-1-12, 88 lb down and 137 lb up at 8-1-12, 156 lb down and 137 lb up at 10-1-12, 157 lb down and 137 lb up at 12-1-12, 157 lb down and 137 lb up at 13-7-12, 157 lb down and 137 lb up at 14-7-4, and 184 lb down at 15-3-4, and 184 lb down at 17-3-4 on top chord. The design/selection of such connection device(s) is the responsibility of others.
 - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 12-18=-10, 1-11=-100
Concentrated Loads (lb)
Vert: 20=-104(F) 21=-77(F) 22=-77(F) 23=-77(F) 24=-77(F) 25=-77(F) 26=-77(F) 27=-77(F) 28=-104(F) 29=-104(F)



Job Pinehurst Floor	Truss F15	Truss Type Floor	Qty 3	Ply 1	Pinehurst Job Reference (optional)	147722491
------------------------	--------------	---------------------	----------	----------	---------------------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:33 2021 Page 1
ID:SMVEKygkIeYRH9FtFyqHoHyi35J-FebU6lb9oem?_Kqzh5wViDPqDqsdLo1XutToxy1y




Plate Offsets (X,Y)--	[6:0-1-8,0-0-12]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.20	Vert(LL) 0.00 5 **** 480	MT20	197/144
TCDL 10.0	Lumber DOL 1.00	BC 0.18	Vert(CT) -0.03 4-5 >999 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.06	Horz(CT) 0.00 4 n/a n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-P		Weight: 23 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 3-11-8 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (size) 5=Mechanical, 4=0-3-8
Max Grav 5=204(LC 1), 4=198(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - 2) Refer to girder(s) for truss to truss connections.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 4) CAUTION, Do not erect truss backwards.



September 1, 2021

Job Pinehurst Floor	Truss F15E	Truss Type Floor Supported Gable	Qty 2	Ply 1	Pinehurst Job Reference (optional)	147722492
------------------------	---------------	-------------------------------------	----------	----------	---------------------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:33 2021 Page 1
ID:SMVEKygkleYRH9FtFyqHoHyi35J-FebU6lb9oem?_Kqzh5wViDPsDquCoLC1XutToxyi1yu




Plate Offsets (X,Y)--	[9:0-1-8,0-0-12]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.07	Vert(LL) n/a - n/a 999	MT20	197/144
TCDL 10.0	Lumber DOL 1.00	BC 0.01	Vert(CT) n/a - n/a 999		
BCLL 0.0	Rep Stress Incr YES	WB 0.03	Horz(CT) 0.00 5 n/a n/a		
BCDL 5.0	Code IRC2015/TPI2014	Matrix-R		Weight: 20 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 3-11-8 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 3-11-8.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 8, 5, 7, 6

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.




September 1, 2021

Job	Truss	Truss Type	Qty	Ply	Pinehurst	147722493
Pinehurst Floor	F16	Floor	7	1		

84 Components (Dunn), Dunn, NC - 28334,

8.520 s Aug 27 2021 MiTek Industries, Inc. Wed Sep 1 09:31:34 2021 Page 1
ID:SMVEKygkleYRH9FtFyqHoHyi35J-jq9sK5cnZyurcUPAFoRkFQx_ZDBVXnLBmYd1KNyi1yt



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.29	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.00	BC 0.14	Vert(LL) 0.00 6-7 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.10	Vert(CT) -0.02 6-7 >999 360		
BCDL 5.0	Rep Stress Incr NO	Matrix-P	Horz(CT) 0.00 6 n/a n/a		
	Code IRC2015/TPI2014			Weight: 30 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 4-11-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. (size) 7=Mechanical, 6=0-3-8
Max Uplift 7=-37(LC 4)
Max Grav 7=177(LC 3), 6=701(LC 1)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=0/302, 3-4=0/300
WEBS 2-6=-381/0, 4-6=-442/0

NOTES-

- 1) Unbalanced floor live loads have been considered for this design.
- 2) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 37 lb uplift at joint 7.
- 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 6) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard


- 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 5-7=-10, 1-4=-100
Concentrated Loads (lb)
Vert: 4=-300




September 1, 2021

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

* Plate location details available in **MITek 20/20 software** or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TPI 1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing, Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8
dimensions shown in ft-in-sixteenths
(Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITteK® All Rights Reserved



MITek Engineering Reference Sheet: Mill-7473 rev. 5/19/2020



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.