North Carolina 2018 - R402.1.5 Total UA

Property

174 Walker Grove Lane Lillington, NC 27546 Model: 1601 Bayside E-G2_2 Community: Walkers Grove

Walkers Grove 11

True_Walkers Grove 11_1601 Bayside E-G2 2 GL WinPerPlan Organization

Performance Point, LLC. Rick Blair

704-614-7175

Builder

True Homes

This report is based on a proposed design and does not confirm field enforcement of design elements.

Inspection Status

Results are projected

Building UA

Elements	NC Reference	As Designed
Ceilings	51.0	45.5
Above-Grade Walls	170.0	176.2
Windows, Doors and Skylights	100.3	87.5
Slab Floor:	89.7	89.7
Framed Floors	0.0	0.0
Foundation Walls	0.0	0.0
Rim Joists	11.5	11.3
Overall UA (Design must be equal or lower):	422.5	410.2

Requirements

402.1.5	Total UA alternative compliance passes by 2.9%.	
402.3.2	Average SHGC: 0.30 Max SHGC: 0.30	
R402.4.2.2	Air Leakage Testing	Air sealing is 0.30 CFM50 / ft² Shell Area. It must not exceed 0.30 CFM50 / ft² Shell Area.
R402.5	Area-weighted average fenestration SHGC	
R402.5	Area-weighted average fenestration U-Factor	
R404.1	Lighting Equipment Efficiency	
Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met.	
R403.3.1	Duct Insulation	
403.3.3	Duct Testing	

Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 2.9%.

Name:	Rick Blair	Signature:	12/152
Organization:	Performance Point, LLC.	Digitally signed:	11/1/21 at 9:22 AM

Property

174 Walker Grove Lane Lillington, NC 27546 Model: 1601 Bayside E-G2_2

Community: Walkers Grove

Walkers Grove 11

True_Walkers Grove 11_1601 Bayside E-G2_2_GL_WinPerPlan Organization

Performance Point, LLC. Rick Blair 704-614-7175

Builder

True Homes

Inspection StatusResults are projected

General Building Information

Conditioned Area (sq ft) 2,342
Conditioned Volume (cubic ft) 21,638
Insulated Shell Area (sq ft) 6,082

The building energy model in Ekotrope reflects the building assemblies and energy features listed below. Sometimes energy features will change in the field from what has been modeled. The inspection process should identify any changes and ensure that the home continues to meet the applicable energy code.

Slab

\Box	Name: House Slab(1,680	s.f.,	180 ft.	exterior	perimeter)
\longrightarrow	R-10 perimeter insulation	, R-0	under	slab insu	ulation.

Framed Floor

None Present

Foundation Wall

None Present

Above Grade Wall

	Name: 2x4 Ambient (1,641.9 s.f.) R-0 continuous insulation, R-15 cavity insulation Insulation Grade: I
Д	Name: Niche (2 s.f.) R-3 continuous insulation, R-0 cavity insulation Insulation Grade: I
Д	Name: 2x4 Garage (261.1 s.f.) R-0 continuous insulation, R-15 cavity insulation Insulation Grade: I
	Name: 2x4 Kneewall (589.5 s.f.) R-0 continuous insulation, R-15 cavity insulation Insulation Grade: I

Property

174 Walker Grove Lane Lillington, NC 27546 Model: 1601 Bayside E-G2_2 Community: Walkers Grove

Walkers Grove 11 True_Walkers Grove 11_1601 Bayside E-G2_2_GL_WinPerPlan

Organization

Performance Point, LLC. Rick Blair 704-614-7175

Builder

True Homes

Inspection StatusResults are projected

,		
Rim	Joist	
	Name: Ambient (59.1 s.f.) R: 13.30	
	Name: Attic (147.4 s.f.) R: 13.30	
Ceili	ng / Roof	
	Name: Ceiling - Blown (1,018 s.f.) R-28.5 continuous insulation, R-9.5 cavity insulation Insulation Grade: I	
	Name: Ceiling - Batted (462 s.f.) R-0 continuous insulation, R-38 cavity insulation Insulation Grade: I	
	Name: Vault (221 s.f.) R-0 continuous insulation, R-38 cavity insulation Insulation Grade: I	
Opa	que Door	
	Name: Front Door (20 s.f.) R: 7.00	
	Name: Garage Entry (17.8 s.f.) R: 7.00	
Glaz	ing	
	Name: Front SHD (30 s.f.), U: 0.330, SHGC: 0.3, Orientation: SOUTH_EAST	
	Name: Right (90 s.f.), U: 0.330, SHGC: 0.3, Orientation: NORTH_EAST	2
\Box	Name: Back (60 s.f.), U: 0.330, SHGC: 0.3, Orientation: NORTH_WEST	_

Property

174 Walker Grove Lane Lillington, NC 27546 Model: 1601 Bayside E-G2_2 Community: Walkers Grove Organization

Performance Point, LLC. Rick Blair 704-614-7175 **Inspection Status**Results are projected

Walkers Grove 11

True_Walkers Grove 11_1601
Bayside E-G2_2_GL_WinPerPlan

Build	der
True	Homes

J 4, J 0.	2 2 2 2 2 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1
	Name: Back Door (17.8 s.f.), U: 0.330, SHGC: 0.3, Orientation: NORTH_WEST
	Name: Left (45 s.f.), U: 0.330, SHGC: 0.3, Orientation: SOUTH_WEST
	Name: Left - MSTR BA 2'x3' (6 s.f.), U: 0.330, SHGC: 0.3, Orientation: SOUTH_WEST

Skylight

None Present

Mechanical Ventilation

None Present

Mechanical Equipment

Water Heater • Electric • 100% Hot Water Load @ 0.95 Energy Factor
Heat Pump / All • Electric • 100% Heating Load @ 8.2 HSPF, 100% Cooling Load @ 14 SEER

Air Leakage Control

Test Status: Blower-door tested House is air-sealed as to achieve 1,803 CFM50 (5.00 ACH50) or less at final blower-door test.

Infiltration Requirements for IECC in Climate Zone 4

2009 IECC Infiltration limit for the design home is 7 ACH50.

2012 IECC Infiltration limit for the design home is 3 ACH50.

2015 IECC Infiltration limit for the design home is 3 ACH50.

2018 IECC Infiltration limit for the design home is 3 ACH50.

2021 IECC Infiltration limit for the design home is 5 ACH50.

Duct Leakage

Duct System 1

NOT entirely within conditioned space, testing required Leakage to Outside specified as: 4 CFM25 / 100 ft² Total Leakage specified as: 4 CFM25 / 100 ft² (Post-Construction)

Property

174 Walker Grove Lane Lillington, NC 27546 Model: 1601 Bayside E-G2_2

Community: Walkers Grove

Walkers Grove 11 True_Walkers Grove 11_1601 Bayside E-G2 2 GL WinPerPlan Organization

Performance Point, LLC. Rick Blair 704-614-7175

Builder

True Homes

Inspection StatusResults are projected

Duct Leakage Code Requirements for IECC

2009 IECC:

Postconstruction Leakage Test: Duct Leakage to Outdoors <= 8 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage <= 6 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

2012 IECC Mandatory, 2015 and 2018 IECC Prescriptive Paths:

Postconstruction Leakage Test: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage <= 3 CFM25 / 100 sq ft CFA.

2015 and 2018 IECC Performance Paths (Cost Compliance):

Leakage testing is required UNLESS all ducts and air handlers are located entirely within the thermal envelope.

There is no pass/fail threshold for duct leakage on the performance path.

Project Notes

HG_10/26/2021___N/S Performance Report True_1601 Bayside E-G2_2 Worst orientation (SE) DG_11/01/2021 Revised

Energy Specifications Label

174 Walker Grove Lane

Model: 1601 Bayside E-G2_2 Ekotrope RATER - Version: 4.0.1.2771

Building Envelope Specs

Ceiling: R-38

Above Grade Walls: R-15 Foundation Walls: N/A Exposed Floor: N/A

Slab: R-10

Infiltration: 5 ACH50

Duct Insulation: Supply: R8, Return: R8 Duct Lkg to Outdoors: 4 CFM25 / 100 ft²

Window & Door Specs

U-Value: 0.33, SHGC: 0.3

Door: R-7

Mechanical Equipment Specs

Heating: Air Source Heat Pump • Electric • 8.2

HSPF

Cooling: Air Source Heat Pump • Electric • 14

SEER

Hot Water: Residential Water Heater • Electric •

0.95 Energy Factor

Average Mechanical Ventilation: 0 CFM

Builder or Design Professional

Signature:

Builder Affidavit

Property

174 Walker Grove Lane Lillington, NC 27546 Model: 1601 Bayside E-G2_2 Community: Walkers Grove

W. II. C. 44

Walkers Grove 11 True_Walkers Grove 11_1601 Bayside E-G2_2_GL_WinPerPlan Organization

Performance Point, LLC. Rick Blair 704-614-7175

Builder

True Homes

Inspection StatusResults are projected

Important Notice to Builder

Builder affirms in this affidavit that all building characteristics described in the Building Summary Report accurately reflect this New Home. Builder agrees to allow the Home Energy Rating System (HERS) Provider and/or Rater to verify building characteristics of this New Home fully at the HERS Rater/Provider's discretion. The HERS Provider and Rater do not create or imply any duty or obligations to Builder or any subsequent owner. Builder is responsible for taking any actions necessary to protect Builder's interest. There is no guarantee or warranty whatsoever expressed or implied from the HERS Provider or Rater.

HERS® Index Score:78

Builder Name: True Ho	omes	Builder Signature: Megan Q. Parmiter		
Name:	Rick Blair	Signature:	TalTSZ	
Organization:	Performance Point, LLC.	 Digitally signed:	11/1/21 at 9:22 AM	