1. All bracing, blocking, beams, purlins @ 2'0" o.c., ledger, etc. provided by others.
2. Roof truss to roof truss connections provided by Riverside Roof Truss.
3. Truss to building connections provided by others.

Refer to Sealed drawings for connection detail of multiple ply trusses.

NOT ALL TRUSSES ARE SYMMETRICAL AND MAY NOT PERFORM CORRECTLY IF INSTALLED BACKWARDS. PLEASE REFER TO SEALS WHILE SETTING TRUSSES TO ENSURE TRUSSES ARE ORIENTED CORRECTLY





Products				
PlotID	Length	Product	Plies	Net Qty
FJ46	46-00-00	11 7/8" NI-40x	1	6
FJ20	20-00-00	11 7/8" NI-40x	1	11
FJ18	18-00-00	11 7/8" NI-40x	1	12
FJ16	16-00-00	11 7/8" NI-40x	1	1
BM14	20-00-00	1 3/4" x 11 7/8" (2.0E 3100) LVL	2	2
BM9	20-00-00	1 3/4" x 11 7/8" (2.0E 3100) LVL	2	2
BM10	14-00-00	1 3/4" x 11 7/8" (2.0E 3100) LVL	2	2
BM11	4-00-00	1 3/4" x 11 7/8" (2.0E 3100) LVL	1	1
BM12	4-00-00	1 3/4" x 11 7/8" (2.0E 3100) LVL	1	1
BM15	30-00-00	1 3/4" x 16" (2.0E 3100) LVL	3	3
BM8	22-00-00	1 3/4" x 18" (2.0E 3100) LVL	2	2
RIM1	12-00-00	1 1/8" x 11 7/8" APA Rim Board	1	11
Bk1	33-00-00	11 7/8" NI-40x	1	1
Pt1	10-00-00	Glulam Column 3.5 x 5.5	1	1
Pt2	10-00-00	GluLam Column 5.5x5.5	1	1

Connector Summary		
Qty	Manuf	Product
1	Simpson	HHUS410
1	Simpson	HHUS410
4	Simpson	IUS2.56/11.88
16	Simpson	IUS2.66/11.88

SHOP DRAWING APPROVAL

THIS LAYOUT IS THE SOLE SOURCE FOR FABRICATION OF TRUSSES AND VOIDS ALL PREVIOUS ARCHITECTURAL OR OTHER TRUSS LAYOUTS. REVIEW AND APPROVAL OF THIS LAYOUT MUST BE RECEIVED BEFORE ANY TRUSSES WILL BE BUILT. VERIFY ALL CONDITIONS TO INSURE AGAINST CHANGES THAT WILL RESULT IN EXTRA CHARGES TO YOU.

REVIEWED BY:_____ APPROVED BY:_____ DATE:_____

THIS IS A TRUSS PLACEMENT DIAGRAM ONLY. These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing. The building designer is responsible for temporary and permanent bracing of the roof and floor system and for the overall structure. The design of the truss support structure including headers, beams, walls, columns, and sufficient blocking in floor cavity under point loads, is the responsibility of the building designer. For general guidance regarding bracing, consult "Bracing of Wood Trusses" available from the Truss Plate Institute, 583 D'Onofrio Drive; Madison, WI 53719.

Client: PARKS BUILDING SUPPLY
Job Name: LASSEK RES. EWP SECOND FLOOR
Model:
Lot #: Subdivision:
Order #: 21-6482-B
Sales Rep: C Smiley
Designer: R S
Date: 10/4/2021

Hanger Conversion Chart

Simpson	USP
LUS26	JUS26
HUS26	THD26
HHUS26-2	THD26-2
THJA26	HJC26
THA422	MSH422

733 RIVER PARK DRIVE
DANVILLE, VA 24540
(434) 793-0217
FAX: (434) 799-8767

RIVERSIDE ROOF TRUSS, LLC

Roof Surface Area: 0 ft² Sq. Ft.
Floor Surface Area: 3860 ft² Sq. Ft.

MiTek® SIMPSON StrongTie®