







FRONT ELEVATION  
SCALE: 1/4" = 1'-0"




LEFT ELEVATION



RAKE DETAIL FOR GABLE ENDS



RIGHT ELEVATION



REAR ELEVATION  
SCALE: 1/8" = 1'-0"

HERO PACKAGE

ATTIC VENTILATION CALCULATIONS	
ATTIC AREA	3064 SQ.FT. (AREA VENTILATION REQUIRED 18.4 SQ.FT.)
? EACH 2' FT. BASE GABLE LOUVER @ 2' SQ.FT. NET FREE AREA	
? EACH 2' FT. BASE GABLE LOUVER @ 3' SQ.FT. NET FREE AREA	
? EACH 2' FT. BASE GABLE LOUVER @ 2' SQ.FT. NET FREE AREA	
? EACH 2' FT. BASE GABLE LOUVER @ 3' SQ.FT. NET FREE AREA	
174 LIN.FT. EAVE VENT @ 11 SQ.IN./FT. = 13.3 SQ.FT. NET FREE AREA	
103 LIN.FT. RIDGE VENT @ 18 SQ.IN./FT. = 12.9 SQ.FT. NET FREE AREA	

EXCLUSIVE RESIDENCE DESIGN FOR:  
**WATERMARK HOMES**

**T M DESIGNS**  
RESIDENTIAL PLANS BY TINA MCFADDEN  
(910) 354-4736 TMDDESIGNS2016@GMAIL.COM

LOT: 37 OAK HAVEN

NAME: PONDEROSA

© 2016 COPYRIGHT ALL RIGHTS RESERVED

T M DESIGNS WILL NOT BE LIABLE FOR ANY ERRORS NOT BROUGHT TO THEIR ATTENTION PRIOR TO THE START OF CONSTRUCTION. WHILE EVERY EFFORT WAS MADE IN THE PREPARATION OF THESE DRAWINGS AND DIMENSIONS TO AVOID ERRORS THE OWNER AND / OR BUILDER SHALL VERIFY ALL DIMENSIONS DETAILS, LOCAL AND STATE CODES.

I HEREBY CERTIFY THAT THIS DRAWING MEETS LOCAL CODES, 2018 INTERNATIONAL BUILDING CODES.

THIS IS FOR THE CONSTRUCTION OF ONE HOUSE ON A SINGLE LOT, NOT TO BE REUSED

PLAN NUMBER  
RG21-A01


OPTION #2

1	GARAGE	R	F
	DATE:	2/15/21	


**ENERGY TABLE**  
UFACTOR OF WINDOWS .30  
CLIMATE ZONE 3  
INSULATION: WALLS 15  
CEILING 38  
FLOORS 19

EXTERIOR WALLS (2) 2X10 HEADERS		
CLEAR SPAN FOR HEADER	NUMBER OF STUDS	
	JACKS	KINGS
ALL DOOR & C.O. BELOW 4'	1	1
ALL DOOR & C.O. 4' TO 7'-11"	2	2
ALL DOOR & C.O. 8' AND ABOVE	SIZED BY ENGINEER	

\*\*UNLESS NOTED OTHER WISE\*\*



EXTERIOR WALL TO BE FULLY SHEATHED WITH 7/16" OSB. NAILING PATTERN TO BE 3" ON ALL EDGES AND 12" IN FIELD, WITH 8d NAIL.S.



FOUNDATION CRIPPLE WALLS SHALL BE FRAMED OF STUDS NOT SMALLER THAN THE STUDING ABOVE. WHEN EXCEEDING 4 FT. IN HEIGHT, SUCH WALLS SHALL BE FRAMED OF STUDS HAVING THE SIZE REQUIRED FOR AN ADDITIONAL STORY.  
CRIPPLE WALLS WITH A STUD HEIGHT LESS THAN 14 INCHES SHALL BE CONTINUOUSLY SHEATHED ON ONE SIDE WITH WOOD STRUCTURAL PANELS FASTENED TO BOTH THE TOP AND BOTTOM PLATES IN ACCORDANCE WITH TABLE R602.3(1), OR CRIPPLE WALLS SHALL BE CONSTRUCTED OF SOLID BLOCKING.

**FIRST FLOOR PLAN**  
SCALE: 1/4"=1'-0"



**HEATED AREA**

1ST FL	2111	SQ FT
2ND FL	348	SQ FT
TOTAL	2459	SQ FT

**OTHER AREAS**

GARAGE	611	SQ FT
F.PORCH	144	SQ FT
R.PORCH	198	SQ FT
STORAGE	302	SQ FT
TOTAL	1255	SQ FT

**NOTE:**  
CEILINGS ARE 9'-0" UNLESS NOTED.  
SET WINDOWS @ 7'-4" A.F.F.




**GARAGE PANEL WALL**

GARAGE PANEL WALLS UNDER 24" WIDE SHOULD BE EITHER PORTAL FRAMED OR 7/16" OSB ON BOTH SIDES WITH A NAILING PATTERN OF 3" ON ALL PANEL EDGES AND 6" IN THE FIELD.


**HERO PACKAGE**

HERO PACKAGE



EXTERIOR WALLS (2) 2X10 HEADERS		
NUMBER OF STUDS KINGS	JACKS	CLEAR SPAN FOR HEADER
1	1	ALL DOOR & C.O. BELOW 4'
2	2	ALL DOOR & C.O. 4' TO 7'-11"
SIZED BY ENGINEER		ALL DOOR & C.O. 8' AND ABOVE

\*\*UNLESS NOTED OTHER WISE\*\*



SECOND FLOOR PLAN  
SCALE: 1/4" = 1'-0"

EXCLUSIVE RESIDENCE DESIGN FOR:

**WATERMARK HOMES**

NAME: PONDEROSA

LOT: 37 OAK HAVEN

© 2016. COPYRIGHT ALL RIGHTS RESERVED

T.M. DESIGNS WILL NOT BE LIABLE FOR ANY ERRORS NOT BROUGHT TO THEIR ATTENTION PRIOR TO THE START OF CONSTRUCTION, WHILE EVERY EFFORT WAS MADE IN THE PREPARATION OF THESE DRAWINGS AND DIMENSIONS TO AVOID ERRORS THE OWNER AND/OR BUILDER SHALL VERIFY ALL DIMENSIONS, DETAILS, LOCAL AND STATE CODES.

I HEREBY CERTIFY THAT THIS DRAWING MEETS LOCAL CODES, 2018 INTERNATIONAL BUILDING CODES

THIS IS FOR THE CONSTRUCTION OF ONE HOUSE ON A SINGLE LOT, NOT TO BE REUSED

PLAN NUMBER  
RG21-A01

OPTION #2



2	GARAGE	R	F
	DATE:	2/15/21	

**T.M. DESIGNS**


RESIDENTIAL PLANS BY TINA MCFADDEN  
(910) 354-4736 T.MDESIGNS2016@GMAIL.COM

**NOTE:**  
 FOUNDATION DETAILS SHOWN ARE BASED ON ASSUMED SOIL BEARING CAPACITY OF 2000 PSF. LOCAL SITE CONDITIONS MUST BE INVESTIGATED. ALL FOOTING TO BE LOCATED BELOW FROST DEPTH.


**USE ANCHOR BOLTS**  
 ANCHOR BOLTS: 1/2" DIA. BOLTS AT 6'-0" O.C. AND NOT MORE THAN 12" FROM CORNERS, EMBEDDED MIN. 7" INTO FOUNDATION. USE A MIN. OF 2 BOLTS PER EACH STUD WALL.



CONCRETE SLAB FLOOR — (A)




GARAGE WALL — (B)



LOAD BEARING WALL THICKENED SLAB — (C)

**FOUNDATION PLAN**  
 SCALE: 1/4"=1'-0"



**STEPS:**  
 SET BRICK STEPS ON 6" CONCRETE SIDEWALK

© 2016. COPYRIGHT ALL RIGHTS RESERVED

T M DESIGNS WILL NOT BE LIABLE FOR ANY ERRORS NOT BROUGHT TO THEIR ATTENTION PRIOR TO THE START OF CONSTRUCTION. WHILE EVERY EFFORT WAS MADE IN THE PREPARATION OF THESE DRAWINGS AND DIMENSIONS TO AVOID ERRORS THE OWNER AND/OR BUILDER SHALL VERIFY ALL DIMENSIONS, DETAILS, LOCAL AND STATE CODES.

I HEREBY CERTIFY THAT THIS DRAWING MEETS LOCAL CODES, 2018 INTERNATIONAL BUILDING CODES

THIS IS FOR THE CONSTRUCTION OF ONE HOUSE ON A SINGLE LOT, NOT TO BE REUSED

PLAN NUMBER		
RG21-A01		
OPTION #2		
3	GARAGE	R   F
	DATE:	2/15/21




# ROOF & FLOOR TRUSSES & BEAMS

Reilly Road Industrial Park  
Fayetteville, N.C. 28309  
Phone: (910) 864-8787  
Fax: (910) 864-4444

**THIS IS A TRUSS PLACEMENT DIAGRAM ONLY.**  
These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. The individual design sheets for each truss design identified on the drawing are the property of the building designer. The building designer is responsible for the design of the building system and for the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer. For general guidance regarding trusses, consult ICC-ES E-1000 and E-1001 provided with the truss delivery package or visit [www.structuredesign.com](http://www.structuredesign.com)

Bearing reactions less than or equal to 3000# are deemed to comply with the prescriptive Code requirements. The contractor shall refer to the attached Tables (derived from the prescriptive Code requirements) to determine the minimum foundation size and number of wood studs required to support reactions greater than 3000# but not greater than 15000#. A registered design professional shall be retained to design the support system for any reaction that exceeds those specified in the attached Tables. A registered design professional shall be retained to design the support system for all reactions that exceed 15000#.

Signature: Anthony Williams



**Dimension Notes**  
1. All exterior wall to wall dimensions are to face of sheathing unless noted otherwise.  
2. All interior wall dimensions are to face of frame wall unless noted otherwise.  
3. All exterior wall to truss dimensions are to face of frame wall unless noted otherwise.

Roof Area = 4411.57 sq.ft.  
Ridge Line = 111.2 ft.  
Hip Line = 0 ft.  
Horiz. OH = 189.14 ft.  
Raked OH = 323.95 ft.  
Decking = 152 sheets

All Walls Shown Are Considered Load Bearing

▲ = Indicates Left End of Truss (Reference Engineered Truss Drawing)  
Do Not Erect Trusses Backwards

Connector Information				Nail Information		
Sym	Product	Manuf	Qty	Supported Member	Header	Truss
■	HUS26	USP	3	Varies	16d/3-1/2"	16d/3-1/2"

Beam Schedule					
PlotID	Length	Product	Plies	Net Qty	Fab Type
BM2	7' 0"	1-3/4"x 9-1/4" LVL Kerto-S	2	2	FF
BM3	6' 0"	1-3/4"x 9-1/4" LVL Kerto-S	2	2	FF
GDH	24' 0"	1-3/4"x 11-7/8" LVL Kerto-S	2	2	FF
BM1	10' 0"	1-3/4"x 11-7/8" LVL Kerto-S	2	2	FF

All Truss Reactions are Less than 3,000 lbs. Unless Noted Otherwise.  
○ -- Denotes Reaction Greater than 3,000 lbs. Reaction / # of Studs

Truss Placement Plan  
SCALE: 1/4" = 1'-0"


BUILDER	Watermark Homes	Johnston County
JOB NAME	Lot 37 Oak Haven	Lot 37 Oak Haven
PLAN	Ponderosa	Roof
SEAL DATE	Plan Date: 1/15/21	6/29/21
QUOTE #	Quote #	Anthony Williams
JOB #	J0322-1082	Anthony Williams

COUNTY	Watermark Homes	Johnston County
ADDRESS	Lot 37 Oak Haven	Lot 37 Oak Haven
MODEL	Ponderosa	Roof
DATE REV.	Plan Date: 1/15/21	6/29/21
DRAWN BY	Quote #	Anthony Williams
SALESMAN	J0322-1082	Anthony Williams

LOAD CHART FOR JACK STUDS			
BASED ON TABLES ENR202.1 & 202		BASED ON TABLES ENR202.1 & 202	
END REACTION (LBS)	REQ'D STUDS FOR JACK STUDS	END REACTION (LBS)	REQ'D STUDS FOR JACK STUDS
1700	1	2550	1
3400	2	5100	2
5100	3	7650	3
6800	4	10200	4
8500	5	12750	5
10200	6	15300	6
11900	7		
13600	8		
15300	9		

**GDH-FRONT Kerto-S LVL 1.750" X 11.875" 2-Ply - PASSED**

Level: Level



**Member Information**

Type:	Girder	Application:	Floor
Plies:	2	Design Method:	ASD
Moisture Condition:	Dry	Building Code:	IBC 2012
Deflection LL:	480	Load Sharing:	No
Deflection TL:	360	Deck:	Not Checked
Importance:	Normal - II		
Temperature:	Temp <= 100°F		

**Reactions UNPATTERNED lb (Uplift)**

Brg	Direction	Live	Dead	Snow	Wind	Const
1	Vertical	173	1805	173	0	0
2	Vertical	173	1805	173	0	0

**Bearings**

Bearing	Length	Dir.	Cap.	React D/L lb	Total	Ld. Case	Ld. Comb.
1 - SPF End Grain	6.000"	Vert	11%	1805 / 259	2063	L	D+0.75(L+S)
2 - SPF End Grain	6.000"	Vert	11%	1805 / 259	2063	L	D+0.75(L+S)

**Analysis Results**

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	7013 ft-lb	8'7 1/2"	17919 ft-lb	0.391 (39%)	D	Uniform
Unbraced	8019 ft-lb	8'7 1/2"	8035 ft-lb	0.998 (100%)	D+0.75(L+S)	L
Shear	1502 lb	15'9 1/8"	7980 lb	0.188 (19%)	D	Uniform
LL Defl inch	0.052 (L/3745)	8'7 9/16"	0.409 (L/480)	0.128 (13%)	0.75(L+S)	L
TL Defl inch	0.418 (L/470)	8'7 9/16"	0.546 (L/360)	0.767 (77%)	D+0.75(L+S)	L

**Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at a maximum of 12' 11/16" o.c.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Top	200 PLF	20 PLF	20 PLF	0 PLF	0 PLF	ROOF/WALL
	Self Weight				9 PLF					

**Notes**

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

chemicals

**Handling & Installation**

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 3/30/2024

**Manufacturer Info**

Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
 www.metsawood.com/us  
 ICC-ES: ESR-3633

Comtech, Inc.  
 1001 S. Reilly Road, Suite #639  
 Fayetteville, NC  
 USA  
 28314  
 910-864-TRUS






Client: Watermark Homes  
 Project:  
 Address: Lot 37 Oak Haven / Johnston County

Date: 3/1/2022  
 Input by: Anthony Williams  
 Job Name: Lot 37 Oak Haven  
 Project #: J0322-1082

**GDH-FRONT Kerto-S LVL 1.750" X 11.875" 2-Ply - PASSED**

Level: Level



**Multi-Ply Analysis**

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

Capacity	0.0 %
Load	0.0 PLF
Yield Limit per Foot	163.7 PLF
Yield Limit per Fastener	81.9 lb.
Yield Mode	IV
Edge Distance	1 1/2"
Min. End Distance	3"
Load Combination	
Duration Factor	1.00

**Notes**

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive

chemicals

**Handling & Installation**

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 3/30/2024

**Manufacturer Info**


Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
 www.metsawood.com/us  
 ICC-ES: ESR-3633

Comtech, Inc.  
 1001 S. Reilly Road, Suite #639  
 Fayetteville, NC  
 USA  
 28314  
 910-864-TRUS



# BM1 Kerto-S LVL 1.750" X 11.875" 2-Ply - PASSED

Level: Level



### Member Information

Type:	Girder	Application:	Floor
Plies:	2	Design Method:	ASD
Moisture Condition:	Dry	Building Code:	IBC 2012
Deflection LL:	480	Load Sharing:	No
Deflection TL:	360	Deck:	Not Checked
Importance:	Normal - II		
Temperature:	Temp <= 100°F		

### Reactions UNPATTERNED lb (Uplift)

Brg	Direction	Live	Dead	Snow	Wind	Const
1	Vertical	0	2426	2384	0	0
2	Vertical	0	2426	2384	0	0

### Bearings

Bearing	Length	Dir.	Cap.	React D/L lb	Total	Ld. Case	Ld. Comb.
1 - SPF End Grain	4.500"	Vert	35%	2426 / 2384	4811	L	D+S
2 - SPF End Grain	4.500"	Vert	35%	2426 / 2384	4811	L	D+S

### Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	9473 ft-lb	4'6 1/2"	22897 ft-lb	0.414 (41%)	D+S	L
Unbraced	9473 ft-lb	4'6 1/2"	10675 ft-lb	0.887 (89%)	D+S	L
Shear	3374 lb	1'4 3/8"	10197 lb	0.331 (33%)	D+S	L
LL Defl inch	0.075 (L/1355)	4'6 9/16"	0.211 (L/480)	0.354 (35%)	S	L
TL Defl inch	0.151 (L/672)	4'6 9/16"	0.282 (L/360)	0.536 (54%)	D+S	L

### Design Notes

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at end bearings.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Top	525 PLF	0 PLF	525 PLF	0 PLF	0 PLF	B1
	Self Weight				9 PLF					

### Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

### Lumber

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

### Handling & Installation

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 3/30/2024

### Manufacturer Info

Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
[www.metsawood.com/us](http://www.metsawood.com/us)  
 ICC-ES: ESR-3633


Comtech, Inc.  
 1001 S. Reilly Road, Suite #639  
 Fayetteville, NC  
 USA  
 28314  
 910-864-TRUS





**BM1 Kerto-S LVL 1.750" X 11.875" 2-Ply - PASSED**

Level: Level



**Multi-Ply Analysis**

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

Capacity	0.0 %
Load	0.0 PLF
Yield Limit per Foot	163.7 PLF
Yield Limit per Fastener	81.9 lb.
Yield Mode	IV
Edge Distance	1 1/2"
Min. End Distance	3"
Load Combination	
Duration Factor	1.00

**Notes**

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive

**Handling & Installation**

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 3/30/2024

**Manufacturer Info**



Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
[www.metsawood.com/us](http://www.metsawood.com/us)  
 ICC-ES: ESR-3633

Comtech, Inc.  
 1001 S. Reilly Road, Suite #639  
 Fayetteville, NC  
 USA  
 28314  
 910-864-TRUS



# BM2 Kerto-S LVL 1.750" X 9.250" 2-Ply - PASSED

Level: Level



### Member Information

Type:	Girder
Plies:	2
Moisture Condition:	Dry
Deflection LL:	480
Deflection TL:	360
Importance:	Normal - II
Temperature:	Temp <= 100°F

Application:	Floor
Design Method:	ASD
Building Code:	IBC 2012
Load Sharing:	No
Deck:	Not Checked

### Reactions UNPATTERNED lb (Uplift)

Brg	Direction	Live	Dead	Snow	Wind	Const
1	Vertical	513	1120	928	0	0
2	Vertical	513	1120	928	0	0

### Bearings

Bearing	Length	Dir.	Cap.	React D/L lb	Total	Ld. Case	Ld. Comb.
1 - SPF	3.500"	Vert	42%	1120 / 1081	2201	L	D+0.75(L+S)
2 - SPF	3.500"	Vert	42%	1120 / 1081	2201	L	D+0.75(L+S)

### Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	3158 ft-lb	3'3 3/4"	14423 ft-lb	0.219 (22%)	D+0.75(L+S)	L
Unbraced	3158 ft-lb	3'3 3/4"	10411 ft-lb	0.303 (30%)	D+0.75(L+S)	L
Shear	1501 lb	5'6 3/4"	7943 lb	0.189 (19%)	D+0.75(L+S)	L
LL Defl inch	0.029 (L/2595)	3'3 3/4"	0.154 (L/480)	0.185 (18%)	0.75(L+S)	L
TL Defl inch	0.058 (L/1274)	3'3 3/4"	0.206 (L/360)	0.282 (28%)	D+0.75(L+S)	L

### Design Notes

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at end bearings.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Top	331 PLF	155 PLF	280 PLF	0 PLF	0 PLF	D2A
	Self Weight				7 PLF					

### Notes

Calculated Structural Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive

**Handling & Installation**

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 3/30/2024

### Manufacturer Info


Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
[www.metsawood.com/us](http://www.metsawood.com/us)  
 ICC-ES: ESR-3633

Comtech, Inc.  
 1001 S. Reilly Road, Suite #639  
 Fayetteville, NC  
 USA  
 28314  
 910-864-TRUS



**BM2 Kerto-S LVL 1.750" X 9.250" 2-Ply - PASSED**

Level: Level



**Multi-Ply Analysis**

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

Capacity	0.0 %
Load	0.0 PLF
Yield Limit per Foot	163.7 PLF
Yield Limit per Fastener	81.9 lb.
Yield Mode	IV
Edge Distance	1 1/2"
Min. End Distance	3"
Load Combination	
Duration Factor	1.00

**Notes**

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive

chemicals

**Handling & Installation**

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 3/30/2024

**Manufacturer Info**



Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
 www.metsawood.com/us  
 ICC-ES: ESR-3633

Comtech, Inc.  
 1001 S. Reilly Road, Suite #639  
 Fayetteville, NC  
 USA  
 28314  
 910-864-TRUS



**BM3 Kerto-S LVL 1.750" X 9.250" 2-Ply - PASSED**

Level: Level



**Member Information**

Type: Girder	Application: Floor
Plies: 2	Design Method: ASD
Moisture Condition: Dry	Building Code: IBC 2012
Deflection LL: 480	Load Sharing: No
Deflection TL: 360	Deck: Not Checked
Importance: Normal - II	
Temperature: Temp <= 100°F	

**Reactions UNPATTERNED lb (Uplift)**

Brg	Direction	Live	Dead	Snow	Wind	Const
1	Vertical	0	1479	1458	0	0
2	Vertical	0	1479	1458	0	0

**Bearings**

Bearing	Length	Dir.	Cap.	React D/L lb	Total	Ld. Case	Ld. Comb.
1 - SPF End Grain	3.000"	Vert	32%	1479 / 1458	2938	L	D+S
2 - SPF End Grain	3.000"	Vert	32%	1479 / 1458	2938	L	D+S

**Analysis Results**

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	3751 ft-lb	2'11"	14423 ft-lb	0.260 (26%)	D+S	L
Unbraced	3751 ft-lb	2'11"	11110 ft-lb	0.338 (34%)	D+S	L
Shear	1915 lb	4'9 3/4"	7943 lb	0.241 (24%)	D+S	L
LL Defl inch	0.028 (L/2318)	2'11"	0.136 (L/480)	0.207 (21%)	S	L
TL Defl inch	0.057 (L/1151)	2'11"	0.182 (L/360)	0.313 (31%)	D+S	L

**Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at end bearings.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Top	500 PLF	0 PLF	500 PLF	0 PLF	0 PLF	A2
	Self Weight				7 PLF					

**Notes**

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive

**Handling & Installation**

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 3/30/2024

**Manufacturer Info**



Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5851  
 www.metsawood.com/us  
 ICC-ES: ESR-3633

Comtech, Inc.  
 1001 S. Reilly Road, Suite #639  
 Fayetteville, NC  
 USA  
 28314  
 910-864-TRUS



**BM3 Kerto-S LVL 1.750" X 9.250" 2-Ply - PASSED**

Level: Level



**Multi-Ply Analysis**

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

Capacity	0.0 %
Load	0.0 PLF
Yield Limit per Foot	163.7 PLF
Yield Limit per Fastener	81.9 lb.
Yield Mode	IV
Edge Distance	1 1/2"
Min. End Distance	3"
Load Combination	
Duration Factor	1.00

**Notes**  
 Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

**Lumber**

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

**Handling & Installation**

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 3/30/2024

**Manufacturer Info**

Metsä Wood  
 301 Merritt 7 Building, 2nd Floor  
 Norwalk, CT 06851  
 (800) 622-5850  
 www.metsawood.com/us  
 ICC-ES: ESR-3633

Comtech, Inc.  
 1001 S. Reilly Road, Suite #639  
 Fayetteville, NC  
 USA  
 28314  
 910-864-TRUS



# Reaction Summary of Order



**ROOF & FLOOR TRUSSES & BEAMS**  
 Reilly Road Industrial Park P.O. Box 40408  
 Fayetteville, N.C. 28309 (910) 864-TRUS

REQ. QUOTE DATE	/ /	ORDER #	J0322-1082
ORDER DATE	03/01/22	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT #	000030
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	Brady Rufenacht	INVOICE #	
COUNTY	Johnston	TERMS	Net 10 Days
SUPERINTENDANT	Justin Thomas	SALES REP	Anthony Williams
JOBSITE PHONE #	(910) 759-1307	SALES AREA	Anthony Williams

SOLD TO	<b>Watermark Homes, Inc.</b> 196 Annette Drive Benson, NC 27504 (919) 938-8194	<b>JOB NAME:</b> Lot 37 Oak Haven <b>MODEL:</b> Roof <b>TAG:</b> Ponderosa Pine II <b>DELIVERY INSTRUCTIONS:</b> Delivery charge added for wide load.	<b>LOT # 37</b> <b>SUBDIV:</b> Oak Haven <b>JOB CATEGORY:</b> B & S - Build and Ship
	SHIPP TO	<b>Watermark Homes</b> Lot 37 Oak Haven Benson, NC	<b>SPECIAL INSTRUCTIONS:</b> Copied from Lot 9 SB (J0221-0783) jb

BUILDING DEPARTMENT Roof Order	OVERHANG INFO	HEEL HEIGHT	00-06-08	REQ. LAYOUTS	REQ. ENGINEERING	QUOTE	/ /
	END CUT	RETURN		NONE	NONE	LAYOUT	/ /
PLUMB	NO	GABLE STUDS	16 IN. OC			CUTTING	/ /

**ROOF TRUSSES**      **LOADING INFORMATION**      TOLL-TCDL-BCLL-BCDL      STRESS INCR.      **ROOF TRUSS SPACING:** 24.0 IN. O.C. (TYP.)  
 20.0,10.0,0.0,10.0      1.15

PROFILE	QTY	PITCH		TYPE ID	BASE O/A	LUMBER		OVERHANG		REACTIONS				
		TOP	BOT			TOP	BOT	LEFT	RIGHT	Joint 2	Joint 4	Joint 5	Joint 13	Joint 20
	2	3.50	0.00	ROOF A1	50-11-00 50-11-00	2 X 6	2 X 6	01-05-00	01-05-00	Joint 2 135.2 lbs. -7.6 lbs.	Joint 4 48.2 lbs. -41.8 lbs.	Joint 5 36.3 lbs. 1.5 lbs.	Joint 13 1983.6 lbs. -121.7 lbs.	Joint 20 1964.6 lbs. -191.0 lbs.
	1	3.50	0.00	GABLE A1-GE	50-11-00 50-11-00	2 X 6	2 X 6	01-05-00	01-05-00	Joint 2 286.5 lbs. -274.0 lbs.	Joint 26 395.2 lbs. 51.1 lbs.	Joint 28 1147.2 lbs. -725.3 lbs.	Joint 29 669.0 lbs. 13.6 lbs.	Joint 36 2150.9 lbs. -516.6 lbs.
	9	8.00	0.00	COMMON A2	37-11-00 37-11-00	2 X 6	2 X 6	01-05-00	01-05-00	Joint 2 1529.9 lbs. -92.2 lbs.	Joint 12 1997.5 lbs. -115.3 lbs.			
	1	8.00	0.00	FINK A2-GE	37-11-00 37-11-00	2 X 6	2 X 6	01-05-00	01-05-00	Joint 2 1630.9 lbs. -268.1 lbs.	Joint 19 434.2 lbs. 44.0 lbs.	Joint 21 -13.6 lbs. -232.4 lbs.	Joint 22 1850.5 lbs. -540.5 lbs.	
	3	3.50	0.00	ROOF B1	44-11-00 44-11-00	2 X 6	2 X 6	01-05-00	01-05-00	Joint 2 300.6 lbs. -200.3 lbs.	Joint 11 1644.1 lbs. -90.8 lbs.	Joint 18 2100.5 lbs. -176.5 lbs.		
	1	3.50	0.00	GABLE B1-GE	44-11-00 44-11-00	2 X 6	2 X 6	01-05-00	01-05-00	Joint 2 435.1 lbs. -295.7 lbs.	Joint 27 365.8 lbs. 53.2 lbs.	Joint 29 222.4 lbs. -373.5 lbs.	Joint 30 1611.7 lbs. -734.2 lbs.	Joint 35 1917.3 lbs. -485.3 lbs.
	4	8.00	0.00	COMMON B2	31-11-00 31-11-00	2 X 6	2 X 6	01-05-00	01-05-00	Joint 2 1578.0 lbs. -83.7 lbs.	Joint 10 1578.0 lbs. -83.7 lbs.			
	1	8.00	0.00	COMMON B2-GE	31-11-00 31-11-00	2 X 6	2 X 6	01-05-00	01-05-00	Joint 2 276.3 lbs. -129.3 lbs.	Joint 22 214.4 lbs. -38.4 lbs.	Joint 24 186.9 lbs. -168.2 lbs.	Joint 25 176.4 lbs. -79.3 lbs.	Joint 26 176.7 lbs. -88.4 lbs.
	3	3.50	0.00	ROOF C1	40-11-00 40-11-00	2 X 6	2 X 6	01-05-00	01-05-00	Joint 2 439.7 lbs. -213.3 lbs.	Joint 11 1278.9 lbs. -84.4 lbs.	Joint 17 1872.9 lbs. -246.9 lbs.		
	5	10.00	0.00	ATTIC D1	23-11-00 23-11-00	2 X 6	2 X 10	01-05-00	01-05-00	Joint 12 1617.4 lbs. 158.9 lbs.	Joint 16 1617.4 lbs. 158.9 lbs.			
	2	10.00	0.00	ATTIC D1-GE	23-11-00 23-11-00	2 X 6	2 X 10	01-05-00	01-05-00	Joint 12 1613.4 lbs. 16.5 lbs.	Joint 16 1613.4 lbs. 16.5 lbs.			

# Reaction Summary of Order












**ROOF & FLOOR TRUSSES & BEAMS**  
 Reilly Road Industrial Park P.O. Box 40408  
 Fayetteville, N.C. 28309 (910) 864-TRUS

REQ. QUOTE DATE	/ /	ORDER #	J0322-1082
ORDER DATE	03/01/22	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT #	000030
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	Brady Rufenacht	INVOICE #	
COUNTY	Johnston	TERMS	Net 10 Days
SUPERINTENDANT	Justin Thomas	SALES REP	Anthony Williams
JOBSITE PHONE #	(910) 759-1307	SALES AREA	Anthony Williams

<b>SOLD TO</b>	<b>Watermark Homes, Inc.</b> 196 Annette Drive Benson, NC 27504 (919) 938-8194	<b>JOB NAME:</b> Lot 37 Oak Haven <b>MODEL:</b> Roof <b>TAG:</b> Ponderosa Pine II <b>DELIVERY INSTRUCTIONS:</b> Delivery charge added for wide load.	<b>LOT # 37</b> <b>SUBDIV:</b> Oak Haven <b>JOB CATEGORY:</b> B & S - Build and Ship
	<b>Watermark Homes</b> Lot 37 Oak Haven Benson, NC	<b>SPECIAL INSTRUCTIONS:</b> Copied from Lot 9 SB (J0221-0783) jb	<b>PLAN SEAL DATE:</b> BY      DATE

<b>BUILDING DEPARTMENT</b> Roof Order	<b>OVERHANG INFO</b>	<b>HEEL HEIGHT</b>	00-06-08	<b>REQ. LAYOUTS</b>	<b>REQ. ENGINEERING</b>	<b>QUOTE</b>	/ /			
	<table border="1"> <tr> <td>END CUT</td> <td>RETURN</td> </tr> <tr> <td>PLUMB</td> <td>NO</td> </tr> </table>	END CUT	RETURN	PLUMB	NO	<b>GABLE STUDS</b>	16 IN. OC	<b>NONE</b>	<b>NONE</b>	<b>LAYOUT</b>
END CUT	RETURN									
PLUMB	NO									
					<b>CUTTING</b>	/ /				

<b>ROOF TRUSSES</b>	<b>LOADING INFORMATION</b>	TCLL-TCDL-BCLL-BCDL	STRESS INCR.	<b>ROOF TRUSS SPACING:</b> 24.0 IN. O.C. (TYP.)
		20.0,10.0,0.0,10.0	1.15	

PROFILE	QTY	PITCH		TYPE ID	BASE O/A	LUMBER		OVERHANG		REACTIONS
		TOP	BOT			TOP	BOT	LEFT	RIGHT	
	13	10.00	0.00	ATTIC D2	23-11-00 23-11-00	2 X 6	2 X 10	01-05-00		Joint 10      Joint 14 1530.5 lbs.      1620.5 lbs. 179.8 lbs.      161.0 lbs.
	3	10.00	0.00	ATTIC D2A	23-11-00 23-07-08	2 X 6	2 X 10			Joint 8      Joint 12 1514.1 lbs.      1530.3 lbs. 178.3 lbs.      185.2 lbs.
	2 2 Ply	10.00	0.00	ATTIC D3	23-11-00 23-11-00	2 X 6	2 X 10	01-05-00		Joint 10      Joint 14 3058.0 lbs.      3240.2 lbs. 358.4 lbs.      319.4 lbs.
	1	10.00	0.00	GABLE VA-1	20-10-06 20-10-06	2 X 4	2 X 4			Joint 1      Joint 11      Joint 12      Joint 13      Joint 14 221.7 lbs.      216.5 lbs.      205.5 lbs.      189.6 lbs.      145.8 lbs. -45.3 lbs.      -37.6 lbs.      -127.3 lbs.      -102.1 lbs.      -131.2 lbs.
	1	10.00	0.00	GABLE VA-2	17-08-00 17-08-00	2 X 4	2 X 4			Joint 1      Joint 5      Joint 6      Joint 8      Joint 9 120.9 lbs.      89.8 lbs.      548.0 lbs.      611.7 lbs.      548.1 lbs. -68.4 lbs.      -37.3 lbs.      -185.6 lbs.      75.8 lbs.      -185.7 lbs.
	1	10.00	0.00	GABLE VA-3	14-05-09 14-05-09	2 X 4	2 X 4			Joint 1      Joint 3      Joint 4 291.9 lbs.      291.9 lbs.      670.9 lbs. -32.0 lbs.      -44.5 lbs.      16.0 lbs.
	1	10.00	0.00	GABLE VA-4	11-03-03 11-03-03	2 X 4	2 X 4			Joint 1      Joint 3      Joint 4 223.5 lbs.      223.5 lbs.      389.8 lbs. -24.5 lbs.      -34.1 lbs.      12.2 lbs.
	1	10.00	0.00	VALLEY VA-5	08-00-13 08-00-13	2 X 4	2 X 4			Joint 1      Joint 3      Joint 4 167.9 lbs.      168.0 lbs.      245.0 lbs. -25.3 lbs.      -32.0 lbs.      25.1 lbs.
	1	10.00	0.00	VALLEY VA-6	04-10-06 04-10-06	2 X 4	2 X 4			Joint 1      Joint 3      Joint 4 93.9 lbs.      93.9 lbs.      137.0 lbs. -14.2 lbs.      -17.9 lbs.      14.0 lbs.

## ITEMS

QTY	ITEM TYPE	SIZE	LENGTH FT-IN-16	PART NUMBER	NOTES
3	Hangers, USP	HUS 26			SIMPSON (HUS26)

# Reaction Summary of Order



**ROOF & FLOOR TRUSSES & BEAMS**  
 Reilly Road Industrial Park P.O. Box 40408  
 Fayetteville, N.C. 28309 (910) 864-TRUS

REQ. QUOTE DATE	/ /	ORDER #	J0322-1082
ORDER DATE	03/01/22	QUOTE #	
DELIVERY DATE	/ /	CUSTOMER ACCT #	000030
DATE OF INVOICE	/ /	CUSTOMER PO #	
ORDERED BY	Brady Rufenacht	INVOICE #	
COUNTY	Johnston	TERMS	Net 10 Days
SUPERINTENDANT	Justin Thomas	SALES REP	Anthony Williams
JOBSITE PHONE #	(910) 759-1307	SALES AREA	Anthony Williams

<b>SOLD TO</b>	<b>Watermark Homes, Inc.</b> 196 Annettte Drive Benson, NC 27504 (919) 938-8194	<b>JOB NAME:</b> Lot 37 Oak Haven <b>MODEL:</b> Roof <b>TAG:</b> Ponderosa Pine II <b>DELIVERY INSTRUCTIONS:</b> Delivery charge added for wide load.	<b>LOT # 37    SUBDIV:</b> Oak Haven <b>JOB CATEGORY:</b> B & S - Build and Ship
	<b>Watermark Homes</b> Lot 37 Oak Haven Benson, NC	<b>SPECIAL INSTRUCTIONS:</b> Copied from Lot 9 SB (J0221-0783) jb	<b>PLAN SEAL DATE:</b> BY      DATE

<b>BUILDING DEPARTMENT</b>	<b>OVERHANG INFO</b>	<b>HEEL HEIGHT</b>	00-06-08	<b>REQ. LAYOUTS</b>	<b>REQ. ENGINEERING</b>	<b>QUOTE</b>	/ /
	<b>END CUT</b>	<b>RETURN</b>		<b>NONE</b>	<b>NONE</b>	<b>LAYOUT</b>	/ /
	<b>PLUMB</b>	NO	<b>GABLE STUDS</b>			16 IN. OC	<b>CUTTING</b>

## ITEMS





QTY	ITEM TYPE	SIZE	LENGTH FT-IN-16	PART NUMBER	NOTES
4	LVL Beams (Sized)	LVL, 1-3/4" x 9-1/4" (S)	07-00-00		BM2 & BM3
2	LVL Beams (Sized)	LVL, 1-3/4" x 11-7/8" (S)	10-00-00		BM1
2	LVL Beams (Sized)	LVL, 1-3/4" x 11-7/8" (S)	24-00-00		GDH



# GENERAL NOTES

- THIS WET PIPE FIRE SPRINKLER SYSTEM IS DESIGNED AS LIGHT HAZARD/RESIDENTIAL OCCUPANCY WITH A DESIGN DENSITY OF .05 GPM/2 SPRINKLERS MAX IN ACCORDANCE WITH 13D (2013 EDITION) AND NFPA 13-11.3.1.1.
- HYDRAULIC CALCULATIONS ARE BASED UPON FLOW DATA PERFORMED BY FLSA ON 04/21/2021 AT 4:00PM. HYDRAULIC CALCULATIONS TO BE BASED ON NFPA 13D (2013 EDITION).
- FIRE SPRINKLER OVERHEAD PIPE AND FITTINGS ARE TO BE CPVC PIPE LISTED FOR FIRE PROTECTION USED UNLESS NOTED OTHERWISE.
- ALL HANGERS TO BE U.L. LISTED FOR FIRE PROTECTION SERVICES. HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH THEIR LISTING. SPACING AND LOCATION TO COMPLY WITH NFPA 13.
- ALL EQUIPMENT TO BE U.L. LISTED FOR FIRE PROTECTION SERVICES AND LISTED IN ACCORDANCE WITH ITS LISTING.
- IN AREAS WHERE WET-TYPE SPRINKLER SYSTEM PIPING HAS BEEN INSTALLED, IT IS THE OWNERS' RESPONSIBILITY TO PROVIDE ADEQUATE HEAT. (AMBIENT TEMPERATURE OF A MINIMUM 40°F)
- ALL DRAINAGE TO COMPLY WITH NFPA 13D AND CONTRACT DOCUMENTS.
- [X'-X'] DENOTES CENTERLINE OF PIPE AFF.
- ALL SPRINKLER HEADS SHALL BE LISTED RESIDENTIAL SPRINKLER HEADS IN ACCORDANCE WITH 7.5.1 OF NFPA 13D.
- FLSA POINT OF CONNECTION IS AT 1'-0" AFF.
- UNDERGROUND PIPING TO BE FLUSHED PRIOR TO SPRINKLER PIPE CONNECTION. FLUSHING IS TO BE COMPLETED BY OTHERS.
- PIPING TO SPRINKLER HEADS 1" CPVC UNLESS OTHERWISE NOTED.

**NOTE:**  
SITE HYDRAULIC REFERENCE PLAN HAS BEEN SHOWN FOR REFERENCE ONLY. ALL UNDERGROUND WORK SHALL BE INSTALLED BY UTILITY CONTRACTOR AND INSTALLED IN ACCORDANCE WITH THE CIVIL SITE UTILITY PLAN. FLSA SHALL BEGIN WORK AT 1'-0" ABOVE FINISHED FLOOR.



**Sprinkler Design Data**

Project Name:	OAKHAVEN LOT 37	System:	WET
Project Street Address:	177 OAKHAVEN DRIVE	Sys. Sq. Ft.:	VARIES
Suite:	-	Floor#:	2
Designed By:	HAILEY WEYANT	Phone:	(919) 872-3250
Occupancy:	RESIDENTIAL	Hazard:	LIGHT/RESIDENTIAL


**Design Summary**

Design Method	RA # 1	RA # 2	RA #	RA #	RA #
Design Area #	REMOTE AREA #1	REMOTE AREA #2	-	-	-
Location	BEDROOM #2	STORAGE	-	-	-
Type of System	WET	WET	-	-	-
Hazard Class	RESIDENTIAL	RESIDENTIAL	-	-	-
Criteria Form	NFPA 13D (2013)	NFPA 13D (2013)	-	-	-
Design Area	1 HEAD	2 HEADS	-	-	-
Sprinkler Spacing	20X20 (400 SF)	16X16 (256 SF)	-	-	-
Density	.05	.05	-	-	-
K-factor	4.9	4.9	-	-	-
Domestic Flow	3 GPM	2 GPM	-	-	-
# Design Sprinklers	1	2	-	-	-
Special Application Spk.	-	-	-	-	-
Requirement @ TEST	24	24	-	-	-
G.P.M. Req'd	22.02 gpm	29.42	-	-	-
P.S.I. Req'd	31.90	30.19	-	-	-
Safety Factor @ TEST	22.41	24.00	-	-	-
Volume of Dry System	-	-	-	-	-

**Water Supply Information**

Tested by	-	Date/Time	4/21/2021	4:00 pm	Pressure Hydrant	4918037
Hydrant Elevation	-	Flow Hydrant	-	-	Static	-
Static (PSI)	54.5	Residual (PSI)	13.5	Flow (GPM)	417	-

Copy of Water Test Data Included with Calculation is required



**TABLE A - CPVC STANDARD SUPPORT SPACING**


NOMINAL SIZE, INCHES	MAX SUPPORT SPACING, FEET
3/4"	5'-0"
1"	6'-0"
1 1/2"	7'-0"
2"	8'-0"
2 1/2"	9'-0"
3"	10'-0"

**TABLE B - MAX SUPPORT SPACING DISTANCE IN LINE SPRINKLER HEAD DROP TEE**

NOMINAL PIPE SIZE, LESS THAN 100 PSI	LESS THAN 100 PSI	MORE THAN 100 PSI
3/4"	4'-0"	3'-0"
1"	5'-0"	4'-0"
1 1/2"	6'-0"	5'-0"
1 1/2" - 3"	7'-0"	7'-0"

**TABLE C - MAX SUPPORT SPACING DISTANCE END SPRINKLER HEAD DROP ELBOW**

NOMINAL PIPE SIZE, LESS THAN 100 PSI	LESS THAN 100 PSI	MORE THAN 100 PSI
3/4"	4'-0"	3'-0"
1"	5'-0"	4'-0"
1 1/2"	6'-0"	5'-0"
1 1/2" - 3"	7'-0"	7'-0"



**NODE LEGEND:**  
UG1 - UG2 = 1-1/4" PVC 55'-0"+/-  
UG2 - UG3 = 6" PVC 1022'-8"+/-  
UG3 - TEST = 6" PVC 1000'-0"+/-

## SITE PLAN - FOR HYDRAULIC REFERENCE ONLY

## SCOPE OF WORK

- FLSA TO BEGIN WORK AT 1'-0" AFF
  - FLSA TO INSTALL AUTOMATIC SPRINKLER SYSTEM UNDER NFPA 13D (2013) TO PROTECT NEW RESIDENTIAL HOME
  - FLSA TO TIE THE NEW SPRINKLER SYSTEM INTO PLUMBING FOR A PASSIVE PURGE SYSTEM.
  - ALL PIPING TO BE CPVC.
  - ALL UNDERGROUND AND RUN-IN BY OTHERS
- THIS FIRE SPRINKLER PLANNING AND DESIGN DRAWING HAS BEEN PREPARED BY FIRE & LIFE SAFETY AMERICA, INC. AS A LICENSED FIRE SPRINKLER CONTRACTOR UNDER ARTICLE 2 OF CHAPTER 87 OR THE GENERAL STATUTES FOR THE STATE OF NORTH CAROLINA.
- EXCLUSIVE USE PURSUANT TO G.S. 89C-25(8) IS FOR FIRE & LIFE SAFETY AMERICA, INC. AND FIRE & LIFE SAFETY AMERICA, INC. SHALL PERFORM ANY AND ALL INSTALLATION WORK AND OTHER WORK PERFORMED IN RELIANCE ON THE DRAWING PURSUANT TO G.S. 85B-15(A)(2).
- INSTALLATION WORK OR ANY OTHER WORK PERFORMED BY ANOTHER PERSON OR ENTITY IN RELIANCE UPON THIS DRAWING OR ANY COPY THEREOF IS STRICTLY PROHIBITED.
- COPYRIGHT FIRE & LIFE SAFETY AMERICA, INC. ALL RIGHTS RESERVED.

**SYSTEM DESIGN CRITERIA**

TYPE SYSTEM:  WET  DRY  DELUGE  NFPA STANDARD:  #13  #13D  #13R  #14  #20  #22  PREACTION  ANTI-FREEZE

OCCUPANCY:  RESIDENTIAL  HAZARD:  LIGHT  PIPE ID REQUIRED:  NO  YES  MAXIMUM SPACING:  VARIES  LOCAL HOSE THREADS:  N.S.T.  SLEEVES REQUIRED:  NO  YES  SPRINKLERS ARE REQUIRED TO BE LOCATED IN THE CENTER OF THE CEILING TILES.

**PIPE TYPES AND FITTING TYPES**

LINE PIPING: CPVC LINE FITTINGS: CPVC  
MAIN PIPING: CPVC MAIN FITTINGS: CPVC

**APPROVING AGENCIES**

APPROVING AUTHORITY: HARNETT COUNTY  
UNDERWRITER: N/A

**GENERAL CONTRACTOR: WATERMARK HOMES**  
ADDRESS: 1303 FT BRAGG ROAD SUITE 201  
CITY & STATE: FAYETTEVILLE, NC 28305  
PHONE NO.: (910) 483-2229  
FAX NO.:

**GENERAL NOTES**

1. Freeze Protection: The owner is responsible for maintaining a min. of 40°F temperature for all wet systems and portions of other systems containing water.
2. M.I.C. Protection: The owner is responsible for all detection testing/prevention.
3. Design is subject to minor deviations arising from field conditions and/or trade coordination. Such deviations shall not affect code compliance or scope of work and shall not require resubmittal except in "as-built" if required by contract documents.
4. Underground piping to ensure lead-in is plumbed, 2-holed, rodded, flushed, thrust blocked and a fully executed underground test certificate required per NFPA to be provided to FLSA prior to connection. FLSA is not responsible for damage to its system or components due to debris entering the system from underground water lines provided by others.
5. This drawing is property of Fire and Life Safety America and is not to be duplicated and/or distributed without written authorization from FLSA.
6. Hydrostatic testing will only be performed with water or air depending on adequate temperature. Any other form of testing is excluded.

**LEGEND**

Symbol	Description
○	Hydraulic Reference Point
○	Elev. Below Top of Steel
○	Elev. Above Finished Floor
+	Elev. Top of Steel
○	Ceiling Height
○	Denotes Hanger Location
○	Denotes Seismic Support
○	Room name or use
○	Sleeve Location
○	FLSA Start Point

**SPRINKLER SUMMARY**

SYMBOL	TYPE	FINISH	TEMP	ORIF.	K*	NPT	MANUF.	SIN#	ESCUTCHEON	QTY
○	RES. PENDENT	WHITE	200°	1/2"	4.9	1/2"	VIKING	VK494	CONCEALED	0
○	#									0
○	DATE									12/20/2021
○	DESCRIPTION									SUBMITTAL TO AHJ
○	BY									HCW
○	TOTAL SPRINKLERS THIS PROJECT									20
○	TOTAL SPRINKLERS THIS DRAWING									0

**REVISIONS**

NO.	DATE	DESCRIPTION	BY
1	12/20/2021	SUBMITTAL TO AHJ	HCW

1721 Round Rock Drive  
Raleigh, NC 27615  
PHONE (919) 872-3250  
FAX (919) 877-8776

**FLSA**  
PROTECTING AMERICA

JONATHAN STELLA  
LEVEL III AUTOMATIC SPRINKLER SYSTEMS  
#11897

NORTH CAROLINA STATE LICENSE #29733

1721 Round Rock Drive  
Raleigh, NC 27615  
PHONE (919) 872-3250  
FAX (919) 877-8776

**FLSA**  
PROTECTING AMERICA

JOB #: 22NC1550  
DATE: 12/19/2021  
DRAWN BY: H. WEYANT  
SCALE: AS NOTED

**HYD. SITE PLAN, GENERAL NOTES & DETAILS**

**OAKHAVEN LOT 37**  
177 OAKHAVEN DR.  
HOLLY SPRINGS, NC 27540

DRAWING #: **FP1**  
OF 2


**NOTES:**

- PORCHES AND GARAGES ARE OMITTED PER NFPA 13D (2013) 8.3.4
- CLOSETS 24 SQ. FT. OR LESS IN AREA ARE UNSPRINKLERED PER NFPA 13D (2013) 8.3.3;
- WALLS AND CEILING TO BE SURFACED WITH NONCOMBUSTIBLE OR LIMITED COMBUSTIBLE MATERIAL AS DEFINED BY NFPA 220
- BATHROOMS 55 SQ. FT. OR LESS IN AREA ARE UNSPRINKLERED PER NFPA 13D (2013) 8.3.2

**SPRINKLER LEGEND**


- NO HEADS REQUIRED
- REMOTE AREA

RA2 - STORAGE  
 Design Area No. 2 - RESIDENTIAL  
 Density .05 Area 2 HEADS  
 Flow 29.42 gpm @ 30.19 psi  
 Includes N/A gpm Hose allowance  
 SAFETY: 24.00



RA1 - BEDROOM #2  
 Design Area No. 1 - RESIDENTIAL  
 Density .05 Area 1 HEADS  
 Flow 23.02 gpm @ 31.90 psi  
 Includes N/A gpm Hose allowance  
 SAFETY: 22.41

**LEVEL 1 - SPRINKLER PLAN**  
 1/4" = 1' - 0"



**LEVEL 2 - SPRINKLER PLAN**  
 1/4" = 1' - 0"

THIS FIRE SPRINKLER PLANNING AND DESIGN DRAWING HAS BEEN PREPARED BY FIRE & LIFE SAFETY AMERICA, INC. AS A LICENSED FIRE SPRINKLER CONTRACTOR UNDER ARTICLE 2 OF CHAPTER 87 OR THE GENERAL STATUTES FOR THE STATE OF NORTH CAROLINA.

EXCLUSIVE USE PURSUANT TO G.S. 89C-25(8) IS FOR FIRE & LIFE SAFETY AMERICA, INC. AND FIRE & LIFE SAFETY AMERICA, INC. SHALL PERFORM ANY AND ALL INSTALLATION WORK AND OTHER WORK PERFORMED IN RELIANCE ON THIS DRAWING PURSUANT TO G.S. 85B-15(A)(2).

INSTALLATION WORK OR ANY OTHER WORK PERFORMED BY ANOTHER PERSON OR ENTITY IN RELIANCE UPON THIS DRAWING OR ANY COPY THEREOF IS STRICTLY PROHIBITED.

COPYRIGHT FIRE & LIFE SAFETY AMERICA, INC. ALL RIGHTS RESERVED.

**APPROVING AGENCIES**

HARNETT COUNTY

UNDERWRITER: N/A

GENERAL CONTRACTOR: WATERMARK HOMES  
 ADDRESS: 1303 FT BRAGG ROAD SUITE 201  
 CITY & STATE: FAYETTEVILLE, NC 28305  
 PHONE NO.: (910) 483-2229  
 FAX NO.:

**GENERAL NOTES**

- Freeze Protection: The owner is responsible for maintaining a min. of 40° F temperature for all wet systems and portions of other systems containing water.
- M.I.C. Protection: The owner is responsible for all detection/testing/prevention.
- Design is subject to minor deviations arising from field conditions and/or trade coordination. Such deviations shall not affect code compliance or scope of work and shall not require resubmittal except in "as-built" if required by contract documents.
- Underground provider to ensure lead-in is plumbed, 2-holed, rodded, flushed, thrust blocked and a fully executed underground test certificate required per NFPA to be provided to FLSA prior to connection. FLSA is not responsible for damage to its system or components due to debris entering the system from underground water lines provided "by others".
- This drawing is property of Fire and Life Safety America and is not to be duplicated and/or distributed without written authorization from FLSA.
- Hydrostatic testing will only be performed with water or air depending on adequate temperature. Any other form of testing is excluded.

**LEGEND**

Symbol	Description
○	Hydraulic Reference Point
●	18" BTS Elev. Below Top of Steel
○	12" AFF Elev. Above Finished Floor
+	TOS 12'-0" Elev. of Top of Steel
○	Ceiling Height
—	Denotes Hanger Location
—	Denotes Seismic Support
□	Room name or use
—	Sleeve Location
○	FLSA Start Point

**SPRINKLER SUMMARY**

SYMBOL	TYPE	FINISH	TEMP	ORIF.	"K"	NPT	MANUF.	SIN#	ESCUTCHEON	QTY.
●	RES. PENDENT	WHITE	200°	1/2"	4.9	1/2"	VIKING	VK494	CONCEALED	20
○	18" BTS									0
○	12" AFF									0
+	TOS 12'-0"									0
○	Ceiling Height									0
—	Denotes Hanger Location									0
—	Denotes Seismic Support									0
□	Room name or use									0
—	Sleeve Location									0
○	FLSA Start Point									0
TOTAL SPRINKLERS THIS PROJECT										20
TOTAL SPRINKLERS THIS DRAWING										20

**REVISIONS**

#	DATE	DESCRIPTION	BY
1	12/20/2021	SUBMITTAL TO AHJ	ICW

GRAPHIC SCALE: 1/8" = 1' - 0"

1721 Round Rock Drive  
 Raleigh, NC 27616  
 PHONE (919) 872-3250  
 FAX (919) 877-0776

**FLSA**  
 FIRE & LIFE SAFETY AMERICA

JONATHAN STELLA  
 LEVEL III AUTOMATIC SPRINKLER SYSTEMS  
 #111897  
 NORTH CAROLINA STATE LICENSE #29733

JOB #: 22NC1550  
 DATE: 12/19/2021  
 DRAWN BY: H.WEYANT  
 SCALE: AS NOTED

**LEVEL 1 & 2 - SPRINKLER PLAN**

**OAKHAVEN LOT 37**  
 177 OAKHAVEN DR.  
 HOLLY SPRINGS, NC 27540

DRAWING #:  
**FP2**  
 OF 2




---

1731 Round Rock Drive, Raleigh, NC 27615 • (919) 872-3250 • fax (919) 877-5775 • [www.flssamerica.com](http://www.flssamerica.com)

# OAKHAVEN LOT 37

## HYDRAULIC CALCULATIONS

12/20/2021



Hydraulic calculations using HydraCALC

Fire & Life Safety America  
1731 Roundrock Drive  
Raleigh, NC 27615  
P: (919) 872-3250  
F: (919) 877-5775

Job Name : Oakhaven Lot 37- Bedroom #2  
Drawing : FP1  
Location : 177 Oakhaven Drive  
Remote Area : RA1  
Contract : 22NC1550  
Data File : RA1- Master Bedroom.WXF

---

**HYDRAULIC CALCULATIONS**  
**for**

**Project name:** Oakhaven Lot 37  
**Location:** 177 Oakhaven Drive  
**Drawing no:** FP1  
**Date:** 12/20/2021

**Design**

**Remote area number:** RA1  
**Remote area location:** Bedroom #2  
**Occupancy classification:** Residential  
**Density:** .05 - Gpm/SqFt  
**Area of application:** 240 - SqFt  
**Coverage per sprinkler:** 400 - SqFt  
**Type of sprinklers calculated:** VK494  
**No. of sprinklers calculated:** 1  
**In-rack demand:** N/A - GPM  
**Hose streams:** 3 - GPM  
**Total water required (including hose streams):** 23.02 - GPM @ 31.90 - Psi  
**Type of system:** WET  
**Volume of dry or preaction system:** N/A - Gal

**Water supply information**

**Date:** 4/21/2021  
**Location:** NC 42, NC 27540  
**Source:** Fire & Life Safety America

**Name of contractor:** Fire & Life Safety America  
**Address:** 1731 Roundrock Drive / Raleigh, NC 27615 / P: (919) 872-3250  
**Phone number:** F: (919) 877-57  
**Name of designer:** H. WEYANT  
**Authority having jurisdiction:** Harnett County  
**Notes: (Include peaking information or gridded systems here.)**


# Water Supply Curve C

Fire & Life Safety America  
Oakhaven Lot 37- Bedroom #2

Page 2  
Date 12/20/2021

City Water Supply:  
C1 - Static Pressure : 54.5  
C2 - Residual Pressure: 13.5  
C2 - Residual Flow : 417

Demand:  
D1 - Elevation : 2.599  
D2 - System Flow : 20.024  
D2 - System Pressure : 31.898  
Hose ( Demand ) : 3  
D3 - System Demand : 23.024  
Safety Margin : 22.409



# Fittings Used Summary

Fire & Life Safety America  
Oakhaven Lot 37- Bedroom #2

Page 3  
Date 12/20/2021

## Fitting Legend

Abbrev.	Name	1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	5	6	8	10	12	14	16	18	20	24
Ball	B Ball Milw BB-SC100			2.25	2	2.5	2.25	10													
E	NFPA 13 90' Standard Elbow	1	2	2	3	4	5	6	7	8	10	12	14	18	22	27	35	40	45	50	61
F	NFPA 13 45' Elbow	1	1	1	1	2	2	3	3	3	4	5	7	9	11	13	17	19	21	24	28
G	NFPA 13 Gate Valve	0	0	0	0	0	1	1	1	1	2	2	3	4	5	6	7	8	10	11	13
N *	CPVC 90'Ell Harvel-Spears		7	7	8	9	11	12	13	0	0	0	0	0	0	0	0	0	0	0	0
O *	CPVC Tee - Branch	3	3	5	6	8	10	12	15	0	0	0	0	0	0	0	0	0	0	0	0
T	NFPA 13 90' Flow thru Tee	3	4	5	6	8	10	12	15	17	20	25	30	35	50	60	71	81	91	101	121

## Units Summary

Diameter Units                   Inches  
Length Units                       Feet  
Flow Units                         US Gallons per Minute  
Pressure Units                   Pounds per Square Inch

Note: Fitting Legend provides equivalent pipe lengths for fittings types of various diameters. Equivalent lengths shown are standard for actual diameters of Sched 40 pipe and CFactors of 120 except as noted with \*. The fittings marked with a \* show equivalent lengths values supplied by manufacturers based on specific pipe diameters and CFactors and they require no adjustment. All values for fittings not marked with a \* will be adjusted in the calculation for CFactors of other than 120 and diameters other than Sched 40 per NFPA.

# Flow Summary - NFPA

Fire & Life Safety America  
Oakhaven Lot 37- Bedroom #2

Page 4  
Date 12/20/2021

## SUPPLY ANALYSIS

<i>Node at Source</i>	<i>Static Pressure</i>	<i>Residual Pressure</i>	<i>Flow</i>	<i>Available Pressure</i>	<i>Total Demand</i>	<i>Required Pressure</i>
TEST	54.5	13.5	417.0	54.307	23.02	31.898

## NODE ANALYSIS

<i>Node Tag</i>	<i>Elevation</i>	<i>Node Type</i>	<i>Pressure at Node</i>	<i>Discharge at Node</i>	<i>Notes</i>
S101	9.0	4.9	16.7	20.02	
101	10.0		16.81		
M101	10.0		18.62		
M102	10.0		21.13		
TOR	8.0		25.5		
BOR	3.0		28.99		
UG1	3.0		29.78	3.0	
UG2	-3.0		34.45		
UG3	-3.0		34.47		
TEST	3.0		31.9		




# Final Calculations : Hazen-Williams

Fire & Life Safety America  
Oakhaven Lot 37- Bedroom #2

Page 5  
Date 12/20/2021

Node1 to Node2	Elev1 Elev2	K Fact	Qa Qt	Nom Act	Fitting or Eqiv	Len	Pipe Ftngs Total	CFact Pf/Ft	Pt Pe Pf	*****	Notes	*****
S101 to 101	9 10	4.90	20.02 20.02	1 1.101	N O	7.0 0.0 0.0	1.000 7.000 8.000	150 0.0681	16.700 -0.433 0.545		Vel = 6.75	
101			0.0 20.02						16.812		K Factor = 4.88	
101 to M101	10 10		20.02 20.02	1 1.101	N O	7.0 5.0 0.0	14.500 12.000 26.500	150 0.0682	16.812 0.0 1.808		Vel = 6.75	
M101 to M102	10 10		0.0 20.02	1 1.101	O O	5.0 0.0 0.0	31.750 5.000 36.750	150 0.0682	18.620 0.0 2.506		Vel = 6.75	
M102 to TOR	10 8		0.0 20.02	1 1.101	2O N	10.0 7.0 0.0	34.500 17.000 51.500	150 0.0682	21.126 0.866 3.512		Vel = 6.75	
TOR			0.0 20.02						25.504		K Factor = 3.96	
TOR to BOR	8 3		20.02 20.02	1 1.101	N Ball	7.0 4.303 0.0	8.000 11.303 19.303	150 0.0682	25.504 2.166 1.316		Vel = 6.75	
BOR to UG1	3 3		0.0 20.02	1 1.101	2E	7.65 0.0 0.0	4.000 7.650 11.650	150 0.0682	28.986 0.0 0.794		Vel = 6.75	
UG1 to UG2	3 -3	H3	3.00 23.02	1.25 1.394	T 2E	9.523 9.523 0.0	55.000 19.046 74.046	150 0.0280	29.780 2.599 2.071		Vel = 4.84	
UG2 to UG3	-3 -3		0.0 23.02	6 6.09	2G 3E 2F	9.25 64.749 21.583	1022.667 95.581 1118.248	150 0	34.450 0.0 0.024		Vel = 0.25	
UG3 to TEST	-3 3		0.0 23.02	6 6.16	T 2E G	48.896 45.637 4.89	1000.000 99.422 1099.422	150 0	34.474 -2.599 0.023		Vel = 0.25	
TEST			0.0 23.02						31.898		K Factor = 4.08	



Hydraulic calculations using HydraCALC

Fire & Life Safety America  
1731 Roundrock Drive  
Raleigh, NC 27615  
P: (919) 872-3250  
F: (919) 877-5775

Job Name : Oakhaven Lot 37 - Storage  
Drawing : FP1  
Location : 177 Oakhaven Dr.  
Remote Area : RA2  
Contract : 22NC1550  
Data File : RA2- Bonus Room.WXF

---

**HYDRAULIC CALCULATIONS**  
**for**

**Project name:** Oakhaven Lot 37  
**Location:** 177 Oakhaven Dr.  
**Drawing no:** FP1  
**Date:** 12/20/2021

**Design**

**Remote area number:** RA2  
**Remote area location:** Storage  
**Occupancy classification:** Residential  
**Density:** .05 - Gpm/SqFt  
**Area of application:** 2 Heads - SqFt  
**Coverage per sprinkler:** 256 - SqFt  
**Type of sprinklers calculated:** VK494  
**No. of sprinklers calculated:** 2  
**In-rack demand:** N/A - GPM  
**Hose streams:** 3 - GPM  
**Total water required (including hose streams):** 29.42 - GPM @ 30.19 - Psi  
**Type of system:** WET  
**Volume of dry or preaction system:** N/A - Gal

**Water supply information**

**Date:** 4/21/2021  
**Location:** NC 42, NC 27540  
**Source:** Fire & Life Safety America

**Name of contractor:** Fire & Life Safety America  
**Address:** 1731 Roundrock Drive / Raleigh, NC 27615 / P: (919) 872-3250  
**Phone number:** F: (919) 877-57  
**Name of designer:** H. WEYANT  
**Authority having jurisdiction:** Harnett County  
**Notes: (Include peaking information or gridded systems here.)**


# Water Supply Curve C

Fire & Life Safety America  
Oakhaven Lot 37 - Storage

Page 2  
Date 9/7/2021

City Water Supply:  
C1 - Static Pressure : 54.5  
C2 - Residual Pressure: 13.5  
C2 - Residual Flow : 417

Demand:  
D1 - Elevation : 6.496  
D2 - System Flow : 26.416  
D2 - System Pressure : 30.192  
Hose ( Demand ) : 3  
D3 - System Demand : 29.416  
Safety Margin : 24.004



# Fittings Used Summary

Fire & Life Safety America  
Oakhaven Lot 37 - Storage

Page 3  
Date 9/7/2021

## Fitting Legend

Abbrev.	Name	1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	5	6	8	10	12	14	16	18	20	24
Ball	B Ball Milw BB-SC100			2.25	2	2.5	2.25	10													
E	NFPA 13 90' Standard Elbow	1	2	2	3	4	5	6	7	8	10	12	14	18	22	27	35	40	45	50	61
F	NFPA 13 45' Elbow	1	1	1	1	2	2	3	3	3	4	5	7	9	11	13	17	19	21	24	28
G	NFPA 13 Gate Valve	0	0	0	0	0	1	1	1	1	2	2	3	4	5	6	7	8	10	11	13
N *	CPVC 90'ElI Harvel-Spears		7	7	8	9	11	12	13	0	0	0	0	0	0	0	0	0	0	0	0
O *	CPVC Tee - Branch	3	3	5	6	8	10	12	15	0	0	0	0	0	0	0	0	0	0	0	0
T	NFPA 13 90' Flow thru Tee	3	4	5	6	8	10	12	15	17	20	25	30	35	50	60	71	81	91	101	121

## Units Summary

Diameter Units                   Inches  
Length Units                       Feet  
Flow Units                         US Gallons per Minute  
Pressure Units                   Pounds per Square Inch

Note: Fitting Legend provides equivalent pipe lengths for fittings types of various diameters. Equivalent lengths shown are standard for actual diameters of Sched 40 pipe and CFactors of 120 except as noted with \*. The fittings marked with a \* show equivalent lengths values supplied by manufacturers based on specific pipe diameters and CFactors and they require no adjustment. All values for fittings not marked with a \* will be adjusted in the calculation for CFactors of other than 120 and diameters other than Sched 40 per NFPA.

**SUPPLY ANALYSIS**

<i>Node at Source</i>	<i>Static Pressure</i>	<i>Residual Pressure</i>	<i>Flow</i>	<i>Available Pressure</i>	<i>Total Demand</i>	<i>Required Pressure</i>
TEST	54.5	13.5	417.0	54.196	29.42	30.192

**NODE ANALYSIS**

<i>Node Tag</i>	<i>Elevation</i>	<i>Node Type</i>	<i>Pressure at Node</i>	<i>Discharge at Node</i>	<i>Notes</i>
S201	18.0	4.9	7.0	12.96	
S202	18.0	4.9	7.54	13.45	
201	19.0		6.81		
202	19.0		7.3		
M201	19.0		8.55		
M202	10.0		14.53		
M203	10.0		16.35		
M204	10.0		17.4		
TOR	8.0		21.17		
BOR	3.0		25.53		
UG1	3.0		26.86	3.0	
UG2	-3.0		32.72		
UG3	-3.0		32.76		
TEST	3.0		30.19		

# Final Calculations : Hazen-Williams

Fire & Life Safety America  
Oakhaven Lot 37 - Storage

Page 5  
Date 9/7/2021

Node1 to Node2	Elev1 Elev2	K Fact	Qa Qt	Nom Act	Fitting or Eqiv	Len	Pipe Ftngs Total	CFact Pf/Ft	Pt Pe Pf	*****	Notes	*****
S201 to 201	18 19	4.90	12.96 12.96	1 1.101	N	7.0 0.0 0.0	1.000 7.000 8.000	150 0.0305	7.000 -0.433 0.244			Vel = 4.37
201			0.0 12.96						6.811			K Factor = 4.97
S202 to 202	18 19	4.90	13.45 13.45	1 1.101	O	5.0 0.0 0.0	1.000 5.000 6.000	150 0.0327	7.536 -0.433 0.196			Vel = 4.53
202			0.0 13.45						7.299			K Factor = 4.98
201 to 202	19 19		12.96 12.96	1 1.101		0.0 0.0 0.0	16.000 0.0 16.000	150 0.0305	6.811 0.0 0.488			Vel = 4.37
202 to M201	19 19		13.46 26.42	1 1.101	O	5.0 0.0 0.0	6.000 5.000 11.000	150 0.1138	7.299 0.0 1.252			Vel = 8.90
M201 to M202	19 10		0.0 26.42	1 1.101	O N	5.0 7.0 0.0	6.250 12.000 18.250	150 0.1139	8.551 3.898 2.078			Vel = 8.90
M202 to M203	10 10		0.0 26.42	1 1.101	N	7.0 0.0 0.0	9.000 7.000 16.000	150 0.1139	14.527 0.0 1.822			Vel = 8.90
M203 to M204	10 10		0.0 26.42	1 1.101	O	5.0 0.0 0.0	4.250 5.000 9.250	150 0.1138	16.349 0.0 1.053			Vel = 8.90
M204 to TOR	10 8		0.0 26.42	1 1.101	O N	5.0 7.0 0.0	13.500 12.000 25.500	150 0.1138	17.402 0.866 2.903			Vel = 8.90
TOR			0.0 26.42						21.171			K Factor = 5.74
TOR to BOR	8 3		26.42 26.42	1 1.101	N Ball	7.0 4.303 0.0	8.000 11.303 19.303	150 0.1138	21.171 2.166 2.197			Vel = 8.90
BOR to UG1	3 3		0.0 26.42	1 1.101	2E	7.65 0.0 0.0	4.000 7.650 11.650	150 0.1138	25.534 0.0 1.326			Vel = 8.90
UG1 to UG2	3 -3	H3	3.00 29.42	1.25 1.394	T 2E	9.523 9.523 0.0	55.000 19.046 74.046	150 0.0440	26.860 2.599 3.259			Vel = 6.18
UG2 to UG3	-3 -3		0.0 29.42	6 6.09	2G 3E 2F	9.25 64.749 21.583	1022.667 95.581 1118.248	150 0	32.718 0.0 0.038			Vel = 0.32
UG3 to TEST	-3 3		0.0 29.42	6 6.16	T 2E G	48.896 45.637 4.89	1000.000 99.422 1099.422	150 0	32.756 -2.599 0.035			Vel = 0.32
TEST			0.0 29.42						30.192			K Factor = 5.35



---

1731 Round Rock Drive, Raleigh, NC 27615 • (919) 872-3250 • fax (919) 877-5775 • [www.flssamerica.com](http://www.flssamerica.com)

# OAKHAVEN LOT 37

## FIRE SPRINKLER PRODUCT DATA

12/20/2021



# Steel Pipe Submittal Data for Fire Sprinkler System

See Chart For Inside Diameters and Wall Thickness

All piping to be one or more of the following: (Refer to checked for submittal items).

- Schedule 40 Steel pipe conforming to ASTM A-135 or A-795 using Cast Iron, Malleable Iron or Ductile Iron screw fittings in accordance with standard ANSI B16.3 or ANSI B16.4. Pipe may also be joined by grooved fittings approved for fire protection use.
- Schedule 7 or 10 Steel Pipe conforming to ASTM A-135 or A-795 using grooved fittings listed for fire protection use.
- All welding will comply with the applicable requirements of AWS B2.1, Specification for Welding Procedure and Performance Qualification. This will be limited to pipe outlets and flanged end treatments.

All materials to be used in the installation of sprinkler system are to conform to NFPA 13, Local Authorities Having Jurisdiction and any applicable referenced codes and standards.

### Steel Pipe Dimensions per NFPA 13:

Pipe		Sch 40		Sch 10		Sch 07	
Nom. Dia.	O.D (in)	I.D. (in)	Wall (in)	I.D. (in)	Wall (in)	I.D. (in)	Wall (in)
1"	1.315	1.049	0.133	1.097	0.109	n/a	n/a
1¼"	1.660	1.380	0.140	1.442	0.109	1.536	0.062
1½"	1.900	1.610	0.145	1.682	0.109	1.728	0.086
2"	2.375	2.067	0.154	2.157	0.109	2.203	0.086
2½"	2.875	2.469	0.203	2.635	0.120	2.703	0.086
3"	3.500	3.068	0.216	3.260	0.120	3.314	0.093
4"	4.500	4.026	0.237	4.260	0.120	4.310	0.095
6"	6.625	6.065	0.280	6.357	0.134	n/a	n/a
8"	8.625	7.981	0.322	8.249	0.188	n/a	n/a
10"	10.750	10.020	0.365	n/a	n/a	n/a	n/a
12"	12.750	11.938	0.406	n/a	n/a	n/a	n/a

**This submittal shall include the following checked items.**

	<i>Domestic</i>	<i>Foreign</i>
<b>Origin of Manufacture</b>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

	<i>Black</i>	<i>Galvanized</i>
<b>Exterior Finish</b>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

	<i>Sch. 40</i>	<i>Sch. 10</i>	<i>Sch. 7</i>
<b>Schedule</b>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

	<i>A-135</i>	<i>A-795</i>	<i>A-53</i>
<b>ASTM</b>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>



## Submittal Data CPVC Pipe and Fittings

### Listings:

- Light hazard occupancies as defined in the standard for “Installation of Sprinkler Systems”, NFPA 13.
- Residential occupancies as defined in the standard for “Installation of Sprinkler Systems in Residential Occupancies up to and Including Four Stories in Height”, NFPA 13R.
- Residential occupancies as defined in the standard for “Installation of Sprinkler Systems in One and Two Family Dwellings and Manufactured Homes”, NFPA 13D. - Underground fire service systems as described in the “Installation of Sprinkler
- Systems”, NFPA 13 2007 Edition, and where appropriate the “Standard for Installation of Private Service Mains & Their Appurtenances”, NFPA 24
- Local Authorities having jurisdiction and any applicable referenced
- codes and standards.

### Approvals:

UL, FM, CUL, NSF, Dade County, LPCB, MEA, and the City of Los Angeles.

### Material Specifications:

Pipe: ASTM F442, SDR 13.5

Fittings: ASTM F438, (Sch. 40) and ASTM F439 (Sch. 80)

Maximum Working Pressure of 175 PSI



Straight Elbow



Reducing Elbow



Straight Tee



Reducing Tee



Cross



Reducing Cross



45 Elbow



Coupling



Sprinkler Adapter  
w/ Brass Insert



Slip-Thread Adapter



Sprinkler Head Adapter 90° Ell



Sprinkler Head Adapter Tee



Back-to-Back Tee



Grooved Coupling Adapter



Reducer Bushing



Cap

### CPVC Pipe Submittal Data for Fire Sprinkler Systems

All material used in the installation of the sprinkler system conforms to:

NFPA 13

NFPA 13R

NFPA 13D



- All CPVC piping should be pressure tested at 200 PSI for 2 hours.
- Chemical compatibility should be checked per manufacturer.
- Glycerin antifreeze solutions are acceptable and installation of antifreeze systems should comply with NFPA Section 7.6.2 of NFPA 13 (2007 Edition).

BlazeMaster® Pipe Dimensions and Weights SDR 13.5 (ASTM F 442)									
Nominal Size		Average OD		Average ID		Pounds Per Foot	Kilograms Per Meter	Pounds Per Foot	Kilograms Per Meter
Inches	mm	Inches	mm	Inches	mm	Empty	Empty	H <sub>2</sub> O Filled	H <sub>2</sub> O Filled
3/4	20.0	1.050	26.7	.874	22.2	0.168	0.250	0.428	0.637
1	25.0	1.315	33.4	1.101	28.0	0.262	0.390	0.675	1.005
1 1/4	32.0	1.660	42.2	1.394	35.4	0.418	0.622	1.079	1.606
1 1/2	40.0	1.900	48.3	1.598	40.6	0.548	0.816	1.417	2.109
2	50.0	2.375	60.3	2.003	50.9	0.859	1.278	2.224	3.310
2 1/2	65.0	2.875	73.0	2.423	61.5	1.257	1.871	3.255	4.844
3	80.0	3.500	88.9	2.950	75.0	1.867	2.778	4.829	7.186

Note: The above average OD and average ID information is per ASTM F442. Check with individual manufacturers for actual OD and ID information.

Allowance for Friction Loss in Fittings (Equivalent Feet of Pipe)								
Fitting Size (In.)	3/4"	1"	1 1/4"	1 1/2"	2"	2 1/2"	3"	
Tee Branch	3	5	6	8	10	12	15	
Elbow 90° *	4	5	6	7	9	12	13	
Elbow 45°	1	1	2	2	2	3	4	
Coupling	1	1	1	1	1	2	2	
Tee Run	1	1	1	1	1	2	2	



## Submittal Data for CPVC Strap Hangers

All materials to be used in the installation of sprinkler system are to conform to NFPA 13, 13R and 13D, Local Authorities having Jurisdiction and any applicable referenced codes and standards.

UL Listed in the USA and Canada to support fire sprinkler piping.


- A “one-hole strap” can function as a hanger and restraining device. It supports CPVC pipe horizontally from top or side of beam. As a restraining device, the hanger will be inverted so the fastener is downward. This installation will prevent upward movement of the sprinkler during activation.
- A “two-hole strap” can function as a hanger and restraining device. It supports CPVC pipe horizontally from top, bottom, or side of beam. A hex-head self-threading screw (furnished with most CPVC hangers) is easily installed using an electric drill. No pre-drilling pilot hole is required.
- A “side-mount strap” supports the CPVC pipe horizontally from top or bottom of beam
- A “stand-off 2-hole strap” supports the CPVC pipe off of the vertical face of the structural or composite wood joists.

Hangers must be clean, free of burrs, and all surface oils. Any contaminants must be removed from the hanger.

The pipe size of the hanger shall be the same size as the supported pipe.

Pipe hangers must have a load bearing surface at least ½” inch wide.

Examples of CPVC Hangers



### This submittal shall include the following checked items:

Product	
<input type="checkbox"/>	¾” Hangers
<input checked="" type="checkbox"/>	1” Hangers
<input type="checkbox"/>	1-1/4” Hangers
<input type="checkbox"/>	1-1/2” Hangers
<input type="checkbox"/>	2” Hangers

Origin of Manufacture	
Domestic	Foreign
<input checked="" type="checkbox"/>	<input type="checkbox"/>



## TECHNICAL DATA

## FREEDOM® RESIDENTIAL CONCEALED PENDENT SPRINKLER VK494 (K4.9)

The Viking Corporation, 210 N Industrial Park Drive, Hastings MI 49058

Telephone: 269-945-9501 Technical Services: 877-384-5464 Fax: 269-818-1680 Email: techsvcs@vikingcorp.com

Visit the Viking website for the latest edition of this technical data page [www.vikinggroupinc.com](http://www.vikinggroupinc.com)

### 1. DESCRIPTION

Viking Freedom® Residential Concealed Pendent Sprinkler VK494 is a small thermosensitive, glass-bulb residential sprinkler designed for installation on concealed pipe systems where the appearance of a smooth ceiling is desired. The orifice design, with a K-factor of 4.9 (70.6 metric\*), allows the sprinkler's efficient use of available water supplies for the hydraulically designed fire-protection system. The fast response glass bulb operating element and special deflector characteristics meet the challenges of residential sprinkler standards.


The sprinkler is pre-assembled with a threaded adapter for installation with a low-profile small-diameter cover assembly installed flush to the ceiling. The two-piece design allows installation and testing of the sprinkler prior to installation of the cover plate. The "push-on" and "thread-on" designs of the concealed cover plate assemblies allow easy installation of the cover plate after the system has been tested and the ceiling finish has been applied, while also providing up to 1/2" (13 mm) of vertical adjustment. The cover assembly can be removed and reinstalled, allowing temporary removal of ceiling panels without taking the sprinkler system out of service or removing the sprinkler. The Electroless Nickel PTFE (ENT) coating has been investigated for installation in corrosive atmospheres and is C-UL-US-EU Listed as indicated in the Approval Charts. The ENT finish is only available for the sprinkler assembly, the cover plate is not plated.

### 2. LISTINGS AND APPROVALS



**cULusEU Listed:** Category VKKW

Refer to the Approval Charts and Design Criteria for C-UL-US-EU Listing requirements that must be followed.



**WARNING:** Cancer and Reproductive Harm-  
[www.P65Warnings.ca.gov](http://www.P65Warnings.ca.gov)

### 3. TECHNICAL DATA

#### Specifications:

Minimum Operating Pressure: Refer to the Approval Chart.

Maximum Working Pressure: 175 psi (12 bar). Factory tested hydrostatically to 500 psi (34.5 bar).

Thread size: 1/2" (15 mm) NPT

Nominal K-factor: 4.9 U.S. (70.6 metric\*)

Glass-bulb fluid temperature rating: to -65 °F (-55 °C)

\* Metric K-factor measurement shown is in Bar. When pressure is measured in kPa, divide the metric K-factor shown by 10.0.

#### Material Standards:

Sprinkler Body: Brass UNS-C84400 or QM Brass

Deflector: Phosphor Bronze UNS-C51000

Deflector Pins: Stainless Steel UNS-S30200

Button: Brass UNS-C36000

Pip Cap and Insert Assembly: Copper UNS-C11000 and Stainless Steel UNS-S30400

Compression Screw: 18-8 Stainless Steel

Yoke: Phosphor Bronze UNS-C51000

Belleville Spring Sealing Assembly: Beryllium Nickel Alloy, coated on both sides with PTFE Tape

Cover Adapter: Cold Rolled Steel UNS-G10080, Finish: Clear Chromate over Zinc Plating

Shipping Cap: High Density Polyethylene

#### Cover Plate Materials:

Cover Plate Assembly: Copper UNS-C11000 and Brass UNS-C26800 or Stainless Steel UNS-S30400

Spring: Beryllium Nickel

Solder: Eutectic

**Ordering Information:** The sprinkler and cover plate must be ordered separately. Refer to Tables 1 and 2.

### 4. INSTALLATION

Refer to appropriate NFPA Installation Standards.

### 5. OPERATION

During fire conditions, when the temperature around the sprinkler approaches the cover plate's nominal temperature rating, the cover plate detaches and releases the deflector. Continued heating of the exposed sprinkler causes the heat-sensitive liquid in the glass bulb to expand. When the temperature reaches the sprinkler's nominal temperature rating, the glass bulb shatters releasing the yoke, pip cap assembly and sealing spring. Water begins flowing through the sprinkler orifice and strikes the deflector forming a uniform spray pattern over a specific area of coverage, which is determined by the water supply pressure at the sprinkler, in order to extinguish or control the fire.



## TECHNICAL DATA

## FREEDOM® RESIDENTIAL CONCEALED PENDENT SPRINKLER VK494 (K4.9)

The Viking Corporation, 210 N Industrial Park Drive, Hastings MI 49058  
 Telephone: 269-945-9501 Technical Services: 877-384-5464 Fax: 269-818-1680 Email: techsvcs@vikingcorp.com  
 Visit the Viking website for the latest edition of this technical data page www.vikinggroupinc.com

### 6. INSPECTIONS, TESTS AND MAINTENANCE

Refer to NFPA 25 for Inspection, Testing and Maintenance requirements.

### 7. AVAILABILITY

Viking Sprinkler Model VK494 is available through a network of domestic and international distributors. See The Viking Corporation web site for the closest distributor or contact The Viking Corporation.

### 8. GUARANTEE

For details of warranty, refer to Viking's current list price schedule or contact Viking directly.

**TABLE 1: SPRINKLER ORDERING INFORMATION**

#### Instructions:

- (1) Select a Sprinkler Base Part Number
- (2) Add the suffix for the desired Finish
- (3) Add the suffix for the desired Sprinkler Temperature Rating
- (4) Order a cover plate (refer to Table 2)

#### Example:

20759AE = 200 °F (93 °C) Temperature Rated Sprinkler with a standard Brass finish.

Sprinkler Base Part Number <sup>1</sup>	Size	1: Finishes		2: Temperature Ratings <sup>7</sup>			
	NPT Inch	Description	Suffix	Nominal Rating	Bulb Color	Max. Ambient Ceiling Temperature <sup>2</sup>	Suffix
20759	1/2	Brass	A	155 °F (68 °C)	Red	100 °F (38 °C)	B
		ENT <sup>5,6</sup>	JN	200 °F (93 °C)	Green	150 °F (65 °C)	E
		<b>Corrosion Resistant Sprinkler Finish: ENT</b>					

#### Accessories

##### Sprinkler Wrenches and tools:

- A. Heavy Duty Part Number: 14047W/B<sup>3</sup> (available since 2006)
- B. Head Cabinet Wrench Part Number: 14031<sup>3,4</sup> (available since 2006)
- C. Optional Concealed Cover Plate Installer Tool Part Number: 14412<sup>8</sup> (available since 2007)
- D. Optional Large Concealed Cover Plate Installer Tool Part No. 14867<sup>8</sup> (available since 2007)

##### Sprinkler Cabinet:

Holds up to 6 sprinklers: Part number 01731A (available since 1971).

#### Footnotes

1. Part number shown is the base part number. For complete part number, refer to the current Viking price list schedule.
2. Based on NFPA 13, NFPA 13R, and NFPA 13D. Other limits may apply, depending on fire loading, sprinkler location, and other requirements of the Authority Having Jurisdiction. Refer to specific installation standards.
3. Requires a 1/2" ratchet (not available from Viking).
4. Also optional for removal of the protective cap. Ideal for sprinkler cabinets.
5. cULus Listed as corrosion resistant.
6. The corrosion resistant coatings have passed the standard corrosion test required by the approving agencies indicated in the Approval Charts. These tests cannot and do not represent all possible corrosive environments. Prior to installation, verify through the end-user that the coatings are compatible with or suitable for the proposed environment. For automatic sprinklers, the ENT coating is applied to all exposed exterior surfaces, including the waterway. For ENT coated sprinklers, the Belleville spring is exposed.
7. The sprinkler temperature rating is stamped on the deflector.
8. The installer tool is for push-on style cover plates only.



## TECHNICAL DATA

## FREEDOM® RESIDENTIAL CONCEALED PENDENT SPRINKLER VK494 (K4.9)

The Viking Corporation, 210 N Industrial Park Drive, Hastings MI 49058  
 Telephone: 269-945-9501 Technical Services: 877-384-5464 Fax: 269-818-1680 Email: techsvcs@vikingcorp.com  
 Visit the Viking website for the latest edition of this technical data page www.vikinggroupinc.com

### TABLE 2: COVER PLATE ORDERING INFORMATION

#### Instructions:

- (1) Select a Cover Plate Base Part Number
- (2) Add the suffix for the desired Finish
- (3) Add the suffix for the required Cover Plate Nominal Rating.

#### Example:

23190MC/W = 165 °F (74 °C) Temperature Rated, 2-3/4" (70 mm) diameter, Thread-On style, Round Cover Plate with a Painted White finish.

1: Select a Cover Plate Base Part Number <sup>3</sup>						2: Select a Finish	
Thread-On Style			Push-On Style			Description	Suffix <sup>5</sup>
Base Part Number <sup>1</sup>	Size Inch (mm)	Type	Base Part Number	Size Inch (mm)	Type		
23190	2-3/4 (70)	Round	23447	2-3/4 (70)	Round	Polished Chrome	F
23174	3-5/16 (84)	Round	23463	3-5/16 (84)	Round	Brushed Chrome	F-/B
23179	3-5/16 (84)	Square	23482	3-5/16 (84)	Square	Bright Brass	B
23193 <sup>5</sup>	2-3/4 (70)	Stainless Steel Round	23455 <sup>5</sup>	2-3/4 (70)	Stainless Steel Round	Antique Brass	B-/A
						Brushed Brass	B-/B
23183 <sup>5</sup>	3-5/16 (84)	Stainless Steel Round	23473 <sup>5</sup>	3-5/16 (84)	Stainless Steel Round	Brushed Copper	E-/B
						Painted White	M-/W
						Painted Ivory	M-/I
						Painted Black	M-/B

3: Temperature Rating Matrix <sup>1,2</sup>				
Cover Plate Nominal Rating (Required)	Temperature Classification	Sprinkler Nominal Rating	Sprinkler Maximum Ambient Ceiling Temperature <sup>2</sup>	Suffix
135 °F (57 °C)	Ordinary	155 °F (68 °C)	100 °F (38 °C)	<b>A</b>
165 °F (74 °C)	Intermediate	200 °F (93 °C)	150 °F (65 °C)	<b>C</b>

#### Footnotes

1. Part number shown is the base part number. For complete part number, refer to the current Viking price list schedule.
2. The sprinkler temperature rating is stamped on the deflector.
3. Based on NFPA-13, NFPA 13R, and NFPA 13D. Other limits may apply, depending on fire loading, sprinkler location, and other requirements of the Authority Having Jurisdiction. Refer to specific installation standards.
4. Where a dash (-) is shown in the Finish suffix designation, insert the desired Temperature Rating suffix. See example above.
5. Stainless Steel versions are not available with any finishes or paint.




## TECHNICAL DATA

## FREEDOM® RESIDENTIAL CONCEALED PENDENT SPRINKLER VK494 (K4.9)

The Viking Corporation, 210 N Industrial Park Drive, Hastings MI 49058  
 Telephone: 269-945-9501 Technical Services: 877-384-5464 Fax: 269-818-1680 Email: techsvcs@vikingcorp.com  
 Visit the Viking website for the latest edition of this technical data page www.vikinggroupinc.com

### Approval Chart Viking VK494, 4.9 K-factor Residential Concealed Pendent Sprinkler

For systems designed to NFPA 13D or NFPA 13R. For systems designed to NFPA 13, refer to the Design Criteria. For Ceiling types refer to current editions of NFPA 13, 13R or 13D

Sprinkler Base Part Number <sup>1</sup>	SIN	NPT Thread Size		Nominal K-factor		Maximum Water Working Pressure
		Inches	mm	U.S.	metric <sup>2</sup>	
20759	VK494	1/2	15	4.9	70.6	175 psi (12 bar)
Max. Coverage Area <sup>6</sup> W X L Ft. X Ft. (m X m)	Flow GPM (LPM)	Pressure PSI (bar)	Deflector to Ceiling	Installation Type	Listings and Approvals <sup>3,5</sup>	Minimum Spacing Ft. (m)
155 °F (68 °C), 200 °F (93 °C) Temperature Rated Sprinklers		Refer to Figure 2			 See Footnotes 8, & 9	
12 X 12 (3.7 X 3.7)	13 (49.2)			7.0 (0.48)		Concealed with Cover Plate Assembly. See Footnote 7.
14 X 14 (4.3 X 4.3)	13 (49.2)	7.0 (0.48)				
16 X 16 (4.9 X 4.9)	13 (49.2)	7.0 (0.48)				
18 X 18 (5.5 X 5.5)	17 (64.4)	12.0 (0.83)				
20 X 20 (6.1 X 6.1)	20 (75.7)	16.7 (1.15)				

#### Footnotes

- Part number shown is the base part number. For complete part number, refer to the current Viking price schedule.
- Metric K-factor measurement shown is when pressure is measured in Bar. When pressure is measured in kPa, divide the metric K-factor shown by 10.0.
- This chart shows the listings and approvals available at the time of printing. Other approvals may be in process. Check with the manufacturer for any additional approvals. Refer also to Design Criteria.
- Listed by Underwriter's Laboratories, Inc. for use in the U.S., Canada, and European Union.
- Meets New York City requirements, effective July 1, 2008.
- For areas of coverage smaller than shown, use the "Flow" and "Pressure" for the next larger area listed. Flows and pressures listed are per sprinkler. The distance from sprinklers to walls shall not exceed one-half the sprinkler spacing indicated for the minimum "Flow" and "Pressure" used.
- Other paint colors are available on request with the same listings as the standard finish colors. Stainless Steel cover plates are not available with any finishes or paint. Listings and approvals apply for any paint manufacturer. Contact Viking for additional information. Custom colors are indicated on a label inside the cover assembly. Refer to Figure 3.
- Accepted Cover Plate Finishes are: Polished Chrome, Brushed Chrome, Bright Brass, Antique Brass, Brushed Brass, Brushed Copper, Painted White, Painted Ivory, or Painted Black.
- C-UL-US-EU Listed as corrosion resistant - Electroless Nickel PTFE (ENT)





**TECHNICAL DATA**

**FREEDOM® RESIDENTIAL CONCEALED PENDENT SPRINKLER VK494 (K4.9)**

The Viking Corporation, 210 N Industrial Park Drive, Hastings MI 49058  
 Telephone: 269-945-9501 Technical Services: 877-384-5464 Fax: 269-818-1680 Email: techsvcs@vikingcorp.com  
 Visit the Viking website for the latest edition of this technical data page www.vikinggroupinc.com

**DESIGN CRITERIA**

(Also refer to the Approval Chart.)

**UL Listing Requirements (C-UL-US-EU):**

When using Viking Residential Concealed Pendent Sprinkler VK494 for systems designed to NFPA 13D or NFPA 13R, apply the listed areas of coverage and minimum water supply requirements shown in the Approval Chart.

For systems designed to NFPA 13: The number of design sprinklers is to be the four contiguous most hydraulically demanding sprinklers. The minimum required discharge from each of the four sprinklers is to be the greater of the following:


- The flow rates given in the Approval Chart for NFPA 13D and NFPA 13R applications for each listed area of coverage, or
- Calculated based on a minimum discharge of 0.1 gpm/sq. ft. over the “design area” in accordance with sections 9.5.2.1 or 10.2.4.1.2 of the current edition of NFPA 13.
- Minimum distance between residential sprinklers: 8 ft. (2.4 m).

**NOTE: Concealed sprinklers must be installed in neutral or negative pressure plenums only.**


**IMPORTANT: Always refer to Bulletin Form No. F\_080415 - Best Practices for Residential Sprinkler Handling and Installation. Also refer to Form No. F\_080614 for general care, installation, and maintenance information. Viking sprinklers are to be installed in accordance with the latest edition of Viking technical data, the appropriate standards of NFPA and any other similar Authorities Having Jurisdiction, and also with the provisions of governmental codes, ordinances, and standards, whenever applicable. Final approval and acceptance of all residential sprinkler installations must be obtained from the Authorities Having Jurisdiction.**

**Sprinkler and Adapter Assembly**

- Protective cap removed
- Use wrench 14047W/B\*\*




**Step 1:**  
 Carefully slide the wrench sideways around the deflector and pins



**Step 2:**  
 Carefully press the wrench upward and turn slightly to ensure engagement with the sprinkler wrench flats.

**NEVER** install the sprinkler by applying the installation wrench across the frame arms. **DO NOT** overtighten. Use only the designated sprinkler wrenches, Viking Part Numbers 14047W/B\*\* or 14031\*\*. A leak tight seal should be achieved by turning the sprinkler clockwise 1 to 1-1/2 turns beyond finger tight.



**Figure 1: Sprinkler Installation and Proper Wrench Usage**  
 \*\* A 1/2" ratchet is required (Not available from Viking)



TECHNICAL DATA

FREEDOM® RESIDENTIAL CONCEALED PENDENT SPRINKLER VK494 (K4.9)

The Viking Corporation, 210 N Industrial Park Drive, Hastings MI 49058  
 Telephone: 269-945-9501 Technical Services: 877-384-5464 Fax: 269-818-1680 Email: techsvcs@vikingcorp.com  
 Visit the Viking website for the latest edition of this technical data page www.vikinggroupinc.com

