





LEFT ELEVATION






<u>FRONT ELEVATION</u> SCALE:1/4"=1'-0"





REAR ELEVATION SCALE:1/8"=1'-0"

RAKE DETAIL FOR GABLE ENDS



- ROOF SHEATHING (SEE SPECIFICATION)





<u>RIGHT ELEVATION</u>


| ATTIC VENTILATION CALCULATIONS |
|--|
| ATTIC AREA <u>2378</u> SQ.FT.(AREA VENTILATION REQUIRED <u>16.6</u> SQ.FT.) |
| EACH ?FT. BASE GABLE LOUVER @ ?SQ.FT. NET FREE AREA EACH ?FT. BASE GABLE LOUVER @ ?SQ.FT. NET FREE AREA |
| EACH _?LOUVER @ _? SQ.FT. NET FREE AREA |
| <u>130</u> LIN.FT. EAVE VENT @ 11 SQ.IN./FT.= <u>9.9</u> SQ.FT.NET FREE AREA <u>102</u> LIN.FT. RIDGE VENT @ 18 SQ.IN./FT.= <u>12.8</u> SQ.FT.NET FREE AREA |












GARAGE PANEL WALL

GARAGE PANEL WALLS UNDER 24" WIDE SHOULD BE EITHER PORTAL FRAMED OR 7/16" OSB ON BOTH SIDES WITH A NAILING PATTERN OF 311 ON ALL PANEL EDGES AND 6" IN THE FIELD,





CRIPPLE WALL

FOUNDATION CRIPPLE WALLS SHALL BE FRAMED OF STUDS NOT SMALLER THAN THE STUDDING ABOVE. WHEN EXCEEDING 4 FT. IN HEIGHT, SUCH WALLS SHALL BE FRAMED OF STUDS HAVING THE SIZE REQUIRED FOR


CRIPPLE WALLS WITH A STUD HEIGHT LESS THAN 14 INCHES SHALL BE CONTINUOUSLY SHEATHED ON ONE SIDE WITH WOOD STRUCTURAL PANELS FASTENED TO BOTH THE TOP AND BOTTOM PLATES IN ACCORDANCE WITH TABLE R602.3(1).

OR CRIPPLE WALLS SHALL BE CONSTRUCTED OF SOLID BLOCKING,










CLEA FOR ALL DO BELOW ALL DO 4' TO ALL DO 8' AND





SECOND FLOOR PLAN SCALE: 1/4"=1'-0"




| VALLS IEADER: | S |
|------------------|-------------------------------|
| NUMBER | OF STUDS |
| 1 | 1 |
| 2 | 2 |
| | |
| | EADER NUMBER JACKS 1 |


UNLESS NOTED OTHER WISE









<u>Truss Placement Plan</u> SCALE: 1/4" = 1'-0"







| | Client: | Watermark Homes | Date: | 3/1/2022 | Page 3 of 14 |
|--------------------------|-----------------------|--------------------------------|-------------------|----------------------|---------------|
| | Project: | | Input by: | Anthony Williams | |
| isDesign | Address: | Lot 35 Oak Haven | Job Name: | Lot 35 Oak Haven | |
| · · · · | | | Project #: | J0322-1085/1086 | |
| BM1 Kerto- | S LVL 1.750 | " X 11.875" 3-Ply | - PASSED | evel: Level | |
| 1 SPF | · · · · · | | · · · | · · · | |
| | i'5 1/4" | ļ | 11'6 3/4" | | 5 1/4" |
| 0 | 55 1/4 | 1 | 110 3/4 | | 5 1/4 |
| 1 | | 18' | | | 1 |
| Multi-Ply Analysis | | | | | |
| Fasten all plies using 2 | rows of 10d Box nails | (.128x3") at 12" o.c Nail from | both sides. Maxin | num end distance not | to exceed |
| 6". | | . , | | | |
| Capacity | 0.0 % | | | | |
| Load | 0.0 PLF | | | | |
| Yield Limit per Foot | 163.7 PLF | | | | |
| Yield Limit per Fastener | 81.9 lb. | | | | |

| Notes | chemicals | 6. For flat roofs provide proper drainage to prevent | Manufacturer Info | Comtech, Inc. 1001 S. Reilly Road, Suite #639 |
|--|--|--|--|--|
| structural adequacy of this component based on the | LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements multi-nly | ponding This design is valid until 3/30/2024 | Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633 | Fayetteville, NC USA 22314 910-864-TRUS |
| | | | | |

Yield Mode

Edge Distance


Min. End Distance

Load Combination Duration Factor IV

3"

1.00

1 1/2"



| | | Client: Water Project: | nark Homes | Date: Input by: | 3/1/2022 Anthony Williams | Page 5 of 1 |
|-----------------------------|-------------|---------------------------|----------------------|---------------------------------|---------------------------------|---|
| 1 | isDesign | | 5 Oak Haven | Job Nam | e: Lot 35 Oak Haven | |
| | Kerto-S LVL | 4 750" V 46 | | Project #: | J0322-1085/1086 Level: Level | |
| BM3 | Rerto-5 LVL | 1.750 X 10 | .000" 2-Ply | PASSED | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| • | | • • • | | • • • | • • • • | · · · · · · · · · · · · · · · · · · · |
| • | | | · · · · | · · · · · | · · · | · · · · · · · · · · · · · · · · · · · |
| 1 SPF | | | | | | |
| | | | 20'4" | | | 1/3 1/2" |
| 1 | | | 20'4" | | | 1 |
| Multi-Ply | y Analysis | | | | | |
| Fasten all | | f 10d Box nails (.128x | 3") at 12" o.c Maxim | um end distance n | ot to exceed 6". | |
| Capacity Load | 0. | 0 % 0 PLF | | | | |
| Yield Limit p | | 45.6 PLF | | | | |
| Yield Limit p Yield Mode | IV | 1.9 lb. | | | | |
| Edge Distan | | 1/2" | | | | |
| Min. End Dis | | , | | | | |
| Load Combi Duration Fac | | 00 | | | | |
| Duration rat | 1. | 00 | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| Notes | | chemicals | 6 For flat reafs are | vide proper drainage to prevent | Manufacturer Info | Comtech, Inc. 1001 S. Bailly Baard, Suite #630 |


| Notes | chemicals | 6. For flat roofs provide proper drainage to prevent | Manufacturer Info | Comtech, Inc. 1001 S. Reilly Road, Suite #639 |
|---|---|--|--|--|
| Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads. Lumber 1. Dry service conditions, unless noted otherwise 2. LVL not to be treated with fire retardant or corrosive | I. LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals Damaged Beams must not be used Design assumes top edge is laterally restrained Design assumes top edge is laterally restrained. Design assumes top edge is laterally restrained. | ponding This design is valid until 3/30/2024 | Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633 | Fayetteville, NC USA 28314 910-864-TRUS |

| | | Client: Wate | ermark Homes | | Date: | 3/1/2022 | , | | | Page 6 of 1 |
|---|--|---|---------------------------------------|-------------------------|--------------------------|----------------------------|--------------------|------------------------|---------------|--------------|
| 2 | | Project: | indik Homes | | Input b | | Williams | | | 1 age 0 of 1 |
| is 🚺 | sDesign | - | 35 Oak Haven | | | ame: Lot 35 O | | | | |
| | | | | | Project | t #: J0322-1 | 085/1086 | | | |
| BM4 | Kerto-S LVL | 1.750" X 1 | 6.000" | 2-Ply - P | ASSED | Level: Level | | | | |
| | | | | , | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | 2 | | | | | | | | | |
| | 1 | | | | | | | | | |
| • | | | | | | | | | | |
| | | | | | | | | | MM | |
| • | and the second second | | • • | | | | | | IĂIĂI | 1'4" |
| | | Martin Ballin | | | | | | | / W V | , |
| 1 SPF | | 2 | SPF | | | | | | | |
| , | | | | | | | | | | |
| | 6'3 1/ | | | | | | | | · ´ 3 | 1/2" |
| 1 | 6'3 1 | /2" | 1 | | | | | | | |
| | | | | | | | | | | |
| Member In | nformation | | | | Reactions U | INPATTERN | NED lb (Uplift) | | | |
| Туре: | Girder | Application: | Roof | | Brg Direction | n Live | Dead | Snow | Wind | Cons |
| Plies: | 2 | Slope: | 0/12 | | 1 Vertical | 1746 | 1471 | 0 | 0 | (|
| Moisture Cor | | Design Metho | | | 2 Vertical | 1746 | 1471 | 0 | 0 | (|
| Deflection LL Deflection TL | | Building Code Load Sharing | | | | | | | | |
| Importance: | Normal - II | Deck: | Not Check | ed | | | | | | |
| Temperature | | Book | | | | | | | | |
| | | | | | Bearings | | | | | |
| | | | | | Bearing Ler | ngth Dir. | Cap. React D/L lb | Total L | d. Case | Ld. Comb |
| | | | | | 1 - SPF 3.50 | 00" Vert | 62% 1471 / 1746 | 3216 L | | D+L |
| | •- | | | | 2 - SPF 3.50 | 00" Vert | 62% 1471 / 1746 | 3216 L | | D+L |
| Analysis Re | | cation Allowed Ca | apacity Comb | . Case | 7 | | | | | |
| Analysis Moment | | | apacity Comb. 27 (13%) D+L | L L | | | | | | |
| Unbraced | | | 223 (22%) D+L | L | | | | | | |
| Shear | | | 32 (13%) D+L | L | | | | | | |
| | | '1 3/4" 0.146 (L/480) 0.0 | | L | | | | | | |
| | | '1 3/4" 0.195 (L/360) 0.1 | . , | L | | | | | | |
| Design No | tes | · · | | | 1 | | | | | |
| | | novement and rotation at the | ne end bearings. I | _ateral support | 4 | | | | | |
| - | | bearings by the building c | | | | | | | | |
| 2 Fasten all to exceed | | Box nails (.128x3") at 12" | o.c. Maximum en | id distance not | | | | | | |
| | | r fasteners required for sp | | | | | | | | |
| | e designed to be supporte must be supported equal | ed on the bottom edge onl | у. | | | | | | | |
| | be laterally braced at end | , , , | | | | | | | | |
| | ust be laterally braced at e | - | | | | | | | | |
| | enderness ratio based on | 8 1 3 | | Deed 0.0 | | Deary 4.45 | Wind 1.C. Conot 1 | 05 Carran | ta | |
| ID | Load Type | Location Trib | | Dead 0.9 | | Snow 1.15 | Wind 1.6 Const. 1 | | | |
| 1 | Uniform | | Тор | 50 PLF | 150 PLF | 0 PLF | | PLF FLOO | к | |
| 2 | Uniform | | Тор | 405 PLF | 405 PLF | 0 PLF | 0 PLF 0 F | PLF J1 | | |
| | Self Weight | | | 12 PLF | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| Notes | | chemicals | 6. F | or flat roofs provide p | roper drainage to prever | Manufactur | er Info | Comtech, Inc. | Road, Suite # | 630 |
| Calculated Structure | d Designs is responsible only of the of this component based on the | Handling & Installation | p | onding | - • | Metsä Wood | | Fayetteville, N USA | IC | |
| design criteria ar responsibility of the | nd loadings shown. It is the customer and/or the contractor to | LVL beams must not be cut or drill Refer to manufacturer's proregarding installation require | oduct information ments, multi-ply | | | Norwalk, CT | | 28314 910-864-TRU | s | |
| ensure the compo | onent suitability of the intended erify the dimensions and loads. | fastening details, beam strength approvals | values, and code | | | (800) 622-58 www.metsav | 350 vood.com/us | | | |
| Lumber 1. Dry service cond | itions, unless noted otherwise | Damaged Beams must not be use Design assumes top edge is latera | ally restrained | | | ICC-ES: ES | | | | |
| 2. LVL not to be tre | eated with fire retardant or corrosive | Provide lateral support at bearin lateral displacement and rotation | | This design is valid | until 3/30/2024 | | | CC | omt | есн |
| ersion 21 20 299 | 9 Powered by iStruct™ Datase | et: embedded | | | | | | | DAW | |


| isDesign | Client: Watermark Hom Project: Address: Lot 35 Oak H | Input b | ame: Lot 35 Oak Haven | Page 7 of 14 |
|---|---|-----------------------------|--|--|
| BM4 Kerto-S LVL | - 1.750" X 16.000" | 2-Ply - PASSED | Level: Level | |
| | · · · · · · · · · · · · · · · · · · · | 7+112" | | 1'4" 1'4" 3 1/2" |
| Multi-Ply Analysis | of 10d Box pails (128x3") at 12 | 2" o.c Maximum end distance | not to exceed 6" | |
| Load0Yield Limit per Foot2Yield Limit per Fastener8Yield ModeINEdge Distance1Min. End Distance3Load Combination3 | 0.0 % 0.0 PLF :45.6 PLF :1.9 lb. V 1/2" ;" | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| Notes Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to | e 1. LVL beams must not be cut or drilled e 2. Refer to manufacturer's product informatio 9 regarding installation requirements, multi-pi | ly | Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 | Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS |
| ensure the component suitability of the intended application, and to verify the dimensions and loads. Lumber 1. Dry service conditions, unless noted otherwise 2. LVL not to be treated with fire retardant or corrosive | fastening details, beam strength values, and cod approvals Damaged Beams must not be used Design assumes top edge is laterally restrained Drevide lateral support at bearing points to avoid | e | (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633 | соттесн |

This design is valid until 3/30/2024

соттесн




| Í | isDesign | Client: Project: Address | | | | me: Lot 35 Oak Haven | Page 9 of 1 |
|-------------------------------------|---|--|--|---|--------------------------------|---|--|
| GDH | Kerto-S I | _VL 1.750 | " X 16.000" | 2-Ply | Project | #: J0322-1085/1086 | |
| | | | | | | | |
| | | | | | | | |
| | • • • | · · · | • • | · · · | · · · | · · · · | · · · [2] [14" |
| | ÞF | · · · | • • | 17'3" | •••• | · · · | 2 SPF |
| <u>/</u> | | | | 17'3" | | | |
| - | y Analysis | (10) 5 | | | | | |
| asten all Capacity oad | I plies using 3 ro | ws of 10d Box na 0.0 % 0.0 PLF | ils (.128x3") at 12' | o.c Maxim | um end distance | not to exceed 6". | |
| ield Limit p | er Foot er Fastener | 245.6 PLF 81.9 lb. | | | | | |
| ield Mode | | IV | | | | | |
| dge Distan lin. End Dis | | 1 1/2" 3" | | | | | |
| oad Combin Ouration Fac | | 1.00 | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| Notes | | chemicals | Uction | For flat roofs prov ponding | vide proper drainage to preven | | Comtech, Inc. 1001 S. Reilly Road, Suite #639 |
| structural adequ design criteria | ctured Designs is responsible or uacy of this component based and loadings shown. It | on the 1. LVL beams must no is the 2. Refer to manu | | ang | | Metsä Wood 301 Merritt 7 Building, 2nd Flo | 20314 |
| responsibility of ensure the co | the customer and/or the cont omponent suitability of the to verify the dimensions and loa | intended fastening details, I | acturer's product information ation requirements, multi-ply beam strength values, and code | | | Norwalk, CT 06851 (800) 622-5850 | 910-864-TRUS |
| Lumber | conditions, unless noted otherwis | Damaged Beams n Design assumes to | p edge is laterally restrained | | | www.metsawood.com/us ICC-ES: ESR-3633 | |
| | be treated with fire retardant or o | | port at bearing points to avoid t and rotation | This design is | valid until 3/30/2024 | | сотесн |
| | 200 Powered by iStruct | | | | | | |



| | • | | Client: | Watermark Homes | 6 | Date: | 3/1/2022 | | Page 11 of 1 |
|---|---|------------------------------------|---|--|-----------------------|--------------------------------|--|------------------------------------|---------------------------------|
| L iel | Docign | | Project: | | | Input b | | | |
| | Design | | Address: | Lot 35 Oak Ha | ven | Job Na Projec | ame: Lot 35 Oak Haven t #: J0322-1085/1086 | | |
| GDH-9 | Korto S | | 1 75 | N" Y Q 250' | ' 2 Dhv | - PASSED | Level: Level | | |
| GDH-9 | Reno-3 | LVL | 1.750 | J A 9.250 | 2-619 | - PASSED | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| • | • | • | • | • | • | • • | • | • | €MM = |
| | | • | • | • | | | | | <u> </u> |
| | • | • | • | • | • | • • | • | | |
| 1 SPF | = | | | | | | | 2 SPF | |
| / | | | | | 10'3" | | | | 3 1/2" |
| <u>/</u> | | | | | 10'3" | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| Multi-Ply A | | | | | | | | | |
| | es using 2 rov | | Box nails | (.128x3") at 12" | o.c Maxim | um end distance | not to exceed 6". | | |
| Capacity Load | | 0.0 % 0.0 PLF | | | | | | | |
| Yield Limit per Fo | oot | 163.7 PL | .F | | | | | | |
| Yield Limit per Fa | astener | 81.9 lb. | | | | | | | |
| Yield Mode Edge Distance | | IV 1 1/2" | | | | | | | |
| Min. End Distanc | e | 3" | | | | | | | |
| Load Combinatio | n | | | | | | | | |
| Duration Factor | | 1.00 | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| Notes | | chor | nicals | | 6. For flat roofe pro | vide proper drainage to prever | Manufacturer Info | Comtech, | Inc. |
| Calculated Structured [| Designs is responsible only f this component based | of the Hand | ling & Installa | | ponding | FF-: aramage to biever | Metsä Wood | Fayetteville | eilly Road, Suite #639 e, NC |
| design criteria and responsibility of the cu | loadings shown. It ustomer and/or the contra | is the 2. Refe | beams must not be to manufact | urer's product information | | | 301 Merritt 7 Building, 2 Norwalk, CT 06851 | nd Floor USA 28314 910-864-T | RUS |
| ensure the compone | nt suitability of the in y the dimensions and load | itended faste s. appi | ening details, bear rovals | n requirements, multi-ply m strength values, and code | | | (800) 622-5850 www.metsawood.com/us | | |
| Lumber | ns, unless noted otherwise | Dan 4. Des | naged Beams must ign assumes top eo | dge is laterally restrained | | | ICC-ES: ESR-3633 | | |
| 2. LVL not to be treate | ed with fire retardant or co | J. FIU | vide lateral suppor al displacement an | rt at bearing points to avoid ad rotation | This design is | valid until 3/30/2024 | | C | отесн |
| V | Doworod by CtructIM | D. I | | | | | | | |


| 2 | • | Client: Project: | Watermark Homes | | Date: Input | | 2022 hony Williams | | | Page 12 o |
|--|---|--|---|-------------------------------------|-------------------------|---|---|---------------|---|-----------|
| lis | Design | Address | Lot 35 Oak Haven | | • | | 35 Oak Have | | | |
| | | | | | Proje | | 22-1085/1086 | 6 | | |
| Sliding D | oor Header | Kerto-S LV | L 1.750" X 11.8 | 375" 2-P | ly - PASSE | D Level: L | _evei | | | |
| 1 | | | 3 | | | | | | | |
| | e d Grain | | 2 SPF End Grain | | | | | | | |
| | | 5'7" | | | | | | | T | 3 1/2" |
| 1 | | 5'7" | | _1 | | | | | | |
| vember Inf | formation | | | | Reactions | ΙΝΡΔΤΤ | FRNFD Ib | (Uplift) | | |
| Туре: | Girder | Арр | ication: Floor | | Brg Directi | | | - | Snow Wind | d Cor |
| Plies: | 2 | | gn Method: ASD | | 1 Vertical | | 684 | 2489 | | D |
| Moisture Conc Deflection LL: | | | ling Code: IBC 2012 I Sharing: No | | 2 Vertical | | 709 | 960 | 0 |) |
| Deflection TL: | | Dec | - | ed | | | | | | |
| Importance: | Normal - II | | | | | | | | | |
| Temperature: | Temp <= 100 | °F | | | Bearings | | | | | |
| | | | | | Bearing Le | ngth Dir | Can | React D/L lb | Total Ld. Case | e Ld. Com |
| | | | | | 1 - SPF 3.0 | - | • | 2489 / 684 | 3173 L | D+L |
| | | | | | End | | | | | |
| Analysis Re | | | | - | Grain 2 - SPF 3.0 | 000" Ver | t 18% | 960 / 709 | 1669 L | D+L |
| Analysis Moment | Actual 2327 ft-lb | Location Allowed 2'5 3/16" 19911 ft- | | | End | | 1070 | 0007700 | | DIE |
| Unbraced | 2327 ft-lb | 2'5 3/16" 15061 ft | | L | Grain | | | | | |
| Shear | 1840 lb | 1'2 7/8" 8867 lb | 0.208 (21%) D+L | L | | | | | | |
| | 0.007 (L/9597) | | 360) 0.038 (4%) L | L | | | | | | |
| TL Defl inch | 0.018 (L/3391) | | 240) 0.071 (7%) D+L | L | | | | | | |
| Design Not | es | | | | 1 | | | | | |
| may also be 2 Fasten all p to exceed 6 3 Refer to las 4 Girders are 5 Top loads n 6 Top must be 7 Bottom must 8 Lateral sign | e required at the inte lies using 2 rows of ". It page of calculation designed to be sup nust be supported e e laterally braced at st be laterally braced derness ratio based | erior bearings by the 10d Box nails (.128x ns for fasteners requi ported on the bottom qually by all plies. end bearings. d at end bearings. d on single ply width. | 3") at 12" o.c. Maximum en ed for specified loads. edge only. | distance not | | | | | | |
| ID | Load Type | Location | | Dead 0.9 | | Snow 1.15 | | .6 Const. 1.2 | | |
| 1 | Part. Uniform | 0-0-0 to 0-9- | · | 125 PLF | | 0 PLF | | | | |
| 2 | Point Bearing Length | 0-9-6 | | 2312 lb | 407 lb | 0 lb | J 0 | lb 0 | lb BM3 Brg 1 | |
| 3 | Bearing Length Part. Uniform | 0-3-1 1-9-8 to 5-7-1 | | 260 PLF | 260 PLF | 0 PLF | = 0 Pl | F 0.PI | LF C2 | |
| 5 | Self Weight | 1-9-0 10 5-7-1 | ιομ | 9 PLF | | UTE | 011 | | | |
| | | | | | | Manuf | acturer Info | | Comtech, Inc. | |
| structural adequacy of design criteria and responsibility of the of ensure the compon- application, and to veri | Designs is responsible only of f this component based or loadings shown. It is ustomer and/or the contract ent suitability of the inte fy the dimensions and loads. | the 2. Refer to manuf tor to regarding installa fastening details, b approvals | lation p be cut or drilled cturer's product information ion requirements, multi-ply aam strength values, and code | for flat roofs provide p oonding | proper drainage to prev | Metsä V 301 Me Norwal (800) 6 www.m | Wood erritt 7 Building k, CT 06851 /22-5850 letsawood.com | | 1001 S. Reilly Road, Suit Fayetteville, NC USA 28314 910-864-TRUS | e #639 |
| | ons, unless noted otherwise | 5. Provide lateral sup | edge is laterally restrained port at bearing points to avoid | | | | 6: ESR-3633 | | com | есн |
| LVL not to be treat | ted with fire retardant or corr | osive lateral displacement | | This design is valio | d until 3/30/2024 | | | | | |



| | | | Manufacturer Info | Comtech, Inc. |
|--|---|---|--|---|
| Notes Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads. Lumber 1. Dry service conditions, unless noted otherwise 2. LVL not to be treated with fire retardant or corrosive | I. LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals Damaged Beams must not be used Design assumes top edge is laterally restrained Design lateral suprod at bearing cortex to avoid | For flat roofs provide proper drainage to prevent ponding This design is valid until 3/30/2024 | Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633 | 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-884-TRUS |


CSD BUILD

| | | | Client: | Watermark Homes | | | te: | 3/1/2022 | Page 14 |
|----------------------------------|--|---|--|---------------------------------------|-----------------------------|-----------------|---------------------|--|---|
| | isDe | sign | Project: Address: | Lot 35 Oak Hav | en | - | out by: b Name: | Anthony Williams Lot 35 Oak Haven | |
| | | | , | Lot 55 Oak Hav | en | | oject #: | J0322-1085/1086 | |
| C1 | Anthe | ony Power | Column | 5.500" 2 | X 7.000" - | PASSE | D L | evel: Level | |
| | | | | Design | Method: ASD | | | Design OK. | |
| | | | | Building | |)12 | | Design Notes | |
| | | | | Importar | | | | 1. Axial load eccentricity of 1/6 cross-section axes, each axis | |
| | 0-5 | i-8 _ [0-7-0 | | Applicati | | in Free Standin | g | 2. Designed in accordance with | |
| | | | | Load Sh | Condition: Dry aring: No | | | IBC 2012. 3. Top and bottom ends of the r | member must be |
| | | | | | ang. No | | | supported to prevent lateral r 4. Holes and notches are not al | movement and rotation. |
| | | 0.4.0 | | | | | | | |
| | | 8-1-8 | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| nalys | sis | | | | | | Desigr | Properties | |
| lenderr | | Actual 17.7 | Allowed 50.0 | Capacity 35% | Load C | ombination | E: Ey: | 1900000 Fc: 2300 1900000 Fv: 0 | |
| xial (lb. | | 12263 | 71395 | 17% | D+L | | Fb: | 2100 Fvy: 0 | |
| | | | | | D+L | | TD. | | |
| | Bending | 0.20 | 1 | 20% | D+L | | Fby: | 2300 | |
| earing | SPF (lb.) | | | 20% 75% | | | | - | |
| earing L Defle | SPF (lb.) | 0.20 12348 0.056 (in.) L/1731 | 1 16363 | 20% 75% | D+L D+L | | | - | |
| earing L Defle Appl | SPF (lb.) | 0.20 12348 0.056 (in.) L/1731 | 1 16363 | 20% 75% | D+L D+L L | Const. 1.25 | Fby: | 2300 | |
| earing L Defle Appl | SPF (lb.) ection | 0.20 12348 0.056 (in.) L/1731 | 1 16363 0.271 (in.) L/36 | 20% 75% 0 21% | D+L D+L L | Const. 1.25 | Fby: | 2300 | |
| earing L Defle Appl | SPF (lb.) ection | 0.20 12348 0.056 (in.) L/1731 | 1 16363 0.271 (in.) L/36 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Comr | 2300 | |
| earing _ Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| earing _ Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| earing Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| earing Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| earing Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| aring Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| earing Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| aring Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| aring Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| aring Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| earing Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| earing _ Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| earing _ Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| earing _ Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| earing _ Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com | 2300 | |
| earing _ Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com BM1 | 2300 ments | |
| earing L Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Com BM1 | 2300 ments Manufacturer Info Anthony Forest Products Co 200 | Zomtech, Inc. 1001 S. Reilly Road, Suite #639 Tayetteville, NC ISA |
| earing L Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Comr BM1 | 2300 ments | Comtech, Inc. 001 S. Reilly Road, Suite #639 ayettevile, NC JSA 28314 110-864-TRUS |
| Bearing L Defle | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | | Fby: Comr BM1 | 2300 ments | JSA 28314 |
| earing L Defle Appl | SPF (lb.) ection ied Load Load Type | 0.20 12348 0.056 (in.) L/1731 S e Location | 1 16363 0.271 (in.) L/36 Dead 0.9 | 20% 75% 0 21% Live 1 Snow 1. | D+L D+L L | 0 lb | Fby: Comr BM1 | 2300 ments Manufacturer Info Anthony Forest Products Co 309 North Washington El Dorado, AR 71730 800) 221-2326 | JSA 28314 |



FLSA Start Point

TOTAL SPRINKLERS THIS PROJECT



LINE PIPING: CPVC

MAIN PIPING: CPVC

LINE FITTINGS: CPVC

MAIN FITTINGS: CPVC

CITY & STATE: FAYETTEVILLE, NC 28305

PHONE NO.: (910) 483-2229

FAX NO.:

| GENERAL NOTES |] | LEGEND | | S P I | RINK | LER SU | J M M A R Y | - | | | | 0 | 2 4 8 | 16 | RICHMOND, VA CHESA | APEAKE, VA ROANOKE, VA SPRINGFIELD, VA ORLANDO, FL | |
|---|-------------|---------------------------|--------------|-------------------|----------|---------|-------------|------------|--------------------|------|-------------------------|------------|---------------------------------|-----|--|--|--------------|
| 1. Freeze Protection: The owner is responsible for maintaining a min. of 40° F | Symbol | Description | SYM TYPE | FINISH TEM | P ORIF. | "K" NP | T MANUF. | SIN# | ESCUTCHEON | QTY. | | | GRAPHIC SCALE: $1/4$ " = 1'- 0" | | HOUSTON, TX CHARLOTTE, NC RAL | SAN ANTONIO, TX DALLAS, TX AUSTIN, FL LEIGH, NC BALTIMORE, MD ATLANTA, GA | |
| temperature for all wet systems and portions of other systems containing water. 2. M.I.C. Protection: The owner is responsible for all detection/testing/prevention. | \bigcirc | Hydraulic Reference Point | RES. PENDENT | WHITE 200 | ° 1/2" | 4.9 1/2 | " VIKING | VK494 | CONCEALED | 20 | | | REVISIONS | | | | |
| 3 Design is subject to minor deviations arising from field conditions and/or trade | [* 18" BTS | Elev. Below Top of Steel | | 0 | | | | | | 0 | # | DATE | DESCRIPTION | BY | 1731 Round Rock Drive Raleigh, NC 27615 | | |
| coordination. Such deviations shall not affect code compliance or scope of work and shall not require resubmittal except in "as-built" if required by contract documents. | | | | 0 | | | | | | 0 | Λ | 12/21/2021 | SUBMITTAL TO AHJ | RCC | PHONE (919) 872-325 FAX (919) 877-5775 | | |
| 4. Underground provider to ensure lead-in is plumbed, 2-holed, rodded, flushed, | | Elev. of Top of Steel | | • | | | | | | 0 | $\overline{\mathbb{A}}$ | | | | | FIRE & LIFE SAFETY AMERICA PROTECT | TING AMERICA |
| thrust blocked and a fully executed underground test certificate required per NFPA to be provided to FLSA prior to connection. FLSA is not responsible for damage to | (10-0) | Ceiling Height | | • | | | | | | 0 | $\overline{\mathbb{A}}$ | | | | JOB #: 22NC1557 | LEVEL 1 & 2 FIRE PROTECTION PLANS | DRAWING #: |
| its system or components due to debris entering the system from underground water | | Denotes Hanger Location | | ° | - | | | | | 0 | $\frac{233}{4}$ | | | | DATE: 12/21/2021 | | |
| lines provided "by others". 5. This drawing is property of Fire and Life Safety America and is not to be | 4 | Denotes Seismic Support | ┨──┤───── | | - | | | | | 0 | $\frac{74}{\Delta}$ | | | | DATE: 12/21/2021 | OAKHAVEN LOT 35 | |
| duplicated and/or distributed without written authorization from FLSA. | DESCRIPTION | Room name or use | ┣─┼──── | l | | | _ | | | | $\frac{72}{\sqrt{2}}$ | | | | DRAWN BY: R. COLLINS | 49 BUCKHAVEN DR. | |
| 6. Hydrostatic testing will only be performed with water or air depending on adequate temperature. Any other form of testing is excluded. | = | Sleeve Location | | ° | | | | | | 0 | <u>/6\</u> | | | | | | OF 2 |
| | • | FLSA Start Point | TOTAI | L SPRINKLERS THIS | S PROJEC | T 20 | Т | OTAL SPRIN | KLERS THIS DRAWING | G 20 | \triangle | | | | SCALE: AS NOTED | HOLLY SPRINGS, NC 27540 | |

SPRINKLER LEGEND

NO HEADS REQUIRED REMOTE AREA



JONATHAN STEBILA LEVEL III AUTOMATIC SPRINKLER SYSTEMS #111897

NORTH CAROLINA STATE LICENSE #29733




1731 Round Rock Drive, Raleigh, NC 27615 • (919) 872-3250 • fax (919) 877-5775 • www.flsamerica.com

OAK HAVEN LOT 35

HYDRAULIC CALCULATIONS

12/22/2021



Hydraulic calculations using HydraCALC

FIRE & LIFE SAFETY AMERICA 1731 ROUND ROCK DRIVE RALEIGH, NC 27615 919-872-3250

Job Name:OAK HAVEN LOT 35Drawing:FP1Location:49 BUCKHAVEN DR.Remote Area:RA1Contract:22NC1557Data File:RA1.WXF

HYDRAULIC CALCULATIONS for

Project name: OAK HAVEN LOT 35 - RA1 Location: 49 BUCKHAVEN DR. Drawing no: FP1 Date: 12/21/2021

Design


Remote area number:RA1Remote area location:BEDROOM #2Occupancy classification:RESIDENTIALDensity:.05 - Gpm/SqFtArea of application:2 HEADS - SqFtCoverage per sprinkler:256 - SqFtType of sprinklers calculated:VK494No. of sprinklers calculated:2In-rack demand:N/A - GPMHose streams:3 - GPMTotal water required (including hose streams):29.000 - GPM@ 29Type of system:WET CPVC 13DVolume of dry or preaction system:N/A - Gal

@ 29.526 - Psi

Water supply information

Date: 4/21/2021 Location: NC42, NC 27540 Source: FIRE & LIFE SAFETY AMERICA

Name of contractor: FIRE & LIFE SAFETY AMERICA Address: 1731 ROUND ROCK DRIVE / RALEIGH, NC 27615 / 919-872-3250 Phone number: (919) 872-3250 Name of designer: R. COLLINS Authority having jurisdiction: HARNETT COUNTY Notes: (Include peaking information or gridded systems here.)



Computer Programs by Hydratec Inc. Revision: 50.53.5

Water Supply Curve C

FIRE & LIFE SAFETY AMERICA OAK HAVEN LOT 35

Fittings Used Summary

| FIRE & LIFE SAFETY AMERICA | |
|----------------------------|--|
| OAK HAVEN LOT 35 | |

| Fitting Lo | egend | | | | | | | | | | | | | | | | | | | | |
|------------|----------------------------|-----|-----|---|----|----|----|------|----|------|----|----|----|----|----|----|----|----|----|-----|-----|
| Abbrev. | Name | 1/2 | 3/4 | 1 | 1¼ | 1½ | 2 | 21⁄2 | 3 | 31⁄2 | 4 | 5 | 6 | 8 | 10 | 12 | 14 | 16 | 18 | 20 | 24 |
| F | NFPA 13 90' Standard Elbow | 1 | 2 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 10 | 12 | 14 | 18 | 22 | 27 | 35 | 40 | 45 | 50 | 61 |
| F | NFPA 13 45' Elbow | 1 | 1 | 1 | 1 | 2 | 2 | 3 | 3 | 3 | 4 | 5 | 7 | 9 | 11 | 13 | 17 | 19 | 21 | 24 | 28 |
| G | NFPA 13 Gate Valve | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 1 | 1 | 2 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 10 | 11 | 13 |
| N * | CPVC 90'Ell Harvel-Spears | | 7 | 7 | 8 | 9 | 11 | 12 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 0 * | CPVC Tee - Branch | 3 | 3 | 5 | 6 | 8 | 10 | 12 | 15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Т | NFPA 13 90' Flow thru Tee | 3 | 4 | 5 | 6 | 8 | 10 | 12 | 15 | 17 | 20 | 25 | 30 | 35 | 50 | 60 | 71 | 81 | 91 | 101 | 121 |

Units Summary

| Diameter Units | Inches |
|----------------|------------------------|
| Length Units | Feet |
| Flow Units | US Gallons per Minute |
| Pressure Units | Pounds per Square Inch |

Note: Fitting Legend provides equivalent pipe lengths for fittings types of various diameters. Equivalent lengths shown are standard for actual diameters of Sched 40 pipe and CFactors of 120 except as noted with *. The fittings marked with a * show equivalent lengths values supplied by manufacturers based on specific pipe diameters and CFactors and they require no adjustment. All values for fittings not marked with a * will be adjusted in the calculation for CFactors of other than 120 and diameters other than Sched 40 per NFPA.

Flow Summary - NFPA

FIRE & LIFE SAFETY AMERICA OAK HAVEN LOT 35

Page 4 Date 12/22/2021

| Node at Source | Static Pressure | Residual Pressure | Flow | Available Pressure | Total Demand | Required Pressure |
|-------------------|--------------------|----------------------|-------|-----------------------|--------------|-------------------|
| TEST | 54.5 | 13.5 | 417.0 | 54.204 | 29.0 | 29.526 |

NODE ANALYSIS

| Node Tag | Elevation | Node Type | Pressure at Node | Discharge at Node | Notes |
|----------|-----------|-----------|---------------------|----------------------|-------|
| A1 | 22.0 | 4.9 | 7.08 | 13.04 | |
| A2 | 22.0 | 4.9 | 7.0 | 12.96 | |
| 101 | 22.0 | | 7.31 | | |
| 102 | 22.0 | | 7.23 | | |
| 103 | 22.0 | | 7.48 | | |
| 104 | 22.0 | | 9.47 | | |
| 105 | 11.0 | | 15.45 | | |
| M1 | 11.0 | | 16.31 | | |
| M2 | 11.0 | | 18.14 | | |
| TOR | 11.0 | | 19.85 | | |
| BOR | 3.0 | | 24.98 | | |
| UG1 | 3.0 | | 26.27 | 3.0 | |
| UG2 | -3.0 | | 32.04 | | |
| UG3 | -3.0 | | 32.05 | | |
| UG4 | -3.0 | | 32.09 | | |
| TEST | 3.0 | | 29.53 | | |

Final Calculations : Hazen-Williams

Κ

Qa

Nom Fitting

FIRE & LIFE SAFETY AMERICA OAK HAVEN LOT 35

Node1 Elev1

| Node1 | Eleví | ĸ | Qa | Nom | Fitting | | Pipe | CFact | Pt Pe | ****** Notoo | ***** |
|-------------|----------|------|---------------------|--------|------------|------------------|------------------------|---------------|-----------------|------------------|-------|
| to Node2 | Elev2 | Fact | Qt | Act | or Eqiv | Len | Ftngs Total | Pf/Ft | Pe Pf | ******* Notes | |
| | | | | | | | | | | | |
| A1 | 22 | 4.90 | 13.04 | 1 | N | 7.0 | 0.500 | 150 | 7.077 | | |
| to | | | | | | 0.0 | 7.000 | | 0.0 | | |
| 101 | 22 | | 13.04 | 1.101 | | 0.0 | 7.500 | 0.0308 | 0.231 | Vel = 4.39 | |
| 101 | | | 0.0 13.04 | | | | | | 7.308 | K Factor = 4.82 | |
| A2 | 22 | 4.90 | 12.96 | 1 | N | 7.0 | 0.500 | 150 | 7.000 | | |
| to | | | 10.00 | | | 0.0 | 7.000 | | 0.0 | | |
| 102 | 22 | | 12.96 | 1.101 | | 0.0 | 7.500 | 0.0305 | 0.229 | Vel = 4.37 | |
| 102 | | | 0.0 12.96 | | | | | | 7.229 | K Factor = 4.82 | |
| 101 | 22 | | 13.04 | 1 | | 0.0 | 5.583 | 150 | 7.308 | | |
| to | 22 | | 10.04 | 1 101 | | 0.0 | 0.0 | 0.0240 | 0.0 | $\lambda = 4.20$ | |
| 103 | 22 | | <u>13.04</u> 0.0 | 1.101 | | 0.0 | 5.583 | 0.0310 | 0.173 | Vel = 4.39 | |
| 103 | | | 13.04 | | | | | | 7.481 | K Factor = 4.77 | |
| 102 | 22 | | 12.96 | 1 | 0 | 5.0 | 3.250 | 150 | 7.229 | | |
| to | | | | • | • | 0.0 | 5.000 | | 0.0 | | |
| 103 | 22 | | 12.96 | 1.101 | | 0.0 | 8.250 | 0.0305 | 0.252 | Vel = 4.37 | |
| 103 | 22 | | 13.04 | 1 | | 0.0 | 18.000 | 150 | 7.481 | | |
| to 104 | 22 | | 26.0 | 1.101 | | 0.0 0.0 | 0.0 18.000 | 0.1105 | 0.0 1.989 | Vel = 8.76 | |
| 104 | 22 | | 0.0 | 1 | | 0.0 | 11.000 | 150 | 9.470 | VCI - 0.70 | |
| to | | | 0.0 | • | | 0.0 | 0.0 | 100 | 4.764 | | |
| 105 | 11 | | 26.0 | 1.101 | | 0.0 | 11.000 | 0.1106 | 1.217 | Vel = 8.76 | |
| 105 | 11 | | 0.0 | 1 | 0 | 5.0 | 2.750 | 150 | 15.451 | | |
| to M1 | 11 | | 26.0 | 1.101 | | 0.0 0.0 | 5.000 7.750 | 0.1105 | 0.0 0.856 | Vel = 8.76 | |
| M1 | 11 | | 0.0 | 1.101 | | 0.0 | 16.583 | 150 | 16.307 | VCI 0.70 | |
| to | •• | | 0.0 | • | | 0.0 | 0.0 | 100 | 0.0 | | |
| M2 | 11 | | 26.0 | 1.101 | | 0.0 | 16.583 | 0.1106 | 1.834 | Vel = 8.76 | |
| M2 | 11 | | 0.0 | 1 | Ν | 7.0 | 8.500 | 150 | 18.141 | | |
| to TOR | 11 | | 26.0 | 1.101 | | 0.0 0.0 | 7.000 15.500 | 0.1105 | 0.0 1.713 | Vel = 8.76 | |
| | | | 0.0 | 1.101 | | 0.0 | 10.000 | 0.1100 | 1.1.10 | 101 0.10 | |
| TOR | | | 26.00 | | | | | | 19.854 | K Factor = 5.84 | |
| TOR | 11 | | 26.00 | 1 | Ν | 7.0 | 8.000 | 150 | 19.854 | | |
| to | 2 | | 26.0 | 1.101 | | 0.0 0.0 | 7.000 | 0 1105 | 3.465 | Vel = 8.76 | |
| BOR BOR | 3 3 | | 26.0 0.0 | 1.101 | 2E | 7.65 | <u>15.000</u> 4.000 | 0.1105 150 | 1.658 24.977 | ver = 0.70 | |
| to | 3 | | 0.0 | I | 20 | 0.0 | 7.650 | 150 | 0.0 | | |
| UG1 | 3 | | 26.0 | 1.101 | | 0.0 | 11.650 | 0.1106 | 1.288 | Vel = 8.76 | |
| UG1 | 3 | H3 | 3.00 | 1.25 | Т | 9.523 | 55.000 | 150 | 26.265 | | |
| to | 2 | | 20.0 | 1 20 4 | 2E | 9.523 | 19.046 | 0.0400 | 2.599 | $\lambda = 0.10$ | |
| UG2 | -3 -3 | | 29.0 | 1.394 | | 0.0 | 74.046 | 0.0429 | 3.175 | Vel = 6.10 | |
| UG2 to | -3 | | 0.0 | 6 | 3E 2F | 64.749 21.583 | 326.000 86.332 | 150 | 32.039 0.0 | | |
| ŬG3 | -3 | | 29.0 | 6.09 | | 0.0 | 412.332 | 0 | 0.013 | Vel = 0.32 | |
| UG3 | -3 | | 0.0 | 6 | 2G | | 1149.000 | 150 | 32.052 | | |
| to | 2 | | 20.0 | 6.00 | 3F | 32.374 | 41.623 | 0 | 0.0 | $V_{0} = 0.22$ | |
| UG4 | -3 | | 29.0 | 6.09 | | 0.0 | 1190.623 | 0 | 0.039 | Vel = 0.32 | |

Pipe

CFact

Pt


Page Date

5

12/22/2021

Final Calculations : Hazen-Williams

| | FIRE & LIFE SAFETY AMERICA OAK HAVEN LOT 35 | | | | | | | | | Page 6 Date 12/22/2021 | | | | |
|-------------|--|------|-------|------|---------------|--------|---------------|-------|----------|---------------------------|-------|-------|--|--|
| Node1 to | Elev1 | К | Qa | Nom | Fitting or | | Pipe Ftngs | CFact | Pt Pe | ***** | Notes | ***** | | |
| Node2 | Elev2 | Fact | Qt | Act | Eqiv | Len | Total | Pf/Ft | Pf | | | | | |
| | | | | | | | | | | | | | | |
| UG4 | -3 | | 0.0 | 6 | T | | 1000.000 | 150 | 32.091 | | | | | |
| to | | | | | 2E | 45.637 | 99.422 | | -2.599 | | | | | |
| TEST | 3 | | 29.0 | 6.16 | G | 4.89 | 1099.422 | 0 | 0.034 | Vel = 0.3 | 1 | | | |
| | | | 0.0 | | | | | | | | | | | |
| TEST | | | 29.00 | | | | | | 29.526 | K Factor = | 5.34 | | | |



Hydraulic calculations using HydraCALC

FIRE & LIFE SAFETY AMERICA 1731 ROUND ROCK DRIVE RALEIGH, NC 27615 919-872-3250

Job Name:OAK HAVEN LOT 35 - RA2Drawing:FP1Location:49 BUCKHAVEN DR.Remote Area:RA2Contract:22NC1557Data File:RA2.WXF

HYDRAULIC CALCULATIONS for

Project name: OAK HAVEN LOT 35 - RA2 Location: 49 BUCKHAVEN DR. Drawing no: FP1 Date: 12/21/2021


Design

Remote area number: RA2 Remote area location: BEDROOM #2 Occupancy classification: RESIDENTIAL Density: .05 - Gpm/SqFt Area of application: 2 HEADS - SqFt Coverage per sprinkler: 324 - SqFt Type of sprinklers calculated: VK494 No. of sprinklers calculated: 2 *In-rack demand:* N/A - GPM Hose streams: 3 - GPM Total water required (including hose streams): 37.116 - GPM @ 34.223 - Psi Type of system: WET CPVC 13D Volume of dry or preaction system: N/A - Gal

Water supply information

Date: 4/21/2021 Location: NC42, NC 27540 Source: FIRE & LIFE SAFETY AMERICA

Name of contractor: FIRE & LIFE SAFETY AMERICA Address: 1731 ROUND ROCK DRIVE / RALEIGH, NC 27615 / 919-872-3250 **Phone number:** (919) 872-3250 Name of designer: R. COLLINS Authority having jurisdiction: HARNETT COUNTY Notes: (Include peaking information or gridded systems here.)



FIRE & LIFE SAFETY AMERICA OAK HAVEN LOT 35 - RA2

Water Supply Curve C

Page 2 Date 12/22/2021

Fittings Used Summary

FIRE & LIFE SAFETY AMERICA OAK HAVEN LOT 35 - RA2

| Fitting Le | egend | | | | | | | | | | | | | | | | | | | | |
|------------|----------------------------|-----|-----|---|----|----|----|------|----|------|----|----|----|----|----|----|----|----|----|-----|-----|
| Abbrev. | | 1/2 | 3/4 | 1 | 1¼ | 1½ | 2 | 21⁄2 | 3 | 31⁄2 | 4 | 5 | 6 | 8 | 10 | 12 | 14 | 16 | 18 | 20 | 24 |
| | | | | | | | | | | | | | | | | | | | | | |
| E | NFPA 13 90' Standard Elbow | 1 | 2 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 10 | 12 | 14 | 18 | 22 | 27 | 35 | 40 | 45 | 50 | 61 |
| F | NFPA 13 45' Elbow | 1 | 1 | 1 | 1 | 2 | 2 | 3 | 3 | 3 | 4 | 5 | 7 | 9 | 11 | 13 | 17 | 19 | 21 | 24 | 28 |
| G | NFPA 13 Gate Valve | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 1 | 1 | 2 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 10 | 11 | 13 |
| N * | CPVC 90'Ell Harvel-Spears | | 7 | 7 | 8 | 9 | 11 | 12 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 0 * | CPVC Tee - Branch | 3 | 3 | 5 | 6 | 8 | 10 | 12 | 15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ť | NFPA 13 90' Flow thru Tee | 3 | 4 | 5 | 6 | 8 | 10 | 12 | 15 | 17 | 20 | 25 | 30 | 35 | 50 | 60 | 71 | 81 | 91 | 101 | 121 |

Units Summary

| Inches |
|------------------------|
| Feet |
| US Gallons per Minute |
| Pounds per Square Inch |
| |

Note: Fitting Legend provides equivalent pipe lengths for fittings types of various diameters. Equivalent lengths shown are standard for actual diameters of Sched 40 pipe and CFactors of 120 except as noted with *. The fittings marked with a * show equivalent lengths values supplied by manufacturers based on specific pipe diameters and CFactors and they require no adjustment. All values for fittings not marked with a * will be adjusted in the calculation for CFactors of other than 120 and diameters other than Sched 40 per NFPA.

Flow Summary - NFPA

| FIRE & LIFE SAFETY AMERICA |
|----------------------------|
| OAK HAVEN LOT 35 - RA2 |

Page 4 Date 12/22/2021

| SUPPLY ANALYSIS | | | | | | | | |
|-------------------|--------------------|----------------------|-------|-----------------------|--------------|-------------------|--|--|
| Node at Source | Static Pressure | Residual Pressure | Flow | Available Pressure | Total Demand | Required Pressure | | |
| TEST | 54.5 | 13.5 | 417.0 | 54.033 | 37.12 | 34.223 | | |

NODE ANALYSIS

| Node Tag | Elevation | Node Type | Pressure at Node | Discharge at Node | Notes |
|----------|-----------|-----------|---------------------|----------------------|-------|
| B1 | 11.0 | 4.9 | 12.24 | 17.14 | |
| B2 | 11.0 | 4.9 | 12.0 | 16.97 | |
| 201 | 11.0 | | 12.62 | | |
| 202 | 11.0 | | 12.38 | | |
| 203 | 11.0 | | 12.9 | | |
| M2 | 11.0 | | 17.91 | | |
| TOR | 11.0 | | 20.74 | | |
| BOR | 3.0 | | 26.95 | | |
| UG1 | -3.0 | | 31.67 | 3.0 | |
| UG2 | -3.0 | | 36.68 | | |
| UG3 | -3.0 | | 36.71 | | |
| UG4 | -3.0 | | 36.77 | | |
| TEST | 3.0 | | 34.22 | | |

Final Calculations : Hazen-Williams

FIRE & LIFE SAFETY AMERICA OAK HAVEN LOT 35 - RA2

| Node1 to | Elev1 | К | Qa | Nom | Fitting or | | Pipe Ftngs | CFact | Pt Pe | ****** Notes | ***** |
|-------------|----------|------|---------------------|-------|---------------|------------------|--------------------|--------|------------------|-----------------|-------|
| Node2 | Elev2 | Fact | Qt | Act | Eqiv | Len | Total | Pf/Ft | Pf | Notes | |
| | | | | | | | | | | | |
| B1 | 11 | 4.90 | 17.14 | 1 | N | 7.0 | 0.500 | 150 | 12.239 | | |
| to | | 4.50 | | | IN | 0.0 | 7.000 | | 0.0 | | |
| 201 | 11 | | 17.14 | 1.101 | | 0.0 | 7.500 | 0.0512 | 0.384 | Vel = 5.78 | |
| 201 | | | 0.0 17.14 | | | | | | 12.623 | K Factor = 4.82 | |
| B2 | 11 | 4.90 | 16.97 | 1 | Ν | 7.0 | 0.500 | 150 | 12.000 | | |
| to 202 | 11 | | 16.97 | 1.101 | | 0.0 0.0 | 7.000 7.500 | 0.0503 | 0.0 0.377 | Vel = 5.72 | |
| | | | 0.0 | 1.101 | | 0.0 | 1.000 | 0.0000 | 0.011 | VGI 0.72 | |
| 202 | | | 16.97 | | | | | | 12.377 | K Factor = 4.82 | |
| 201 to | 11 | | 17.14 | 1 | | 0.0 0.0 | 5.500 0.0 | 150 | 12.623 0.0 | | |
| 203 | 11 | | 17.14 | 1.101 | | 0.0 | 5.500 | 0.0511 | 0.281 | Vel = 5.78 | |
| 202 | | | 0.0 | | | | | | 12.004 | K Faster - 477 | |
| 203 202 | 11 | | 17.14 16.97 | 1 | 0 | 5.0 | 5.500 | 150 | 12.904 12.377 | K Factor = 4.77 | |
| to | | | | | Ũ | 0.0 | 5.000 | | 0.0 | | |
| 203 | 11 | | 16.97 | 1.101 | | 0.0 | 10.500 | 0.0502 | 0.527 | Vel = 5.72 | |
| 203 | | | 0.0 16.97 | | | | | | 12.904 | K Factor = 4.72 | |
| 203 | 11 | | 34.12 | 1 | 0 | 5.0 | 22.375 | 150 | 12.904 | | |
| to M2 | 11 | | 34.12 | 1.101 | | 0.0 0.0 | 5.000 27.375 | 0.1828 | 0.0 5.003 | Vel = 11.50 | |
| M2 | 11 | | 0.0 | 1 | N | 7.0 | 8.500 | 150 | 17.907 | | |
| to | 11 | | 24 12 | 1 101 | | 0.0 | 7.000 | 0 1007 | 0.0 | $V_{0} = 11.50$ | |
| TOR | 11 | | <u>34.12</u> 0.0 | 1.101 | | 0.0 | 15.500 | 0.1827 | 2.832 | Vel = 11.50 | |
| TOR | | | 34.12 | | | | | | 20.739 | K Factor = 7.49 | |
| TOR | 11 | | 34.12 | 1 | Ν | 7.0 0.0 | 8.000 7.000 | 150 | 20.739 3.465 | | |
| to BOR | 3 | | 34.12 | 1.101 | | 0.0 | 15.000 | 0.1827 | 3.403 2.741 | Vel = 11.50 | |
| BOR | 3 | | 0.0 | 1 | 2E | 7.65 | 4.000 | 150 | 26.945 | | |
| to UG1 | -3 | | 34.12 | 1.101 | | 0.0 0.0 | 7.650 11.650 | 0.1827 | 2.599 2.129 | Vel = 11.50 | |
| UG1 | -3 | H3 | 3.00 | 1.25 | Т | 9.523 | 55.000 | 150 | 31.673 | | |
| to UG2 | -3 | | 37.12 | 1.394 | 2E | 9.523 0.0 | | 0.0677 | 0.0 5.012 | Vel = 7.80 | |
| UG2 | -3 | | 0.0 | 6 | 3E | 64.749 | 74.046 | 150 | 36.685 | ver = 7.00 | |
| to | | | | | 2F | 21.583 | 86.332 | | 0.0 | | |
| UG3 UG3 | -3 -3 | | 37.12 | 6.09 | 20 | 0.0 | 412.332 | 0.0001 | 0.021 | Vel = 0.41 | |
| to | -3 | | 0.0 | 6 | 2G 3F | 9.25 32.374 | | 150 | 36.706 0.0 | | |
| UG4 | -3 | | 37.12 | 6.09 | _ | 0.0 | 1190.623 | 0.0001 | 0.062 | Vel = 0.41 | |
| UG4 to | -3 | | 0.0 | 6 | T 2E | 48.896 45.637 | 1000.000 99.422 | 150 | 36.768 -2.599 | | |
| TEST | 3 | | 37.12 | 6.16 | G | 4.89 | 1099.422 | 0 | 0.054 | Vel = 0.40 | |
| TEST | | | 0.0 37.12 | | | | | | 34.223 | K Factor = 6.35 | |
| | | | . | | | | | | J | 0.00 | |

Page Date

5

12/22/2021

Final Calculations : Hazen-Williams

FIRE & LIFE SAFETY AMERICA

| FIRE & LIFE SAF OAK HAVEN LO | | CA | | | | | | | Page Date | 6 12/22 | /2021 |
|----------------------------------|-----------|----------|------------|-----------------------|-----|------------------------|----------------|----------------|--------------|------------|-------|
| Node1 Elev1 to Node2 Elev2 | K Fact | Qa Qt | Nom Act | Fitting or Eqiv | Len | Pipe Ftngs Total | CFact Pf/Ft | Pt Pe Pf | ***** | Notes | ***** |



1731 Round Rock Drive, Raleigh, NC 27615 • (919) 872-3250 • fax (919) 877-5775 • www.flsamerica.com

OAK HAVEN LOT 35

FIRE SPRINKLER PRODUCT DATA

12/21/2021

Steel Pipe Submittal Data for Fire Sprinkler System

See Chart For Inside Diameters and Wall Thickness

All piping to be one or more of the following: (Refer to checked for submittal items).

- Schedule 40 Steel pipe conforming to ASTM A-135 or A-795 using Cast Iron, Malleable Iron or Ductile Iron screw fittings in accordance with standard ANSI B16.3 or ANSI B16.4. Pipe may also be joined by grooved fittings approved for fire protection use.
- Schedule 7 or 10 Steel Pipe conforming to ASTM A-135 or A-795 using grooved fittings listed for fire protection use.
- All welding will comply with the applicable requirements of AWS B2.1, Specification for Welding Procedure and Performance Qualification. This will be limited to pipe outlets and flanged end treatments.

All materials to be used in the installation of sprinkler system are to conform to NFPA 13, Local Authorities Having Jurisdiction and any applicable referenced codes and standards.

| Pip | e | Scl | n 40 | Sc | h 10 | Sc | h 07 |
|------|--------|-----------|-----------|-----------|-----------|-----------|-----------|
| Nom. | O.D | | | | | | |
| Dia. | (in) | I.D. (in) | Wall (in) | I.D. (in) | Wall (in) | I.D. (in) | Wall (in) |
| 1" | 1.315 | 1.049 | 0.133 | 1.097 | 0.109 | n/a | n/a |
| 1¼" | 1.660 | 1.380 | 0.140 | 1.442 | 0.109 | 1.536 | 0.062 |
| 1½" | 1.900 | 1.610 | 0.145 | 1.682 | 0.109 | 1.728 | 0.086 |
| 2" | 2.375 | 2.067 | 0.154 | 2.157 | 0.109 | 2.203 | 0.086 |
| 2½" | 2.875 | 2.469 | 0.203 | 2.635 | 0.120 | 2.703 | 0.086 |
| 3" | 3.500 | 3.068 | 0.216 | 3.260 | 0.120 | 3.314 | 0.093 |
| 4" | 4.500 | 4.026 | 0.237 | 4.260 | 0.120 | 4.310 | 0.095 |
| 6" | 6.625 | 6.065 | 0.280 | 6.357 | 0.134 | n/a | n/a |
| 8" | 8.625 | 7.981 | 0.322 | 8.249 | 0.188 | n/a | n/a |
| 10" | 10.750 | 10.020 | 0.365 | n/a | n/a | n/a | n/a |
| 12" | 12.750 | 11.938 | 0.406 | n/a | n/a | n/a | n/a |

Steel Pipe Dimensions per NFPA 13:

This submittal shall include the following checked items.

| | Dome | stic | Foreign | | Black | Galv | anized |
|--------------------------|---------|-------|----------|--------------------|-------|-------|--------|
| Origin of Manufacture | | | | Exterior Finish | | | |
| | Sch. 40 | Sch.1 | 10 Sch.7 | | A-135 | A-795 | A-53 |
| Schedule | | | | ASTM | | | |



Submittal Data CPVC Pipe and Fittings

Listings:

- Light hazard occupancies as defined in the standard for "Installation of Sprinkler Systems", NFPA 13.
- Residential occupancies as defined in the standard for "Installation of Sprinkler Systems in Residential Occupancies up to and Including Four Stories in Height", NFPA 13R.
- Residential occupancies as defined in the standard for "Installation of Sprinkler Systems in One and Two Family Dwellings and Manufactured Homes", NFPA 13D.- Underground fire service systems as described in the "Installation of Sprinkler
- Systems", NFPA 13 2007 Edition, and where appropriate the "Standard for Installation of Private Service Mains & Their Appurtenances", NFPA 24
- Local Authorities having jurisdiction and any applicable referenced
- codes and standards.

Approvals:

UL, FM, CUL, NSF, Dade County, LPCB, MEA, and the City of Los Angeles.

Material Specifications:

Pipe: ASTM F442, SDR 13.5 Fittings: ASTM F438, (Sch. 40) and ASTM F439 (Sch. 80) Maximum Working Pressure of 175 PSI



Straight Elbow



Reducing Elbow

45 Elbow



Straight Tee



Reducing Tee



Cross



-



Sprinkler Adapter w/ Brass Insert



Slip-Thread Adapter

Reducing Cross



Sprinkler Head Adapter 90° Ell



Reducer Bushing



Sprinkler Head Adapter Tee





Back-to Back Tee

Grooved Coupling Adapter



Cap

CPVC Pipe Submittal Data for Fire Sprinkler Systems

All material used in the installation of the sprinkler system conforms to:



- All CPVC piping should be pressure tested at 200 PSI for 2 hours.
- Chemical compatibility should be checked per manufacturer.
- Glycerin antifreeze solutions are acceptable and installation of antifreeze systems should comply with NFPA Section 7.6.2 of NFPA 13 (2007 Edition).

| | | | BlazeN | | e Dimensi .5 (ASTM F | ons and Wei 442) | ghts | | |
|---------------|------|--------|---------------|--------|-------------------------|------------------------|--------------------|-------------------------|-------------------------|
| Nomir Size | | | orage Average | | Pounds Per Foot | Kilograms Per Meter | Pounds Per Foot | Kilograms Per Meter | |
| Inches | mm | Inches | mm | Inches | mm | Empty | Empty | H ₂ O Filled | H ₂ O Filled |
| 3/4 | 20.0 | 1.050 | 26.7 | .874 | 22.2 | 0.168 | 0.250 | 0.428 | 0.637 |
| 1 | 25.0 | 1.315 | 33.4 | 1.101 | 28.0 | 0.262 | 0.390 | 0.675 | 1.005 |
| 11/4 | 32.0 | 1.660 | 42.2 | 1.394 | 35.4 | 0.418 | 0.622 | 1.079 | 1.606 |
| 11/2 | 40.0 | 1.900 | 48.3 | 1.598 | 40.6 | 0.548 | 0.816 | 1.417 | 2.109 |
| 2 | 50.0 | 2.375 | 60.3 | 2.003 | 50.9 | 0.859 | 1.278 | 2.224 | 3.310 |
| 21/2 | 65.0 | 2.875 | 73.0 | 2.423 | 61.5 | 1.257 | 1.871 | 3.255 | 4.844 |
| 3 | 80.0 | 3.500 | 88.9 | 2.950 | 75.0 | 1.867 | 2.778 | 4.829 | 7.186 |

Note: The above average OD and average ID information is per ASTM F442. Check with individual manufacturers for actual OD and ID information.

| | Allo | | Friction Lo lent Feet o | | ngs | | |
|--------------------|------|----|----------------------------|-----|-----|-------|----|
| Fitting Size (In.) | 34" | 1" | 1½" | 1½" | 2" | 21/2" | 3" |
| Tee Branch | 3 | 5 | 6 | 8 | 10 | 12 | 15 |
| Elbow 90° * | 4 | 5 | 6 | 7 | 9 | 12 | 13 |
| Elbow 45° | 1 | 1 | 2 | 2 | 2 | 3 | 4 |
| Coupling | 1 | 1 | 1 | 1 | 1 | 2 | 2 |
| Tee Run | 1 | 1 | 1 | 1 | 1 | 2 | 2 |



Submittal Data for CPVC Strap Hangers

All materials to be used in the installation of sprinkler system are to conform to NFPA 13, 13R and 13D, Local Authorities having Jurisdiction and any applicable referenced codes and standards.

UL Listed in the USA and Canada to support fire sprinkler piping.

- A "one-hole strap" can function as a hanger and restraining device. It supports CPVC pipe horizontally from top or side of beam. As a restraining device, the hanger will be inverted so the fastener is downward. This installation will prevent upward movement of the sprinkler during activation.
- A "two-hole strap" can function as a hanger and restraining device. It supports CPVC pipe horizontally from top, bottom, or side of beam. A hex-head self-threading screw (furnished with most CPVC hangers) is easily installed using an electric drill. No pre-drilling pilot hole is required.
- A "side-mount strap" supports the CPVC pipe horizontally from top or bottom of beam
- A "stand-off 2-hole strap" supports the CPVC pipe off of the vertical face of the structural or composite wood joists.

Hangers must be clean, free of burrs, and all surface oils. Any contaminants must be removed from the hanger.

The pipe size of the hanger shall be the same size as the supported pipe. Pipe hangers must have a load bearing surface at least $\frac{1}{2}$ " inch wide.

Examples of CPVC Hangers

| 1-Hole Strap | 2-Hole Strap | Side-Mount Strap | Stand-Off 2-Hole Strap |
|--------------|--------------|------------------|------------------------|

This submittal shall include the following checked items:

| □ ¾" Hangers ☑ 1" Hangers | Product | | | | | | | | | |
|---|---------|--|--|--|--|--|--|--|--|--|
| | | | | | | | | | | |
| | | | | | | | | | | |
| □ 1-1/4" Hangers | | | | | | | | | | |
| □ 1-1/2" Hangers | | | | | | | | | | |
| 2" Hangers | | | | | | | | | | |

| Origin of M | anufacture |
|-------------|------------|
| Domestic | Foreign |
| \boxtimes | |

NIKING°

TECHNICAL DATA

FREEDOM® RESIDENTIAL CONCEALED PENDENT SPRINKLER VK494 (K4.9)

The Viking Corporation, 210 N Industrial Park Drive, Hastings MI 49058 Telephone: 269-945-9501 Technical Services: 877-384-5464 Fax: 269-818-1680 Email: techsvcs@vikingcorp.com Visit the Viking website for the latest edition of this technical data page www.vikinggroupinc.com

1. DESCRIPTION

Viking Freedom[®] Residential Concealed Pendent Sprinkler VK494 is a small thermosensitive, glass-bulb residential sprinkler designed for installation on concealed pipe systems where the appearance of a smooth ceiling is desired. The orifice design, with a K-factor of 4.9 (70.6 metric*), allows the sprinkler's efficient use of available water supplies for the hydraulically designed fire-protection system. The fast response glass bulb operating element and special deflector characteristics meet the challenges of residential sprinkler standards.

The sprinkler is pre-assembled with a threaded adapter for installation with a low-profile small-diameter cover assembly installed flush to the ceiling. The twopiece design allows installation and testing of the sprinkler prior to installation of the cover plate. The "push-on" and "thread-on" designs of the concealed cover plate assemblies allow easy installation of the cover plate after the system has been tested and the ceiling finish has been applied, while also providing up to 1/2" (13 mm) of vertical adjustment. The cover assembly can be removed and reinstalled, allowing temporary removal of ceiling panels without taking the sprinkler system out of service or removing the sprinkler. The Electroless Nickel PTFE (ENT) coating has been investigated for installation in corrosive atmospheres and is C-UL-US-EU Listed as indicated in the Approval Charts. The ENT finish is only unside for the sprinkler charts and the sprinkler charts and the sprinkler charts. available for the sprinkler assembly, the cover plate is not plated.

2. LISTINGS AND APPROVALS

cULusEU Listed: Category VKKW

Refer to the Approval Charts and Design Criteria for C-UL-US-EU Listing requirements that must be followed.



3. TECHNICAL DATA

c(VL)us

Specifications: Minimum Operating Pressure: Refer to the Approval Chart. Maximum Working Pressure: 175 psi (12 bar). Factory tested hydrostatically to 500 psi (34.5 bar). Thread size: 1/2" (15 mm) NPT Nominal K-factor: 4.9 U.S. (70.6 metric*) Glass-bulb fluid temperature rating: to -65 °F (-55 °C) Metric K-factor measurement shown is in Bar. When pressure is measured in kPa, divide the metric K-factor shown by 10.0. Material Standards:

Sprinkler Body: Brass UNS-C84400 or QM Brass Deflector: Phosphor Bronze UNS-C51000 Deflector Pins: Stainless Steel UNS-S30200 Button: Brass UNS-C36000 Pip Cap and Insert Assembly: Copper UNS-C11000 and Stainless Steel UNS-S30400 Compression Screw: 18-8 Stainless Steel Yoke: Phosphor Bronze UNS-C51000 Belleville Spring Sealing Assembly: Beryllium Nickel Alloy, coated on both sides with PTFE Tape Cover Adapter: Cold Rolled Steel UNS-G10080, Finish: Clear Chromate over Zinc Plating Shipping Cap: High Density Polyethylene **Cover Plate Materials:** Cover Plate Assembly: Copper UNS-C11000 and Brass UNS-C26800 or Stainless Steel UNS-S30400 Spring: Beryllium Nickel

Solder: Eutectic

Ordering Information: The sprinkler and cover plate must be ordered separately. Refer to Tables 1 and 2.

4. INSTALLATION

Refer to appropriate NFPA Installation Standards.

5. OPERATION

During fire conditions, when the temperature around the sprinkler approaches the cover plate's nominal temperature rating, the cover plate detaches and releases the deflector. Continued heating of the exposed sprinkler causes the heat-sensitive liquid in the glass bulb to expand. When the temperature reaches the sprinkler's nominal temperature rating, the glass bulb shatters releasing the yoke, pip cap assembly and sealing spring. Water begins flowing through the sprinkler orifice and strikes the deflector form-ing a uniform spray pattern over a specific area of coverage, which is determined by the water supply pressure at the sprinkler, in order to extinguish or control the fire.



FREEDOM[®] RESIDENTIAL CONCEALED PENDENT SPRINKLER VK494 (K4.9)

The Viking Corporation, 210 N Industrial Park Drive, Hastings MI 49058

Telephone: 269-945-9501 Technical Services: 877-384-5464 Fax: 269-818-1680 Email: techsvcs@vikingcorp.com Visit the Viking website for the latest edition of this technical data page www.vikinggroupinc.com

6. INSPECTIONS, TESTS AND MAINTENANCE

Refer to NFPA 25 for Inspection, Testing and Maintenance requirements.

7. AVAILABILITY

Viking Sprinkler Model VK494 is available through a network of domestic and international distributors. See The Viking Corporation web site for the closest distributor or contact The Viking Corporation.

8. GUARANTEE

For details of warranty, refer to Viking's current list price schedule or contact Viking directly.

TABLE 1: SPRINKLER ORDERING INFORMATION

Instructions:

(1) Select a Sprinkler Base Part Number

(2) Add the suffix for the desired Finish

(3) Add the suffix for the desired Sprinkler Temperature Rating

(4) Order a cover plate (refer to Table 2)

Example:

20759AE = 200 °F (93 °C) Temperature Rated Sprinkler with a standard Brass finish.

| Sprinkler | Size | 1: Finishes | | 2: Temperature Ratings ⁷ | | | | | | |
|----------------------------------|-------------|--------------------------------------|--------|-------------------------------------|------------|--|--------|--|--|--|
| Base Part Number ¹ | NPT Inch | Description | Suffix | Nominal Rating | Bulb Color | Max. Ambient Ceiling Temperature ² | Suffix | | | |
| 20759 | 1/2 | Brass | Α | 155 °F (68 °C) | Red | 100 °F (38 °C) | В | | | |
| | | ENT ^{5,6} | JN | 200 °F (93 °C) | Green | 150 °F (65 °C) | E | | | |
| | | Corrosion Resis Sprinkler Finish: | | | | | | | | |

Accessories

Sprinkler Wrenches and tools:

- A. Heavy Duty Part Number: 14047W/B³ (available since 2006)
- B. Head Cabinet Wrench Part Number: 14031^{3,4} (available since 2006)
- C. Optional Concealed Cover Plate Installer Tool Part Number: 144128 (available since 2007)

D. Optional Large Concealed Cover Plate Installer Tool Part No. 14867⁸ (available since 2007)

Sprinkler Cabinet:

Holds up to 6 sprinklers: Part number 01731A (available since 1971).

Footnotes

- 1. Part number shown is the base part number. For complete part number, refer to the current Viking price list schedule.
- 2. Based on NFPA 13, NFPA 13R, and NFPA 13D. Other limits may apply, depending on fire loading, sprinkler location, and other requirements of the Authority Having Jurisdiction. Refer to specific installation standards.
- 3. Requires a 1/2" ratchet (not available from Viking).
- 4. Also optional for removal of the protective cap. Ideal for sprinkler cabinets.
- ^{5.} cULus Listed as corrosion resistant.
- 6. The corrosion resistant coatings have passed the standard corrosion test required by the approving agencies indicated in the Approval Charts. These tests cannot and do not represent all possible corrosive environments. Prior to installation, verify through the end-user that the coatings are compatible with or suitable for the proposed environment. For automatic sprinklers, the ENT coating is applied to all exposed exterior surfaces, including the waterway. For ENT coated sprinklers, the Belleville spring is exposed.

7. The sprinkler temperature rating is stamped on the deflector.

8. The installer tool is for push-on style cover plates only.



FREEDOM[®] RESIDENTIAL CONCEALED PENDENT SPRINKLER VK494 (K4.9)

The Viking Corporation, 210 N Industrial Park Drive, Hastings MI 49058

Telephone: 269-945-9501 Technical Services: 877-384-5464 Fax: 269-818-1680 Email: techsvcs@vikingcorp.com Visit the Viking website for the latest edition of this technical data page www.vikinggroupinc.com

TABLE 2: COVER PLATE ORDERING INFORMATION

Instructions:

(1) Select a Cover Plate Base Part Number

(2) Add the suffix for the desired Finish

(3) Add the suffix for the required Cover Plate Nominal Rating.

Example:

23190MC/W = 165 °F (74 °C) Temperature Rated, 2-3/4" (70 mm) diameter, Thread-On style, Round Cover Plate with a Painted White finish.

| | 1: Sele | ect a Cover Pla | ate Base Par | t Number ³ | | 2: Select a Fini | sh | |
|----------------------------------|-------------------|-----------------|---------------------|------------------------|------------------------------|------------------|---------|--|
| Т | hread-On St | yle | | Push-On St | yle | | | |
| Base Part Number ¹ | Size Inch (mm) | Туре | Base Part Number | Size Inch (mm) Type | | Description | Suffix⁵ | |
| 23190 | 2-3/4 (70) | Round | 23447 | 2-3/4 (70) | Round | Polished Chrome | F | |
| 23174 | 3-5/16 (84) | Round | 23463 | 3-5/16 (84) | Round | Brushed Chrome | F-/B | |
| 23179 | 3-5/16 (84) | Square | 23482 | 3-5/16 (84) | Square | Bright Brass | В | |
| 231935 | 2 2/4 (70) | Stainless | 23455⁵ | 004555 0.044 (70) | | Antique Brass | B-/A | |
| 23193 | 2-3/4 (70) | Steel Round | 23433° | 2-3/4 (70) | Steel Round | Brushed Brass | B-/B | |
| 004005 | 2 5/4 6 (04) | Stainless | 004705 | 2 5/40 (04) | Stainless | Brushed Copper | E-/B | |
| 231835 | 3-5/16 (84) | Steel Round | 234735 | 3-5/16 (84) | Steel Round | Painted White | M-/W | |
| | • | | | | | Painted Ivory | M-/I | |
| | | | | | | Painted Black | M-/B | |
| | | | 3: Т | emperature | Rating Matrix ^{1,2} | | | |

| Cover Plate Nominal Rating (Required) | Temperature Classification | Sprinkler Nominal Rating | Sprinkler Maximum Ambient Ceiling Temperature ² | Suffix |
|--|-------------------------------|--------------------------|---|--------|
| 135 °F (57 °C) | Ordinary | 155 °F (68 °C) | 100 °F (38 °C) | Α |
| 165 °F (74 °C) | Intermediate | 200 °F (93 °C) | 150 °F (65 °C) | С |

Footnotes

1. Part number shown is the base part number. For complete part number, refer to the current Viking price list schedule.

2. The sprinkler temperature rating is stamped on the deflector.

3. Based on NFPA-13, NFPA 13R, and NFPA 13D. Other limits may apply, depending on fire loading, sprinkler location, and other requirements of the Authority Having Jurisdiction. Refer to specific installation standards.

4. Where a dash (-) is shown in the Finish suffix designation, insert the desired Temperature Rating suffix. See example above.

5. Stainless Steel versions are not available with any finishes or paint.



FREEDOM[®] RESIDENTIAL CONCEALED PENDENT SPRINKLER VK494 (K4.9)

The Viking Corporation, 210 N Industrial Park Drive, Hastings MI 49058

Telephone: 269-945-9501 Technical Services: 877-384-5464 Fax: 269-818-1680 Email: techsvcs@vikingcorp.com Visit the Viking website for the latest edition of this technical data page www.vikinggroupinc.com

Approval Chart Viking VK494, 4.9 K-factor Residential Concealed Pendent Sprinkler

For systems designed to NFPA 13D or NFPA 13R. For systems designed to NFPA 13, refer to the Design Criteria. For Ceiling types refer to current editions of NFPA 13, 13R or 13D

| Sprinkler Base | orinkler Base SIN | | NPT | Thread Siz | ze | Nominal K | -factor | Maximur | m Water | | | |
|---|-------------------|-------------------------|---------------------------|--------------|-------------------|--|---------------------|--------------------|------------|--|--|--|
| Part Number ¹ | 51N | Inc | hes | | mm | U.S. | metric ² | Working | Pressure | | | |
| 20759 | VK494 | 1. | /2 | 15 | | 4.9 | 70.6 | 175 psi (| (12 bar) | | | |
| Max. Coverage Area ⁶ W X L | Fie GF (LF | M Pressure PSI (bar) | | Deflector to | Installation | Listings and Approvals ^{3,5} | | Minimum Spacing | | | | |
| Ft. X Ft. (m X m) | | | 200 °F (93 ated Sprink | | Cening | Ceiling Type | | Ft. (m) | | | | |
| 12 X 12 (3.7 X 3.7) | | 3 9.2) | | .0 48) | | | | | | | | |
| 14 X 14 (4.3 X 4.3) | | 3 9.2) | | .0 48) | | Concealed with Cover Plate Assembly. | | | | | | |
| 16 X 16 (4.9 X 4.9) | | 3 9.2) | | .0 48) | Refer to Figure 2 | | See Foot | notes 8, & 9 | 8 (2.4) | | | |
| 18 X 18 (5.5 X 5.5) | | 7 I.4) | | 2.0 83) | See Footnote 7 | See Footnote 7. | | | | | | |
| 20 X 20 (6.1 X 6.1) | | 0 5.7) | - | 6.7 15) | | | | | | | | |

Footnotes

1. Part number shown is the base part number. For complete part number, refer to the current Viking price schedule.

2. Metric K-factor measurement shown is when pressure is measured in Bar. When pressure is measured in kPa, divide the metric K-factor shown by 10.0.

3. This chart shows the listings and approvals available at the time of printing. Other approvals may be in process. Check with the manufacturer for any additional approvals. Refer also to Design Criteria.

4. Listed by Underwriter's Laboratories, Inc. for use in the U.S., Canada, and European Union.

5. Meets New York City requirements, effective July 1, 2008.

6. For areas of coverage smaller than shown, use the "Flow" and "Pressure" for the next larger area listed. Flows and pressures listed are per sprinkler. The distance from sprinklers to walls shall not exceed one-half the sprinkler spacing indicated for the minimum "Flow" and "Pressure" used.

7. Other paint colors are available on request with the same listings as the standard finish colors. Stainless Steel cover plates are not available with any finishes or paint. Listings and approvals apply for any paint manufacturer. Contact Viking for additional information. Custom colors are indicated on a label inside the cover assembly. Refer to Figure 3.

8. Accepted Cover Plate Finishes are: Polished Chrome, Brushed Chrome, Bright Brass, Antique Brass, Brushed Brass, Brushed Copper, Painted White, Painted Ivory, or Painted Black 7.

9. C-UL-US-EU Listed as corrosion resistant - Electroless Nickel PTFE (ENT)



FREEDOM[®] RESIDENTIAL CONCEALED PENDENT SPRINKLER VK494 (K4.9)

The Viking Corporation, 210 N Industrial Park Drive, Hastings MI 49058

Telephone: 269-945-9501 Technical Services: 877-384-5464 Fax: 269-818-1680 Email: techsvcs@vikingcorp.com Visit the Viking website for the latest edition of this technical data page www.vikinggroupinc.com

DESIGN CRITERIA

(Also refer to the Approval Chart.)

UL Listing Requirements (C-UL-US-EU):

When using Viking Residential Concealed Pendent Sprinkler VK494 for systems designed to NFPA 13D or NFPA 13R, apply the listed areas of coverage and minimum water supply requirements shown in the Approval Chart.

For systems designed to NFPA 13: The number of design sprinklers is to be the four contiguous most hydraulically demanding sprinklers. The minimum required discharge from each of the four sprinklers is to be the greater of the following:

- The flow rates given in the Approval Chart for NFPA 13D and NFPA 13R applications for each listed area of coverage, or
- Calculated based on a minimum discharge of 0.1 gpm/sq. ft. over the "design area" in accordance with sections 9.5.2.1 or 10.2.4.1.2 of the current edition of NFPA 13.
- Minimum distance between residential sprinklers: 8 ft. (2.4 m).

NOTE: Concealed sprinklers must be installed in neutral or negative pressure plenums only.


IMPORTANT: Always refer to Bulletin Form No. F_080415 - Best Practices for Residential Sprinkler Handling and Installation. Also refer to Form No. F_080614 for general care, installation, and maintenance information. Viking sprinklers are to be installed in accordance with the latest edition of Viking technical data, the appropriate standards of NFPA and any other similar Authorities Having Jurisdiction, and also with the provisions of governmental codes, ordinances, and standards, whenever applicable. Final approval and acceptance of all residential sprinkler installations must be obtained from the Authorities Having Jurisdiction.

Sprinkler and Adapter Assembly

- Protective cap removed
- Use wrench 14047W/B**




Step 1: Carefully slide the wrench sideways around the deflector and pins



Carefully press the wrench upward and turn slightly to ensure engagement with the sprinkler wrench flats.

NEVER install the sprinkler by applying the installation wrench across the frame arms. DO NOT overtighten. Use only the designated sprinkler wrenches, Viking Part Numbers 14047W/B** or 14031**. A leak tight seal should be achieved by turning the sprinkler clockwise 1 to 1-1/2 turns beyond finger tight.





FREEDOM[®] RESIDENTIAL CONCEALED PENDENT SPRINKLER VK494 (K4.9)

The Viking Corporation, 210 N Industrial Park Drive, Hastings MI 49058

Telephone: 269-945-9501 Technical Services: 877-384-5464 Fax: 269-818-1680 Email: techsvcs@vikingcorp.com Visit the Viking website for the latest edition of this technical data page www.vikinggroupinc.com

