North Carolina 2018 - R402.1.5 Total UA

Property

216 Walker Grove Lillington, NC 27546 Model: 2816 Kipling E-F4_1 Community: Walkers Grove

Organization

Performance Point, LLC. Rick Blair 704-614-7175

Inspection Status Results are projected

Builder

Walkers Grove 9 True Walkers Grove 9 2816 Kipling

E-F4 1 GL WinPerPlan

True Homes

This report is based on a proposed design and does not confirm field enforcement of design elements.

Building UA

Elements	NC Reference	As Designed
Ceilings	48.2	41.6
Above-Grade Walls	193.9	193.2
Windows, Doors and Skylights	118.1	104.3
Slab Floor:	79.2	79.2
Framed Floors	18.6	18.8
Foundation Walls	0.0	0.0
Rim Joists	11.1	10.9
Overall UA (Design must be equal or lower):	469.1	448.0

Requirements

402.1.5	Total UA alternative compliance passes by 4.5%.	
402.3.2	Average SHGC: 0.30 Max SHGC: 0.30	
R402.4.2.2	Air Leakage Testing	Air sealing is 5.00 ACH at 50 Pa. It must not exceed 5.00 ACH at 50 Pa.
R402.5	Area-weighted average fenestration SHGC	
R402.5	Area-weighted average fenestration U-Factor	
R404.1	Lighting Equipment Efficiency	
Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met.	
R403.3.1	Duct Insulation	
403.3.3	Duct Testing	

Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 4.5%.

Name:	Rick Blair	Signature:	12/152
Organization:	Performance Point, LLC.	Digitally signed:	12/27/21 at 6:55 PM

Property

216 Walker Grove Lillington, NC 27546 Model: 2816 Kipling E-F4_1 Community: Walkers Grove

Walkers Grove 9
True Walkers Grove 9 2816 Kipling

E-F4 1 GL WinPerPlan

Organization

Performance Point, LLC. Rick Blair 704-614-7175

Builder

Inspection StatusResults are projected

True Homes

General Building Information

Conditioned Area (sq ft) 2,820 Conditioned Volume (cubic ft) 25,525 Insulated Shell Area (sq ft) 6,271.1

The building energy model in Ekotrope reflects the building assemblies and energy features listed below. Sometimes energy features will change in the field from what has been modeled. The inspection process should identify any changes and ensure that the home continues to meet the applicable energy code.

Slab

П	Name: House Slab(1,212 s.f., 162 ft. exterior perimeter) R-10 perimeter insulation, R-0 under slab insulation.		
Fram	ned Floor		
	Name: Over Garage (396 s.f.) R-0 continuous insulation, R-19 cavity insulation Insulation Grade: I		
Foundation Wall			
	None Present		
Abov	ve Grade Wall		
	Name: 2x4/ Ambient (2,463.5 s.f.) R-0 continuous insulation, R-15 cavity insulation Insulation Grade: I		
	Name: Niche (2 s.f.) R-3 continuous insulation, R-0 cavity insulation Insulation Grade: I		

Name: 2x4/ Garage (269.4 s.f.)

Insulation Grade: I

R-0 continuous insulation, R-15 cavity insulation

Lilling Mode	erty /alker Grove ton, NC 27546 l: 2816 Kipling E-F4_1 nunity: Walkers Grove	Organization Performance Point, LLC. Rick Blair 704-614-7175	Inspection Status Results are projected	
True_	ers Grove 9 Walkers Grove 9_2816 Kipling _1_GL_WinPerPlan	Builder True Homes		
	Name: 2x4/ Kneewall (48.6 s.f.) R-0 continuous insulation, R-15 of Insulation Grade: I	eavity insulation		
	Name: 2x6 Garage (72.4 s.f.) R-0 continuous insulation, R-19 cavity insulation Insulation Grade: I			
Rim	Joist			
	Name: Ambient (124.2 s.f.) R: 13.30			
	Name: Garage (31.6 s.f.) R: 13.30			
	Name: Attic (43.4 s.f.) R: 13.30			
Ceili	ng / Roof			
	Name: Flat Ceiling 8:12 (1,238 s. R-28.5 continuous insulation, R-9 Insulation Grade: I			
	Name: Flat Ceiling 12:12 (370 s.f.) R-28.5 continuous insulation, R-9.5 cavity insulation Insulation Grade: I			
Opa	que Door			
	Name: Front Door (20 s.f.) R: 7.00			
	Name: Garage Entry (17.8 s.f.) R: 7.00			

Glazing

Test Status: Blower-door tested

Property Organization Inspection Status 216 Walker Grove Performance Point, LLC. Results are projected Lillington, NC 27546 Rick Blair Model: 2816 Kipling E-F4 1 704-614-7175 Community: Walkers Grove Builder Walkers Grove 9 True Homes True Walkers Grove 9 2816 Kipling E-F4 1 GL WinPerPlan Name: Front (90 s.f.), U: 0.330, SHGC: 0.3, Orientation: EAST Name: Front Shd. SL (13.33 s.f.), U: 0.330, SHGC: 0.3, Orientation: EAST Name: Right (30 s.f.), U: 0.330, SHGC: 0.3, Orientation: NORTH Name: Right Fxd. (12 s.f.), U: 0.330, SHGC: 0.3, Orientation: NORTH Name: Back (100 s.f.), U: 0.330, SHGC: 0.3, Orientation: WEST Name: Back door Shd. /Most (1/2) (16.67 s.f.), U: 0.330, SHGC: 0.3, Orientation: WEST Name: Back door Shd. Fxd. /Most (1/2) (16.67 s.f.), U: 0.330, SHGC: 0.3, Orientation: WEST Name: Left (21 s.f.), U: 0.330, SHGC: 0.3, Orientation: SOUTH Skylight None Present Mechanical Ventilation None Present Mechanical Equipment Water Heater • Electric • 100% Hot Water Load @ 0.95 Energy Factor Heat Pump / All • Electric • 100% Heating Load @ 8.2 HSPF, 100% Cooling Load @ 14 SEER Air Leakage Control

House is air-sealed as to achieve 2,127 CFM50 (5.00 ACH50) or less at final blower-door test.

3

Property

216 Walker Grove Lillington, NC 27546 Model: 2816 Kipling E-F4_1 Community: Walkers Grove Organization

Performance Point, LLC. Rick Blair 704-614-7175 **Inspection Status**Results are projected

Walkers Grove 9

True_Walkers Grove 9_2816 Kipling E-F4_1_GL_WinPerPlan

Builder True Homes

Infiltration Requirements for IECC in Climate Zone 4

2009 IECC Infiltration limit for the design home is 7 ACH50.

2012 IECC Infiltration limit for the design home is 3 ACH50.

2015 IECC Infiltration limit for the design home is 3 ACH50.

2018 IECC Infiltration limit for the design home is 3 ACH50.

2021 IECC Infiltration limit for the design home is 5 ACH50.

Duct Leakage

Duct System 1

NOT entirely within conditioned space, testing required Leakage to Outside specified as: 4 CFM25 / 100 ft²

Total Leakage specified as: 4 CFM25 / 100 ft² (Post-Construction)

Duct Leakage Code Requirements for IECC

2009 IECC:

Postconstruction Leakage Test: Duct Leakage to Outdoors <= 8 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage <= 6 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

2012 IECC Mandatory, 2015 and 2018 IECC Prescriptive Paths:

Postconstruction Leakage Test: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage <= 3 CFM25 / 100 sq ft CFA.

2015 and 2018 IECC Performance Paths (Cost Compliance):

Leakage testing is required UNLESS all ducts and air handlers are located entirely within the thermal envelope.

There is no pass/fail threshold for duct leakage on the performance path.

Project Notes

EP_12/24/2021_Performance Report True_2816 Kipling E-F4_1
Used Worst Orientation (E)
DG_12/27/2021
Revised

Energy Specifications Label

216 Walker Grove

Model: 2816 Kipling E-F4_1 Ekotrope RATER - Version: 4.0.1.2803

Building Envelope Specs

Ceiling: R-38

Above Grade Walls: R-15 Foundation Walls: N/A Exposed Floor: R-19

Slab: R-10

Infiltration: 5 ACH50

Duct Insulation: Supply: R8, Return: R8 Duct Lkg to Outdoors: 4 CFM25 / 100 ft²

Window & Door Specs

U-Value: 0.33, SHGC: 0.3

Door: R-7

Mechanical Equipment Specs

Heating: Air Source Heat Pump • Electric • 8.2

HSPF

Cooling: Air Source Heat Pump • Electric • 14

SEER

Hot Water: Residential Water Heater • Electric •

0.95 Energy Factor

Average Mechanical Ventilation: 0 CFM

Builder or Design Professional

Signature:

Builder Affidavit

Property

216 Walker Grove Lillington, NC 27546 Model: 2816 Kipling E-F4_1 Community: Walkers Grove

Walkers Grove 9
True_Walkers Grove 9_2816 Kipling
E-F4 1 GL WinPerPlan

Organization

Performance Point, LLC. Rick Blair 704-614-7175

Builder True Homes Inspection Status
Results are projected

Important Notice to Builder

Builder affirms in this affidavit that all building characteristics described in the Building Summary Report accurately reflect this New Home. Builder agrees to allow the Home Energy Rating System (HERS) Provider and/or Rater to verify building characteristics of this New Home fully at the HERS Rater/Provider's discretion. The HERS Provider and Rater do not create or imply any duty or obligations to Builder or any subsequent owner. Builder is responsible for taking any actions necessary to protect Builder's interest. There is no guarantee or warranty whatsoever expressed or implied from the HERS Provider or Rater.

HERS® Index Score:80

Builder Name: True Hom	nes	Builder Signature:	
Name:	Rick Blair	Signature:	TalTSZ
Organization:	Performance Point, LLC.	 Digitally signed:	12/27/21 at 6:55 PM