North Carolina 2018 - R402.1.5 Total UA

Property , NC 27546 Model: CC 2574 Organization Southern Energy Manager Justin Smith

Inspection Status Results are projected



Template - Caviness & Cates - CC 2574 plan - CZ 4 slab - HERS

2574 slab

Builder Caviness and Cates

This report is based on a proposed design and does not confirm field enforcement of design elements.

Building UA

Elements	NC Reference	As Designed
Ceilings	49.0	43.8
Above-Grade Walls	201.9	164.2
Windows, Doors and Skylights	105.5	86.6
Slab Floor:	81.1	105.0
Framed Floors	23.5	22.9
Foundation Walls	0.0	0.0
Rim Joists	9.6	8.4
Overall UA (Design must be equal or lower):	470.6	430.9

Requirements

	402.1.5	Total UA alternative compliance passes by 8.4%.	
	402.3.2	Average SHGC: 0.23 Max SHGC: 0.30	
	R402.4.2.2	Air Leakage Testing	Air sealing is 4.80 ACH at 50 Pa. It must not exceed 5.00 ACH at 50 Pa.
\bigcirc	R402.5	Area-weighted average fenestration SHGC	
	R402.5	Area-weighted average fenestration U-Factor	
	R404.1	Lighting Equipment Efficiency	
	Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met.	
\bigcirc	R403.3.1	Duct Insulation	
	403.3.3	Duct Testing	

Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 8.4%.

Name:	Justin Smith	Signature:	Justin Smith
Organization:	Southern Energy Management	Digitally signed:	1/24/22 at 4:09 PM

Property , NC 27546 Model: CC 2574

Template - Caviness & Cates - CC

2574 plan - CZ 4 slab - HERS

2574 slab

Organization Southern Energy Manager

Justin Smith

Builder

Caviness and Cates



General Building Information

Conditioned Area (sq ft) 2.574 Conditioned Volume (cubic ft) 23,240 Insulated Shell Area (sq ft) 6,360

The building energy model in Ekotrope reflects the building assemblies and energy features listed below. Sometimes energy features will change in the field from what has been modeled. The inspection process should identify any changes and ensure

Inspection Status

Results are projected

that th	ne home continues to meet the applicable energy coo
Slab	
	Name: slab(1,132 s.f., 172 ft. exterior perimeter) R-0 perimeter insulation, R-0 under slab insulation.
Fran	ned Floor
	Name: over garage (500 s.f.) R-0 continuous insulation, R-19 cavity insulation Insulation Grade: I
Four	ndation Wall
	None Present
Abo	ve Grade Wall
	Name: 1st floor ambient (1,092 s.f.) R-0 continuous insulation, R-19 cavity insulation Insulation Grade: II
	Name: 1st floor garage (456 s.f.) R-0 continuous insulation, R-19 cavity insulation Insulation Grade: II
	Name: 2nd floor ambient (1,224 s.f.) R-0 continuous insulation, R-19 cavity insulation Insulation Grade: II

Property , NC 27546 Model: CC 2574 **Organization**Southern Energy Manager
Justin Smith

Inspection Status
Results are projected



	ate - Caviness & Cates - CC plan - CZ 4 slab - HERS slab	Builder Caviness	and Cates		
	Name: 2nd floor attic (152 s.f.) R-0 continuous insulation, R-19 c Insulation Grade: II	avity insula	ation		
Rim	Joist				
	Name: 1st floor ambient (121 s.f.) R: 15.40)			
	Name: 1st floor garage (51 s.f.) R: 15.40				
Ceili	ng / Roof				
	Name: attic (1,632 s.f.) R-13 continuous insulation, R-25 Insulation Grade: I	cavity insu	llation		
Opad	que Door				
	Name: front entry (20 s.f.) U: 0.200				
	Name: garage entry (18 s.f.) U: 0.200				
Glaz	ing				
	Name: front_shaded (37 s.f.), U	J: 0.300,	SHGC: 0.23,	Orientation	n: EAST
	Name: front 2nd unshaded (56.8	s.f.), U:	0.300, SHG0	D: 0.23, C	Orientation: EAST
	Name: left 2nd unshaded (30 s.f.)), U: 0.30	0, SHGC: 0.	23, Orien	tation: SOUTH
$\overline{\Box}$	Name: right unshaded (36 s.f.),	U: 0.300,	SHGC: 0.23,	, Orientati	ion: NORTH

Name: rear unshaded (30 s.f.), U: 0.300, SHGC: 0.23, Orientation: WEST

Property , NC 27546 Model: CC 2574 Organization Southern Energy Manager Justin Smith Inspection Status
Results are projected



Template - Caviness & Cates - CC 2574 plan - CZ 4 slab - HERS

Builder

Caviness and Cates

slab			
Name: rear shaded (35.5 s.f.), U: 0.300, SHGC: 0.23, Orientation: WEST			
Name: rear 2nd unshaded (38 s.f.), U: 0.300, SHGC: 0.23, Orientation: WEST			
ight			
None Present			
hanical Ventilation			
None Present			
hanical Equipment			
whole house heat pump • Electric • 100% Heating Load @ 8 HSPF, 100% Cooling Load @ 14 SEER			
Water Heating • Electric • 100% Hot Water Load @ 0.91 Energy Factor			
eakage Control			
Test Status: Blower-door tested House is air-sealed as to achieve 1,859 CFM50 (4.80 ACH50) or less at final blower-door test.			
Infiltration Requirements for IECC in Climate Zone 4			
2009 IECC Infiltration limit for the design home is 7 ACH50. 2012 IECC Infiltration limit for the design home is 3 ACH50.			

Duct Leakage

Duct System 1

NOT entirely within conditioned space, testing required Leakage to Outside specified as: 102 CFM @ 25Pa (3.96 / 100 ft²) Total Leakage specified as: 102 CFM @ 25Pa (Post-Construction)

2015 IECC Infiltration limit for the design home is 3 ACH50. 2018 IECC Infiltration limit for the design home is 3 ACH50. 2021 IECC Infiltration limit for the design home is 5 ACH50.

Property , NC 27546

Model: CC 2574

Organization Southern Energy Manager

Justin Smith

Inspection Status Results are projected



Template - Caviness & Cates - CC 2574 plan - CZ 4 slab - HERS

2574 slab

Builder

Caviness and Cates

Duct Leakage Code Requirements for IECC

2009 IECC:

Postconstruction Leakage Test: Duct Leakage to Outdoors <= 8 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage <= 6 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

2012 IECC Mandatory, 2015 and 2018 IECC Prescriptive Paths:

Postconstruction Leakage Test: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage <= 3 CFM25 / 100 sq ft CFA.

2015 and 2018 IECC Performance Paths (Cost Compliance):

Leakage testing is required UNLESS all ducts and air handlers are located entirely within the thermal envelope.

There is no pass/fail threshold for duct leakage on the performance path.

Project Notes

	10 04/04/0000	
Initial Inputs	JS 01/24/2022	

- -confirm HVAC specs
- -confirm if programmable thermostats installed
- -modeled to worst case orientation
- -confirm cfl lighting %