

Adams Soil Consulting
1676 Mitchell Road
Angier, NC 27501
919-414-6761

January 10, 2022
Project #1190

Stout Land Development, LLC
1786 Metromedical Drive
Fayetteville, NC 28304

RE: Preliminary soil/site evaluation for Lots #1-5 of the proposed minor subdivision located adjacent to Spring Hill Church Road in Harnett County.

Mr. Stout,

Adams Soil Consulting (ASC) conducted a preliminary soil evaluation on the above referenced parcel to determine the areas of soils which are suitable for subsurface wastewater disposal systems (conventional & LPP). The evaluation was performed using hand auger borings during moist soil conditions based on the criteria found in the State Subsurface Rules, 15ANCAC 18A .1900 "Laws and Rules for Sewage Treatment and Disposal Systems". From this evaluation, ASC sketched the boundary between the suitable soils and unsuitable soils onto a preliminary plat supplied by your surveyor.

The suitable soils shown on the accompanying soil map have potential for a subsurface septic initial and repair area for at least one 3-bedroom home site on Lots 1-5. Each of these lots contains greater than 18,000 ft² of provisionally suitable soils that consist of sandy clay loam to clay subsoil that can support a daily loading rate of 0.25-0.8 gallons/day/ft². Each of these lots should accommodate a house foot print of at least 50' x 50'. Potential septic system types may include; conventional, modified conventional, mound, drip, and or septic systems utilizing low profile chambers.


The specific septic systems and/or repair systems will be permitted by the Harnett County Health Department. Additionally, the Harnett County Health Department will establish the loading rates for any proposed system. The areas for the proposed septic fields shall not be impacted by home sites, pools, garages and shall not be mechanically altered from the natural lay of the land. .

The lots will require a detailed soils evaluation by the Harnett County Health Department prior to issuance of any permits for a septic system. A septic system layout may be required before a permit can be issued on the above referenced lot demonstrating available space for the primary and repair septic areas. Due to the subjective nature of the permitting process and the variability of naturally occurring soils, Adams Soil Consulting cannot guarantee that areas delineated as suitable for on-site wastewater disposal systems will be permitted by the governing agency. The lot may require a septic system utilizing pumps, shallow or ultra-shallow conventional trench placement, low pressure pipe system, and/or reductions system for final approval. The

accompanying soil map is preliminary in nature, no further assumptions or subdivision should be made without a more detailed evaluation.

If you have any questions regarding the findings on the attached map or in this report, please feel free to contact me anytime. Thank you allowing me to perform this site evaluation for you.

Sincerely,



Alex Adams
NC Licensed Soil Scientist #1247

