

# Estimate

Carter Components - Sanford

298 Harvey Faulk Road

Sanford NC 27332

Phone: FAX:



Quote In:	5/19/2022	Job Number:	22050131
Quote Sent:		Customer Acct #:	
		Job Category:	Roof
		Sales Rep:	Kelly Hudson
Order Date:		Sch. Delivery	
Estimator:	PG - Au Do	Customer P.O. #	
Truss Rep:	Kelly Hudson		

SOLD TO	Walk-in	Job Name:	1099 Lloyd Stewart Roof	Lot:		Subdiv:	
		Model:	Custom-Ciucevich Res	Delivery Area:	Richmond		
SHIP TO	Custom-Ciucevich Res 1099 Lloyd Stewart Road Broadway NC 27505	Job Notes:					

## Rectangular EWP

### Roof Trusses

#### 2.0 RigidLam DF LVL 1-3/4 x 11-7/8

LABEL	SIZE	QTY	LENGTH	NOTE
BM2	2.0 RigidLam DF LVL 1-3/4 x 11-7/8	3	38-00-00	
<b>Total: 2.0 RigidLam DF LVL 1-3/4 x 11-7/8</b>		<b>(3)</b>	<b>114-00-00 - L/F</b>	

#### 2.0 RigidLam DF LVL 1-3/4 x 16

LABEL	SIZE	QTY	LENGTH	NOTE
BM1	2.0 RigidLam DF LVL 1-3/4 x 16	3	38-00-00	
<b>Total: 2.0 RigidLam DF LVL 1-3/4 x 16</b>		<b>(3)</b>	<b>114-00-00 - L/F</b>	

**Total: Roof Trusses (6) 228-00-00 - L/F**

## Hangers

### Roof Trusses

QTY	TYPE	MANUFACTURER	SIZE	LENGTH	NOTE
8	Hanger	Simpson	One H2.5A		
346	Hanger	MiTek	One RT7A		
1	Hanger	MiTek	One RT8A		
18	Hanger	MiTek	One RT16A		
34	Hanger	MiTek	THD26		
1	Hanger	MiTek	THDH26-2		
1	Hanger	MiTek	THDH28-2		

**Total: Roof Trusses**

## Roof Trusses

DIAGRAM	QTY	PLY	PITCH	LABEL	Height		OVERHANG		CANTILEVER		STUB	
					Shipping (Alternate)	Base Span	SPAN	LUMBER	LEFT	RIGHT	LEFT	RIGHT
	1		12 /12	A01	11-10-00	31-02-00	2 x 4					
	1		12 /12	A02	11-10-00	31-02-00	2 x 4					
	1		12.25 /1 2	A03	11-10-00	31-02-00	2 x 6					
	4		12 /12	A04	11-10-00	31-02-00	2 x 4					



























Roof Trusses

DIAGRAM	QTY	PITCH	LABEL	Height		LUMBER	OVERHANG		CANTILEVER		STUB	
				Shipping (Alternate)	Base Span		LEFT	RIGHT	LEFT	RIGHT	LEFT	RIGHT
	1	12 /12	A05	11-10-00	<del>31-02-00</del> 30-08-12	2 x 4					5-04	-
	3	12 /12	A06	11-10-00	<del>31-02-00</del> 30-08-12	2 x 4					5-04	-
	10	12 /12 4.5 /12	A07	11-10-00 (11-07-12)	<del>32-08-12</del> 30-08-12	2 x 4					-	2-00-00
	1	12 /12 4.5 /12	A08	11-10-00 (11-07-12)	<del>32-08-12</del> 30-08-12	2 x 4					-	2-00-00
	1 2-ply	9 /12	B01	11-04-12		2 x 4 2 x 6					-	-
	1	9 /12	B02	11-04-12		2 x 4					-	-
	1	9 /12	B03	11-04-12		2 x 4					-	-
	1	9 /12	B04	11-04-12		2 x 4					-	-
	1	9 /12	B05	11-04-12		2 x 4					-	-
	1	9 /12	B06	11-05-10 (11-05-04)		2 x 4	1-04-00				-	-
	1	9 /12	B07	11-05-10 (11-05-04)		2 x 4	1-04-00				-	-
	1	9 /12	B08	11-05-10 (11-05-04)		2 x 4	1-04-00				-	-
	1	9 /12	B09	11-05-10 (11-05-04)		2 x 4 2 x 6	1-04-00				-	-
	1	9 /12	C01	8-06-07 (8-03-11)		2 x 4	1-04-00				-	-
	1	9 /12	C02	8-06-07 (8-03-11)		2 x 4	1-04-00				-	-
	1	9 /12	C03	8-06-07 (8-03-11)		2 x 4	1-04-00				-	-
	1	9 /12 7.22 /12	C04	8-06-07 (8-03-11)		2 x 6	1-04-00				-	-
	1 2-ply	9 /12 7.22 /12	C05	8-06-07 (8-04-02)		2 x 6	1-04-00				-	-
	1	3.5 /12	D01	8-05-01		2 x 4	2-04-00				-	-
	6	3.5 /12	D02	8-05-01		2 x 4	2-04-00				-	-
	4	3.5 /12	D03	8-05-01		2 x 4	2-04-00	1-04-00			-	-
	2	3.5 /12	D04	8-05-01		2 x 4	2-04-00	1-04-00			-	-
	1 2-ply	3.5 /12	D05	8-05-01		2 x 4 2 x 8	2-04-00	1-00-00			-	-
	2	3.5 /12	D06	5-00-06 (4-10-00)		2 x 4	2-04-00				-	-
	1 2-ply	3.5 /12	D07	5-00-06 (4-04-05)		2 x 4 2 x 6	<del>12-01-06</del> 10-01-08	4-03-14			1-11-14	-
	1	7 /12	E01	8-05-01		2 x 4	1-04-00				-	-

Roof Trusses

DIAGRAM	QTY	PLY	PITCH	LABEL	Height	Base Span		OVERHANG		CANTILEVER		STUB	
					Shipping (Alternate)	SPAN	LUMBER	LEFT	RIGHT	LEFT	RIGHT	LEFT	RIGHT
	1		7 /12	E02	8-05-01	22-11-00	2 x 4	1-04-00	-	-	-	-	
	10		2.5 /12	EJ01	1-09-13 (1-08-11)	6-00-00	2 x 4	1-04-00	-	-	-	-	
	1		3 /12	EJ02	2-01-08 (2-00-10)	6-00-00	2 x 4	1-04-00	-	-	-	-	
	4		2 /12	EJ05	10-03 (9-15)	2-00-00	2 x 4	1-04-00	-	-	-	-	
	4		2.5 /12	EJ06	11-13 (10-14)	2-00-00	2 x 4	1-04-00	-	-	-	-	
	1		7 /12	G01	9-06-15	28-11-12	2 x 4	1-04-00	1-04-00	-	-	-	
	5		7 /12	G02	9-06-15	28-11-12	2 x 4	1-04-00	1-04-00	-	-	-	
	4		7 /12	G03	9-06-15	28-11-12	2 x 4			-	-	-	
	1		2.5 /12	H01	1-09-13 (1-09-09)	17-10-12	2 x 4 2 x 6	1-04-00	-	-	-	-	
	1		2.5 /12	H02	2-02-13 (2-00-00)	8-09-00	2 x 4	1-04-00	-	-	-	-	
	1		2.5 /12	H03	2-02-13 (2-02-03)	8-09-00	2 x 4	1-04-00	-	-	-	-	
	1		2.5 /12	H04	1-09-13 (1-09-08)	13-02-00	2 x 4 2 x 6	1-04-00	-	-	-	-	
	14		2.5 /12	H05	2-04-11 (2-03-06)	8-09-00	2 x 4	1-04-00	-	-	-	-	
	2		1.77 /12	HJ01	11-10 (10-12)	2-08-07	2 x 4	1-10-10	-	-	-	-	
	1		1.66 /12	HJ02	9-15 (9-12)	1-05-10	2 x 6 2 x 4	2-04-14	-	-	-	-	
	1		1.66 /12	HJ03	10-00 (9-12)	2-03-14	2 x 4	1-07-04	-	-	-	-	
	1		2 /12	K01	3-01-07	10-11-12	2 x 4 2 x 6	1-04-00	-	-	-	-	
	1		2 /12	K02	3-04-01 (3-03-08)	10-11-12	2 x 4	1-04-00	-	-	-	-	
	9		2 /12	K03	3-04-15 (3-00-07)	11-05-04	2 x 4	1-04-00	-	-	-	-	
	5		2 /12	K04	2-04-02 (2-03-10)	10-11-12	2 x 4	1-04-00	-	-	-	-	
	1		2 /12	K05	2-01-08 (2-01-07)	11-05-04	2 x 4 2 x 6	1-04-00	-	-	-	-	
	4		3 /12	L01	2-02-04 (2-01-06)	6-03-00	2 x 4	1-04-00	-	-	-	-	
	1 2-ply		3 /12	L02	2-02-04 (2-01-06)	6-03-00	2 x 4 2 x 6	1-04-00	-	-	-	-	
	2		2.5 /12	MH01	11-13 (11-08)	6-00-00	2 x 4	1-04-00	-	-	-	-	
	2		2.5 /12	MH02	1-04-13 (1-04-05)	6-00-00	2 x 4	1-04-00	-	-	-	-	
	1		3 /12	MH03	10-03 (10-02)	6-00-00	2 x 6 2 x 4	1-04-00	-	-	-	-	

Roof Trusses

DIAGRAM	QTY	PLY	PITCH	LABEL	Height		OVERHANG		CANTILEVER		STUB	
					Shipping (Alternate)	Base Span SPAN	LUMBER	LEFT	RIGHT	LEFT	RIGHT	LEFT
	1		3 /12	MH04	1-02-03 (1-02-02)	6-00-00	2 x 6 2 x 4	1-04-00	-	-	-	-
	1		3 /12	MH05	1-06-03 (1-06-02)	6-00-00	2 x 6 2 x 4	1-04-00	-	-	-	-
	1		3 /12	MH06	1-10-03 (1-10-01)	6-00-00	2 x 4	1-04-00	-	-	-	-
	1		3 /12	MH07	1-03-05 (1-01-04)	6-00-00	2 x 6 2 x 4	3-00-08	-	-	-	-
	1		3 /12	MH08	1-07-05 (1-04-07)	6-00-00	2 x 6 2 x 4	3-00-08	-	-	-	-
	1		3 /12	MH09	1-11-05 (1-07-09)	6-00-00	2 x 6 2 x 4	3-00-08	-	-	-	-
	1		3 /12	MH10	2-03-05 (1-10-12)	6-00-00	2 x 6 2 x 4	3-00-08	-	-	-	-
	2		12 /12	PB01	7-01-07	14-02-13	2 x 4		-	-	-	-
	20		12 /12	PB02	7-01-07	14-02-13	2 x 4		-	-	-	-
	4		12 /12	PB03	8-00-13	16-01-09	2 x 4		-	-	-	-
	2		12 /12	PB04	8-00-13	16-01-09	2 x 4		-	-	-	-
	1		12 /12	VL01	8-04-01	32-09-12	2 x 4		-	-	-	-
	2		12 /12	VL02	6-10-09	29-10-04	2 x 4		-	-	-	-
	2		12 /12	VL03	4-10-09	25-10-04	2 x 4		-	-	-	-
	2		12 /12	VL04	10-11-06	21-10-04	2 x 4		-	-	-	-
	2		12 /12	VL05	8-11-06	17-10-04	2 x 4		-	-	-	-
	2		12 /12	VL06	6-11-06	13-10-04	2 x 4		-	-	-	-
	2		12 /12	VL07	4-11-06	9-10-04	2 x 4		-	-	-	-
	2		12 /12	VL08	2-11-06	5-10-04	2 x 4		-	-	-	-
	1		12 /12	VL09	9-06-00	30-00-07	2 x 4		-	-	-	-
	1		12 /12	VL10	3-11-04 (2-09-07)	3-11-00	2 x 4		-	-	-	-
	1		7 /12	VL11	5-03-13	18-01-14	2 x 4		-	-	-	-
	1		7 /12	VL12	4-08-00	15-11-02	2 x 4		-	-	-	-
	1		7 /12	VL13	3-06-00	11-11-02	2 x 4		-	-	-	-
	1		7 /12	VL14	2-04-00	7-11-02	2 x 4		-	-	-	-
	1		7 /12	VL15	1-02-00	3-11-02	2 x 4		-	-	-	-
					<b>195</b>		<b>3339.76</b>					

**22050131**

**1099 Lloyd Stewart Roof**

**Page: 5 of 5**

Temporary and permanent bracing by others.

Quote valid for 15 days.

Price valid for 30 days from purchase date.

NOTES:

**Accepted by Seller**

BY: \_\_\_\_\_

TITLE: \_\_\_\_\_

DATE OF ACCEPTANCE: \_\_\_\_\_

**Accepted by Buyer**

PURCHASER: \_\_\_\_\_

BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

PHONE: \_\_\_\_\_ DATE: \_\_\_\_\_

Delivery	Included
Sub-Total	\$34,900.00
NC 7.0% (7%)	\$2,443.00
<b>Grand Total</b>	<b>\$37,343.00</b>