

RE: 30136-30136A
 60 PRINCE PLACE - ROOF

Trenco
 818 Soundside Rd
 Edenton, NC 27932

Site Information:

Customer: Project Name: 30136-30136A
 Lot/Block: Model:
 Address: Subdivision:
 City: State:

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):


Design Code: IRC2015/TPI2014 Design Program: MiTek 20/20 8.5
 Wind Code: ASCE 7-10 Wind Speed: 115 mph
 Roof Load: 40.0 psf Floor Load: N/A psf

This package includes 43 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I49963390	A1E	1/31/2022	21	I49963410	H3	1/31/2022
2	I49963391	A2	1/31/2022	22	I49963411	J1E	1/31/2022
3	I49963392	A2A	1/31/2022	23	I49963412	M1	1/31/2022
4	I49963393	A3G	1/31/2022	24	I49963413	M1E	1/31/2022
5	I49963394	A4G	1/31/2022	25	I49963414	M2	1/31/2022
6	I49963395	A5	1/31/2022	26	I49963415	M2E	1/31/2022
7	I49963396	A6	1/31/2022	27	I49963416	M2G	1/31/2022
8	I49963397	A6A	1/31/2022	28	I49963417	M3	1/31/2022
9	I49963398	A7E	1/31/2022	29	I49963418	M6	1/31/2022
10	I49963399	B1	1/31/2022	30	I49963419	M7	1/31/2022
11	I49963400	C1E	1/31/2022	31	I49963420	M8	1/31/2022
12	I49963401	C2	1/31/2022	32	I49963421	PB1	1/31/2022
13	I49963402	C3G	1/31/2022	33	I49963422	PB1GE	1/31/2022
14	I49963403	D1E	1/31/2022	34	I49963423	PB2	1/31/2022
15	I49963404	D2	1/31/2022	35	I49963424	PB3	1/31/2022
16	I49963405	D3	1/31/2022	36	I49963425	PB4	1/31/2022
17	I49963406	D4	1/31/2022	37	I49963426	PB4E	1/31/2022
18	I49963407	FT1	1/31/2022	38	I49963427	V1	1/31/2022
19	I49963408	H1	1/31/2022	39	I49963428	V2	1/31/2022
20	I49963409	H2	1/31/2022	40	I49963429	V3	1/31/2022

The truss drawing(s) referenced above have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by 84 Components - #2383.
 Truss Design Engineer's Name: Sevier, Scott
 My license renewal date for the state of North Carolina is December 31, 2022.
 North Carolina COA: C-0844

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to TRENCO. Any project specific information included is for TRENCO customers file reference purpose only, and was not taken into account in the preparation of these designs. TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



January 31, 2022


Job	Truss	Truss Type	Qty	Ply	60 PRINCE PLACE - ROOF	149963390
30136-30136A	A1E	GABLE	1	1	Job Reference (optional)	

84 Components (Dunn),

Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:01:59 2022 Page 1

ID:BLJh112d3vwZK_wUdDgFCyrbmE-wnlqxrMzIRkhBam44oMq4Nw5Le8Ql2Xog0NyXzqny



Scale = 1:82.1





Plate Offsets (X, Y)-- [2:0-3-0,0-1-8], [6:0-4-4,0-2-4], [7:0-3-12,0-2-0], [10:0-4-0,Edge], [17:0-2-12,Edge], [18:0-8-0,Edge]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.47	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.82	Vert(LL) -0.16 17-18 >915 240	MT18HS	197/144
BCLL 0.0 *	Lumber DOL 1.15	WB 0.18	Vert(CT) -0.22 17-18 >671 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-MS	Horz(CT) 0.00 13 n/a n/a		
	Code IRC2015/TPI2014		Attic -0.16 17-18 909 360	Weight: 342 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2 *Except* 7-10: 2x6 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-7.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2 *Except* 18-22: 2x6 SP DSS, 17-18: 2x10 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 9-8-5 oc bracing: 18-19 7-2-13 oc bracing: 17-18.
WEBS 2x4 SP No.3 *Except* 5-18,9-17,5-8: 2x4 SP No.2 or 2x4 SPF No.2	WEBS 1 Row at midpt 5-18, 9-17
OTHERS 2x4 SP No.3	JOINTS 1 Brace at Jt(s): 24, 25

REACTIONS. All bearings 18-10-4 except (jt=length) 17=17-10-4, 14=17-10-4, 13=17-10-4, 16=17-10-4, 15=17-10-4.
(lb) - Max Horz 22=242(LC 11)
Max Uplift All uplift 100 lb or less at joint(s) 22, 14, 16 except 19=-853(LC 18)
Max Grav All reactions 250 lb or less at joint(s) 16, 15 except 22=415(LC 1), 18=1798(LC 20), 21=473(LC 1), 17=1224(LC 21), 14=454(LC 1), 13=261(LC 1), 20=253(LC 18)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-313/62, 3-5=-300/108, 5-6=-533/73, 6-7=-383/76, 7-8=-552/81, 8-9=-378/141, 9-11=-302/79, 2-22=-357/83
BOT CHORD 21-22=-239/351, 20-21=-123/252, 19-20=-123/252, 18-19=-123/252
WEBS 3-21=-362/73, 5-18=-573/78, 9-17=-659/111, 14-23=-394/119, 11-23=-381/149

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) -0-10-8 to 2-9-9, Exterior(2) 2-9-9 to 16-0-0, Corner(3) 16-0-0 to 19-8-1, Exterior(2) 19-8-1 to 21-0-0, Corner(3) 21-0-0 to 24-10-4, Exterior(2) 24-10-4 to 36-6-12 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) All plates are MT20 plates unless otherwise indicated.
 - 6) All plates are 1.5x4 MT20 unless otherwise indicated.
 - 7) Gable studs spaced at 2-0-0 oc.
 - 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 10) Ceiling dead load (5.0 psf) on member(s). 8-9, 5-24, 24-25, 8-25; Wall dead load (5.0psf) on member(s).5-18, 9-17
 - 11) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 17-18
 - 12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 22, 14, 16 except



Job 30136-30136A	Truss A1E	Truss Type GABLE	Qty 1	Ply 1	60 PRINCE PLACE - ROOF Job Reference (optional)	I49963390
---------------------	--------------	---------------------	----------	----------	--	-----------

84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:01:59 2022 Page 2
ID:BLJh1112d3wvZK_wUdDgFCyrbmE-wnlqxrMzIRkhBam44oMq4Nw5Le8Ql2Xog0NyXzqny

NOTES-

- 13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 14) Attic room checked for L/360 deflection.

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
Edenton, NC 27932

Job 30136-30136A	Truss A2	Truss Type ROOF TRUSS	Qty 6	Ply 1	60 PRINCE PLACE - ROOF	149963391
---------------------	-------------	--------------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:01 2022 Page 1

ID:BLJh1112d3wvZK_wUdDgFCyrbmE-tAtaFdT0UwiRwVk9BUqqvVS8u8IVuUWqF_VU0Pzqnyq



Scale = 1:71.8




Plate Offsets (X, Y)--	[6:0-4-4,0-2-4], [7:0-3-12,0-2-0], [10:0-4-0,Edge], [13:Edge,0-3-8], [15:0-4-0,Edge], [16:0-8-0,Edge]
------------------------	---

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.96	Vert(LL)	-0.41 14-15	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.95	Vert(CT)	-0.49 14-15	>882	180	MT18HS	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.82	Horz(CT)	0.04 13	n/a	n/a		
BCDL 10.0	Code IRC2015/TP12014		Matrix-MS	Attic	-0.32 15-16	448	360		Weight: 285 lb FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2 *Except* 7-10: 2x6 SP No.2	TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-7.
BOT CHORD 2x6 SP No.2 *Except* 16-18: 2x6 SP DSS, 15-16: 2x10 SP DSS	BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 5-16,9-15,5-8: 2x4 SP No.2 or 2x4 SPF No.2, 2-18: 2x6 SP No.2	WEBS 1 Row at midpt 9-14
	JOINTS 1 Brace at Jt(s): 19, 20

REACTIONS. (size) 18=0-3-8, 13=Mechanical
Max Horz 18=241(LC 11)
Max Grav 18=1947(LC 20), 13=1953(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2529/0, 3-5=-2539/0, 5-6=-602/72, 6-7=-438/72, 7-8=-622/72, 8-9=-1938/0, 9-11=-2617/0, 11-12=-2525/0, 2-18=-1840/0, 12-13=-1911/0
BOT CHORD 17-18=-157/555, 16-17=0/2172, 15-16=0/2091, 14-15=0/2077
WEBS 3-17=-429/119, 3-16=-355/281, 5-16=0/917, 9-15=0/933, 9-14=-335/350, 11-14=-407/215, 2-17=0/1638, 12-14=0/1997, 5-19=-1689/0, 19-20=-1682/0, 8-20=-1689/0

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-10-8 to 2-9-9, Interior(1) 2-9-9 to 16-0-0, Exterior(2) 16-0-0 to 26-2-5, Interior(1) 26-2-5 to 36-6-12 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) All plates are MT20 plates unless otherwise indicated.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Ceiling dead load (5.0 psf) on member(s). 8-9, 5-19, 19-20, 8-20; Wall dead load (5.0psf) on member(s).5-16, 9-15
 - 8) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 15-16
 - 9) Refer to girder(s) for truss to truss connections.
 - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - 11) Attic room checked for L/360 deflection.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601


ENGINEERING BY
TRENCO
 A MiTek Affiliate
 818 Soundside Road
 Edenton, NC 27932

Job 30136-30136A	Truss A2A	Truss Type ROOF TRUSS	Qty 2	Ply 1	60 PRINCE PLACE - ROOF	149963392
---------------------	--------------	--------------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:02 2022 Page 1

ID:BLJh112d3wvZK_wUdDgFCyrbmE-LMRySzUjFDqIYeILICL3Si?NOYe2dvwzUeE1Yszqny



Scale = 1:71.8




Plate Offsets (X, Y)--	[2:0-2-0,0-1-12], [6:0-4-4,0-2-4], [7:0-3-12,0-2-0], [9:0-3-0,0-4-4], [15:0-4-0,Edge], [16:0-8-0,Edge]
------------------------	--

LOADING (psf)	SPACING- 2-4-8	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.72	Vert(LL) -0.42 14-15 >999 240	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.87	Vert(CT) -0.51 14-15 >854 180	MT18HS	197/144
BCLL 0.0 *	Rep Stress Incr NO	WB 0.93	Horz(CT) 0.04 13 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-MS	Attic -0.34 15-16 430 360	Weight: 295 lb	FT = 20%

LUMBER-

TOP CHORD	2x4 SP No.2 or 2x4 SPF No.2 *Except* 7-10,10-12: 2x6 SP No.2
BOT CHORD	2x6 SP DSS *Except* 15-16: 2x10 SP DSS
WEBS	2x4 SP No.3 *Except* 5-16,9-15,5-8: 2x4 SP No.2 or 2x4 SPF No.2, 2-18,12-13: 2x6 SP No.2

BRACING-

TOP CHORD	Structural wood sheathing directly applied or 2-10-2 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-7.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 7-10-3 oc bracing: 16-17.
WEBS	1 Row at midpt 9-14
JOINTS	1 Brace at Jt(s): 19, 20

REACTIONS. (size) 18=0-3-8, 13=Mechanical
Max Horz 18=285(LC 9)
Max Grav 18=2307(LC 20), 13=2317(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2996/0, 3-5=-3000/0, 5-6=-727/94, 6-7=-532/93, 7-8=-745/89, 8-9=-2288/0, 9-11=-3159/12, 11-12=-3021/0, 2-18=-2180/0, 12-13=-2244/0

BOT CHORD 17-18=-192/658, 16-17=0/2574, 15-16=0/2477, 14-15=0/2459, 13-14=-3/279

WEBS 3-17=-485/126, 3-16=-407/308, 5-16=0/1083, 9-15=0/1131, 9-14=-419/475, 11-14=-534/271, 2-17=0/1946, 12-14=0/2266, 5-19=-1994/0, 19-20=-1985/0, 8-20=-1993/0

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-9-9, Interior(1) 2-9-9 to 16-0-0, Exterior(2) 16-0-0 to 26-2-5, Interior(1) 26-2-5 to 36-5-12 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) All plates are MT20 plates unless otherwise indicated.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Ceiling dead load (5.0 psf) on member(s). 8-9, 5-19, 19-20, 8-20; Wall dead load (5.0psf) on member(s).5-16, 9-15
 - 8) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 15-16
 - 9) Refer to girder(s) for truss to truss connections.
 - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - 11) Attic room checked for L/360 deflection.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job 30136-30136A	Truss A3G	Truss Type ROOF TRUSS	Qty 1	Ply 2	60 PRINCE PLACE - ROOF	149963393
---------------------	--------------	--------------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:04 2022 Page 1

ID:BLJh112d3wvZK_wUdDgFCyrbmE-HkZjEvnvr40nySktdOXX7412MM45rNGxyj8dkzqny



Scale = 1:71.8





Plate Offsets (X,Y)--	[2:0-3-0,0-1-12], [6:0-4-4,0-2-4], [7:0-3-12,0-2-0], [9:0-6-1,Edge], [10:0-4-0,Edge], [13:Edge,0-3-8], [15:0-2-12,0-3-4], [16:0-2-12,0-3-8]
-----------------------	---

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.58	Vert(LL)	-0.18 15-16	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.71	Vert(CT)	-0.37 16-17	>806	180		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.81	Horz(CT)	0.04 13	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MS	Attic	-0.10 15-16	1512	360	Weight: 559 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2 *Except* 7-10: 2x6 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-10-5 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-7.
BOT CHORD 2x6 SP DSS *Except* 15-16: 2x10 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 5-16,9-15,5-8: 2x4 SP No.2 or 2x4 SPF No.2	JOINTS 1 Brace at Jt(s): 20, 21

REACTIONS. (size) 18=0-3-8, 15=0-3-8, 13=0-5-8
 Max Horz 18=240(LC 5)
 Max Uplift 18=110(LC 8), 15=1064(LC 20), 13=80(LC 8)
 Max Grav 18=3855(LC 42), 15=1644(LC 7), 13=3696(LC 42)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-5435/165, 3-5=-5496/195, 5-6=-690/40, 6-7=-523/40, 7-8=-760/49, 8-9=-4048/199,
 9-11=-5561/250, 11-12=-4712/153, 2-18=-3749/145, 12-13=-3518/101
 BOT CHORD 17-18=-236/695, 16-17=-186/4587, 15-16=-107/4643, 14-15=-76/3830, 13-14=-11/252
 WEBS 3-17=-410/52, 3-16=-222/308, 5-16=-98/2576, 9-15=-228/2421, 15-19=-177/911,
 14-19=-1082/84, 11-19=-698/104, 2-17=0/3929, 12-14=-81/3727, 5-20=-4161/256,
 20-21=-4149/257, 8-21=-4163/257

- NOTES-**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
 Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x10 - 2 rows staggered at 0-9-0 oc.
 Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Ceiling dead load (5.0 psf) on member(s). 8-9, 5-20, 20-21, 8-21; Wall dead load (5.0psf) on member(s).5-16, 9-15
 - Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 15-16
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 13 except (jt=lb) 18=110, 15=1064.
 - Load case(s) 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.



Job	Truss	Truss Type	Qty	Ply	60 PRINCE PLACE - ROOF	149963393
30136-30136A	A3G	ROOF TRUSS	1	2	Job Reference (optional)	

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:04 2022 Page 2
ID:BLJh112d3wvZK_wUdDgFCyrbmE-HkZjteVnr40nySktdOXX74I2MM45rNGxyj8dkzqny

NOTES-

- 12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 13) This truss has large uplift reaction(s) from gravity load case(s). Proper connection is required to secure truss against upward movement at the bearings. Building designer must provide for uplift reactions indicated.
- 14) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1100 lb down at 24-10-4, and 2278 lb down and 203 lb up at 12-5-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 15) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-60, 2-6=-60, 6-7=-60, 7-8=-60, 8-9=-70, 9-12=-60, 16-18=-20, 15-16=-30, 13-15=-20, 5-8=-10
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=-2278(F) 15=-1100(F)
- 2) Dead + 0.75 Roof Live (balanced) + 0.75 Attic Floor: Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-50, 2-6=-50, 6-7=-50, 7-8=-50, 8-9=-60, 9-12=-50, 16-18=-20, 15-16=-90, 13-15=-20, 5-8=-10
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=-1991(F) 15=-1100(F)
- 3) Dead + Uninhabitable Attic Without Storage: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-2=-20, 2-6=-20, 6-7=-20, 7-8=-20, 8-9=-30, 9-12=-20, 16-18=-40, 15-16=-30, 13-15=-40, 5-8=-10
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=-1704(F) 15=-1100(F)
- 4) Dead + 0.6 MWFRS Wind (Pos. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-4, 2-6=-14, 6-7=18, 7-8=5, 8-9=-1, 9-12=5, 16-18=-12, 15-16=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-8, 2-6=2, 7-12=17, 2-18=12, 12-13=16
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=195(F) 15=-1100(F)
- 5) Dead + 0.6 MWFRS Wind (Pos. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=1, 2-6=5, 6-7=18, 7-8=-14, 8-9=-20, 9-12=-14, 16-18=-12, 15-16=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-13, 2-6=-17, 7-12=-2, 2-18=-16, 12-13=-12
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=195(F) 15=-1100(F)
- 6) Dead + 0.6 MWFRS Wind (Neg. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-27, 2-6=-31, 6-7=2, 7-8=-12, 8-9=-22, 9-12=-12, 16-18=-20, 15-16=-30, 13-15=-20, 5-8=-10
Horz: 1-2=7, 2-6=11, 7-12=8, 2-18=21, 12-13=7
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=203(F) 15=-1100(F)
- 7) Dead + 0.6 MWFRS Wind (Neg. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-7, 2-6=-12, 6-7=2, 7-8=-31, 8-9=-41, 9-12=-31, 16-18=-20, 15-16=-30, 13-15=-20, 5-8=-10
Horz: 1-2=-13, 2-6=-8, 7-12=-11, 2-18=-7, 12-13=-21
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=203(F) 15=-1100(F)
- 8) Dead + 0.6 MWFRS Wind (Pos. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=14, 2-6=18, 6-7=5, 7-8=5, 8-9=-1, 9-12=5, 16-18=-12, 15-16=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-26, 2-6=-30, 7-12=17, 2-18=10, 12-13=15
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=195(F) 15=-1100(F)
- 9) Dead + 0.6 MWFRS Wind (Pos. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=1, 2-6=5, 6-7=5, 7-8=18, 8-9=12, 9-12=18, 16-18=-12, 15-16=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-13, 2-6=-17, 7-12=30, 2-18=-15, 12-13=-10
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=195(F) 15=-1100(F)
- 10) Dead + 0.6 MWFRS Wind (Pos. Internal) 3rd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=14, 2-6=18, 6-7=5, 7-8=5, 8-9=-1, 9-12=5, 16-18=-12, 15-16=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-26, 2-6=-30, 7-12=17, 2-18=10, 12-13=15
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=195(F) 15=-1100(F)
- 11) Dead + 0.6 MWFRS Wind (Pos. Internal) 4th Parallel: Lumber Increase=1.60, Plate Increase=1.60

Continued on page 3

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	60 PRINCE PLACE - ROOF	149963393
30136-30136A	A3G	ROOF TRUSS	1	2	Job Reference (optional)	

84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:04 2022 Page 3
ID:BLJh112d3wvZK_wUdDgFCyrbmE-HkZjteVnr40nySktdOXX7412MM45rNGxyj8dkzqny

LOAD CASE(S) Standard

Uniform Loads (plf)

Vert: 1-2=1, 2-6=5, 6-7=5, 7-8=18, 8-9=12, 9-12=18, 16-18=-12, 15-16=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-13, 2-6=-17, 7-12=30, 2-18=-15, 12-13=-10
Drag: 5-16=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 16=195(F) 15=-1100(F)

12) Dead + 0.6 MWFRS Wind (Neg. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=6, 2-6=2, 6-7=-12, 7-8=-12, 8-9=-22, 9-12=-12, 16-18=-20, 15-16=-30, 13-15=-20, 5-8=-10
Horz: 1-2=-26, 2-6=-22, 7-12=8, 2-18=19, 12-13=6
Drag: 5-16=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 16=203(F) 15=-1100(F)

13) Dead + 0.6 MWFRS Wind (Neg. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-7, 2-6=-12, 6-7=-12, 7-8=2, 8-9=-8, 9-12=2, 16-18=-20, 15-16=-30, 13-15=-20, 5-8=-10
Horz: 1-2=-13, 2-6=-8, 7-12=22, 2-18=-6, 12-13=19
Drag: 5-16=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 16=203(F) 15=-1100(F)

15) Dead: Lumber Increase=1.00, Plate Increase=1.00

Uniform Loads (plf)

Vert: 1-2=-20, 2-6=-20, 6-7=-20, 7-8=-20, 8-9=-30, 9-12=-20, 16-18=-20, 15-16=-110, 13-15=-20, 5-8=-10
Drag: 5-16=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 16=-1129(F) 15=-1100(F)

16) Dead + 0.75 Roof Live (bal.) + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) Left): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-55, 2-6=-58, 6-7=-34, 7-8=-44, 8-9=-54, 9-12=-44, 16-18=-20, 15-16=-90, 13-15=-20, 5-8=-10
Horz: 1-2=5, 2-6=8, 7-12=6, 2-18=16, 12-13=5
Drag: 5-16=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 16=-15(F) 15=-1100(F)

17) Dead + 0.75 Roof Live (bal.) + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) Right): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-40, 2-6=-44, 6-7=-34, 7-8=-58, 8-9=-68, 9-12=-58, 16-18=-20, 15-16=-90, 13-15=-20, 5-8=-10
Horz: 1-2=-10, 2-6=-6, 7-12=8, 2-18=-5, 12-13=16
Drag: 5-16=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 16=-15(F) 15=-1100(F)

18) Dead + 0.75 Roof Live (bal.) + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) 1st Parallel): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-31, 2-6=-34, 6-7=-44, 7-8=-44, 8-9=-54, 9-12=-44, 16-18=-20, 15-16=-90, 13-15=-20, 5-8=-10
Horz: 1-2=-19, 2-6=-16, 7-12=6, 2-18=14, 12-13=5
Drag: 5-16=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 16=-15(F) 15=-1100(F)

19) Dead + 0.75 Roof Live (bal.) + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) 2nd Parallel): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-40, 2-6=-44, 6-7=-44, 7-8=-34, 8-9=-44, 9-12=-34, 16-18=-20, 15-16=-90, 13-15=-20, 5-8=-10
Horz: 1-2=-10, 2-6=-6, 7-12=16, 2-18=-5, 12-13=14
Drag: 5-16=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 16=-15(F) 15=-1100(F)

20) 1st Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-60, 2-6=-60, 6-7=-60, 7-8=-20, 8-9=-30, 9-12=-20, 16-18=-20, 15-16=-30, 13-15=-20, 5-8=-10
Drag: 5-16=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 16=-2278(F) 15=-1100(F)

21) 2nd Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-20, 2-6=-20, 6-7=-60, 7-8=-60, 8-9=-70, 9-12=-60, 16-18=-20, 15-16=-30, 13-15=-20, 5-8=-10
Drag: 5-16=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 16=-2278(F) 15=-1100(F)

22) 3rd Dead + 0.75 Roof Live (unbalanced) + 0.75 Attic Floor: Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-50, 2-6=-50, 6-7=-50, 7-8=-20, 8-9=-30, 9-12=-20, 16-18=-20, 15-16=-90, 13-15=-20, 5-8=-10
Drag: 5-16=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 16=-1991(F) 15=-1100(F)

23) 4th Dead + 0.75 Roof Live (unbalanced) + 0.75 Attic Floor: Lumber Increase=1.15, Plate Increase=1.15

Continued on page 4

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	60 PRINCE PLACE - ROOF	149963393
30136-30136A	A3G	ROOF TRUSS	1	2	Job Reference (optional)	

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:04 2022 Page 4
ID:BLJh112d3wvZK_wUdDgFCyrbmE-HkZjteVnr40nySktdOXX74I2MM45rNGxyj8dkzqny

LOAD CASE(S) Standard

- Uniform Loads (plf)
Vert: 1-2=-20, 2-6=-20, 6-7=-50, 7-8=-50, 8-9=-60, 9-12=-50, 16-18=-20, 15-16=-90, 13-15=-20, 5-8=-10
Drag: 5-16=-10, 9-15=-10
- Concentrated Loads (lb)
Vert: 16=-1991(F) 15=-1100(F)
- 24) Reversal: Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-60, 2-6=-60, 6-7=-60, 7-8=-60, 8-9=-70, 9-12=-60, 16-18=-20, 15-16=-30, 13-15=-20, 5-8=-10
Drag: 5-16=-10, 9-15=-10
- Concentrated Loads (lb)
Vert: 16=-1129(F) 15=-1100(F)
- 25) Reversal: Dead + 0.75 Roof Live (balanced) + 0.75 Attic Floor: Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-50, 2-6=-50, 6-7=-50, 7-8=-50, 8-9=-60, 9-12=-50, 16-18=-20, 15-16=-90, 13-15=-20, 5-8=-10
Drag: 5-16=-10, 9-15=-10
- Concentrated Loads (lb)
Vert: 16=-1129(F) 15=-1100(F)
- 27) Reversal: Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 1-2=-20, 2-6=-20, 6-7=-20, 7-8=-20, 8-9=-30, 9-12=-20, 16-18=-20, 15-16=-110, 13-15=-20, 5-8=-10
Drag: 5-16=-10, 9-15=-10
- Concentrated Loads (lb)
Vert: 16=-1129(F) 15=-1100(F)
- 28) Reversal: 1st Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-60, 2-6=-60, 6-7=-60, 7-8=-20, 8-9=-30, 9-12=-20, 16-18=-20, 15-16=-30, 13-15=-20, 5-8=-10
Drag: 5-16=-10, 9-15=-10
- Concentrated Loads (lb)
Vert: 16=-1129(F) 15=-1100(F)
- 29) Reversal: 2nd Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-20, 2-6=-20, 6-7=-60, 7-8=-60, 8-9=-70, 9-12=-60, 16-18=-20, 15-16=-30, 13-15=-20, 5-8=-10
Drag: 5-16=-10, 9-15=-10
- Concentrated Loads (lb)
Vert: 16=-1129(F) 15=-1100(F)
- 30) Reversal: 3rd Dead + 0.75 Roof Live (unbalanced) + 0.75 Attic Floor: Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-50, 2-6=-50, 6-7=-50, 7-8=-20, 8-9=-30, 9-12=-20, 16-18=-20, 15-16=-90, 13-15=-20, 5-8=-10
Drag: 5-16=-10, 9-15=-10
- Concentrated Loads (lb)
Vert: 16=-1129(F) 15=-1100(F)
- 31) Reversal: 4th Dead + 0.75 Roof Live (unbalanced) + 0.75 Attic Floor: Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-20, 2-6=-20, 6-7=-50, 7-8=-50, 8-9=-60, 9-12=-50, 16-18=-20, 15-16=-90, 13-15=-20, 5-8=-10
Drag: 5-16=-10, 9-15=-10
- Concentrated Loads (lb)
Vert: 16=-1129(F) 15=-1100(F)
- 32) Reversal: Dead + 0.6 MWFRS Wind (Pos. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-4, 2-6=-14, 6-7=18, 7-8=5, 8-9=-1, 9-12=5, 16-18=-12, 15-16=-18, 13-15=-12, 5-8=-6
Horz: 1-2=8, 2-6=2, 7-12=17, 2-18=12, 12-13=16
Drag: 5-16=-10, 9-15=-10
- Concentrated Loads (lb)
Vert: 16=-1539(F) 15=-1100(F)
- 33) Reversal: Dead + 0.6 MWFRS Wind (Pos. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=1, 2-6=5, 6-7=18, 7-8=-14, 8-9=-20, 9-12=-14, 16-18=-12, 15-16=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-13, 2-6=-17, 7-12=-2, 2-18=-16, 12-13=-12
Drag: 5-16=-10, 9-15=-10
- Concentrated Loads (lb)
Vert: 16=-1539(F) 15=-1100(F)
- 34) Reversal: Dead + 0.6 MWFRS Wind (Neg. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-27, 2-6=-31, 6-7=2, 7-8=-12, 8-9=-22, 9-12=-12, 16-18=-20, 15-16=-30, 13-15=-20, 5-8=-10
Horz: 1-2=7, 2-6=11, 7-12=8, 2-18=21, 12-13=7
Drag: 5-16=-10, 9-15=-10
- Concentrated Loads (lb)
Vert: 16=-1531(F) 15=-1100(F)
- 35) Reversal: Dead + 0.6 MWFRS Wind (Neg. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-7, 2-6=-12, 6-7=2, 7-8=-31, 8-9=-41, 9-12=-31, 16-18=-20, 15-16=-30, 13-15=-20, 5-8=-10
Horz: 1-2=-13, 2-6=-8, 7-12=-11, 2-18=-7, 12-13=-21
Drag: 5-16=-10, 9-15=-10
- Concentrated Loads (lb)
Vert: 16=-1531(F) 15=-1100(F)

Continued on page 5

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	60 PRINCE PLACE - ROOF	I49963393
30136-30136A	A3G	ROOF TRUSS	1	2	Job Reference (optional)	

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:04 2022 Page 5
ID:BLJh112d3wvZK_wUdDgFCyrbmE-HkZjteVnr40nySktdOXX74I2MM45rNGxyj8dkzqny

LOAD CASE(S) Standard

- 36) Reversal: Dead + 0.6 MWFRS Wind (Pos. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=14, 2-6=18, 6-7=5, 7-8=5, 8-9=-1, 9-12=5, 16-18=-12, 15-16=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-26, 2-6=-30, 7-12=17, 2-18=10, 12-13=15
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=-1539(F) 15=-1100(F)
- 37) Reversal: Dead + 0.6 MWFRS Wind (Pos. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=1, 2-6=5, 6-7=5, 7-8=18, 8-9=12, 9-12=18, 16-18=-12, 15-16=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-13, 2-6=-17, 7-12=30, 2-18=-15, 12-13=-10
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=-1539(F) 15=-1100(F)
- 38) Reversal: Dead + 0.6 MWFRS Wind (Pos. Internal) 3rd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=14, 2-6=18, 6-7=5, 7-8=5, 8-9=-1, 9-12=5, 16-18=-12, 15-16=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-26, 2-6=-30, 7-12=17, 2-18=10, 12-13=15
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=-1539(F) 15=-1100(F)
- 39) Reversal: Dead + 0.6 MWFRS Wind (Pos. Internal) 4th Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=1, 2-6=5, 6-7=5, 7-8=18, 8-9=12, 9-12=18, 16-18=-12, 15-16=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-13, 2-6=-17, 7-12=30, 2-18=-15, 12-13=-10
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=-1539(F) 15=-1100(F)
- 40) Reversal: Dead + 0.6 MWFRS Wind (Neg. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=6, 2-6=2, 6-7=-12, 7-8=-12, 8-9=-22, 9-12=-12, 16-18=-20, 15-16=-30, 13-15=-20, 5-8=-10
Horz: 1-2=-26, 2-6=-22, 7-12=8, 2-18=19, 12-13=6
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=-1531(F) 15=-1100(F)
- 41) Reversal: Dead + 0.6 MWFRS Wind (Neg. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-7, 2-6=-12, 6-7=-12, 7-8=2, 8-9=-8, 9-12=2, 16-18=-20, 15-16=-30, 13-15=-20, 5-8=-10
Horz: 1-2=-13, 2-6=-8, 7-12=22, 2-18=-6, 12-13=19
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=-1531(F) 15=-1100(F)
- 42) Reversal: Dead + 0.75 Roof Live (bal.) + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) Left): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-55, 2-6=-58, 6-7=-34, 7-8=-44, 8-9=-54, 9-12=-44, 16-18=-20, 15-16=-90, 13-15=-20, 5-8=-10
Horz: 1-2=5, 2-6=8, 7-12=6, 2-18=16, 12-13=5
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=-2076(F) 15=-1100(F)
- 43) Reversal: Dead + 0.75 Roof Live (bal.) + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) Right): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-40, 2-6=-44, 6-7=-34, 7-8=-58, 8-9=-68, 9-12=-58, 16-18=-20, 15-16=-90, 13-15=-20, 5-8=-10
Horz: 1-2=-10, 2-6=-6, 7-12=8, 2-18=5, 12-13=16
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=-2076(F) 15=-1100(F)
- 44) Reversal: Dead + 0.75 Roof Live (bal.) + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) 1st Parallel): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-31, 2-6=-34, 6-7=-44, 7-8=-44, 8-9=-54, 9-12=-44, 16-18=-20, 15-16=-90, 13-15=-20, 5-8=-10
Horz: 1-2=-19, 2-6=-16, 7-12=6, 2-18=14, 12-13=5
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=-2076(F) 15=-1100(F)
- 45) Reversal: Dead + 0.75 Roof Live (bal.) + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) 2nd Parallel): Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-40, 2-6=-44, 6-7=-44, 7-8=-34, 8-9=-44, 9-12=-34, 16-18=-20, 15-16=-90, 13-15=-20, 5-8=-10
Horz: 1-2=-10, 2-6=-6, 7-12=16, 2-18=5, 12-13=14
Drag: 5-16=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 16=-2076(F) 15=-1100(F)

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI 1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
Edenton, NC 27932

Job 30136-30136A	Truss A4G	Truss Type ROOF TRUSS	Qty 1	Ply 2	60 PRINCE PLACE - ROOF	149963394
---------------------	--------------	--------------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:06 2022 Page 1

ID:BLJh112d3wvZK_wUdDgFCyrbmE-D7hTIKX9JSKk1Gc6_2Q?cYA799_?ZoZZPGCFhdzqnyl



Scale = 1:71.9





Plate Offsets (X, Y)-- [2:0-2-14,0-2-0], [6:0-4-4,0-2-4], [7:0-3-12,0-2-0], [10:0-4-0,Edge], [15:0-2-12,0-3-8], [17:0-4-0,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.48	Vert(LL)	-0.15 17-18	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 1.00	Vert(CT)	-0.31 17-18	>667	180		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.64	Horz(CT)	0.03 13	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MS	Attic	-0.13 16-17	927	360	Weight: 572 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2 *Except* 7-10: 2x6 SP No.2	TOP CHORD Structural wood sheathing directly applied or 5-8-7 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-7.
BOT CHORD 2x6 SP No.2 *Except* 15-17: 2x10 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 5-17,9-15,5-8: 2x4 SP No.2 or 2x4 SPF No.2	JOINTS 1 Brace at Jt(s): 20, 21

REACTIONS. All bearings 0-3-8.
 (lb) - Max Horz 19=238(LC 5)
 Max Uplift All uplift 100 lb or less at joint(s) except 19=137(LC 8), 13=105(LC 8), 15=869(LC 20)
 Max Grav All reactions 250 lb or less at joint(s) except 19=3007(LC 1), 13=2818(LC 1), 16=1861(LC 42), 15=1676(LC 7)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-4229/202, 3-5=-4221/351, 5-6=-640/41, 6-7=-477/41, 7-8=-699/51, 8-9=-2981/236, 9-11=-3960/302, 11-12=-3849/194, 2-19=-2958/170, 12-13=-2740/126
 BOT CHORD 18-19=-237/537, 17-18=-168/3249, 16-17=-170/3304, 15-16=-170/3288, 14-15=-111/3140, 13-14=-20/255
 WEBS 3-18=-386/207, 5-18=-251/545, 5-17=-218/1550, 9-15=-270/1658, 11-15=-269/379, 11-14=-419/97, 2-18=-10/3078, 12-14=-108/2930, 5-20=-2842/299, 20-21=-2833/300, 8-21=-2843/300

- NOTES-**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
 Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x10 - 2 rows staggered at 0-9-0 oc.
 Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Ceiling dead load (5.0 psf) on member(s). 8-9, 5-20, 20-21, 8-21; Wall dead load (5.0psf) on member(s).5-17, 9-15
 - Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 16-17, 15-16
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 137 lb uplift at joint 19, 105 lb uplift at joint 13 and 69 lb uplift at joint 15.



Job	Truss	Truss Type	Qty	Ply	60 PRINCE PLACE - ROOF	149963394
30136-30136A	A4G	ROOF TRUSS	1	2	Job Reference (optional)	

84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:06 2022 Page 2
ID:BLJh112d3wvZK_wUdDgFCyrbmE-D7hTIKX9JSKk1Gc6_2Q?cYA799_?ZoZZPGCFhdzqnyl

NOTES-

- 11) Load case(s) 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
- 12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 13) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1100 lb down at 25-0-0, and 2261 lb down and 202 lb up at 12-5-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 14) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-60, 2-6=-60, 6-7=-60, 7-8=-60, 8-9=-70, 9-12=-60, 17-19=-20, 15-17=-30, 13-15=-20, 5-8=-10
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-2261(B) 15=-1100(F)
- 2) Dead + 0.75 Roof Live (balanced) + 0.75 Uninhab. Attic Storage + 0.75 Attic Floor: Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-50, 2-6=-50, 6-7=-50, 7-8=-50, 8-9=-60, 9-12=-50, 19-22=-20, 17-22=-50, 16-17=-90, 15-16=-90, 13-15=-20, 5-8=-10
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1976(B) 15=-1100(F)
- 3) Dead + Uninhabitable Attic Without Storage: Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-2=-20, 2-6=-20, 6-7=-20, 7-8=-20, 8-9=-30, 9-12=-20, 17-19=-40, 15-17=-30, 13-15=-40, 5-8=-10
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1691(B) 15=-1100(F)
- 4) Dead + 0.6 MWFRS Wind (Pos. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-4, 2-6=-14, 6-7=18, 7-8=5, 8-9=-1, 9-12=5, 17-19=-12, 15-17=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-8, 2-6=2, 7-12=17, 2-19=12, 12-13=16
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=194(B) 15=-1100(F)
- 5) Dead + 0.6 MWFRS Wind (Pos. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=1, 2-6=5, 6-7=18, 7-8=-14, 8-9=-20, 9-12=14, 17-19=-12, 15-17=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-13, 2-6=17, 7-12=-2, 2-19=-16, 12-13=-12
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=194(B) 15=-1100(F)
- 6) Dead + 0.6 MWFRS Wind (Neg. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-27, 2-6=-31, 6-7=2, 7-8=-12, 8-9=-22, 9-12=-12, 17-19=-20, 15-17=-30, 13-15=-20, 5-8=-10
Horz: 1-2=7, 2-6=11, 7-12=8, 2-19=21, 12-13=7
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=202(B) 15=-1100(F)
- 7) Dead + 0.6 MWFRS Wind (Neg. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-7, 2-6=-12, 6-7=2, 7-8=-31, 8-9=-41, 9-12=-31, 17-19=-20, 15-17=-30, 13-15=-20, 5-8=-10
Horz: 1-2=-13, 2-6=-8, 7-12=-11, 2-19=-7, 12-13=-21
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=202(B) 15=-1100(F)
- 8) Dead + 0.6 MWFRS Wind (Pos. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=14, 2-6=18, 6-7=5, 7-8=5, 8-9=-1, 9-12=5, 17-19=-12, 15-17=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-26, 2-6=-30, 7-12=17, 2-19=10, 12-13=15
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=194(B) 15=-1100(F)
- 9) Dead + 0.6 MWFRS Wind (Pos. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=1, 2-6=5, 6-7=5, 7-8=18, 8-9=12, 9-12=18, 17-19=-12, 15-17=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-13, 2-6=-17, 7-12=30, 2-19=-15, 12-13=-10
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=194(B) 15=-1100(F)
- 10) Dead + 0.6 MWFRS Wind (Pos. Internal) 3rd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=14, 2-6=18, 6-7=5, 7-8=5, 8-9=-1, 9-12=5, 17-19=-12, 15-17=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-26, 2-6=-30, 7-12=17, 2-19=10, 12-13=15
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=194(B) 15=-1100(F)
- 11) Dead + 0.6 MWFRS Wind (Pos. Internal) 4th Parallel: Lumber Increase=1.60, Plate Increase=1.60

Continued on page 3

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	60 PRINCE PLACE - ROOF	I49963394
30136-30136A	A4G	ROOF TRUSS	1	2	Job Reference (optional)	

84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:07 2022 Page 3
ID:BLJh1112d3wvZK_wUdDgFCyrbmE-hJErVgYn4mSbeQBjYixE9milvZKEIFpiewyoE3zqnyk

LOAD CASE(S) Standard

Uniform Loads (plf)

Vert: 1-2=1, 2-6=5, 6-7=5, 7-8=18, 8-9=12, 9-12=18, 17-19=-12, 15-17=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-13, 2-6=-17, 7-12=30, 2-19=-15, 12-13=-10
Drag: 5-17=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 17=194(B) 15=-1100(F)

- 12) Dead + 0.6 MWFRS Wind (Neg. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=6, 2-6=2, 6-7=-12, 7-8=-12, 8-9=-22, 9-12=-12, 17-19=-20, 15-17=-30, 13-15=-20, 5-8=-10
Horz: 1-2=-26, 2-6=-22, 7-12=8, 2-19=19, 12-13=6
Drag: 5-17=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 17=202(B) 15=-1100(F)

- 13) Dead + 0.6 MWFRS Wind (Neg. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-7, 2-6=-12, 6-7=-12, 7-8=2, 8-9=-8, 9-12=2, 17-19=-20, 15-17=-30, 13-15=-20, 5-8=-10
Horz: 1-2=-13, 2-6=-8, 7-12=22, 2-19=-6, 12-13=19
Drag: 5-17=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 17=202(B) 15=-1100(F)

- 15) Dead + Uninhabitable Attic Storage: Lumber Increase=1.00, Plate Increase=1.00

Uniform Loads (plf)

Vert: 1-2=-20, 2-6=-20, 6-7=-20, 7-8=-20, 8-9=-30, 9-12=-20, 19-22=-20, 17-22=-60, 16-17=-110, 15-16=-110, 13-15=-20, 5-8=-10
Drag: 5-17=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 17=-1121(B) 15=-1100(F)

- 16) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) Left): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-55, 2-6=-58, 6-7=-34, 7-8=-44, 8-9=-54, 9-12=-44, 19-22=-20, 17-22=-50, 16-17=-90, 15-16=-90, 13-15=-20, 5-8=-10
Horz: 1-2=5, 2-6=8, 7-12=6, 2-19=16, 12-13=5
Drag: 5-17=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 17=-15(B) 15=-1100(F)

- 17) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) Right): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-40, 2-6=-44, 6-7=-34, 7-8=-58, 8-9=-68, 9-12=-58, 19-22=-20, 17-22=-50, 16-17=-90, 15-16=-90, 13-15=-20, 5-8=-10
Horz: 1-2=-10, 2-6=-6, 7-12=8, 2-19=-5, 12-13=16
Drag: 5-17=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 17=-15(B) 15=-1100(F)

- 18) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) 1st Parallel): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-31, 2-6=-34, 6-7=-44, 7-8=-44, 8-9=-54, 9-12=-44, 19-22=-20, 17-22=-50, 16-17=-90, 15-16=-90, 13-15=-20, 5-8=-10
Horz: 1-2=-19, 2-6=-16, 7-12=6, 2-19=14, 12-13=5
Drag: 5-17=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 17=-15(B) 15=-1100(F)

- 19) Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) 2nd Parallel): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-40, 2-6=-44, 6-7=-44, 7-8=-34, 8-9=-44, 9-12=-34, 19-22=-20, 17-22=-50, 16-17=-90, 15-16=-90, 13-15=-20, 5-8=-10
Horz: 1-2=-10, 2-6=-6, 7-12=16, 2-19=-5, 12-13=-14
Drag: 5-17=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 17=-15(B) 15=-1100(F)

- 20) 1st Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-60, 2-6=-60, 6-7=-60, 7-8=-20, 8-9=-30, 9-12=-20, 17-19=-20, 15-17=-30, 13-15=-20, 5-8=-10
Drag: 5-17=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 17=-2261(B) 15=-1100(F)

- 21) 2nd Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-20, 2-6=-20, 6-7=-60, 7-8=-60, 8-9=-70, 9-12=-60, 17-19=-20, 15-17=-30, 13-15=-20, 5-8=-10
Drag: 5-17=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 17=-2261(B) 15=-1100(F)

- 22) 3rd Dead + 0.75 Roof Live (unbalanced) + 0.75 Uninhab. Attic Storage + 0.75 Attic Floor: Lumber Increase=1.15, Plate Increase=1.15

Continued on page 4

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	60 PRINCE PLACE - ROOF	149963394
30136-30136A	A4G	ROOF TRUSS	1	2	Job Reference (optional)	

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:07 2022 Page 4
ID:BLJh1112d3wvZK_wUdDgFCyrbmE-hJErVgYn4mSbeQBjYxE9milvZKEIFpiewyoE3zqnyk

LOAD CASE(S) Standard

- Uniform Loads (plf)
Vert: 1-2=-50, 2-6=-50, 6-7=-50, 7-8=-20, 8-9=-30, 9-12=-20, 19-22=-20, 17-22=-50, 16-17=-90, 15-16=-90, 13-15=-20, 5-8=-10
Drag: 5-17=-10, 9-15=-10
- Concentrated Loads (lb)
Vert: 17=-1976(B) 15=-1100(F)
- 23) 4th Dead + 0.75 Roof Live (unbalanced) + 0.75 Uninhab. Attic Storage + 0.75 Attic Floor: Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-20, 2-6=-20, 6-7=-50, 7-8=-50, 8-9=-60, 9-12=-50, 19-22=-20, 17-22=-50, 16-17=-90, 15-16=-90, 13-15=-20, 5-8=-10
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1976(B) 15=-1100(F)
- 24) Reversal: Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-60, 2-6=-60, 6-7=-60, 7-8=-60, 8-9=-70, 9-12=-60, 17-19=-20, 15-17=-30, 13-15=-20, 5-8=-10
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1121(B) 15=-1100(F)
- 25) Reversal: Dead + 0.75 Roof Live (balanced) + 0.75 Uninhab. Attic Storage + 0.75 Attic Floor: Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-50, 2-6=-50, 6-7=-50, 7-8=-50, 8-9=-60, 9-12=-50, 19-22=-20, 17-22=-50, 16-17=-90, 15-16=-90, 13-15=-20, 5-8=-10
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1121(B) 15=-1100(F)
- 27) Reversal: Dead + Uninhabitable Attic Storage: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 1-2=-20, 2-6=-20, 6-7=-20, 7-8=-20, 8-9=-30, 9-12=-20, 19-22=-20, 17-22=-60, 16-17=-110, 15-16=-110, 13-15=-20, 5-8=-10
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1121(B) 15=-1100(F)
- 28) Reversal: 1st Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-60, 2-6=-60, 6-7=-60, 7-8=-20, 8-9=-30, 9-12=-20, 17-19=-20, 15-17=-30, 13-15=-20, 5-8=-10
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1121(B) 15=-1100(F)
- 29) Reversal: 2nd Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-20, 2-6=-20, 6-7=-60, 7-8=-60, 8-9=-70, 9-12=-60, 17-19=-20, 15-17=-30, 13-15=-20, 5-8=-10
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1121(B) 15=-1100(F)
- 30) Reversal: 3rd Dead + 0.75 Roof Live (unbalanced) + 0.75 Uninhab. Attic Storage + 0.75 Attic Floor: Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-50, 2-6=-50, 6-7=-50, 7-8=-20, 8-9=-30, 9-12=-20, 19-22=-20, 17-22=-50, 16-17=-90, 15-16=-90, 13-15=-20, 5-8=-10
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1121(B) 15=-1100(F)
- 31) Reversal: 4th Dead + 0.75 Roof Live (unbalanced) + 0.75 Uninhab. Attic Storage + 0.75 Attic Floor: Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-20, 2-6=-20, 6-7=-50, 7-8=-50, 8-9=-60, 9-12=-50, 19-22=-20, 17-22=-50, 16-17=-90, 15-16=-90, 13-15=-20, 5-8=-10
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1121(B) 15=-1100(F)
- 32) Reversal: Dead + 0.6 MWFRS Wind (Pos. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-4, 2-6=-14, 6-7=18, 7-8=5, 8-9=-1, 9-12=5, 17-19=-12, 15-17=-18, 13-15=-12, 5-8=-6
Horz: 1-2=8, 2-6=2, 7-12=17, 2-19=12, 12-13=16
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1533(B) 15=-1100(F)
- 33) Reversal: Dead + 0.6 MWFRS Wind (Pos. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=1, 2-6=5, 6-7=18, 7-8=-14, 8-9=-20, 9-12=-14, 17-19=-12, 15-17=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-13, 2-6=-17, 7-12=-2, 2-19=-16, 12-13=-12
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1533(B) 15=-1100(F)
- 34) Reversal: Dead + 0.6 MWFRS Wind (Neg. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-27, 2-6=-31, 6-7=2, 7-8=-12, 8-9=-22, 9-12=-12, 17-19=-20, 15-17=-30, 13-15=-20, 5-8=-10
Horz: 1-2=7, 2-6=11, 7-12=8, 2-19=21, 12-13=7
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1525(B) 15=-1100(F)

Continued on page 5

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	60 PRINCE PLACE - ROOF	I49963394
30136-30136A	A4G	ROOF TRUSS	1	2	Job Reference (optional)	

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:07 2022 Page 5
ID:BLJh1112d3wvZK_wUdDgFCyrbmE-hJErVgYn4mSbeQBjYixE9milvZKEIFpiewyoE3zqnyk

LOAD CASE(S) Standard

- 35) Reversal: Dead + 0.6 MWFRS Wind (Neg. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-7, 2-6=-12, 6-7=2, 7-8=-31, 8-9=-41, 9-12=-31, 17-19=-20, 15-17=-30, 13-15=-20, 5-8=-10
Horz: 1-2=-13, 2-6=-8, 7-12=-11, 2-19=-7, 12-13=-21
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1525(B) 15=-1100(F)
- 36) Reversal: Dead + 0.6 MWFRS Wind (Pos. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=14, 2-6=18, 6-7=5, 7-8=5, 8-9=-1, 9-12=5, 17-19=-12, 15-17=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-26, 2-6=-30, 7-12=17, 2-19=10, 12-13=15
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1533(B) 15=-1100(F)
- 37) Reversal: Dead + 0.6 MWFRS Wind (Pos. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=1, 2-6=5, 6-7=5, 7-8=18, 8-9=12, 9-12=18, 17-19=-12, 15-17=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-13, 2-6=-17, 7-12=30, 2-19=-15, 12-13=-10
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1533(B) 15=-1100(F)
- 38) Reversal: Dead + 0.6 MWFRS Wind (Pos. Internal) 3rd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=14, 2-6=18, 6-7=5, 7-8=5, 8-9=-1, 9-12=5, 17-19=-12, 15-17=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-26, 2-6=-30, 7-12=17, 2-19=10, 12-13=15
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1533(B) 15=-1100(F)
- 39) Reversal: Dead + 0.6 MWFRS Wind (Pos. Internal) 4th Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=1, 2-6=5, 6-7=5, 7-8=18, 8-9=12, 9-12=18, 17-19=-12, 15-17=-18, 13-15=-12, 5-8=-6
Horz: 1-2=-13, 2-6=-17, 7-12=30, 2-19=-15, 12-13=-10
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1533(B) 15=-1100(F)
- 40) Reversal: Dead + 0.6 MWFRS Wind (Neg. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=6, 2-6=2, 6-7=-12, 7-8=-12, 8-9=-22, 9-12=-12, 17-19=-20, 15-17=-30, 13-15=-20, 5-8=-10
Horz: 1-2=-26, 2-6=-22, 7-12=8, 2-19=19, 12-13=6
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1525(B) 15=-1100(F)
- 41) Reversal: Dead + 0.6 MWFRS Wind (Neg. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-7, 2-6=-12, 6-7=-12, 7-8=2, 8-9=-8, 9-12=2, 17-19=-20, 15-17=-30, 13-15=-20, 5-8=-10
Horz: 1-2=-13, 2-6=-8, 7-12=22, 2-19=-6, 12-13=-19
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-1525(B) 15=-1100(F)
- 42) Reversal: Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) Left):
Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-55, 2-6=-58, 6-7=-34, 7-8=-44, 8-9=-54, 9-12=-44, 19-22=-20, 17-22=-50, 16-17=-90, 15-16=-90, 13-15=-20,
5-8=-10
Horz: 1-2=5, 2-6=8, 7-12=6, 2-19=16, 12-13=5
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-2066(B) 15=-1100(F)
- 43) Reversal: Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) Right):
Lumber Increase=1.60, Plate Increase=1.60
Uniform Loads (plf)
Vert: 1-2=-40, 2-6=-44, 6-7=-34, 7-8=-58, 8-9=-68, 9-12=-58, 19-22=-20, 17-22=-50, 16-17=-90, 15-16=-90, 13-15=-20,
5-8=-10
Horz: 1-2=-10, 2-6=-6, 7-12=-8, 2-19=-5, 12-13=-16
Drag: 5-17=-10, 9-15=-10
Concentrated Loads (lb)
Vert: 17=-2066(B) 15=-1100(F)
- 44) Reversal: Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) 1st Parallel): Lumber Increase=1.60, Plate Increase=1.60

Continued on page 6

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	60 PRINCE PLACE - ROOF	I49963394
30136-30136A	A4G	ROOF TRUSS	1	2	Job Reference (optional)	

84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:07 2022 Page 6
 ID:BLJh1112d3wvZK_wUdDgFCyrbmE-hJErVgYn4mSbeQBJYixE9milvZKEIFpiewyoE3zqnyk

LOAD CASE(S) Standard

Uniform Loads (plf)

Vert: 1-2=-31, 2-6=-34, 6-7=-44, 7-8=-44, 8-9=-54, 9-12=-44, 19-22=-20, 17-22=-50, 16-17=-90, 15-16=-90, 13-15=-20, 5-8=-10
 Horz: 1-2=-19, 2-6=-16, 7-12=6, 2-19=14, 12-13=5
 Drag: 5-17=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 17=-2066(B) 15=-1100(F)

45) Reversal: Dead + 0.75 Roof Live (bal.) + 0.75 Uninhab. Attic Storage + 0.75 Attic Floor + 0.75(0.6 MWFRS Wind (Neg. Int) 2nd Parallel): Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-2=-40, 2-6=-44, 6-7=-44, 7-8=-34, 8-9=-44, 9-12=-34, 19-22=-20, 17-22=-50, 16-17=-90, 15-16=-90, 13-15=-20, 5-8=-10
 Horz: 1-2=-10, 2-6=-6, 7-12=16, 2-19=-5, 12-13=-14
 Drag: 5-17=-10, 9-15=-10

Concentrated Loads (lb)

Vert: 17=-2066(B) 15=-1100(F)

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
 Edenton, NC 27932

Job 30136-30136A	Truss A5	Truss Type ROOF TRUSS	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	149963395
---------------------	-------------	--------------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:08 2022 Page 1

ID:BLJh112d3wvZK_wUdDgFCyrbmE-AWoDj0YPr3aSGZmV6TStHzFPYzhf1gissahMmVzqnyj



Scale = 1:71.9





Plate Offsets (X,Y)--	[2:0-2-0,0-2-0], [6:0-4-4,0-2-4], [7:0-3-12,0-2-0], [13:0-3-0,0-2-0], [15:0-2-12,0-2-12], [17:0-8-0,Edge]
-----------------------	---

LOADING (psf)	SPACING-	2-5-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.68	Vert(LL)	-0.40 14-15	>569	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.86	Vert(CT)	-0.58 14-15	>400	180	MT18HS	197/144
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.72	Horz(CT)	0.03 13	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MS	Attic	-0.30 16-17	401	360		
								Weight: 296 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2 *Except*
7-10,10-12: 2x6 SP No.2
BOT CHORD 2x6 SP DSS *Except*
15-17: 2x10 SP No.2
WEBS 2x4 SP No.3 *Except*
5-17,9-15,5-8: 2x4 SP No.2 or 2x4 SPF No.2, 2-19,12-13: 2x6 SP No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-5-2 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-7.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 5-18, 5-17
JOINTS 1 Brace at Jt(s): 20, 21

REACTIONS. (size) 19=0-3-8, 13=0-3-8, 16=0-3-8
Max Horz 19=288(LC 9)
Max Grav 19=1782(LC 1), 13=1789(LC 21), 16=1267(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2274/0, 3-5=-2264/91, 5-6=-741/98, 6-7=-539/97, 7-8=-739/95, 8-9=-1617/70, 9-11=-2089/0, 11-12=-2465/0, 2-19=-1674/27, 12-13=-1752/0
BOT CHORD 18-19=-200/566, 17-18=0/1625, 16-17=0/1645, 15-16=0/1643, 14-15=0/1976, 13-14=-13/277
WEBS 3-18=-451/251, 5-18=-365/674, 5-17=-319/619, 9-15=0/485, 11-15=-577/243, 2-18=0/1449, 12-14=0/1757, 5-20=-1255/56, 20-21=-1244/56, 8-21=-1248/53

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-9-14, Interior(1) 2-9-14 to 16-0-0, Exterior(2) 16-0-0 to 26-2-13, Interior(1) 26-2-13 to 36-9-4 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) All plates are MT20 plates unless otherwise indicated.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Ceiling dead load (5.0 psf) on member(s). 8-9, 5-20, 20-21, 8-21; Wall dead load (5.0psf) on member(s).5-17, 9-15
 - 8) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 16-17, 15-16
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - 10) Attic room checked for L/360 deflection.



Job 30136-30136A	Truss A6A	Truss Type ROOF TRUSS	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	149963397
---------------------	--------------	--------------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:11 2022 Page 1

ID:BLJh1112d3wvZK_wUdDgFCyrbmE-a5UML1b18_y171U4nb0AJctwoAjME1hYYw0Nqzqnyg

0-10-8	6-4-6	8-1-12	12-5-4	16-0-0	21-0-0	24-10-4	28-10-4	31-10-4	32-0-0	37-0-0	37-10-8
0-10-8	6-4-6	1-9-6	4-3-8	3-6-12	5-0-0	3-10-4	4-0-0	3-0-0	0-1-12	5-0-0	0-10-8

Scale = 1:71.8




Plate Offsets (X, Y)--	[2:0-2-0,0-2-0], [6:0-4-4,0-2-4], [7:0-3-12,0-2-0], [14:0-3-0,0-2-0], [16:0-2-12,0-2-12], [18:0-8-0,Edge]
------------------------	---

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-5-0	TC 0.68	Vert(LL)	-0.40	15-16	>571	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.86	Vert(CT)	-0.57	15-16	>402	MT18HS	197/144
BCLL 0.0 *	Lumber DOL 1.15	WB 0.71	Horz(CT)	0.03	14	n/a		
BCDL 10.0	Rep Stress Incr NO	Matrix-MS	Attic	-0.30	17-18	401		
	Code IRC2015/TPI2014					360	Weight: 299 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2 *Except* 7-10,10-13: 2x6 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-5-3 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-7.
BOT CHORD 2x6 SP DSS *Except* 16-18: 2x10 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 5-18,9-16,5-8: 2x4 SP No.2 or 2x4 SPF No.2, 2-20,12-14: 2x6 SP No.2	WEBS 1 Row at midpt 5-19, 5-18
	JOINTS 1 Brace at Jt(s): 21, 22

REACTIONS. (size) 20=0-3-8, 14=0-3-8, 17=0-3-8
 Max Horz 20=295(LC 10)
 Max Grav 20=1781(LC 1), 14=1864(LC 21), 17=1268(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-2273/0, 3-5=-2262/93, 5-6=-740/98, 6-7=-538/97, 7-8=-739/95, 8-9=-1616/72, 9-11=-2085/0, 11-12=-2460/0, 2-20=-1673/29, 12-14=-1827/8
 BOT CHORD 19-20=-193/574, 18-19=0/1623, 17-18=0/1643, 16-17=0/1641, 15-16=0/1960, 14-15=0/319
 WEBS 3-19=-451/251, 5-19=-364/674, 5-18=-319/618, 9-16=0/483, 11-16=-565/242, 2-19=0/1449, 12-15=0/1711, 5-21=-1254/58, 21-22=-1244/58, 8-22=-1247/55

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-10-8 to 2-9-14, Interior(1) 2-9-14 to 16-0-0, Exterior(2) 16-0-0 to 26-2-13, Interior(1) 26-2-13 to 37-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) All plates are MT20 plates unless otherwise indicated.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Ceiling dead load (5.0 psf) on member(s). 8-9, 5-21, 21-22, 8-22; Wall dead load (5.0psf) on member(s).5-18, 9-16
 - 8) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 17-18, 16-17
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - 10) Attic room checked for L/360 deflection.




Job	Truss	Truss Type	Qty	Ply	60 PRINCE PLACE - ROOF	I49963398
30136-30136A	A7E	ROOF TRUSS	1	1	Job Reference (optional)	

84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:13 2022 Page 1

ID:BLJh112d3wvZK_wUdDgFCyrbmE-WTc6mjcYgcCkMLeTu02e00yJw_Sii37b0rP7Rjzqny



Scale = 1:83.1

Plate Offsets (X,Y)--	[2:0-3-0,0-1-8], [6:0-4-4,0-2-4], [7:0-3-12,0-2-0], [10:0-4-0,Edge], [12:0-2-14,0-2-0], [19:0-8-0,Edge], [20:0-3-0,0-3-0]
-----------------------	---

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.51	Vert(LL)	-0.11 19-20	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.67	Vert(CT)	-0.15 19-20	>957	180	MT18HS	244/190
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.20	Horz(CT)	0.00 14	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MS	Attic	-0.11 19-20	1314	360		Weight: 362 lb FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2 *Except* 7-10: 2x6 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-7.
BOT CHORD 2x6 SP DSS *Except* 19-20: 2x10 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except* 12-14: 2x4 SP No.2 or 2x4 SPF No.2	WEBS 1 Row at midpt 5-23, 5-20, 9-19
OTHERS 2x4 SP No.3	JOINTS 1 Brace at Jt(s): 25, 26

REACTIONS. All bearings 18-6-0.
 (lb) - Max Horz 24=-243(LC 6)
 Max Uplift All uplift 100 lb or less at joint(s) 15, 16 except 23=-107(LC 8), 21=-619(LC 14), 18=-867(LC 14)
 Max Grav All reactions 250 lb or less at joint(s) 22 except 24=350(LC 1), 20=1528(LC 14), 23=701(LC 1), 19=1774(LC 17), 14=363(LC 1), 15=496(LC 1), 17=264(LC 14)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 5-6=-536/37, 6-7=-385/37, 7-8=-555/46, 8-9=-425/85, 9-11=-369/87, 11-12=-278/33, 2-24=-292/12, 12-14=-318/19
 BOT CHORD 23-24=-229/351, 22-23=-56/259, 21-22=-56/259, 20-21=-56/259, 19-20=-55/254
 WEBS 3-23=-395/203, 5-20=-439/98, 9-19=-636/111, 11-15=-415/65

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - All plates are 1.5x4 MT20 unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Ceiling dead load (5.0 psf) on member(s). 8-9, 5-25, 25-26, 8-26; Wall dead load (5.0psf) on member(s).5-20, 9-19
 - Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 19-20
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 15, 16 except (jt=lb) 23=107, 21=619, 18=867.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - Attic room checked for L/360 deflection.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ENGINEERING BY
TRENCO
 A MiTek Affiliate
 818 Soundside Road
 Edenton, NC 27932


Job 30136-30136A	Truss B1	Truss Type KINGPOST	Qty 4	Ply 1	60 PRINCE PLACE - ROOF Job Reference (optional)	149963399
---------------------	-------------	------------------------	----------	----------	--	-----------

84 Components (Dunn),

Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:14 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYtyw97h-g9U_3dARvKb_UDfSjZtXEVTVOrqRYikFV8gz9zqnyd



Scale = 1:29.1

Plate Offsets (X,Y)--	[1:0-0-0,0-0-9]								
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.52	Vert(LL)	-0.06 4-10	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.49	Vert(CT)	-0.11 4-10	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.11	Horz(CT)	0.01 3	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MS					Weight: 48 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2 or 2x4 SPF No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	2x4 SP No.2 or 2x4 SPF No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS.	(size) 1=0-3-8, 3=0-3-8
	Max Horz 1=-81(LC 8)
	Max Uplift 1=-9(LC 12), 3=-10(LC 13)
	Max Grav 1=500(LC 1), 3=500(LC 1)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	1-2=-618/60, 2-3=-616/61
BOT CHORD	1-4=0/436, 3-4=0/436
WEBS	2-4=0/300

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 6-2-8, Exterior(2) 6-2-8 to 9-2-8, Interior(1) 9-2-8 to 12-5-15 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Bearing at joint(s) 3 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
 - Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.




Job 30136-30136A	Truss C1E	Truss Type GABLE	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	149963400
---------------------	--------------	---------------------	----------	----------	------------------------	-----------

84 Components (Dunn),

Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:15 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-SsjtBPeoBDSSceor0R46TR1kGnGSA?buT9uDWbzqny



3x4 =

Scale = 1:37.8




Plate Offsets (X, Y)--	[6:0-2-0,Edge]								
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.14	Vert(LL)	-0.00	11	n/r	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.08	Vert(CT)	-0.00	11	n/r		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.07	Horz(CT)	0.00	12	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-R						
								Weight: 83 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 13-0-0.
(lb) - Max Horz 19=151(LC 10)
Max Uplift All uplift 100 lb or less at joint(s) 19, 12, 17, 14 except 18=127(LC 12), 13=124(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 19, 12, 16, 17, 18, 15, 14, 13

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) -0-10-8 to 2-1-8, Exterior(2) 2-1-8 to 6-6-0, Corner(3) 6-6-0 to 9-7-12, Exterior(2) 9-7-12 to 13-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) All plates are 1.5x4 MT20 unless otherwise indicated.
- 5) Gable requires continuous bottom chord bearing.
- 6) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- 7) Gable studs spaced at 2-0-0 oc.
- 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 19, 12, 17, 14 except (jt=lb) 18=127, 13=124.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932


Job 30136-30136A	Truss C2	Truss Type Common Structural Gable	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	149963401
---------------------	-------------	---------------------------------------	----------	----------	------------------------	-----------

84 Components (Dunn),

Dunn, NC - 28334,


8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:16 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-x2HFOlRyXaJDoN1a8bL0fapsBSPvL?1ipdn22zqnyb



4x4 =

Scale = 1:58.4



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.53	Vert(LL)	-0.20 13-15	>757	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.74	Vert(CT)	-0.41 13-15	>372	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.58	Horz(CT)	0.02 8	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MS					Weight: 155 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
 BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
 WEBS 2x4 SP No.3
 OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 6-7-0 except (jt=length) 15=0-3-8, 12=0-3-8.
 (lb) - Max Horz 15=201(LC 11)
 Max Uplift All uplift 100 lb or less at joint(s) 15, 8 except 12=118(LC 3)
 Max Grav All reactions 250 lb or less at joint(s) 11, 10, 9 except 15=804(LC 1), 8=748(LC 1)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-293/88, 3-4=-621/113, 4-5=-621/113, 2-15=-322/106, 6-8=-268/136
 BOT CHORD 13-15=-55/563, 12-13=0/506, 11-12=0/506, 10-11=0/506, 9-10=0/506, 8-9=0/506
 WEBS 4-13=-57/450, 3-15=-549/28, 5-8=-629/0

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 9-7-12, Exterior(2) 9-7-12 to 12-7-12, Interior(1) 12-7-12 to 20-2-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 1.5x4 MT20 unless otherwise indicated.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 15, 8 except (jt=lb) 12=118.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
 Edenton, NC 27932

Job 30136-30136A	Truss C3G	Truss Type FAN	Qty 1	Ply 2	60 PRINCE PLACE - ROOF Job Reference (optional)	149963402
---------------------	--------------	-------------------	----------	----------	--	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:18 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-tRP?pRghU8r1T6XQhZep54f9X?4yNBdK976t7wzqnyZ



5x9 ||

Scale = 1:56.9




Plate Offsets (X, Y)-- [9:0-3-8,0-6-4], [10:0-3-8,0-5-8], [11:0-6-0,0-6-0], [12:0-3-8,0-5-8], [13:0-3-8,0-6-4]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.52	Vert(LL)	-0.08	12	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.99	Vert(CT)	-0.15	11-12	>999		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.76	Horz(CT)	0.04	8	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MS					Weight: 401 lb	FT = 20%

LUMBER-
 TOP CHORD 2x6 SP No.2
 BOT CHORD 2x8 SP No.2
 WEBS 2x4 SP No.3 *Except*
 4-11: 2x4 SP No.1, 1-13,7-9: 2x4 SP No.2 or 2x4 SPF No.2
 OTHERS 2x6 SP No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 4-11-11 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 14=0-3-8, 8=0-3-8
 Max Horz 14=-178(LC 23)
 Max Grav 14=8878(LC 2), 8=8530(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-9393/0, 2-3=-8543/0, 3-4=-6888/0, 4-5=-6887/0, 5-6=-8511/0, 6-7=-9145/0,
 1-14=-7874/0, 7-8=-7671/0
 BOT CHORD 13-14=0/1158, 12-13=0/7105, 11-12=0/6524, 10-11=0/6497, 9-10=0/6918, 8-9=0/1111
 WEBS 4-11=0/8370, 5-11=-2563/0, 5-10=0/3304, 6-10=-654/0, 6-9=0/835, 3-11=-2623/0,
 3-12=0/3373, 2-12=-899/0, 2-13=0/1164, 1-13=0/6193, 7-9=0/6046

- NOTES-**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
 Bottom chords connected as follows: 2x8 - 2 rows staggered at 0-4-0 oc.
 Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Bearing at joint(s) 14, 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1922 lb down at 2-0-12, 1922 lb down at 4-0-12, 1922 lb down at 6-0-12, 1922 lb down at 8-0-12, 1922 lb down at 10-0-12, 1922 lb down at 12-0-12, and 2280 lb down at 14-0-12, and 2280 lb down at 16-10-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard



January 31, 2022

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
 Edenton, NC 27932

Job 30136-30136A	Truss C3G	Truss Type FAN	Qty 1	Ply 2	60 PRINCE PLACE - ROOF I49963402 Job Reference (optional)
---------------------	--------------	-------------------	----------	-----------------	---

84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:18 2022 Page 2
ID:6ghGmW2wjVRjEest?1fGYTyw97h-tRP?pRghU8r1T6XQhZep54f9X?4yNBdK976t7wzqnyZ

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-4=-60, 4-7=-60, 8-14=-20

Concentrated Loads (lb)

Vert: 15=-1647(F) 16=-1647(F) 17=-1647(F) 18=-1647(F) 19=-1647(F) 20=-1647(F) 21=-1952(F) 22=-1952(F)

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932


Job 30136-30136A	Truss D1E	Truss Type GABLE	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	149963403
---------------------	--------------	---------------------	----------	----------	------------------------	-----------

84 Components (Dunn),

Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:20 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-ppXmE6ix0I5liPgpp_gHAVITzoxlrEfdRb_BpzqnyX



Scale = 1:53.2




Plate Offsets (X,Y)--	[2:0-2-0,0-1-12], [6:0-2-0,0-1-13], [11:0-2-0,0-1-13], [15:0-2-0,0-1-12], [17:Edge,0-1-8]
-----------------------	---

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.65	Vert(LL)	-0.00	16	n/r	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.29	Vert(CT)	-0.00	16	n/r		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.15	Horz(CT)	-0.00	17	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-R						
								Weight: 191 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (10-0-0 max.): 6-11.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 8-23, 7-24, 9-22, 10-21
OTHERS 2x4 SP No.3	

REACTIONS. All bearings 21-0-0.
 (lb) - Max Horz 29=227(LC 10)
 Max Uplift All uplift 100 lb or less at joint(s) 23, 26, 27, 22, 19 except 29=348(LC 8), 17=343(LC 9), 28=348(LC 9), 18=344(LC 8)
 Max Grav All reactions 250 lb or less at joint(s) 23, 24, 26, 27, 22, 21, 20, 19 except 29=400(LC 11), 17=395(LC 10), 28=455(LC 10), 18=451(LC 11)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) -0-10-8 to 2-1-8, Exterior(2) 2-1-8 to 6-6-0, Corner(3) 6-6-0 to 9-3-8, Exterior(2) 9-3-8 to 14-6-0, Corner(3) 14-6-0 to 17-8-8, Exterior(2) 17-8-8 to 21-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - Provide adequate drainage to prevent water ponding.
 - All plates are 1.5x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 23, 26, 27, 22, 19 except (jt=lb) 29=348, 17=343, 28=348, 18=344.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



January 31, 2022


Job 30136-30136A	Truss D2	Truss Type Common	Qty 2	Ply 1	60 PRINCE PLACE - ROOF	149963404
---------------------	-------------	----------------------	----------	----------	------------------------	-----------

84 Components (Dunn),

Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:21 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-H058SSiZn3DckZF?MhBWjHfCD9agBms5LYjFzqnyW



Scale = 1:52.8

Plate Offsets (X,Y)-- [2:0-1-0,0-1-12], [3:0-2-12,0-4-0], [4:0-4-4,0-3-0], [5:0-1-0,0-1-12]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.58	Vert(LL)	-0.13	8-9	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.51	Vert(CT)	-0.19	8-9	>999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.19	Horz(CT)	0.01	7	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MS						
								Weight: 154 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2 *Except*
3-4: 2x6 SP No.2
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 3-9, 3-8, 4-8

REACTIONS.

(size) 11=0-3-8, 7=0-3-8
Max Horz 11=226(LC 11)
Max Grav 11=890(LC 1), 7=890(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-678/109, 3-4=-426/137, 4-5=-678/108, 2-11=-834/110, 5-7=-834/110
BOT CHORD 8-9=-90/484
WEBS 2-9=-27/471, 5-8=-28/450

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 6-6-0, Exterior(2) 6-6-0 to 10-8-15, Interior(1) 10-8-15 to 14-6-0, Exterior(2) 14-6-0 to 18-8-15, Interior(1) 18-8-15 to 21-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

818 Soundside Road
Edenton, NC 27932

Job 30136-30136A	Truss D3	Truss Type Common	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	149963405
---------------------	-------------	----------------------	----------	----------	------------------------	-----------

84 Components (Dunn),

Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:22 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-lCeWfojCYNLTxjqBwPllFwqqTcZNUJ7Nw4l45GhzqnyV




Plate Offsets (X,Y)-- [2:0-2-12,0-4-0], [3:0-4-4,0-3-0], [4:0-1-0,0-1-12]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.59	Vert(LL)	-0.13	7-8	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.51	Vert(CT)	-0.19	7-8	>999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.20	Horz(CT)	0.01	6	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MS						
								Weight: 152 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2 *Except*
2-3: 2x6 SP No.2
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-8-1 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 2-3.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 2-8, 2-7, 3-7

REACTIONS.

(size) 10=0-3-8, 6=0-3-8
Max Horz 10=-221(LC 10)
Max Grav 10=827(LC 1), 6=891(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-676/101, 2-3=-427/134, 3-4=-679/105, 1-10=-771/86, 4-6=-835/108
BOT CHORD 7-8=-88/487
WEBS 1-8=-28/481, 4-7=-26/451

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 3-1-12, Interior(1) 3-1-12 to 6-6-0, Exterior(2) 6-6-0 to 10-8-15, Interior(1) 10-8-15 to 14-6-0, Exterior(2) 14-6-0 to 18-8-15, Interior(1) 18-8-15 to 21-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

818 Soundside Road
Edenton, NC 27932


Job 30136-30136A	Truss D4	Truss Type Common	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	149963406
---------------------	-------------	----------------------	----------	----------	------------------------	-----------

84 Components (Dunn),

Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:23 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-DOCus8kqJgTKZtPOU6E_o7N?M0vc2ac3JPqeo8zqnyU



Scale = 1:52.8

Plate Offsets (X,Y)--	[2:0-2-12,0-4-0], [3:0-4-4,0-3-0]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.58	Vert(LL) -0.13 6-7 >999 240	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.51	Vert(CT) -0.19 6-7 >999 180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.20	Horz(CT) 0.01 5 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-MS		Weight: 150 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2 *Except* 2-3: 2x6 SP No.2	TOP CHORD Structural wood sheathing directly applied or 5-7-14 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 2-3.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 2-7, 2-6, 3-6

REACTIONS. (size) 9=0-3-8, 5=0-3-8
 Max Horz 9=210(LC 9)
 Max Grav 9=828(LC 1), 5=828(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-678/98, 2-3=-431/131, 3-4=-678/98, 1-9=-773/83, 4-5=-773/83
 BOT CHORD 6-7=-94/480
 WEBS 1-7=-26/481, 4-6=-26/464

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 3-1-12, Interior(1) 3-1-12 to 6-6-0, Exterior(2) 6-6-0 to 10-8-15, Interior(1) 10-8-15 to 14-6-0, Exterior(2) 14-6-0 to 18-8-15, Interior(1) 18-8-15 to 20-10-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.




January 31, 2022

Job 30136-30136A	Truss FT1	Truss Type FLAT GIRDER	Qty 1	Ply 2	60 PRINCE PLACE - ROOF	149963407
---------------------	--------------	---------------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:24 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTYw97h-ibmG4UIS4_bBB1_a2qDLLv6rQLxntdDY3ZCKazqnyT



Scale = 1:18.0

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.79	Vert(LL)	-0.05	5	>999	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.31	Vert(CT)	-0.09	5	>999		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.85	Horz(CT)	0.00	4	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MS					Weight: 127 lb	FT = 20%

LUMBER-
 TOP CHORD 2x6 SP No.2
 BOT CHORD 2x6 SP No.2
 WEBS 2x4 SP No.3

BRACING-
 TOP CHORD 2-0-0 oc purlins (5-11-5 max.): 1-3, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 6=Mechanical, 4=Mechanical
 Max Horz 6=44(LC 4)
 Max Uplift 6=183(LC 4), 4=182(LC 5)
 Max Grav 6=2312(LC 15), 4=2299(LC 15)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-6=-2127/194, 1-2=-4294/331, 2-3=-4294/331, 3-4=-2112/191
 BOT CHORD 5-6=-59/382, 4-5=-35/328
 WEBS 1-5=-327/4116, 2-5=-2784/291, 3-5=-332/4195

NOTES-

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
 Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
 Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=183, 4=182.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1027 lb down and 75 lb up at 1-9-12, 1027 lb down and 75 lb up at 3-9-12, and 1027 lb down and 75 lb up at 5-9-12, and 1027 lb down and 75 lb up at 7-9-12 on top chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
 Uniform Loads (plf)
 Vert: 1-3=-60, 4-6=-20



January 31, 2022

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
 Edenton, NC 27932

Job 30136-30136A	Truss FT1	Truss Type FLAT GIRDER	Qty 1	Ply 2	60 PRINCE PLACE - ROOF Job Reference (optional)	I49963407
---------------------	--------------	---------------------------	----------	-----------------	--	-----------

84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:24 2022 Page 2
ID:6ghGmW2wjVRjEest?1fGYTyw97h-ibmG4UIS4_bBB1_a2qlDLLv6rQLxntdDY3ZCKazqnyT

LOAD CASE(S) Standard
Concentrated Loads (lb)
Vert: 7=-957 8=-957 9=-957 10=-957

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601





818 Soundside Road
Edenton, NC 27932

Job 30136-30136A	Truss H1	Truss Type Half Hip	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	149963408
---------------------	-------------	------------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:25 2022 Page 1



Scale = 1:14.5




Plate Offsets (X,Y)--	[3:0-2-0,0-2-0]								
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.10	Vert(LL) 0.00	6	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.06	Vert(CT) -0.00	5-6	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT) -0.01	4	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MR					Weight: 10 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
WEBS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-1-8 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 4=Mechanical, 6=0-3-0, 5=Mechanical
Max Horz 6=39(LC 9)
Max Uplift 4=-21(LC 12), 5=-1(LC 12)
Max Grav 4=43(LC 1), 6=154(LC 1), 5=36(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 5.
 - 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.




January 31, 2022

Job 30136-30136A	Truss J1E	Truss Type Jack-Open Supported Gable	Qty 1	Ply 1	60 PRINCE PLACE - ROOF Job Reference (optional)	149963411
---------------------	--------------	---	----------	----------	--	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:27 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-6ASPiWnKNvzI2Uj9jylwyZxOddO9_RifE1osvxzqnyQ



Scale = 1:8.9

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	0.00	1	n/r	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.02	Vert(CT)	-0.00	1	n/r		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	4	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-R					Weight: 9 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
 BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
 WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 5=1-9-12, 4=1-9-12
 Max Horz 5=30(LC 9)
 Max Uplift 5=-40(LC 8), 4=-3(LC 12)
 Max Grav 5=148(LC 1), 4=50(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- 4) Gable studs spaced at 2-0-0 oc.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 4.
- 8) Non Standard bearing condition. Review required.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
 Edenton, NC 27932

Job 30136-30136A	Truss M1	Truss Type Monopitch	Qty 5	Ply 1	60 PRINCE PLACE - ROOF	I49963412
---------------------	-------------	-------------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:28 2022 Page 1
ID:6ghGmW2wjVRjEest?1fGYTyw97h-aM0nwsy7C5cgeLLHfp9VB4q1YGjsZoThXPTLzqnyP



Scale = 1:19.6




Plate Offsets (X,Y)--	[2:0-0-12,Edge]						
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d
TCLL 20.0	Plate Grip DOL	1.15	TC 0.69	Vert(LL)	-0.20	5-8	>573
TCDL 10.0	Lumber DOL	1.15	BC 0.73	Vert(CT)	-0.45	5-8	>258
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.15	Horz(CT)	0.01	5	n/a
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MS				
							PLATES
							MT20
							GRIP
							197/144
							Weight: 39 lb
							FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
WEBS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-10-6 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 2=0-3-0, 5=Mechanical
Max Horz 2=81(LC 11)
Max Uplift 2=-52(LC 8), 5=-34(LC 12)
Max Grav 2=442(LC 1), 5=385(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-561/79
BOT CHORD 2-5=-102/528
WEBS 3-5=-573/123

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 9-8-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 5.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job 30136-30136A	Truss M1E	Truss Type Monopitch Supported Gable	Qty 2	Ply 1	60 PRINCE PLACE - ROOF Job Reference (optional)	I49963413
---------------------	--------------	---	----------	----------	--	-----------


84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:29 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-2YZ97BpbuWDTHotXqNKO2Od7SR2JSLYyhLHz?ozqnyO
9-10-0
9-10-0

-0-10-8
0-10-8

Scale = 1:19.6



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.15	Vert(LL)	-0.00	1	n/r	120	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.11	Vert(CT)	0.00	1	n/r	120		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.04	Horz(CT)	0.00	7	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S						Weight: 40 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 9-10-0.
(lb) - Max Horz 2=81(LC 9)
Max Uplift All uplift 100 lb or less at joint(s) 7, 2, 8, 9, 10
Max Grav All reactions 250 lb or less at joint(s) 7, 2, 8, 9 except 10=301(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) -0-10-8 to 2-1-8, Exterior(2) 2-1-8 to 9-8-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) All plates are 1.5x4 MT20 unless otherwise indicated.
- 4) Gable requires continuous bottom chord bearing.
- 5) Gable studs spaced at 2-0-0 oc.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7, 2, 8, 9, 10.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
Edenton, NC 27932

Job 30136-30136A	Truss M2	Truss Type Monopitch	Qty 6	Ply 1	60 PRINCE PLACE - ROOF	I49963414
---------------------	-------------	-------------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:29 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYT9w97h-2YZ97BpbuWDTHotXqNKO2OdzRx9SLCyhLHz?ozqnyO



Scale = 1:17.6




Plate Offsets (X,Y)--	[4:Edge,0-1-8]								
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.83	Vert(LL)	-0.12	4-5	>752	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.56	Vert(CT)	-0.26	4-5	>353		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	4	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MR						
								Weight: 29 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2 or 2x4 SPF No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2 or 2x4 SPF No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS. (size) 4=Mechanical, 5=0-3-8
 Max Horz 5=78(LC 9)
 Max Uplift 4=-29(LC 12), 5=-50(LC 8)
 Max Grav 4=304(LC 1), 5=374(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-5=-317/130

NOTES-

- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 7-10-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 5.




January 31, 2022

Job 30136-30136A	Truss M2E	Truss Type Monopitch Supported Gable	Qty 1	Ply 1	60 PRINCE PLACE - ROOF I49963415
---------------------	--------------	---	----------	----------	-------------------------------------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:30 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-Wi7YKXpDfqlKvyRkO4sdac9JgqO6BoS5w?0WYEzqnyN



Scale = 1:16.6

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.12	Vert(LL)	0.00	2	n/r	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.07	Vert(CT)	-0.00	2	n/r		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Horz(CT)	0.00	4	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-R						
	Code IRC2015/TPI2014						Weight: 13 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
 BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
 WEBS 2x4 SP No.3

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 2-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 5=2-0-0, 4=2-0-0
 Max Horz 5=76(LC 9)
 Max Uplift 5=-5(LC 12), 4=-42(LC 9)
 Max Grav 5=148(LC 1), 4=74(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 5) Gable studs spaced at 2-0-0 oc.
 - 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 4.



January 31, 2022

Job 30136-30136A	Truss M2G	Truss Type Monopitch Girder	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	I49963416
---------------------	--------------	--------------------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:31 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-?xhwYtqrQ7TBX60wyoNs7piOAEcWwE8E9fm44gzqnyM



Scale = 1:17.7




Plate Offsets (X, Y)--	[6:0-2-2,0-0-8]
------------------------	-----------------

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.46	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.63	Vert(LL) -0.12 5-6 >774 240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.10	Vert(CT) -0.25 5-6 >366 180		
BCDL 10.0	Rep Stress Incr NO	Matrix-MS	Horz(CT) 0.00 5 n/a n/a		
	Code IRC2015/TPI2014			Weight: 34 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	

REACTIONS. (size) 6=0-3-8, 5=Mechanical
 Max Horz 6=78(LC 22)
 Max Uplift 6=-72(LC 4), 5=-50(LC 8)
 Max Grav 6=409(LC 1), 5=325(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-407/85, 2-6=-293/95
 BOT CHORD 5-6=-81/361
 WEBS 3-5=-365/117

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 5.
 - 6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 12 lb down and 20 lb up at 4-4-12, and 13 lb down and 22 lb up at 6-4-12 on top chord, and 54 lb down and 39 lb up at 2-10-12, and 8 lb down at 4-4-12, and 11 lb down and 11 lb up at 6-4-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)
 Vert: 1-2=-60, 2-4=-60, 5-6=-20

Concentrated Loads (lb)
 Vert: 9=-54(F) 10=-2(F) 11=-1(F)



Job 30136-30136A	Truss M3	Truss Type Monopitch	Qty 3	Ply 1	60 PRINCE PLACE - ROOF	149963417
---------------------	-------------	-------------------------	----------	----------	------------------------	-----------


84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:32 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-T7FIIDrTBRb28Gb6WVu5f1EVkeusfgKONJVdc6zqnyL



Scale = 1:20.5



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.73	Vert(LL)	-0.30 5-6	>388	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.88	Vert(CT)	-0.60 5-6	>194	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.17	Horz(CT)	0.01 5	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MS					Weight: 42 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	

REACTIONS. (size) 6=0-3-0, 5=Mechanical
 Max Horz 6=94(LC 9)
 Max Uplift 6=-55(LC 8), 5=-36(LC 12)
 Max Grav 6=453(LC 1), 5=385(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-515/93, 2-6=-355/133
 BOT CHORD 5-6=-129/457
 WEBS 3-5=-478/143

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 9-10-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 5.




Job 30136-30136A	Truss M6	Truss Type Monopitch	Qty 3	Ply 1	60 PRINCE PLACE - ROOF Job Reference (optional)	I49963418
---------------------	-------------	-------------------------	----------	----------	--	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:33 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-xKpgzZs5ylkvmPAJ3DPKCEng82L3O1NXczFA8ZzqnyK



Scale = 1:53.5

Plate Offsets (X, Y)-- [2:0-3-0,Edge], [5:0-2-0,0-0-2], [6:0-2-12,0-2-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.75	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.44	Vert(LL) -0.08 6-7 >999 240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.56	Vert(CT) -0.18 6-7 >812 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-MS	Horz(CT) 0.01 6 n/a n/a		
	Code IRC2015/TPI2014			Weight: 85 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 5-6

REACTIONS. (size) 8=0-3-8, 6=0-3-8
Max Horz 8=272(LC 9)
Max Uplift 6=88(LC 12)
Max Grav 8=538(LC 1), 6=517(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-534/56, 2-8=-463/83
BOT CHORD 7-8=-198/499, 6-7=-198/499
WEBS 3-6=-460/147

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 12-1-12 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
Edenton, NC 27932

Job 30136-30136A	Truss M7	Truss Type MONOPIITCH	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	I49963419
---------------------	-------------	--------------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:33 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-xKpgzZs5ylkvmPAJ3DPKCEnhC2KMO1LXczFA8ZzqnyK



Scale = 1:53.5

Plate Offsets (X,Y)--	[4:0-2-0,0-0-2], [5:0-2-12,0-2-0]
-----------------------	-----------------------------------

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.68	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.48	Vert(LL) -0.08 5-6 >999 240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.57	Vert(CT) -0.19 5-6 >757 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-MS	Horz(CT) 0.01 5 n/a n/a		
	Code IRC2015/TPI2014			Weight: 84 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 4-5
OTHERS 2x4 SP No.3	

REACTIONS. (size) 7=0-3-8, 5=0-3-8
 Max Horz 7=263(LC 9)
 Max Uplift 5=88(LC 12)
 Max Grav 7=474(LC 1), 5=519(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-529/57, 1-7=-389/51
 BOT CHORD 6-7=-198/500, 5-6=-198/500
 WEBS 2-5=-462/146

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 3-1-12, Interior(1) 3-1-12 to 12-1-12 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5.




January 31, 2022

Job 30136-30136A	Truss M8	Truss Type Monopitch	Qty 4	Ply 1	60 PRINCE PLACE - ROOF	149963420
---------------------	-------------	-------------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:34 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-PWN2Avtj2smOZIVdwwZISKqTSiH7VThrd_kh?zqnyJ



Scale = 1:46.9

Plate Offsets (X,Y)--	[2:0-3-0,Edge]						
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d
TCLL 20.0	Plate Grip DOL	1.15	TC 0.78	Vert(LL)	-0.03	6-7	>999
TCDL 10.0	Lumber DOL	1.15	BC 0.31	Vert(CT)	-0.08	6-7	>999
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.51	Horz(CT)	-0.08	9	n/a
BCDL 10.0	Code IRC2015/TPI2014		Matrix-MS				
							PLATES
							MT20
							GRIP
							197/144
							Weight: 84 lb
							FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 8=0-3-8, 9=0-3-0
Max Horz 8=272(LC 9)
Max Uplift 8=-1(LC 12), 9=-88(LC 12)
Max Grav 8=544(LC 1), 9=512(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-504/63, 6-9=-55/351, 2-8=-473/99
BOT CHORD 7-8=-170/440, 6-7=-170/440
WEBS 3-7=0/258, 3-6=-454/143

NOTES-

- 1) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 12-1-12 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) All plates are 3x4 MT20 unless otherwise indicated.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Bearing at joint(s) 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 9.




January 31, 2022

Job 30136-30136A	Truss PB1	Truss Type GABLE	Qty 12	Ply 1	60 PRINCE PLACE - ROOF Job Reference (optional)	149963421
---------------------	--------------	---------------------	-----------	----------	--	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:35 2022 Page 1

ID:BLJh1112d3wvZK_wUdDgFCyrbmE-tixROfLUM_d?jKhBdRoHfsBar42s3hq4HkHdRzqny!



Scale = 1:10.9

Plate Offsets (X,Y)--	[3:0-2-0,Edge]						
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.05	Vert(LL) n/a	-	n/a	999	MT20 197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.15	Vert(CT) n/a	-	n/a	999	
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) 0.00	5	n/a	n/a	
BCDL 10.0	Code IRC2015/TPI2014	Matrix-P					Weight: 14 lb FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 5-0-0.
(lb) - Max Horz 1=-28(LC 8)
Max Uplift All uplift 100 lb or less at joint(s) 1, 5, 2, 4
Max Grav All reactions 250 lb or less at joint(s) 1, 5, 2, 4

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) Gable requires continuous bottom chord bearing.
- 5) Gable studs spaced at 2-0-0 oc.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5, 2, 4.
- 9) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job 30136-30136A	Truss PB1GE	Truss Type GABLE	Qty 2	Ply 1	60 PRINCE PLACE - ROOF Job Reference (optional)	149963422
---------------------	----------------	---------------------	----------	----------	--	-----------


84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:36 2022 Page 1
ID:BLJh1112d3wvZK_wUdDgFCyrbmE-LuVpbbu_Fg6UdvtlLy1qtPMNFS6bVkJwTqluzqnyH



4x4 =

Scale = 1:12.8



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.05	Vert(LL)	n/a	-	n/a	999	MT20	197/144
BCDL 10.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.01	Horz(CT)	0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-P						Weight: 15 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
 BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
 OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 5-0-0.
 (lb) - Max Horz 1=-28(LC 8)
 Max Uplift All uplift 100 lb or less at joint(s) 1, 5, 2, 4
 Max Grav All reactions 250 lb or less at joint(s) 1, 5, 2, 4, 6

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5, 2, 4.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
 Edenton, NC 27932

Job 30136-30136A	Truss PB2	Truss Type GABLE	Qty 1	Ply 2	60 PRINCE PLACE - ROOF 149963423
---------------------	--------------	---------------------	----------	----------	-------------------------------------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:38 2022 Page 1

ID:BLJh1112d3wvZK_wUdDgFCyrbmE-HHcZ0GwEnHMBsB3Gsm?VvIUjD37v3PRGmEyxqmqnyF



3x4 =

Scale = 1:12.8




Plate Offsets (X, Y)--	[3:0-2-0, Edge]						
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d
TCLL 20.0	Plate Grip DOL	1.15	TC 0.02	Vert(LL)	n/a	-	n/a 999
TCDL 10.0	Lumber DOL	1.15	BC 0.07	Vert(CT)	n/a	-	n/a 999
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	5	n/a n/a
BCDL 10.0	Code IRC2015/TPI2014		Matrix-P				
							PLATES MT20
							GRIP 197/144
							Weight: 28 lb FT = 20%

LUMBER-
 TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
 BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2


BRACING-
 TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 5-0-0.
 (lb) - Max Horz 1=28(LC 11)
 Max Uplift All uplift 100 lb or less at joint(s) 1, 5, 2, 4
 Max Grav All reactions 250 lb or less at joint(s) 1, 5, 2, 4

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 2-ply truss to be connected together as follows:
 Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
 Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5, 2, 4.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
 Edenton, NC 27932

Job 30136-30136A	Truss PB3	Truss Type GABLE	Qty 1	Ply 2	60 PRINCE PLACE - ROOF 149963424
---------------------	--------------	---------------------	----------	----------	-------------------------------------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:39 2022 Page 1

ID:BLJh1112d3wvZK_wUdDgFCyrbmE-mTAxDcwsYbU2UKdSQTWkSV1tyTT8nshQ_uiVMCzqnyE



3x4 =

Scale = 1:12.8




Plate Offsets (X,Y)--	[3:0-2-0,Edge]						
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d
TCLL 20.0	Plate Grip DOL	1.15	TC 0.02	Vert(LL)	n/a	-	n/a 999
TCDL 10.0	Lumber DOL	1.15	BC 0.07	Vert(CT)	n/a	-	n/a 999
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	5	n/a n/a
BCDL 10.0	Code IRC2015/TPI2014		Matrix-P				
							PLATES MT20
							GRIP 197/144
							Weight: 28 lb FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2 or 2x4 SPF No.2	TOP CHORD	Structural wood sheathing directly applied or 5-0-0 oc purlins.
BOT CHORD	2x4 SP No.2 or 2x4 SPF No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 5-0-0.
 (lb) - Max Horz 1=28(LC 11)
 Max Uplift All uplift 100 lb or less at joint(s) 1, 5, 2, 4
 Max Grav All reactions 250 lb or less at joint(s) 1, 5, 2, 4


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 2-ply truss to be connected together as follows:
 Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
 Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5, 2, 4.
 - See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



Job 30136-30136A	Truss PB4	Truss Type GABLE	Qty 4	Ply 1	60 PRINCE PLACE - ROOF	I49963425
---------------------	--------------	---------------------	----------	----------	------------------------	-----------

ID:6ghGmW2wjVRJEest?1fGYTyw97h-KHyuln4XmXmerm8EOwZoES6EPk1LA04prlcqzpsgX
8.530 s Dec 6 2021 MiTek Industries, Inc. Mon Jan 31 10:29:16 2022 Page 1



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.19	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.11	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	4	n/a		
BCDL 10.0	Code	IRC2015/TPI2014	Matrix-P					Weight: 29 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
WEBS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6'-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.

REACTIONS. All bearings 8-0-0.
(lb) - Max Horz 1=-60(LC 8)
Max Uplift All uplift 100 lb or less at joint(s) except 1=-241(LC 19), 5=-211(LC 20), 2=-193(LC 12), 4=-174(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 1, 5, 6 except 2=421(LC 19), 4=400(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TC DL=6.0psf; BC DL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-3-3 to 3-3-3, Interior(1) 3-3-3 to 4-0-0, Exterior(2) 4-0-0 to 7-0-0, Interior(1) 7-0-0 to 7-8-13 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2'-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6-0 tall by 2'-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 241 lb uplift at joint 1, 211 lb uplift at joint 5, 193 lb uplift at joint 2 and 174 lb uplift at joint 4.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S)

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-84, 2-3=-60, 3-4=-60, 4-5=-84, 2-4=-20
- Dead + 0.75 Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-74, 2-3=-50, 3-4=-50, 4-5=-74, 2-4=-20
- Dead + Uninhabitable Attic Without Storage: Lumber Increase=1.25, Plate Increase=1.25



January 31, 2022

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	60 PRINCE PLACE - ROOF	149963425
30136-30136A	PB4	GABLE	4	1	Job Reference (optional)	

8.530 s Dec 6 2021 MiTek Industries, Inc. Mon Jan 31 10:29:16 2022 Page 2
 ID:6ghGmW2wjVRjEest?1fGYTYw97h-KHyulnm4XuXmerm8EOwZoES6EPk1LA04prlcqzpsgX

LOAD CASE(S)

- Uniform Loads (plf)
 Vert: 1-2=-44, 2-3=-20, 3-4=-20, 4-5=-44, 2-4=-40
- 4) Dead + 0.6 C-C Wind (Pos. Internal) Case 1: Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=6, 2-8=21, 3-8=16, 3-10=21, 4-10=16, 4-5=1, 2-4=-12
 Horz: 1-8=-33, 3-8=-28, 3-10=33, 5-10=28
- 5) Dead + 0.6 C-C Wind (Pos. Internal) Case 2: Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=1, 2-7=16, 3-7=21, 3-9=16, 4-9=21, 4-5=6, 2-4=-12
 Horz: 1-7=-28, 3-7=-33, 3-9=28, 5-9=33
- 6) Dead + 0.6 C-C Wind (Neg. Internal) Case 1: Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=-70, 2-3=-46, 3-4=-46, 4-5=-70, 2-4=-20
 Horz: 1-3=26, 3-5=-26
- 7) Dead + 0.6 C-C Wind (Neg. Internal) Case 2: Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=-70, 2-3=-46, 3-4=-46, 4-5=-70, 2-4=-20
 Horz: 1-3=26, 3-5=-26
- 8) Dead + 0.6 MWFRS Wind (Pos. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=-29, 2-3=-14, 3-4=5, 4-5=-9, 2-4=-12
 Horz: 1-3=2, 3-5=17
- 9) Dead + 0.6 MWFRS Wind (Pos. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=-9, 2-3=5, 3-4=-14, 4-5=-29, 2-4=-12
 Horz: 1-3=-17, 3-5=-2
- 10) Dead + 0.6 MWFRS Wind (Neg. Internal) Left: Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=-55, 2-3=-31, 3-4=-12, 4-5=-35, 2-4=-20
 Horz: 1-3=11, 3-5=8
- 11) Dead + 0.6 MWFRS Wind (Neg. Internal) Right: Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=-35, 2-3=-12, 3-4=-31, 4-5=-55, 2-4=-20
 Horz: 1-3=-8, 3-5=-11
- 12) Dead + 0.6 MWFRS Wind (Pos. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=4, 2-3=18, 3-4=5, 4-5=-9, 2-4=-12
 Horz: 1-3=-30, 3-5=17
- 13) Dead + 0.6 MWFRS Wind (Pos. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=-9, 2-3=5, 3-4=18, 4-5=4, 2-4=-12
 Horz: 1-3=-17, 3-5=30
- 14) Dead + 0.6 MWFRS Wind (Pos. Internal) 3rd Parallel: Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=4, 2-3=18, 3-4=5, 4-5=-9, 2-4=-12
 Horz: 1-3=-30, 3-5=17
- 15) Dead + 0.6 MWFRS Wind (Pos. Internal) 4th Parallel: Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=-9, 2-3=5, 3-4=18, 4-5=4, 2-4=-12
 Horz: 1-3=-17, 3-5=30
- 16) Dead + 0.6 MWFRS Wind (Neg. Internal) 1st Parallel: Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=-22, 2-3=2, 3-4=-12, 4-5=-35, 2-4=-20
 Horz: 1-3=-22, 3-5=8
- 17) Dead + 0.6 MWFRS Wind (Neg. Internal) 2nd Parallel: Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=-35, 2-3=-12, 3-4=2, 4-5=-22, 2-4=-20
 Horz: 1-3=-8, 3-5=22
- 18) Dead: Lumber Increase=0.90, Plate Increase=0.90 Plt. metal=0.90
 Uniform Loads (plf)
 Vert: 1-2=-44, 2-3=-20, 3-4=-20, 4-5=-44, 2-4=-20
- 19) Dead + 0.75 Roof Live (bal.) + 0.75(0.6 MWFRS Wind (Neg. Int) Left): Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=-82, 2-3=-58, 3-4=-44, 4-5=-68, 2-4=-20
 Horz: 1-3=8, 3-5=6
- 20) Dead + 0.75 Roof Live (bal.) + 0.75(0.6 MWFRS Wind (Neg. Int) Right): Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=-68, 2-3=-44, 3-4=-58, 4-5=-82, 2-4=-20
 Horz: 1-3=-6, 3-5=8
- 21) Dead + 0.75 Roof Live (bal.) + 0.75(0.6 MWFRS Wind (Neg. Int) 1st Parallel): Lumber Increase=1.60, Plate Increase=1.60
 Uniform Loads (plf)
 Vert: 1-2=-58, 2-3=-34, 3-4=-44, 4-5=-68, 2-4=-20
 Horz: 1-3=-16, 3-5=6
- 22) Dead + 0.75 Roof Live (bal.) + 0.75(0.6 MWFRS Wind (Neg. Int) 2nd Parallel): Lumber Increase=1.60, Plate Increase=1.60

Continued on page 3

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
 Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	60 PRINCE PLACE - ROOF	I49963425
30136-30136A	PB4	GABLE	4	1	Job Reference (optional)	

8.530 s Dec 6 2021 MiTek Industries, Inc. Mon Jan 31 10:29:16 2022 Page 3
 ID:6ghGmW2wjVRjEest?1fGYTyw97h-KHyulnm4XuXmerm8EOwZoES6EPki1LA04prlcqzpsgX

LOAD CASE(S)

Uniform Loads (plf)

Vert: 1-2=-68, 2-3=-44, 3-4=-34, 4-5=-58, 2-4=-20

Horz: 1-3=-6, 3-5=16

23) 1st Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-84, 2-3=-60, 3-4=-20, 4-5=-44, 2-4=-20

24) 2nd Dead + Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-44, 2-3=-20, 3-4=-60, 4-5=-84, 2-4=-20

25) 3rd Dead + 0.75 Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-74, 2-3=-50, 3-4=-20, 4-5=-44, 2-4=-20

26) 4th Dead + 0.75 Roof Live (unbalanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-44, 2-3=-20, 3-4=-50, 4-5=-74, 2-4=-20

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
 Edenton, NC 27932

Job 30136-30136A	Truss PB4E	Truss Type GABLE	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	149963426
---------------------	---------------	---------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:42 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-A2s4sezqkWsdlOM15c3R38fNogVY_D0shsw9zXzqnyB



Scale = 1:22.8

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.05	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.03	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.03	Horz(CT)	0.00	6	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-P					Weight: 32 lb	FT = 20%
	Code IRC2015/TPI2014							

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins.
BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.

REACTIONS. All bearings 8'-0".
(lb) - Max Horz 1=60(LC 9)
Max Uplift All uplift 100 lb or less at joint(s) 1, 2, 10, 8
Max Grav All reactions 250 lb or less at joint(s) 1, 7, 2, 6, 9, 10, 8

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-3-3 to 3-3-3, Interior(1) 3-3-3 to 4-0-0, Exterior(2) 4-0-0 to 7-0-0, Interior(1) 7-0-0 to 7-8-13 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2'-0" oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6" tall by 2'-0" wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 2, 10, 8.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
Edenton, NC 27932

Job 30136-30136A	Truss V1	Truss Type Valley	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	149963427
---------------------	-------------	----------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:43 2022 Page 1
ID:6ghGmW2wjVRjEest?1fGYTyw97h-eFQS3__Nbp_UzyxEfJagLCTi4pYjfQvWgiV_zqnyA



Scale = 1:40.5

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.36	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.17	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.12	Horz(CT)	0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S						Weight: 70 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.3
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 15-10-4.
(lb) - Max Horz 1=-122(LC 8)
Max Uplift All uplift 100 lb or less at joint(s) 1 except 8=-127(LC 12), 6=-127(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 1, 5 except 7=351(LC 22), 8=401(LC 19), 6=401(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

WEBS 2-8=-282/172, 4-6=-281/171

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-4-13 to 3-4-13, Interior(1) 3-4-13 to 7-11-7, Exterior(2) 7-11-7 to 10-11-7, Interior(1) 10-11-7 to 15-6-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1 except (jt=lb) 8=127, 6=127.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
Edenton, NC 27932

Job 30136-30136A	Truss V2	Truss Type Valley	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	I49963428
---------------------	-------------	----------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:43 2022 Page 1

ID:6ghGmW2wjVrjEest?1fGYTyw97h-eFQS3__Nbp_UzyxEfJagcLCKB4mfjeb0vWgiV_zqnyA



Scale = 1:32.3

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.91	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.36	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.13	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code	IRC2015/TPI2014	Matrix-S						Weight: 49 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.3	TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins.
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS. (size) 1=12-7-14, 3=12-7-14, 4=12-7-14
 Max Horz 1=-96(LC 8)
 Max Uplift 1=-16(LC 12), 3=-28(LC 13)
 Max Grav 1=250(LC 1), 3=250(LC 1), 4=452(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-4=-274/47

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-4-13 to 3-4-13, Interior(1) 3-4-13 to 6-4-4, Exterior(2) 6-4-4 to 9-4-4, Interior(1) 9-4-4 to 12-3-10 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.




January 31, 2022

Job 30136-30136A	Truss V3	Truss Type Valley	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	149963429
---------------------	-------------	----------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,


8.530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:44 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-6RzqGK_?M76La6WQD06v8Zkc0U6QS7_98APG1Qzqny9



4x4 =

Scale = 1:25.4



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.15	TC 0.45	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.32	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.06	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code	IRC2015/TPI2014	Matrix-S						Weight: 36 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.3
BOT CHORD 2x4 SP No.3
OTHERS 2x4 SP No.3


BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=9-5-7, 3=9-5-7, 4=9-5-7
Max Horz 1=-70(LC 8)
Max Uplift 1=-12(LC 13), 3=-21(LC 13)
Max Grav 1=182(LC 1), 3=182(LC 1), 4=332(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-4-13 to 3-4-13, Interior(1) 3-4-13 to 4-9-0, Exterior(2) 4-9-0 to 7-9-0, Interior(1) 7-9-0 to 9-1-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
Edenton, NC 27932

Job 30136-30136A	Truss V4	Truss Type GABLE	Qty 1	Ply 1	60 PRINCE PLACE - ROOF	149963430
---------------------	-------------	---------------------	----------	----------	------------------------	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:45 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-adXCUg?d7RECCF5cmkd8hmHr9tVgBamInq9paszqny8



Scale = 1:18.5

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.24	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.13	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.03	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-P					Weight: 23 lb	FT = 20%
	Code IRC2015/TPI2014							

LUMBER-
TOP CHORD 2x4 SP No.3
BOT CHORD 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=6-3-11, 3=6-3-11, 4=6-3-11
Max Horz 1=44(LC 9)
Max Uplift 1=-13(LC 13), 3=-19(LC 13)
Max Grav 1=125(LC 1), 3=125(LC 1), 4=190(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Gable requires continuous bottom chord bearing.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.



January 31, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




818 Soundside Road
Edenton, NC 27932

Job 30136-30136A	Truss V5	Truss Type Valley	Qty 1	Ply 1	60 PRINCE PLACE - ROOF Job Reference (optional)	149963431
---------------------	-------------	----------------------	----------	----------	--	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:46 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-2q5bh?0FukM3qPgoKR8NE_q30HsKw1PScUuM6Izqny7



Scale = 1:9.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.04	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.10	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Code	IRC2015/TPI2014	Matrix-P					Weight: 9 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.3	TOP CHORD Structural wood sheathing directly applied or 3-1-4 oc purlins.
BOT CHORD 2x4 SP No.3	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=3-0-11, 3=3-0-11
 Max Horz 1=-19(LC 8)
 Max Uplift 1=-1(LC 12), 3=-1(LC 13)
 Max Grav 1=92(LC 1), 3=92(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Gable requires continuous bottom chord bearing.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.




January 31, 2022

Job 30136-30136A	Truss V6	Truss Type Valley	Qty 1	Ply 1	60 PRINCE PLACE - ROOF Job Reference (optional)	149963432
---------------------	-------------	----------------------	----------	----------	--	-----------

84 Components (Dunn), Dunn, NC - 28334,

8,530 s Dec 6 2021 MiTek Industries, Inc. Fri Jan 28 15:02:46 2022 Page 1

ID:6ghGmW2wjVRjEest?1fGYTyw97h-2q5bh?0FukM3qPgoKR8NE_q3qHrpw1PScUuM6Izqny7



Scale = 1:9.9

Plate Offsets (X,Y)-- [2:0-2-0,Edge]									
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP				
TCLL 20.0	Plate Grip DOL 1.15	TC 0.05	Vert(LL) n/a - n/a 999	MT20	244/190				
TCDL 10.0	Lumber DOL 1.15	BC 0.14	Vert(CT) n/a - n/a 999						
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) 0.00 3 n/a n/a						
BCDL 10.0	Code IRC2015/TPI2014	Matrix-P				Weight: 10 lb FT = 20%			

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.3	TOP CHORD	Structural wood sheathing directly applied or 3-5-3 oc purlins.
BOT CHORD	2x4 SP No.3	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=3-4-9, 3=3-4-9
 Max Horz 1=-21(LC 8)
 Max Uplift 1=-1(LC 12), 3=-1(LC 13)
 Max Grav 1=105(LC 1), 3=105(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=115mph Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Gable requires continuous bottom chord bearing.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.




January 31, 2022

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

* Plate location details available in **MITek 20/20 software** or upon request.

PLATE SIZE

4 X 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TFP 1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing, Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8
dimensions shown in ft-in-sixteenths
(Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TFP 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITteK® All Rights Reserved



MITek Engineering Reference Sheet: MII-7473 rev. 5/19/2020



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TFP 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TFP 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Rewriting pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TFP 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.