

- *Keep tanks and drain lines 10' from property lines.
- *Not a survey.
- *Not a guarantee of a septic permit.
- *Keep supply lines >5' from property lines.
- *Some lines are flagged longer in the field than lengths indicate.
- *No grading septic area.


System: Pressure Manifold Lines: 5-8, (257') T&J Panel 50% reduction

0.35 Soil LTAR

Repair: Pressure Manifold

Lines: 1-4, (290') T&J Panel 50% reduction

0.35 Soil LTAR





Central Carolina Soil Consulting, PLLC 1900 South Main Street, Suite 110 Wake Forest, North Carolina 27587 Phone (919)569-6704 Fax (919)569-6703

4-Bedroom Septic Layout Engineeered Flow Reduction 90gal/BR/Day Lot 112, Birchwood Subdivision Harnett County, North Carolina

Job# : 3753 Drawn By : LW Date: 07/02/2021

Revision:4/26/22