North Carolina 2018 - R402.1.5 Total UA

Property

Organization

Inspection Status

Lot 45 WFS

Southern Energy Manager

Results are projected

Justin Smith

JSJ Builders - Pinewood plan

78 Hungry Creek Drive, Erwin 28339

HERS

Builder

Pinewood plan

JSJ Builders

This report is based on a proposed design and does not confirm field enforcement of design elements.

Building UA

Elements	NC Reference	As Designed
Ceilings	37.5	33.6
Above-Grade Walls	160.3	131.8
Windows, Doors and Skylights	117.6	103.0
Slab Floor:	66.9	86.9
Framed Floors	10.6	11.5
Foundation Walls	0.0	0.0
Rim Joists	7.8	6.3
Overall UA (Design must be equal or lower):	400.7	373.1

Requirements

0	402.1.5	Total UA alternative compliance passes by 6.9%.	99 A - 198 A -	
\otimes	402.3.2	Average SHGC; 0.21 Max SHGC; 0.30		
	R402.4.2.2	Air Leakage Testing Air sealing i	s 4.80 ACH at 50 Pa. It must not exceed 5.00 ACH	l at 50 Pa.
\otimes	R402.5	Area-weighted average fenestration SHGC		
	R402.5	Area-weighted average fenestration U-Factor		5, 5 1
Ø	R404.1	Lighting Equipment Efficiency		
0	Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met.		医囊膜
\oslash	R403.3.1	Duct Insulation		
\oslash	403.3.3	Duct Testing		

Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 6.9%.

Name:	Justin Smith	Signature:	Justin Smith	
Organization:	Southern Energy Management	Digitally signed:	2/17/22 at 2:22 PM	

Energy Code Inspection Checklist

Property

Organization

Inspection Status

Results are projected

Justin Smith

JSJ Builders - Pinewood plan

HERS

Builder JSJ Builders

Pinewood plan

General Building Information

Conditioned Area (sq ft) Conditioned Volume (cubic ft) 2,240

Southern Energy Manager

19,972

5,060 Insulated Shell Area (sq ft)

The building energy model in Ekotrope reflects the building assemblies and energy features listed below. Sometimes energy features will change in the field from what has been modeled. The inspection process should identify any changes and ensure that the home continues to meet the applicable energy code.

Slab				
П	Name: slab(1,026 s.f., 140 ft. exterior perimeter) R-0 perimeter insulation, R-0 under slab insulation.			
Fran	ned Floor			
	Name: over garage (195 s.f.) R-0 continuous insulation, R-19 cavity insulation Insulation Grade: I			
Д	Name: over ambient (30 s.f.) R-0 continuous insulation, R-19 cavity insulation Insulation Grade: I			
Four	ndation Wall			
	None Present			
Abo	ve Grade Wall			
	Name: 1st floor ambient (1,011 s.f.) R-0 continuous insulation, R-19 cavity insulation Insulation Grade: II			
	Name: 1st floor garage (253 s.f.) R-0 continuous insulation, R-19 cavity insulation Insulation Grade: II			

Checklist

Energy Code Inspection (
Prop	erty	Organ South Justin	
HERS	Builders - Pînewood plan S vood plan	Build JSJ B	
	Name: 2nd Floor Ambient (1,042 R-0 continuous insulation, R-19 d Insulation Grade: II		
	Name: 2nd Floor Attic (112 s.f.) R-0 continuous insulation, R-15 Insulation Grade: I	cavity i	
Rim	Joist		
	Name: 1st Floor Ambient (112 s. R: 17.30	f.)	
	Name: 1st floor garage (28 s.f.) R: 17.30		

nization

nern Energy Manager n Smith

Inspection Status Results are projected



HERS	uilders - Pinewood plan 3 70od plan	Builder JSJ Builders			
	Name: 2nd Floor Ambient (1,042 R-0 continuous insulation, R-19 c Insulation Grade: II			,	
	Name: 2nd Floor Attic (112 s.f.) R-0 continuous insulation, R-15 c Insulation Grade: I	avity insulation			
Rim	Joist				
	Name: 1st Floor Ambient (112 s.f R: 17.30	.)			
	Name: 1st floor garage (28 s.f.) R: 17.30				
Ceili	ng / Roof				
	Name: attic (1,251 s.f.) R-13 continuous insulation, R-25 Insulation Grade: I	cavity insulation	n		
Opa	que Door				
	Name: front entry (20 s.f.) U: 0.200				
	Name: garage entry (18 s.f.) U: 0.200				
Glaz	ing				
	Name: front shaded (28 s.f.), U	: 0.320, SHG0	C: 0.21, Orien	tation: SOUTH_WEST	
0.10.70	Name: front 2nd unshaded (42 s	.f.), U: 0.320,	SHGC: 0.21,	Orientation: SOUTH_WEST	-
П	Name: right 2nd unshaded (28 s.	f.), U: 0.320,	SHGC: 0.21,	Orientation: SOUTH_EAST	2
*	Name: rear unshaded (104 s.f.),	U: 0.320, Sł	-IGC: 0.21, O	rientation: NORTH_EAST	

Energy Code Inspection Checklist

Propert	У	Organization Southern Energy Manager Justin Smith	Inspection Status Results are projected	
JSJ Buil HERS Pinewoo	lders - Pinewood ptar: od plan	Builder JSJ Builders		
	lame: rear 2nd unshaded (44 s.f	.), U: 0.320, SHGC: 0.21,	Orientation: NORTH_EAST	
	Name: left unshaded (28 s.f.),	J: 0.320, SHGC: 0.21, Orie	ntation: NORTH_WEST	
	lame: left 2nd unshaded (24 s.f.)), U: 0.320, SHGC: 0.21,	Orientation: NORTH_WEST	
Skylig	ht			
N	lone Present			
Mecha	anical Ventilation			
V	lone Present			
Mechanical Equipment				
	Heat Pump • Electric • 100% Heating Load @ 8.2 HSPF, 100% Cooling Load @ 14 SEER			
<u> </u>	Water Heating • Electric • 100% Hot Water Load @ 0.92 Energy Factor			
Air Leakage Control				
	est Status: Blower-door tested louse is air-sealed as to achieve	1,598 CFM50 (4.80 ACH50) o	r less at final blower-door test	
lı	nfiltration Requirements for IECC	C in Climate Zone 4		
	2009 IECC Infiltration limit	for the design home is 7 ACH!	50	

Duct Leakage

Duct System 1

NOT entirely within conditioned space, testing required Leakage to Outside specified as: 89 CFM @ 25Pa (3.97 / 100 ft²) Total Leakage specified as: 89 CFM @ 25Pa (Post-Construction)

2012 IECC Infiltration limit for the design home is 3 ACH50. 2015 IECC Infiltration limit for the design home is 3 ACH50. 2018 IECC Infiltration limit for the design home is 3 ACH50. 2021 IECC Infiltration limit for the design home is 5 ACH50.



Energy Code Inspection Checklist

Property

Organization

Southern Energy Manager R

Justin Smith

Inspection Status
Results are projected

SOUTHERNENER AY MANAGEMENT

JSJ Builders - Pinewood plan

HERS

Builder JSJ Builders

Pinewood plan

Duct Leakage Code Requirements for IECC

2009 IECC:

Postconstruction Leakage Test: Duct Leakage to Outdoors <= 8 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage <= 6 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

2012 IECC Mandatory, 2015 and 2018 IECC Prescriptive Paths:

Postconstruction Leakage Test: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA. Rough in Test with AHU: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA. Rough in Test without AHU: Total Duct Leakage <= 3 CFM25 / 100 sq ft CFA.

2015 and 2018 IECC Performance Paths (Cost Compliance):

Leakage testing is required UNLESS all ducts and air handlers are located entirely within the thermal envelope. There is no pass/fail threshold for duct leakage on the performance path.

Project Notes

Initial Inputs ____AT 10/25/2021_____updated JS 02/17/22

- -confirm HVAC specs
- -confirm water heater specs
- -modeled to worst case orientation
- -confirm off lighting %
- -confirm utilities