Harnett County Department of Public Health

Improvement Permit

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: 78 Wendywood Dr. (Mitchell Rd. - SR 1535) ISSUED TO: Southern Touch Homes SUBDIVISION Mitchell Manor Phase II REPAIR Site Improvements required prior to Construction Authorization Issuance: NEW X Type of Structure: 3-Bedroom 50x44 SFD Proposed Wastewater System Type: 25% Reduction Sys. Projected Daily Flow: 360 GPD Number of bedrooms: 3 Number of Occupants: 6 Basement Yes Pump Required: XYes No May be required based on final location and elevations of facilities Type of Water Supply: Community Public Well Distance from well NA feet X Five years Permit valid for: No expiration Permit conditions: 04/21/2022 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. ISSUED TO: Southern Touch Homes PROPERTY LOCATION: 78 Wendywood Dr. (Mitchell Rd. - SR 15 SUBDIVISION Mitchell Manor Phase II LOT # 15 Facility Type: 3-Bedroom 50x44 SFD Expansion Repair Basement Fixtures? Yes Basement? Yes × No Type of Wastewater System** Pump to 25% Reduction Sys. (Initial) Wastewater Flow: 360 GPD (See note below, if applicable) Pump to 25% Reduction Sys. (Repair) Number of trenches 3 Installation Requirements/Conditions Septic Tank Size 1000 gallons Exact length of each trench 80 Trench Spacing: 9 Feet on Center Pump Tank Size 1000 gallons Trenches shall be installed on contour at a Soil Cover: 12 Maximum Trench Depth of: 24 (Maximum soil cover shall not exceed inches (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: ft. TDH vs. __ inches below pipe Aggregate Depth: NA inches above pipe Conditions: WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. **If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH Mm , toro Date: 64/21/2622 Authorized State Agent: Construction Authorization Expiration Date: 04/21/2027 ANDREW CONTIN

Harnett County Department of Public Health Site Sketch

Property Location: 78 Wendywood Dr. (Mitchell Rd. - SR 1535) Issued To: Southern Touch Homes Subdivision Mitchell Manor Phase II Lot # 15 Authorized State Agent: 105.00 S 65"47"32"E PROPOSED HOUSE LOCATION SINCLAIR 250.03 N 24°12'06'E

105.00

N 65°48'51"W