



ROOF & FLOOR TRUSSES & BEAMS


Reilly Road Industrial Park
Fayetteville, N.C. 28309
Phone: (910) 864-8787
Fax: (910) 864-4444

THIS IS A TRUSS PLACEMENT DIAGRAM ONLY. These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. The individual design sheets for each truss design identified on the drawing drawings. The building designer is responsible for all necessary and pertinent details of the roof and floor system and for the overall structure. The design of the steel support structure including bearing, bracing, walls, and columns is the responsibility of the building designer. For general guidance regarding bracing, consult ICC-ES and ICC-ES provided with the truss delivery package or online @ www.iccsd.com

Bearing reactions less than or equal to 3000# are deemed to comply with the prescriptive Code requirements. The contractor shall refer to the attached Tables (derived from the prescriptive Code requirements) to determine the minimum foundation size and number of wood studs required to support reactions greater than 3000# but not greater than 15000#. A registered design professional shall be retained to design the support system for any reaction that exceeds those specified in the attached Tables. A registered design professional shall be retained to design the support system for all reactions that exceed 15000#.

Signature: *Anthony Williams*

Anthony Williams



Connector Information					Nail Information	
Sym	Product	Manuf	Qty	Supported Member	Header	Truss
■	HUS26	USP	12	NA	16d/3-1/2"	16d/3-1/2"
■	JUS24	USP	6	NA	10d/3"	10d/3"

BEAM SCHEDULE						
PlotID	Length	Product	Piles	Net Qty	Fab Type	
HDR-1	6' 0"	1-3/4" x 9-1/4" LVL Kerlo-S	2	2	FF	
HDR-2	6' 0"	1-3/4" x 9-1/4" LVL Kerlo-S	2	2	FF	
HDR-3	6' 0"	1-3/4" x 9-1/4" LVL Kerlo-S	2	2	FF	
GDH	24' 0"	1-3/4" x 14" LVL Kerlo-S	2	2	FF	
GDH-9	12' 0"	2x12 SP No.2	2	2	FF	

▲ = Indicates Left End of Truss (Reference Engineered Truss Drawing)
Do Not Erect Trusses Backwards

Dimension Notes

- All exterior wall to wall dimensions are to face of sheathing unless noted otherwise
- All interior wall dimensions are to face of stud unless noted otherwise
- All exterior wall to truss dimensions are to face of stud unless noted otherwise

BUILDER	Signature Home Builders	CITY / CO.	Lillington / Harnett
JOB NAME	Lot 82 South Creek	ADDRESS	Lot 82 South Creek / Lillington, NC
PLAN	Sinclair (200606B) w/ 3rd Car	MODEL	Roof
SEAL DATE	7/29/20 (Base)	DATE REV.	5/24/23
QUOTE #	NA	DRAWN BY	Anthony Williams
JOB #	J0523-2661	SALES REP.	Anthony Williams

LOAD CHART FOR JACK STUDS			
BASED ON TABLES 802.2.1 & 802.2.2		NUMBER OF JACK STUDS REQUIRED @ EA END OF HEADERS/ORDER	
REQ'D STUDS FOR (1) 1" x 1" HEADERS	REQ'D STUDS FOR (2) 1" x 1" HEADERS	REQ'D STUDS FOR (1) 1" x 1" HEADERS	REQ'D STUDS FOR (2) 1" x 1" HEADERS
1700 1	2550 1	3400 1	
3400 2	5100 2	6800 2	
5100 3	7650 3	10200 3	
6800 4	10200 4	13600 4	
8500 5	12750 5	17000 5	
10200 6	15300 6		
11900 7			
13600 8			
15300 9			

Truss Placement Plan
SCALE: 1/4" = 1'-0"