

\*Keep supply lines >5' from property lines.

\*Some lines are flagged longer in the field than lengths indicate.

\*No grading septic area.

System: Gravity Serial Dist. Lines: 1—5, (365') Accepted Status System

Repair: Pressure Manifold

Lines: 6-8, (230') T&J Panel

0.35 Soil LTAR

0.35 Soil LTAR



Central Carolina Soil Consulting, PLLC 1900 South Main Street, Suite 110 Wake Forest, North Carolina 27587 Phone (919)569-6704 Fax (919)569-6703

4-Bedroom Septic Layout Lot 1, Birchwood Subdivision Harnett County, North Carolina Job# : 3753

Drawn By : MB

Date : 07/02/2021

Revision:3/03/22